



PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

Approval no: DEV2017/862
Date: 21 AUGUST 2017

PRELIMINARY

HERSTON QUARTER
SITE PLAN
DRAWING NUMBER 268-009-C01-01
REVISION 1 OF 2 4

SCALE
1:200 0 2 4 6 8 A1
1:400

APPROVED
RFPE 6807

Rev	Description	Date	Drawn	Check	RFEC No. & Initials
4	RC BRIDGING SLAB AND MAXIMUM LOAD NOTES ADDED	08/08/17	FG	NJ	JR 6807
3	CUT AND FILL VOLUMES ADDED	04/08/17	NJ	NJ	JR 6807
2	REVISED LAYOUT AT EXISTING TREE	20/07/17	NJ	NJ	JR 6807
1	PRELIMINARY ISSUE	12/07/17	JB	NJ	JR 6807

Rev	Description	Date	Drawn	Check	RFEC No. & Initials
4	RC BRIDGING SLAB AND MAXIMUM LOAD NOTES ADDED	08/08/17	FG	NJ	JR 6807
3	CUT AND FILL VOLUMES ADDED	04/08/17	NJ	NJ	JR 6807
2	REVISED LAYOUT AT EXISTING TREE	20/07/17	NJ	NJ	JR 6807
1	PRELIMINARY ISSUE	12/07/17	JB	NJ	JR 6807

CLIENT
WATPAC CONSTRUCTIONS



Projet Partners
PROJECT MANAGEMENT ENGINEERING PLANNING
MEMBER OF THE PARTNERS GROUP
SUNSHINE COAST CAIRNS NOOSA MACKAY GOLD COAST
Ph: 1300 789 214
www.projetpartners.com.au

SETOUT POINTS

POINT No.	EASTING	NORTHING	HEIGHT
1	52578.314	161116.226	43.43
2	52578.850	161110.250	44.02
3	52582.140	161106.668	44.07
4	52585.095	161106.147	43.92
5	52595.662	161104.285	43.92
6	52617.328	161100.467	46.46
7	52621.267	161099.773	46.54
8	52626.730	161100.342	46.01
9	52630.953	161102.038	45.58
10	52639.035	161102.911	44.80
11	52649.596	161101.132	43.78
12	52648.931	161097.187	43.86
13	52638.371	161098.966	44.76
14	52632.444	161098.326	45.94
15	52628.221	161096.630	45.97
16	52620.573	161095.634	46.50
17	52616.634	161096.528	46.42
18	52594.968	161100.346	43.92
19	52584.400	161102.208	43.92
20	52581.446	161102.729	44.07
21	52574.866	161109.893	44.02
22	52574.241	161116.685	43.37

VOLUMES

	Ramp 1	Ramp 2	Track	Total
CUT (m³)	0	0	36	36
FILL (m³)	40	215	8	263



NOTE:
Maximum equipment load
on Haul Road 30 tonnes