

Department of State Development, Manufacturing, Infrastructure and Planning

Our ref: DEV2019/1003

13 August 2019

Herston Development Company Pty Ltd C/- Urbis Pty Ltd Att: Mr Dean Jones Level 7, 123 Albert Street BRISBANE QLD 4000

Dear Dean

SECTION 89(1)(a) PDA DEVELOPMENT APPROVAL FOR A PDA DEVELOPMENT APPLICATION FOR A PDA DEVELOPMENT PERMIT FOR A MATERIAL CHANGE OF USE FOR ROOMING ACCOMMODATION (STUDENT ACCOMMODATION), CHILDCARE CENTRE, FOOD AND DRINK OUTLET, SHOP, HEALTH CARE SERVICE, RESEARCH AND TECHNOLOGY INDUSTRY, OFFICE, INDOOR SPORT AND RECREATION, SHORT TERM ACCOMMODATION (4 STAGES) AND BUILDING WORK FOR STATE HERITAGE PLACE AT 300 HERSTON ROAD, HERSTON DESCRIBED AS LOT 545 ON SP289113

On 9 August 2019 the Minister for Economic Development Queensland (MEDQ) approved the Priority Development Area (PDA) development application pursuant to s.85(4)(b) of the *Economic Development Act 2012*. The MEDQ has decided to grant all of the PDA development approval applied for, subject to PDA development conditions set out in this PDA decision notice.

The PDA decision notice and approved plans/documents can also be viewed in the MEDQ Development Approvals Register via the Department website http://www.dsdmip.qld.gov.au/economic-development-queensland/current-applications-and-approvals.html.

Should you have any queries in relation to this PDA decision notice, please do not hesitate to contact Karina McGill on 3452 7518.

Yours sincerely

Beatriz Gomez Director Development Assessment Economic Development Queensland

Minister for Economic Development Queensland GPO Box 2202 Brisbane Queensland 4001 Australia **Website** www.edq.qld.gov.au ABN 76 590 288 697

PDA Decision Notice – Approval

Site information			
Name of priority development area (PDA)	Herston Quarter PDA		
Site address	300 Herston Road, H	Herston	
Lot on plan description	Lot number	Plan description	
	Lot 545	SP289113	
PDA development application det	ails		
DEV reference number	DEV2019/1003		
'Properly made' date	31 January 2019		
Type of application	 New development involving: Material change of use Development permit Building work Development permit 		
Description of proposal applied for	 PDA Development Permit for – Material Change of Use – Rooming Accommodation (Student Accommodation), Childcare Centre, Food & Drink Outlet, Shop, Health Care Services, Research and Technology Industry, Office, Indoor Sport and Recreation, Short Term Accommodation (4 stages); and Building Work for a State Heritage Place. 		

PDA de	velopment approval details		
Decision	approval ap	has decided to grant all of blied for, subject to PDA d lecision notice	the PDA development levelopment conditions forming
Decision	date 9 August 20	19	
Currenc	y period 6 years from	decision date	
Plans a	nd documents		
	ns and documents approved by the sare detailed in the table below.		n the PDA development
Approve	ed plans and documents	Number (if applicable)	Date (if applicable)
1.	Staging Plan prepared by Hassell	DA-L-212 Rev K	17.04.2019
2.	Existing Tree Plan prepared by Hassell	DA-L-502 Rev H	24.01.2019
3.	Herston Quarter Heritage Precinct – Heritage Building Dilapidation Report prepared by ADG	20574 Version 04	24.05.2019
4.	Heritage Core Landscape Plan prepared by Hassell	DA-L-103 Rev I	02.05.2019 (as amended in red 08/08/19)
5.	Plan prepared by Hassell	DA-L-201 Rev I	02.05.2019 (as amended in red 08/08/19)
6.	Fourth Avenue Section prepared by Hassell	DA-L-202 Rev I	02.05.2019
7.	Plan prepared by Hassell	DA-L-203 Rev I	02.05.2019 (as amended in red 08/08/19)
8.	Play Section prepared by Hassell	DA-L-204 Rev I	02.05.2019 (as amended in red 08/08/19)
9.	Plan prepared by Hassell	DA-L-205 Rev I	02.05.2019 (as amended in red 08/08/19)
10.	Green Gateway Section prepared by Hassell	DA-L-206 Rev I	02.05.2019 (as amended in red 08/08/19)
11.	Plan prepared by Hassell	DA-L-207 Rev I	02.05.2019 (as amended in red 08/08/19)
12.	South Tower Section prepare by Hassell	d DA-L-208 Rev I	02.05.2019 (as amended in red 08/08/19)

13.	Lady Lamington Section prepared by Hassell	DA-L-209 Rev I	02.05.2019 (as amended in red 08/08/19)
14.	Lady Lamington Section prepared by Hassell	DA-L-210 Rev I	02.05.2019 (as amended in red 08/08/19)
15.	Lady Lamington Section prepared by Hassell	DA-L-211 Rev I	02.05.2019 (as amended in red 08/08/19)
16.	Materiality prepared by Hassell	DA-L-401 Rev I	02.05.2019
17.	Planting Palette prepared by Hassell	DA-L-501 Rev I	02.05.2019
18.	Pedestrian Movement prepared by Hassell	DA-L-301 Rev I	02.05.2019 (as amended in red 08/08/19)
19.	Heritage Significance Legend prepared by elevation Architecture	A-DA-00.02 Rev C	01/05/19
20.	Heritage Significance Legend prepared by elevation Architecture	A-DA-00.03 Rev C	01/05/19
21.	Existing/Demolition Site Plan prepared by elevation Architecture	A-DA-01.01 Rev F	01/05/19 (as amended in red 08/08/19)
22.	Proposed Site Plan prepared by elevation Architecture	A-DA-01.02 Rev H	01/05/19 (as amended in red 08/08/19)
23.	Lower Ground Floor Plan prepared by elevation Architecture	A-DA-03.09 Rev G	01/05/19 (as amended in red 08/08/19)
24.	Ground Floor Plan prepared by elevation Architecture	A-DA-03.10 Rev I	01/05/19 (as amended in red 08/08/19)
25.	First Floor Plan prepared by elevation Architecture	A-DA-03.11 Rev H	01/05/19 (as amended in red 08/08/19)
26.	Second Floor Plan prepared by elevation Architecture	A-DA-03.12 Rev K	01/05/19 (as amended in red 08/08/19)
27.	Third Floor Plan prepared by elevation Architecture	A-DA-03.13 Rev H	01/05/19 (as amended in red 08/08/19)
28.	Roof Plan prepared by elevation Architecture	A-DA-04.03 Rev F	01/05/19

29.	Elevations prepared by elevation Architecture	A-DA-09.04 Rev F	01/05/19
30.	Elevations prepared by elevation Architecture	A-DA-09.05 Rev G	01/05/19
31.	Proposed Materials & Details prepared by elevation Architecture	A-DA-09.06 Rev C	01/05/19
32.	Proposed Materials & Details prepared by elevation Architecture	A-DA-09.07 Rev C	01/05/19
33.	Proposed Materials & Details prepared by elevation Architecture	A-DA-09.08 Rev C	01/05/19
34.	04.1 External Materials prepared by Nettleton Tribe	B10369	April 2019
35.	0.41 External Materials prepared by Nettleton Tribe	B10369	April 2019
36.	05.2 Balustrades prepared by Nettleton Tribe	B10369	April 2019
37.	05.2.1 Balustrades prepared by Nettleton Tribe	B10369	April 2019
38.	05.2.2 Balustrades prepared by Nettleton Tribe	B10369	April 2019
39.	05.2.3 Balustrades prepared by Nettleton Tribe	B10369	April 2019
40.	05.4 Front Courtyard prepared by Nettleton Tribe	B10369	April 2019 (as amended in red 08/08/19)
41.	05.7 Tower Lift & Stair prepared by Nettleton Tribe	B10369	April 2019
42.	05.7 Tower Lift & Stair prepared by Nettleton Tribe	B10369	April 2019
43.	05.10 Screening prepared by Nettleton Tribe	B10369	April 2019
44.	05.10 Screening Locations Typical prepared by Nettleton Tribe	B10369	April 2019
45.	05.11 Original Ceiling Locations prepared by Nettleton Tribe	B10369	April 2019
46.	05.11 Original Ceiling Locations prepared by Nettleton Tribe	B10369	April 2019

47.	05.11 Original Ceiling Locations prepared by Nettleton Tribe	B10369	April 2019	
-----	--	--------	------------	--

Supporting documents

To remove any doubt, the following documents are not approved for the purposes of the PDA development approval, and are supporting documents only for information purposes.

Supporting plans, reports and specifications		Number (if applicable)	Date (if applicable)
1.	Existing Roof Plan prepared by elevation Architecture	A-DA-04.01 Rev D	01/05/2019 (as amended in red 10 July 2019)
2.	3D Views prepared by elevation Architecture	A-DA-22.01 Rev F	01/05/2019 (as amended in red 10 July 2019)
3.	3D Views prepared by elevation Architecture	A-DA-22.02 Rev F	01/05/2019 (as amended in red 10 July 2019)
4.	3D Views prepared by elevation Architecture	A-DA-22.03 Rev E	01/05/2019 (as amended in red 10 July 2019)
5.	3D Views prepared by elevation Architecture	A-DA-22.04 Rev D	01/05/2019 (as amended in red 10 July 2019)
6.	GA Plans – Basement 2 prepared by Nettleton Tribe	10369_DA131 Issue: 9	01.05.19 (as amended in red 10 July 2019)
7.	GA Plans – Basement 1 prepared by Nettleton Tribe	10369_DA132 Issue: 8	01.05.19 (as amended in red 10 July 2019)
8.	GA Plans – Ground Level prepared by Nettleton Tribe	10369_DA133 Issue: 12	01.05.19 (as amended in red 10 July 2019)
9.	GA Plans – Level 1 prepared by Nettleton Tribe	10369_DA134 Issue: 8	01.05.19 (as amended in red 10 July 2019)
10.	GA Plans – Level 2 prepared by Nettleton Tribe	10369_DA135 Issue: 8	01.05.19 (as amended in red 10 July 2019)
11.	GA Plans – Typical Tower Levels 3-7 prepared by Nettleton Tribe	10369_DA136 Issue: 8	01.05.19 (as amended in red 10 July 2019)
12.	GA Plans – Tower Roof Plan prepared by Nettleton Tribe	10369_DA138 Issue: 8	01.05.19 (as amended in red 10 July 2019)

13.	Proposed Building Elevation - North prepared by Nettleton Tribe	10369_DA201 Issue: 7	01.05.19 (as amended in red 10 July 2019)
14.	Proposed Building Elevation - West prepared by Nettleton Tribe	10369_DA202 Issue: 7	01.05.19 (as amended in red 10 July 2019)
15.	Proposed Building Elevation - South prepared by Nettleton Tribe	10369_DA203 Issue: 7	01.05.19 (as amended in red 10 July 2019)
16.	Proposed Building Elevation - East prepared by Nettleton Tribe	10369_DA204 Issue: 7	01.05.19 (as amended in red 10 July 2019)
17.	Proposed Building Elevation – NE Courtyard prepared by Nettleton Tribe	10369_DA205 Issue: 1	01.05.19 (as amended in red 10 July 2019)
18.	Proposed Building Elevation – SE Courtyard prepared by Nettleton Tribe	10369_DA206 Issue: 1	01.05.19 (as amended in red 10 July 2019)

Compliance Assessment Process

Where a PDA development condition requires Compliance Assessment to be undertaken by the Minister for Economic Development Queensland (MEDQ) the following provisions apply:

- a) Notwithstanding the timing specified in a PDA development condition, if Compliance Assessment is required for a matter, Compliance Approval must be obtained prior to any work commencing for, or in relation to, the matter.
- b) The Compliance Assessment Process must be repeated and a further Compliance Approval must be obtained from the MEDQ where a different design or solution, to that already approved, is sought.
- c) The process and timeframes that apply to Compliance Assessment are as follows:
 - i. Prior to commencing Compliance Assessment, the applicant must consult with the MEDQ, about the documents, plans and supporting information required to be submitted to meet the requirements of the relevant PDA development condition(s).
 - ii. Compliance Assessment commences on the day after the applicant takes the following steps:
 - 1. submits to the MEDQ a duly completed Compliance Assessment Form;
 - 2. submits to the MEDQ the documents, plans and supporting information required under paragraph (c)(i); and
 - 3. pays to Economic Development Queensland (EDQ):
 - the relevant fee for Compliance Assessment set out in EDQ's development assessment fees and charges schedule (as amended from time to time); and
 - if requested by EDQ, any specialist consultant costs (e.g. an acoustic consultant, hydraulics engineer or architect) which will be charged on a 100% cost recovery basis.

Compliance Assessment Process

- iii. **within 20 business days after Compliance Assessment commences**, the MEDQ will assess the documents, plans and supporting information and:
 - if satisfied with the material as submitted approve the documents, plans and supporting information and the PDA development condition (or the relevant element of the PDA development condition) is determined to have been met; or
 - 2. if not satisfied with the material as submitted notify the applicant in writing accordingly. This notification may also include a request for further information required by the MEDQ to complete its assessment.
- iv. if the applicant **is** notified under paragraph (c)(iii)(2) above that the MEDQ is not satisfied that compliance has been achieved, revised documents, plans and supporting information, and any further information requested by the MEDQ must be submitted to the MEDQ **within 20 business days** after the date on which the applicant receives the notice, or such further period as may be agreed to in writing by the MEDQ.
- v. within 20 business days after the date that the MEDQ receives the revised documents, plans and supporting information and any further information requested under paragraph (c)(iv) above, the MEDQ will assess the revised material received and:
 - if satisfied with the material submitted approve the revised documents plans and supporting information and the PDA development condition (or the relevant element of the PDA development condition) is determined to have been met; or
 - 2. if not satisfied with the material as submitted notify the applicant in writing accordingly.
- vi. if the applicant is notified under paragraph (c)(v)(2) above that the MEDQ is still not satisfied that compliance has been achieved, the applicant must repeat the steps set out in paragraphs (c)(iv) and (v) above until compliance has been achieved.
- vii. If either party is not satisfied by the outcome of the process set out in paragraph (c) above, that party may request the other party to enter into a mediation process with a single, independent, suitably qualified and experienced mediator agreed to by both parties. If a mediation process is entered into by both parties, the costs of the mediator will be shared equally by both parties.
- viii. If the parties cannot, **within five business days** after agreeing to refer the dispute to mediation, agree upon the appointment of the mediator, either party may request the President of the Queensland Law Society Inc. to make the appointment of a single, independent, suitably qualified mediator.
- ix. Notwithstanding any provision or PDA development condition to the contrary, a PDA development condition (or the relevant element of the PDA development condition) that requires Compliance Assessment is determined to have been met only when MEDQ approves the relevant documents, plans and supporting information referred to in the PDA development condition (or the relevant element of the PDA development condition).

For the purposes of interpreting the PDA Development Conditions, the following is a list of definitions and abbreviations utilised:

AILA means the Australian Institute of Landscape Architects.

Certification Procedures Manual (CPM) stands for Certification Procedures Manual and means the document titled *Certification Procedures Manual*, prepared by the Department of Infrastructure, Local Government and Planning, Version 4, effective 16 October 2017.

Compliance Approval means a written notice issued by the MEDQ, or delegate, following completion of the Compliance Assessment Process, where it is confirmed that the submitted plans, documents and supporting information achieve compliance with the relevant PDA development condition(s) or the relevant element of the PDA development condition(s).

Compliance Assessment means the process undertaken by the MEDQ, or delegate, to decide whether the submitted plans or documents for the Works adequately achieve compliance with the relevant PDA development condition(s).

Compliance Assessment Process means the process for Compliance Assessment set out in this PDA decision notice.

Contaminated land register (CLR) stands for Contaminated Land Register and has the meaning given in the *Environmental Protection Act 1994*.

Council means the Brisbane City Council.

DES stands for the Department of Environment and Science, or any other department administering the *Environmental Protection Act 1994* and *Queensland Heritage Act 1992*.

DSDMIP stands for the Department of State Development, Manufacturing, Infrastructure and Planning, or any other department administering the *Economic Development Act 2012*.

Earthworks means carrying out any Works that are for Filling or Excavation.

EDQ means Economic Development Queensland, Development Assessment, DSDMIP, or as otherwise named.

Environmental Management Register (EMR) stands for the Environmental Management Register and has the meaning given in the *Environmental Protection Act 1994*.

Excavation means carrying out any Works involving the removal of material from the Land that will change the ground level.

Filling means carrying out any Works involving the importation and placement of material on the Land that will change the ground level.

Heritage Works means any Works which may impact on a PDA significant heritage building, including but not limited to Works to or adjacent to a PDA significant heritage building.

MEDQ means the Minister for Economic Development Queensland established under the *Economic Development Act 2012*, or the relevant delegate of the MEDQ under a current instrument of delegation or sub-delegation.

Operational Works means all Development described as:

- i. Clearing of Significant Vegetation
- ii. Earthworks
- iii. Public Realm Works
- iv. Retaining Walls
- v. Roadworks (including internal Roadworks)
- vi. Sewer Works
- vii. Stormwater Work
- viii. Water Works

Out-of-Hours means carrying out Works outside of the ordinary construction hours of Monday to Saturday 6:30am to 6:30pm, excluding public holidays.

PDA stands for priority development area.

Queensland Heritage Place has the meaning given in the *Queensland Heritage Act 1992*.

RPEQ stands for Registered Professional Engineer of Queensland.

PDA De	PDA Development Conditions			
No.	Condition	Timing		
All stage	es			
1.	Carry out the approved development			
	Carry out the approved development generally in accordance with the approved plans, reports and documents.	At all times		
2.	Certification of Operational Works			
	All operational works, for contributed assets, undertaken in accordance with this approval are to comply with all requirements of and fulfil all responsibilities outlined in the <i>Certification</i> <i>Procedures Manual.</i>	As required by the <i>Certification Procedures</i> <i>Manual</i>		
3.	Maintain the Approved Development			
	Maintain the approved development (including landscaping, parking, driveways and other external spaces) generally in accordance with the approved plans and documents, and any other approval or endorsement required by these conditions.	At all times		

4.	Staging	
	Development in Stages 1 – 4 as depicted on the approved plan <i>Staging Plan</i> (dated 17/04/2019) can occur in any order, where the following is adhered to:	At all times
	 a) Stage 1 is completed prior to, or in conjunction with, the completion of Stage 2 (Edith Cavell), Stage 3 (Lady Lamington) or Stage 4 (Lady Norman); 	
	 b) The accompanying public realm for each stage, as illustrated on the approved 'Staging Plan', is to be delivered as part of each stage; 	
	c) Where the approved staging arrangement is required to be changed, a revised staging plan is provided to EDQ for Compliance Assessment prior to the commencement of works for the relevant stage.	
5.	Compliance Assessment – Hoarding	
	 a) Submit to the MEDQ for Compliance Assessment detailed plans of any proposed Hoarding and associated signage (if signage is proposed), certified by a suitably qualified and experienced RPEQ 	a) Prior to commencing relevant Works in the relevant stage
	 b) Erect the approved Hoarding in accordance with the plans approved under part a) of this condition. 	b) As required.
6.	Significant Vegetation	
	Retain and protect all significant vegetation as identified on the approved plan – <i>Existing Tree Plan, prepared by Hassell, DA-L-502 Revision H.</i>	Prior to the commencement of use for each stage
7.	Clearing of Significant Vegetation	
	 a) Complete all operational work for clearing of significant vegetation in accordance with the approved plan – Existing Tree Plan, prepared by Hassall, DA-L-502 Revision H. 	 a) Prior to commencing the relevant operational works
	 b) Where clearing of significant vegetation is not in accordance with the approved plan identified in Condition 7 of this approval, submit to the MEDQ for Compliance Assessment: A map identifying all significant vegetation proposed to be cleared An arborist report prepared by a suitably qualified person for all significant vegetation proposed to be cleared 	b) Prior to the commencement of Works in the relevant stage

c)	Complete all works in accordance with the documents approved under part a) and b) of this condition	c)	Prior to the commencement of Works in the relevant stage
Construction	and Engineering Conditions		
3. C	onstruction and Site Management Plan		
a)	 Submit to the MEDQ a Construction and Site Management Plan (CSMP), prepared by the Principal Site Contractor, that provides but is not necessarily limited to the following: a site layout plan superimposed on the road plan identifying the areas to be affected by the construction and access activities; loading and unloading locations for materials; on-site storage and placement of materials, structures, plant and equipment on site, from time to time; if applicable, any proposed arrangement utilising any part of the road reserve for construction related activities; an estimate of the quantity of demolition material to be removed and the approximate number of heavy vehicle movements per day, including destinations for loads; location of proposed external hoardings (ultimate) and gantries; vii. location of perimeter fencing; wiii. management of dust generated from the site during and outside of construction work hours in accordance with the Environmental Protection Act 1994; ix. if required, management of contaminated land including removal, treatment and replacement in accordance with a compliance permit from an approved contaminated land auditor; and a complaints process procedure, including escalation, to be established and maintained through the course of the development; and xi. management of waste for the all works xii. including hazardous waste storage and transportation prepared by the Principal Site Contractor. 	a)	Prior to the commencement of Works for the relevant stage

	 Development Assessment, DSDMIP, construction hours are Monday to Saturday 6:30am to 6:30pm, excluding public holidays. b) Undertake all works in accordance with the CSMP which must be current and available on site at all times during the construction period. 	b) As required
9.	Compliance Assessment Out-of-Hours Works	
	 a) Submit to the MEDQ for compliance assessment, all requests for Out-of-Hours construction works. Requests must be in writing on the EDQ Out-of-Hours Application Form and shall be accompanied by the following information: reason for the request; site plan(s), where applicable; demonstration that the proposed works can only reasonably and/or safely be undertaken out of normal construction hours; potential adverse impacts and proposed mitigation strategies/measures; and v. a community engagement strategy and outcomes therefrom. 	a) At all times
	 b) Undertake all works generally in accordance with the approval obtained under part a) of this condition 	b) As nominated
10.	Development Identification Signage	
	Erect a "Development Identification Sign" on the subject property in accordance with the requirements below:	Prior to the commencement of works
	 a) the sign should provide a brief description of the development proposed; 	
	 b) the sign is to list the company name, general email address and a contact telephone number for the following parties that are undertaking work on the site: Developer; Project Coordinator; and Principal Site Contractor. 	
	 c) the sign is to be positioned as follows: located centrally along each road frontage of the site to Bramston Terrace and Back Road; located on or within 1.5 metres of the road frontage; mounted at least 300 millimetres above ground level; and 	

	iv. clearly visible from the street for a pedestrian;	
	 d) the sign is to contain no commercial or corporate advertising other than the name, logo or slogan of the parties outlined in part b) of this condition; and 	
	 e) both the sign and the supporting structure are to be made of weatherproof material and to be properly maintained at all times 	
11.	Construction Traffic Management Plan	
	a) Submit to the MEDQ a Traffic Management Plan (TMP) for any works within Road Reserve, certified by a person holding a current Traffic Management Level 3 qualification or higher.	a) Prior to the commencement of the relevant works
	 The TMP is to include the following: provision for the management of traffic around and through the site during and outside of construction work hours; provision of parking for workers and materials delivery during and outside of construction hours of work; risk identification, assessment and identification of mitigation measures; ongoing monitoring, management review and certified updates (as required); and traffic control plans and/or traffic control diagrams, prepared in accordance with Manual of Uniform Traffic Control Devices (MUTCD), for any temporary part or full road closures of any Council or State road(s). 	
	 b) Undertake all works generally in accordance with the certified TMP submitted under part a) of this condition which is to be current and available on site at all times. 	b) At all times
12.	Erosion and Sediment Management	
	 a) Submit to the MEDQ an Erosion and Sediment Control Plan (ESCP), certified by a RPEQ or an accredited professional in erosion and sediment control (CPESC), generally in accordance with the following guidelines: i. Urban Stormwater Quality Planning Guidelines 2010 (DEHP); and ii. Best Practice Erosion and Sediment Control (International Erosion Control Association). 	a) Prior to the commencement of works for the relevant stage

	b) Implement the certified ESCP as required under part a) of this condition.	b) At all times
13.	Public Infrastructure: Damage, Repairs and Relocation	
	Repair any damage to existing public infrastructure that occurred during works carried out in association with the approved development within or external to the site. Should existing public infrastructure require relocation, due to the approved development, the developer is responsible for these costs together with compliance with relevant standards and statutory requirements.	At all times
14.	Construction Noise Management Plan	
	 a) Submit to the MEDQ a Construction Noise Management Plan (CNMP), certified by a suitably qualified experienced person. At a minimum, the CNMP must address the following sections of <i>Australian Standard AS2436-2010</i> as they relate to the site and construction activities: i) s3.4 – Community Relations, including schedule of activities, community notification strategy, complaints reporting and response strategies ii) s4.4 – Post Approval/Construction Planning for Noise and Vibration, including strategies to minimise adverse impacts to proximate sensitive land uses/receptors iii) s4.5 – Control of Noise at Source, including strategies to control noise at source; iv) s4.6 – Controlling the Spread of Noise, including noise reduction measures v) s5.0 – Methods for Measurement of Noise and Vibration, including noise measurement and monitoring strategy. 	a) Prior to commencement of works in any stage
	b) Undertake Works in accordance with the certified CNMP required under part a) of this condition.	b) As indicated
	c) Where requested, submit to the MEDQ, Noise Monitoring Reports, certified by a suitably qualified and experienced person, and evidence of compliance with the community relations elements of the CNMP required under part a) of this condition.	c) As indicated
15.	Compliance Assessment - Structural Monitoring and Vibration Report	
	a) Submit to the MEDQ for Compliance Assessment a Structural Monitoring and Vibration Report (SMVR), certified by a suitably qualified and experienced RPEQ structural and vibration,	a) Prior to the commencement of works for the relevant stage

гг		-	
	 addressing at a minimum: The process to be adopted for in-situ testing based upon actual construction equipment and methods and based upon actual geotechnical conditions onsite to forecast what vibration can be expected during all Works, including: a) Details of proposed methods to mitigate and control vibration and ground movements during construction. An instrumentation and monitoring plan including drawings are to be provided with the design documentation. The instrumentation and monitoring plan and drawings must detail the frequency of monitoring, trigger levels and actions to be taken should the trigger levels be exceeded. As a minimum, the monitoring must commence before any works, continue during all works and construction, and finish one month after the completion of the works; iii. Confirmation that the vibrations limits have been submitted to the adjacent utility providers; iv. In relation to the existing Heritage Places in proximity to the works, including Edith Cavell Lady Norman, and Lady Lamington Buildings the report is to provide: a) Existing and/or predicted footing information (i.e. footing width and founding soil type and consistency); b) Evidence that the construction methodology has considered in the design of the construction methodology proposed shoring, underpinning and stabilisation methods; and, d) Evidence to demonstrate that all Heritage Places and other sensitive receptors within the zone of influence (geotechnical and vibrations) are categorised as high risk, and protected accordingly, regardless of the existing condition of the Heritage Place; 	e t	At all times
16	SMVR certified under part a) of this condition.		
16.	Compliance Assessment – Geotechnical Report		
	 Submit to the MEDQ a Geotechnical Report for Compliance Assessment, certified by a suitably qualified and experienced RPEQ. The submission 	Í	Prior to the commencement of works

	 is to include at a minimum: Confirmation that the Works are to be designed to equivalent Australian Standards: AS1726 Geotechnical Site Investigation; AS2159 Piling – Design and Installation; AS4678 Earth Retaining Structures; Any other applicable standard; ii. The basis of design for the design performance criteria, and interface with other disciplines; iii. The basis of design for the geotechnical design criteria; iv. An investigation plan that sets out the proposed geotechnical investigation including laboratory testing and intended purpose of the Work; An analysis of the existing geological conditions, including the stratigraphy, permanent Works outlines (based on the present available information), excavatability and profiling; vi. A table that sets out the geotechnical design parameters that have been used to undertake the detailed designs; vii. Where proposed excavations are mostly ir rock, the assessment must define potentia adverse defect mechanisms (joints, fault zones, volcanic intrusions and weak zones) which have been considered and detailed explanation of mitigation measure to avoid adverse impacts 	
	 b) Undertake all works in accordance with the Geotechnical Report approved under part a) of this condition. 	b) At all times
17.	Compliance Assessment - Earthworks	
	a) Submit to the MEDQ for Compliance Assessment detailed earthworks plans, certified by a RPEQ, generally in accordance with AS3798 – 2007 "Guidelines on Earthworks for Commercial and Residential Developments".	a) Prior to commencement of site works for the relevant stage
	 The certified earthworks plans are to: i. include a geotechnical soils assessment of the site; ii. The location of any cut or fill, and the associated character of material; iii. are coordinated with the public realm landscape design plans iv. The detailed earthworks integrating in with the 	

 heritage buildings including details of existing footings and existing and proposed levels. Provided detailed cross sections of the proposed earthworks at 20m intervals. be consistent with the Erosion and Sediment Control plans submitted under condition 12; vi. provide full details of areas where dispersive soils will be disturbed, treatment of dispersive soils and their rehabilitation; and vii. provide full details of any areas where surplus soils are to be stockpiled. b) Carry out the earthworks generally in accordance with the certified plans submitted under part a) of this condition. c) Submit to the MEDQ certification from a RPEQ that all earthworks have been carried out generally accordance with the certified plans submitted under part a) of this condition and that any unsuitable material encountered has been treated or replaced with suitable material. 18. Compliance Assessment - Internal Roadworks in the Tepl2Q detailing the Internal Private Roadworks, including: i. Car park design, layout and operation in accordance with AS2890.1, ii. functional road usouts; which clearly dimension road reserve widths, carparks, verges, footpaths, service corridors, traffic devices and access points. iii. long and cross sections for the road to demonstrate how the integration into the adjacent heritage buildings. iii. demonstration that active network complex with the intern of the development scheme primary cycle route. ivi. Details of all on-site servicing areas, existing and proposed loading dock capacilites, on-site circulation, nearcomposed loading dock 		
 with the certified plans submitted under part a) of this condition. c) Submit to the MEDQ certification from a RPEQ that all earthworks have been carried out generally accordance with the certified plans submitted under part a) of this condition and that any unsuitable material encountered has been treated or replaced with suitable material. 18. Compliance Assessment - Internal Roadworks a) Submit to the MEDQ for Compliance Assessment functional roadworks layout plans certified by a RPEC detailing the Internal Private Roadworks, including: Car park design, layout and operation in accordance with AS2890.1. functional road layouts; which clearly dimension road reserve widths, carparks, verges, footpaths, service corridors, traffic devices and access points. lii. long and cross sections for the road to demonstrate how the integration into the adjacent heritage buildings. iv. details of the pavement and verge treatments v. signs & line marking. vi. a demonstration that active network complies with the intent of the development scheme primary cycle route. viii. Demonstrate that no cars will queue into the Bramston Street roundabout; viii. Details of all on-site servicing areas, existing and proposed loading dock capacities, on-site circulation, 	 footings and existing and proposed levels. Provided detailed cross sections of the proposed earthworks at 20m intervals. v. be consistent with the Erosion and Sediment Control plans submitted under condition 12; vi. provide full detail of areas where dispersive soils will be disturbed, treatment of dispersive soils and their rehabilitation; and vii. provide full details of any areas where surplus 	
 that all earthworks have been carried out generally accordance with the certified plans submitted under part a) of this condition and that any unsuitable material encountered has been treated or replaced with suitable material. 18. Compliance Assessment - Internal Roadworks a) Submit to the MEDQ for Compliance Assessment functional roadworks layout plans certified by a RPEQ detailing the Internal Private Roadworks, including: i. Car park design, layout and operation in accordance with AS2890.1, ii. functional road layouts; which clearly dimension road reserve widths, carriageways including lane widths, carriageways including lane widths, carriageways includings. iii. long and cross sections for the road to demonstrate how the integration into the adjacent heritage buildings. iv. details of the pavement and verge treatments v. signs & line marking. vi. a demonstration that active network complies with the intent of the development scheme primary cycle route. viii. Demonstrate that no cars will queue into the Bramston Street roundabout; viii. Details of all on-site servicing areas, existing and proposed loading dock capacities, on-site circulation, 	with the certified plans submitted under part a) of use for the relevant stage	
 a) Submit to the MEDQ for Compliance Assessment functional roadworks layout plans certified by a RPEQ detailing the Internal Private Roadworks, including: Car park design, layout and operation in accordance with AS2890.1, functional road layouts; which clearly dimension road reserve widths, carriageways including lane widths, carparks, verges, footpaths, service corridors, traffic devices and access points. lii. long and cross sections for the road to demonstrate how the integration into the adjacent heritage buildings. iv. details of the pavement and verge treatments v. signs & line marking. vi. a demonstration that active network complies with the intent of the development scheme primary cycle route. Vii. Demonstrate that no cars will queue into the Bramston Street roundabout; Viii. Details of all on-site servicing areas, existing and proposed loading dock capacities, on-site circulation, 	that all earthworks have been carried out generally accordance with the certified plans submitted under part a) of this condition and that any unsuitable material encountered has been	
 a) Submit to the MEDQ for Compliance Assessment functional roadworks layout plans certified by a RPEQ detailing the Internal Private Roadworks, including: Car park design, layout and operation in accordance with AS2890.1, functional road layouts; which clearly dimension road reserve widths, carriageways including lane widths, carparks, verges, footpaths, service corridors, traffic devices and access points. lii. long and cross sections for the road to demonstrate how the integration into the adjacent heritage buildings. details of the pavement and verge treatments signs & line marking. a demonstrate that no cars will queue into the Bramston Street roundabout; Details of all on-site servicing areas, existing and proposed loading dock capacities, on-site circulation, 	Compliance Assessment - Internal Roadworks	
	 functional roadworks layout plans certified by a RPEQ detailing the Internal Private Roadworks, including: Car park design, layout and operation in accordance with AS2890.1, functional road layouts; which clearly dimension road reserve widths, carriageways including lane widths, carparks, verges, footpaths, service corridors, traffic devices and access points. long and cross sections for the road to demonstrate how the integration into the adjacent heritage buildings. details of the pavement and verge treatments signs & line marking. a demonstration that active network complies with the intent of the development scheme primary cycle route. Demonstrate that no cars will queue into the Bramston Street roundabout; viii. Details of all on-site servicing areas, existing and proposed loading dock capacities, on-site circulation, manoeuvring and loading bays (i.e. swept 	
		 footings and existing and proposed levels. Provided detailed cross sections of the proposed earthworks at 20m intervals. v. be consistent with the Erosion and Sediment Control plans submitted under condition 12; vi. provide full detail of areas where dispersive soils and their rehabilitation; and vii. provide full details of any areas where surplus soils are to be stockpiled. b) Prior to commencemer with the certified plans submitted under part a) of this condition. b) Prior to commencemer use for the relevant sta generally accordance with the certified plans submitted under part a) of this condition and that any unsuitable material encountered has been treated or replaced with suitable material. compliance Assessment - Internal Roadworks, including: i. Car park design, layout and operation in accordance with AS2890.1, ii. functional roadworks layout plans certified by a RPEQ detailing the Internal Private Roadworks, including; iii. long and cross sections for the road to demonstrate how the integration into the adjacent heritage buildings. iv. details of the pavement and verge treatments v. signs & line marking, vi. a demonstrate how the integration into the adjacent heritage buildings. iv. details of all on-site servicing areas, existing and proposed loading dock capacities, on-site circulation,

	 with the Traffic Impact Assessment Report prepared by Cambray Consulting dated 25th January 2019; ix. Coordination with the public realm plans approved under Condition 46.
	 b) Submit to the MEDQ for detailed roadworks engineering plans certified by a RPEQ detailing the Internal Private Roadworks generally in accordance with the functional layout plans certified under part a) of this condition b) Prior to commencing the internal roadworks in the relevant stage
	c) Construct the works generally in accordance with the certified plans as required under part b) of this condition.c) Prior to commencing of use for the relevant stage
	d) Provide verification, by a RPEQ, that all works have been completed in accordance with the certified plans required under part b) of this condition.d) Prior to commencing of use for the relevant stage
19.	Retaining Walls
	a) Submit to the MEDQ detailed engineering plans, certified by an RPEQ, of all retaining walls 1.0m or greater in height.a) Prior to commencement of site works for the relevant stage
	Retaining walls are to be generally in accordance with <i>PDA Practice Note No. 10 – Plans of</i> <i>development</i> unless otherwise approved by EDQ Development Assessment, DSDMIP.
	b) Construct the works generally in accordance with the certified plans submitted under part a) of this condition.b) Prior to commencing of use for the relevant stage
	 c) Submit to the MEDQ certification by a RPEQ that all retaining wall works 1.0m or greater in height have been carried out generally in accordance with the certified plans submitted under part a) of this condition. c) Prior to commencing of use for the relevant stage
20.	Bicycle Parking
	 a) Submit to the MEDQ for compliance assessment plans and supporting documentation demonstrating the provision and location of bicycle parking of at a rate of 0.5 bicycle parking spaces x student accommodation facility per room and 46 x non-residential and visitor bicycle parking facilities generally in accordance with <i>AS2890.3 – 1993 Bicycle parking facilities,</i> is delivered for the approved development in the wider Herston Health precinct noting that: i. wayfinding signage indicating the location of

	the non-residential and visitor bicycle parking facilities must be included.	
	 b) Submit to the MEDQ written evidence demonstrating bicycle parking facilities have been provided in accordance with part a) of this condition. 	 b) Prior to commencement of use or endorsement of a Building Format Plan for the relevant stage, whichever occurs first
21.	Upgraded QUU Water infrastructure	
	a) Submit to the MEDQ a water reticulation Precinct Network Plan, endorsed by QUU.	a) Prior to the commencement of water works for the relevant stage
	b) Submit to the MEDQ detailed water reticulation design plans, certified by a RPEQ and endorsed by QUU, generally in accordance with the endorsed Precinct Network Plan submitted under part a) of this condition.	 b) Prior to commencement of water works for the relevant stage
	c) Construct the works generally in accordance with the certified plans submitted under part b) of this condition.	 c) Prior to commencement of use for the relevant stage
	 d) Submit to the MEDQ 'as constructed' plans, asset register, pressure and CCTV results in accordance with QUU current adopted standards, of all water reticulation works constructed in accordance with this condition. 	d) Prior to commencement of use for the relevant stage
22.	Water Connection	
	Connect the development to the existing water reticulation network in accordance with QUU current adopted standards.	Prior to commencement of use for the relevant stage
23.	Upgraded QUU Sewer Reticulation	
	a) Submit to the MEDQ a sewer reticulation Precinct Network Plan, endorsed by QUU.	 a) Prior to the commencement of sewer works for the relevant stage.
	b) Submit to the MEDQ detailed sewer reticulation design plans, certified by a RPEQ and endorsed by QUU, generally in accordance with the endorsed Precinct Network Plan submitted under part a) of this condition.	 b) Prior to commencement of sewer works for the relevant stage
	c) Construct the works generally in accordance with the certified plans submitted under part b) of this condition.	 c) Prior to commencement of use for the relevant stage

	 d) Submit to the MEDQ 'as constructed' plans, asset register, pressure and CCTV results in accordance with QUU current adopted standards, of all sewer reticulation works constructed in accordance with this condition. 	d) Prior to commencement of use for the relevant stage
24.	Sewer Connection	
	Connect the development to the existing sewer reticulation network in accordance with QUU current adopted standards.	Prior to commencement of use for the relevant stage
25.	Stormwater Connection	
	Connect the development to a lawful point of discharge with 'no-worsening' to upstream or downstream properties for storm events up to 1% Annual Exceedance Probability (AEP) in accordance with Council current adopted standards.	Prior to commencement of use for the relevant stage
26.	Stormwater Management (Quality)	
	 a) Submit to the MEDQ detailed engineering drawings, certified by a RPEQ for the proposed stormwater treatment devices designed generally in accordance with <i>PDA Guideline No. 13 Engineering standards</i> – Stormwater quality and the following documents: Herston Quarter Redevelopment Heritage Precinct stages 5,6 & 7) Engineering Services Report section 5 prepared by ACOR Consultants (QLD) Pty Ltd dated 30/01/2019 	a) Prior to commencement of stormwater works for the relevant stage
	 b) Construct the works generally in accordance with the certified plans submitted under part a) of this condition. 	 b) Prior to commencement of use for the relevant stage
	c) Provide evidence from a RPEQ that the works have been constructed generally in accordance with the certified plans submitted under part a) of this condition.	c) Prior to commencement of use for the relevant stage
27.	Stormwater Management (Quantity)	
	 a) Submit to the MEDQ detailed design plans and hydraulic calculations, certified by a RPEQ, for the proposed stormwater drainage system generally in accordance with <i>PDA Guideline No. 13 Engineering standards</i> – <i>Stormwater quantity</i> and the following plans/documents: Herston Quarter Redevelopment Heritage Precinct stages 5,6 & 7) Engineering Services Report section 5 prepared by ACOR Consultants (QLD) Pty Ltd dated 30/01/2019 	a) Prior to commencement of stormwater works for the relevant stage

		[]
	 b) Construct the works in accordance with the certified plans submitted under part a) of this condition. 	 b) Prior to commencement of use for the relevant stage
	c) Provide evidence from a RPEQ that the works have been constructed generally in accordance with the certified plans submitted under part a) of this condition.	 Prior to commencement of use for the relevant stage
28.	Outdoor Lighting	
	Outdoor lighting within the development is to be designed and installed in accordance with AS 4282:1997 Control of the Obtrusive Effects of Outdoor Lighting.	Prior to commencement of use and to be maintained for the relevant stage
29.	Street Lighting	
	Design and install a street lighting system, certified by a RPEQ, to all roads, including footpaths/bikeways within road reserves.	Prior to the commencement of use and to be maintained for the relevant stage
	The design of the street lighting system is to:	
	 meet the relevant standards of the electricity supplier; 	
	 be acceptable to the electricity supplier as 'Rate 2 Public Lighting'; 	
	 be endorsed by Council as the Energex 'billable customer'; and 	
	 be generally in accordance with Australian Standard AS1158 – 'Lighting for Roads and Public Spaces". 	
30.	Electricity	
	Submit to the MEDQ either:	Prior to commencement of use
	a) written evidence from Energex confirming that existing underground low-voltage electricity supply or overhead where agreed to by the local council is available to the development; or	or endorsement of Building Format Plan, whichever comes first for the relevant stage
	 b) written evidence from Energex confirming that the applicant has entered into an agreement with it to provide underground or overhead where agreed to by the local council electricity services. 	

31.	Telecommunications	
	Submit to the MEDQ documentation from an authorised telecommunication service provider confirming that an agreement has been entered into for the provision of underground telecommunication services to the proposed development.	Prior to commencement of use or endorsement of Building Format Plan, whichever comes first for the relevant stage
32.	Broadband	
	Submit to the MEDQ a written agreement from an authorised telecommunications service provider that infrastructure within the development as defined under the <i>Telecommunications Legislation</i> <i>Amendment (Fibre Deployment) Act 2011)</i> can be provided in accordance with the Communications Alliance G645:2017 guideline, to accommodate services which are compliant with the Federal Government's National Broadband Network policy.	Prior to commencement of use or endorsement of Building Format Plan, whichever comes first for the relevant stage
33.	Acid Sulfate Soils (ASSMP)	
	 a) Where acid sulfate soils are found on site, submit to the MEDQ an Acid Sulfate Soils Management Plan (ASSMP). The ASSMP is to be prepared certified by a suitably qualified professional in soils and/or erosion sediment control. 	 a) Prior to commencement of or during site works
	 b) Excavate, remove and/or treat on-site all acid sulfate soils generally in accordance with the certified ASSMP submitted under part a) of this condition. 	 b) Prior to commencement of use for the relevant stage
34.	Refuse Collection	
	Submit to the MEDQ refuse collection approval from Council or a private waste contractor.	Prior to commencement of use for the relevant stage
35.	Easements over Infrastructure	
	Public utility easements are to be provided, in favour of and at no cost to the grantee, over infrastructure located in land that becomes contributed assets.	Prior to commencement of use for the relevant stage
	The terms of the easements are to be to the satisfaction of the Chief Executive Officer of the authority which ultimately is to takeover and maintain the contributed assets.	
36.	Contaminated Land	
	 a) Submit to MEDQ a Stage 2 Environmental Site Assessment (ESA) in accordance with the National Environmental Protection (Assessment of Site Contamination) Measure Amendment No. 1 2013 (NEPM) which includes detailed 	a) Prior to commencement of works

		-	
	assessment of the site, health and environmental risk assessment of the results. This should include an assessment of contamination in groundwater in accordance with Schedule B of the NEPM. This Stage 2 ESA should include a Remediation Action Plan (RAP) addressing remedial tasks required to manage contaminated soil and groundwater (if required) and ensure protection of human health and the environment both during construction and following completion of the development. It may be appropriate to produce separate reports for separate areas of the site. All contaminated land investigation work should be undertaken by a Suitably Qualified Professional (SQP) as defined under Section 564 of the Environmental Protection Act (EP Act) 1994 (or subsequent revisions).		
b)	The Stage 2 ESA and RAP are to be reviewed by a Contaminated Land Auditor (CLA), appointed by DES in accordance with Chapter 12, Part 3A of the EP Act (or subsequent revisions). The CLA must provide written agreement to the RAP prior to the commencement of remediation works/earthworks.	b)	Prior to commencement of works
c)	All remediation and validation works must be undertaken under the supervision of an SQP.	c)	For the duration of the works the subject of this approval
d)	Following completion of remediation and validation works, a Contaminated Land Investigation Document (CLID) detailing all investigation, remediation and validation works undertaken and stating that the site is suitable for its intended land use. This document should be prepared in a format consistent with DES Queensland Auditor Handbook for Contaminated Land, Module 6: Content requirements for contaminated land investigation documents, certifications and audit reports (or equivalent) and Section 389 of the Environmental Protection Act (EP Act) 1994 (or subsequent revisions). The CLA will review the CLID and provide a certification report in relation to the CLID prepared. Separate CLIDs may be required for separate areas of the site.	d)	Prior to commencement of use
relat land out c busii	e: Pursuant to the Environmental Protection Act 1994 in tion to Contaminated Land, if the owner or occupier of becomes aware a notifiable activity is being carried on the land, the owner of occupier must, within 22 ness days after becoming aware the activity is being red out, give notice to the relevant State administering		

Heritag	e conditions	
37.	Compliance Assessment – Heritage Structure Management	
	 Management a) Submit to the MEDQ for Compliance Assessment an updated Heritage Management and Monitoring Plan (HMMP), certified by a RPEQ and a suitably qualified and experienced heritage specialist which addresses, but is not limited to, the following: i. impacts of all works on the PDA significant heritage buildings; ii. engineering assessment; iii. a Comprehensive Risk Assessment in accordance with the principals in AS/NZS ISO 31000:2009 Risk management – Principles and guidelines; iv. mitigation measures to protect heritage buildings, including the proposed hoarding (ultimate) and structural augmentation and the shoring of adjacent basements; v. comprehensive monitoring strategy and methodology; vi. a Maintenance and Security Plan for each heritage god provisions on completion of works, or as otherwise agreed to by EDQ Development Assessment DSDMIP; viii. a post-excavation dilapidation report must be submitted upon completion of the early works program; ix. any proposal to add additional structural bracing, which does not form part of this PDA development approval, must be submitted for approval prior to being installed; x. fire protection services to all heritage places must be provided to EDQ Development Assessment, DSDMIP outlining the impact on heritage places; xi. any temporary works required to support the buildings. Any damage is to be appropriately rectified; and xii. neoprene pads must be installed in all locations where steel bracing will come into contact with building fabric. 	for the relevant stage
	b) Submit to the MEDQ for Compliance Assessment a Structural Engineering Report by a RPEQ, accompanied with detailed engineering drawings	b) Prior to the commencement of works

		and a geotechnical report demonstrating that the heritage buildings are adequately protected from damage during the demolition.		
	c)	Undertake monitoring generally in accordance with the certified methodology/program required under part a) of this condition.	c)	As indicated
	d)	Submit to the MEDQ on request survey monitoring results and an accompanying report certified by a RPEQ.	d)	As indicated
	e)	Construct the works generally in accordance with the endorsed plans required under part b) of this condition.	e)	Prior to commencement of use for the relevant stage
	f)	Submit to the MEDQ 'as-constructed' plans certified by a RPEQ or suitably qualified professional, of any mitigation measures, structural augmentation, repairs performed to heritage buildings.	f)	Prior to commencement of use for the relevant stage
	g)	Complete make good provisions as specified in the endorsed HMMP under part a) of this condition.	g)	As indicated
	An <u></u> wh sho	vice Note: y proposal to add additional structural bracing ich does not form part of this current approval ould be submitted for development approval prior to peing installed.		
38.	Не	ritage Architect		
	a)	Submit to the MEDQ for written approval, a nomination for a registered architect, with a minimum of fifteen years' experience working with Heritage Places and a full International Membership of Australia ICOMOS.	a)	Prior to commencing works on or adjacent to a PDA significant heritage building
		The approved Heritage Architect may be changed from time to time, with written approval by the MEDQ. The approved Heritage Architect is to be appointed for all Building Work involving on or adjacent to a PDA significant heritage building or the conservation or adaptive re-use of a PDA significant heritage building.		
	b)	The approved Heritage Architect is to oversee the coordination of all works to and adjacent to the PDA significant heritage buildings.	b)	As indicated

39.	Monthly Reporting – Heritage Works		
	Submit to the MEDQ monthly reporting on the status of construction works to all heritage fabric. These reports are to be prepared by the approved Heritage Architect as specified in Condition 38, titled Heritage Architect	a)	As indicated
40.	Compliance Assessment – Heritage Maintenance Plan		
	 a) Submit to the MEDQ a Heritage Maintenance Plan for Compliance Assessment for each PDA significant heritage building prepared by the approved Heritage Architect as specified in Condition 38, titled Heritage Architect. The Heritage Maintenance Plan is to be based on the relevant Conservation Management Plan for each PDA significant heritage building and must provide for additional inspections where the heritage building – or part of the heritage building – is vacant. 	a)	Prior to commencing works on the relevant PDA significant heritage building
	b) Undertake the works in accordance with the HMP approved under part a) of this condition.	b)	As indicated
	c) Submit an annual report to the MEDQ and DES summarising the condition of each PDA significant Heritage building and detailing the maintenance and repair Works undertaken, certified by the approved Heritage Architect as specified in Condition 38, titled Heritage Architect. This reporting is to continue until such time that the ultimate use of the building commences.	c)	As stated
41.	Compliance Assessment – Schedule of Conservation Works		
	 a) Submit to the MEDQ for Compliance Assessment a Schedule of Conservation Works for each PDA significant heritage building which is prepared by the approved Heritage Architect as specified in Condition 38, titled Heritage Architect. The Schedule of Conservation Works is to be based on the approved Dilapidation Reports and relevant Conservation Management Plan for each PDA significant heritage building. The conservation works are to be specified on plans and elevations for each PDA significant heritage building and should specify the method of conservation. In preparing the Schedule of Conservation Works, consideration is to be given to the condition and structural integrity of fabric proposed to be removed and replaced with the intention of 	a)	Prior to commencing works on the relevant PDA significant heritage building

	 retaining and conserving this fabric where possible. The approved Heritage Architect is to oversee the detailed specification and implementation of the approved Schedule of Works. b) Undertake all Works specified in the Schedule of Conservation Works approved under part a) of this condition. All Conservation Works are to be completed within six years of this PDA development approval, or as otherwise agreed to in writing by the MEDQ. 	b)	As indicated
	c) Submit to the MEDQ certification from the approved Heritage Architect that all Works have been undertaken in accordance with part a) of this condition.		Prior to commencing use of the relevant PDA significant heritage building
42.	Archival Recording		
	 Submit to MEDQ written evidence that the proposed archival recording scope has been approved by DES 	a)	Prior to commencing the relevant Works on the relevant PDA significant heritage building
	b) Submit to MEDQ the archival recording for section each section or part thereof of all PDA significant heritage buildings generally in accordance with the written advice provided in part a) of this condition	b)	Prior to commencing the relevant Works on the relevant section or part thereof of the PDA significant heritage building
	 c) Submit to DES a comprehensive archival recording for each PDA significant heritage building (including its surroundings) in accordance with the written advice provided in part a) of this condition 	Í	Prior to the commencement of use for each PDA significant heritage building or within 3 months of commencing the final stage of Works on the relevant PDA significant building whichever is earlier
43.	Retention Strategy		
	 a) Submit to EDQ Development Assessment, DSDMIP a Retention Strategy prepared by the approved Heritage Architect as specified in Condition 38, titled Heritage Architect, which details the process and methodology of the retention, analysis and storage of heritage fabric approved for removal, including windows, doors, decorative finishes and the like. The Strategy is to: a. Detail the method of analysis which will be used to determine which material will be 	a)	Prior to the commencement of Works on the relevant PDA significant heritage building

				Ţ
		 suitable for retention for the purpose of future repair or reinstatement works b. Outline the storage method and location for material retained as per part (ii) above. The storage location is to be secure and weatherproof. 		
	b)	Complete all works in accordance with the Retention Strategy as above under part a) of this condition.	b)	For the duration of the works
	c)	Submit to EDQ Development Assessment, DSDMIP a report which includes a catalogue of the fabric retained during the works as per part b) of this condition.	c)	No later than 4 weeks after the completion of works on the relevant PDA significant heritage building
Public Rea	alm	conditions		
44.	Со	mpliance Assessment – Public Art Strategy		
	a)	 Submit to the MEDQ for Compliance Assessment, a Public Art Strategy, prepared by a suitably qualified and experienced person. The Public Art Strategy is to include at a minimum: a. A detailed public art strategy incorporating the intent and principles for all public artworks on the site. b. Conceptual designs and details of proposed public art, locations, finishes and materials c. Documentation demonstrating how the proposed public art integrates with the Heritage Interpretation Strategy and Wayfinding Strategy. 	a)	Prior to commencing Public Realm Works
	b)	 Submit to the MEDQ for Compliance Assessment, Detailed Design Plans, including images, for the artworks conceptually described and illustrated in the Public Art Strategy approved under part a) of this condition. The Detailed Design Plans are to at a minimum: a. Be in accordance with the Public Art Strategy approved under part a) of this condition; b. Provide precise locations, materials and finishes. 	b)	Prior to commencing the relevant works (installation of public art)
	c)	Undertake all Works in accordance with the Detailed Design Plans approved under part b) of this condition.	c)	As indicated

45.	Compliance Assessment – Heritage Interpretation Strategy and Plans			
	 a) Submit to the MEDQ for Compliance Assessment, a Heritage Interpretation Strategy prepared by a suitably qualified and experienced heritage interpretation specialist. 		a)	Prior to commencing Public Realm Works
	 The Heritage Interpretation Strategy is to focus on delivering an integrated and holistic approach to heritage interpretation, and to: Identify the potential audience for the interpretation; Identify the historic themes to be interpreted; Identify potential media and location(s) for interpretation; Identify how heritage interpretation will be integrated with the public realm, public art strategies and wayfinding devices; and Ensure any proposal involving the Aboriginal cultural heritage is developed in consultation with the Traditional Owners. 			
	 b) Submit to the MEDQ for Compliance Assessment detailed Heritage Interpretation Plans in accordance with the Heritage Interpretation Strategy approved under part a) of this condition 		b)	Prior to commencing use of the relevant Stage
	 c) Construct the works in accordance with the Heritage Interpretation Plans approved under part b) of this condition. 		c)	Within 20 business days of completion of the relevant works
46.	Compliance Assessment – Wayfinding Strategy			
	 a) Submit to the MEDQ for Compliance Assessment a Wayfinding Strategy for the site. The Wayfinding Strategy is to address the strategic and local context, and detail at a minimum: a. Wayfinding principles and elements within the Development and how these: i. Integrate into the wider surrounding Herston Health landscape; ii. Stitch together a coherent navigable landscape; b. How the following key design elements use been used to deliver wayfinding throughout the development: i. Place specific qualities and architectural clues (landscape, heritage, architecture and public art) 	a)		ior to commencing Iblic Realm Works

		ic communication communication.		
			. 、	
	Wayfinding Strategy	ent in accordance with the approved under part a) of this	b)	At all times
	condition.			
47.	Compliance Assessme Plans	nt – Detailed Public Realm		
			a)	Prior to commencing
		plans including Design Supporting information for all		Public Realm Works for the relevant stage
		certified by an AILA and with		the relevant stage
		professional, as appropriate.		
	The detailed plans a			
	accordance with app	roved plans.		
	The Detailed Doc	umentation and Supporting		
		nclude at a minimum:		
		location and types;		
	ii. Details of	pavement types and		
		(paving stone types and		
	sizes);			
		and details of proposed		
		eritage interpretation wayfinding and signage		
	elements;			
		a schedule of materials and		
		urniture, lighting and signage;		
	v. Planting p	lans including species, sizes		
		ng and location;		
		ate design meets equitable		
		d CPTED requirements;		
	vii. Interface buildings;	with PDA significant heritage		
		with new built form;		
		awnings and shade devices		
		ocation, height and		
	materials;	-		
		id storey and ground cover		
	-	st, including minimum overall		
	•	read and container size;		
		, arrangements and details of WSUD devices;		
		and details of an irrigation		
		establish and sustain the		
	softscape			
		and dimension of street		
	-	ays, footpaths and other		
	pavement			
		type and size of street tree		
		ng park area and ment, including location and		
		of paths, planting, mounding,		
L	ucauneni	or pairio, planting, mounding,		

	 park furniture, shelters and play area. xv. Demonstrated consideration of the relevant Conservation Management Plans to inform planting choice, the location and treatment of footpaths, the location and materiality of furniture, lighting, fencing etc. xvi. An arborist report for any vegetation proposed to be removed.
	b) Construct the works in accordance with plans approved under part a) of this condition.b) As indicated
	 c) Provide certification from an AILA, that the works have been inspected and completed generally in accordance with parts a) and b) of this condition. c) Within 20 business days of completion of works
48.	Compliance Assessment – Public Access 24/7
	 a) Submit to the MEDQ for Compliance Assessment, a plan that provides and maintains unimpeded and safe 24-hour public access through the site and to all buildings internal to the site. This plan is to demonstrate compliance with AS1428.1 and AS1428.2 where applicable. a) Prior to commencing Public Realm Works
	b) Maintain access 24/7 as per the plan approved b) As indicated under part a) of this condition.
49.	Compliance Assessment – Event Management Strategy
	 a) Submit to the MEDQ for Compliance Assessment, an Event Management Plan (EMP), prepared by a suitably qualified and experienced person in event organisation and administration, identifying at a minimum; a. The planned event spaces, their size, their capacity and location; b. The different types of events to be held within each event space; c. The management of service vehicle access for ongoing requirements in event mode; d. The processes to be used for communicating the local community and key stakeholders, and the mechanisms for incorporating their feedback and concerns into future event planning and preparation of any individual event management plans.
	 b) Where necessary, obtain permits from Council for specific events and ensure these are planned in accordance with the EMP approved under part a) of this condition. b) As required

	 c) The approved EMP and any specific event management plan (where related to a Council permitted event) must be kept available on site and be accessible at all times. 	At all times
	d) Undertake any event on the site in accordance d) with the approved EMP.	At all times
50.	Compliance Assessment – Exclusive Use Area Plans	
	 a) Submit to the MEDQ for Compliance Assessment, detailed plans including Design Documentation and Supporting information certified by an AILA and with input from a heritage professional, as appropriate, for all areas identified as Exclusive Use Areas on approved plan Pedestrian Movement prepared by Hassell. The detailed plans are to be generally in accordance with approved plans. 	Prior to commencing the relevant works
	The Detailed Documentation and Supporting Information is to include at a minimum: i. Furniture location and types; ii. Details of pavement types and materials (paving stone types and sizes); iii. Locations and details of proposed artwork, heritage interpretation	
	elements, wayfinding and signage elements; iv. Plans and a schedule of materials and finishes, furniture, lighting and signage;	
	v. Planting plans including species, sizes and spacing and location;	
	vi. Demonstrate design meets equitable access and CPTED requirements; vii. Interface with PDA significant heritage	
	buildings; viii. Interface with new built form; ix. Details of awnings and shade devices including location, height and materials;	
	 x. Details of security fencing; xi. All tree, mid storey and ground cover species list, including minimum overall height, spread and container size; 	
	 xii. Locations, arrangements and details of proposed WSUD devices; xiii. Locations and details of an irrigation 	
	system to establish and sustain the softscape areas; xiv. Location and dimension of street carriageways, footpaths and other pavements;	

xv. Location, type and size of street tree and fencing park area and embellishment, including location and treatment of paths, planting, mounding, park furniture, shelters and play area. xvi. Demonstrated consideration of the relevant Conservation Management Plans to inform planting choice, the location and treatment of footpaths, the location and materiality of furniture, lighting, fencing etc; xvii. An arborist report for any vegetation proposed to be removed. b) Construct the works in accordance with plans approved under part a) of this condition. Infrastructure Contributions b) Juness an infrastructure agreement (or another approved written arrangement) provides to the contrary, pay to the MEDQ infrastructure charges in accordance with the DCOP, indexed to the date of payment In accordance with the construction plans detailing the GFA must also be provided to the MEDQ prior to commencement of use for calculation of final charges. Stage 2 - Edith Cavell Material Change of Use - Childcare Centre, Commercial, Centre Activities and Buildi Work on a State Heritage Listed Place 52. Compliance Assessment - Detailed Demolition Plans a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: i. All floor levels; ii. Roof: iii. All elevations; iv. Detailed cross sections.	
Infrastructure Contributions 51. Infrastructure Contributions Unless an infrastructure agreement (or another approved written arrangement) provides to the contrary, pay to the MEDQ infrastructure charges in accordance with the DCOP, indexed to the date of payment In accordance with the DCOP, indexed to the date of payment Where the application is an MCU, certified construction plans detailing the GFA must also be provided to the MEDQ prior to commencement of use for calculation of final charges. Stage 2 – Edith Cavell Material Change of Use – Childcare Centre, Commercial, Centre Activities and Buildi Work on a State Heritage Listed Place a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: i. All floor levels; ii. Roof: iii. All elevations; a) Prior to commencing the detailing the or compliance Assessment and the compliance Assessment and th	
51. Infrastructure Contributions Unless an infrastructure agreement (or another approved written arrangement) provides to the contrary, pay to the MEDQ infrastructure charges in accordance with the DCOP, indexed to the date of payment In accordance with the DCOP, indexed to the date of payment Where the application is an MCU, certified construction plans detailing the GFA must also be provided to the MEDQ prior to commencement of use for calculation of final charges. Stage 2 – Edith Cavell Material Change of Use – Childcare Centre, Commercial, Centre Activities and Buildi Work on a State Heritage Listed Place a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: All floor levels; Roof: All elevations; a) Prior to commencing the detailing Weight and the provide to the MEDQ for compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment, and the provide to the MEDQ for Compliance Assessment - Detailed for the provide to the	
Unless an infrastructure agreement (or another approved written arrangement) provides to the contrary, pay to the MEDQ infrastructure charges in accordance with the DCOP, indexed to the date of payment In accordance with the DCOP, indexed to the date of payment Where the application is an MCU, certified construction plans detailing the GFA must also be provided to the MEDQ prior to commencement of use for calculation of final charges. Stage 2 – Edith Cavell Material Change of Use – Childcare Centre, Commercial, Centre Activities and Buildi Work on a State Heritage Listed Place a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: All floor levels; Roof: All elevations; a) Prior to commencing	
approved written arrangement) provides to the contrary, pay to the MEDQ infrastructure charges in accordance with the DCOP, indexed to the date of payment where the application is an MCU, certified construction plans detailing the GFA must also be provided to the MEDQ prior to commencement of use for calculation of final charges. Stage 2 – Edith Cavell Material Change of Use – Childcare Centre, Commercial, Centre Activities and Buildi Work on a State Heritage Listed Place 52. Compliance Assessment – Detailed Demolition Plans a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: i. All floor levels; ii. Roof: iii. All elevations; 	
construction plans detailing the GFA must also be provided to the MEDQ prior to commencement of use for calculation of final charges. Stage 2 – Edith Cavell Material Change of Use – Childcare Centre, Commercial, Centre Activities and Buildi Work on a State Heritage Listed Place 52. Compliance Assessment – Detailed Demolition Plans a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: i. All floor levels; ii. Roof: iii. All elevations; a)	DCOP
Material Change of Use – Childcare Centre, Commercial, Centre Activities and Buildi Work on a State Heritage Listed Place 52. Compliance Assessment – Detailed Demolition Plans a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: i. All floor levels; ii. Roof: iii. All elevations; a) Prior to commencing the floor levels;	
Plans a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: All floor levels; Roof: All elevations; a) Prior to commencing relevant Building Weight and the second se	ing
detailed demolitions plans and elevations prepared by a registered architect for: i. All floor levels; ii. Roof: iii. All elevations;	
	•
The plans are to be accompanied by a Heritage Impact Statement as specified in Condition 55.	
The plans are to be accompanied by a 'Hold Points and Heritage Inspection Schedule'. The schedule is to outline 'Hold Points', at which point relevant works cease to enable inspection of the works by a suitably qualified independent reviewer determined by MEDQ.	

	The applicant or their nominated representative must provide at least 5 business days' notice of an upcoming inspection to the Heritage Architect and the independent reviewer as outlined in the approved Schedule. The applicant or their nominated representative will re-confirm the inspection at least 48 hours prior.		
	Following each inspection, within 2 business days both parties must agree the matters discussed in writing. This may include a requirement for the applicant to provide updated detailed documentation to resolve issues identified during the inspection, prior to works to the relevant heritage place continuing, to be submitted under part b) of this condition.		
	b) Submit to the MEDQ for written approval updated detailed documentation as per the outcome of any Heritage Inspection undertaken in accordance with the Heritage Inspection and Hold Points Schedule approved under part a) of this condition.	b)	As indicated
	 c) Construct the Works in accordance with the plans approved under part a) and b) of this condition. 	c)	Prior to commencing use
	 d) Submit to the MEDQ a written statement by a registered architect, confirming that the constructed Works are generally in accordance with the plans approved under part a) and b) of this condition. 		
53.	Compliance Assessment – Detailed Architectural Plans		
	 a) Submit to the MEDQ for Compliance Assessment, detailed architectural floor plans and elevations prepared by a registered architect for: All floor levels; Roof: All elevations; Detailed cross sections; and Demolition plans. 	a)	Prior to commencing the relevant Building Works
	The detailed plans are to be in accordance with the Herston Quarter PDA Development Scheme, the relevant approved concept plans and are to be accompanied by a Heritage Impact Statement as specified in Condition 55.		
	 The plans are to address the following design parameters: i. Elevations are to provide activation and overlooking to the Fourth Avenue frontage through a range of design features, including glazing, landscape treatment and 		

	 outdoor dining areas; ii. Shop or Food or Drink Outlet tenancies are to be less than 250m² per tenancy; iii. The design and demolition (if required) must consider heritage nature of the building in accordance with the relevant Conservation Management Plan; iv. The main entry into the building from Fourth Avenue will be emphasised through architectural and public realm treatment; v. Details of the proposed materials, colours treatments and finishes to all facades where new treatments are proposed; vi. Details of proposed sun shading devices; vii. The location and detailing of all services required to adequately services the site.
an to cea	e plans are to be accompanied by a 'Hold Points d Heritage Inspection Schedule'. The schedule is outline 'Hold Points', at which point relevant works ase to enable inspection of the works by a suitably alified independent reviewer determined by MEDQ.
pro up inc Sc rep	e applicant or their nominated representative must ovide at least 5 business days' notice of an coming inspection to the Heritage Architect and the dependent reviewer as outlined in the approved hedule. The applicant or their nominated presentative will re-confirm the inspection at least hours prior.
bo wri ap to to	llowing each inspection, within 2 business days th parties must agree the matters discussed in iting. This may include a requirement for the plicant to provide updated detailed documentation resolve issues identified during the inspection, prior works to the relevant heritage place continuing, to submitted under part b) of this condition.
b)	Submit to the MEDQ for written approval updated detailed documentation as per the outcome of any Heritage Inspection undertaken in accordance with the Heritage Inspection and Hold Points Schedule approved under part a) of this condition.
c)	Construct the Works in accordance with the plans c) As indicated approved under part a) and b) of this condition.
d)	Submit to the MEDQ a written statement by a registered architect, confirming that the constructed Works are generally in accordance with the plans approved under part a) and b) of this condition.

54.	Fire Services Report – Edith Cavell Building	
	Submit to the MEDQ a Fire Services Report prepared by a suitably qualified building professional for the PDA significant heritage building identified as the Edith Cavell building. The Fire Services Report is to consider how compliance can be achieved while retaining heritage fabric in situ.	Prior to the commencement of Building Work
55.	Heritage Impact Statement	
	Submit to the MEDQ a Heritage Impact Statement (HIS) for all building work and Public Realm work proposed and adjacent to the PDA significant heritage building identified as Edith Cavell. The HIS is to demonstrate how the proposed works have regard to the relevant Conservation Management Plan and be prepared by the approved Heritage Architect, as specified in Condition 38 of this approval.	Prior to the commencement of building works or Public Realm works to or adjacent the relevant PDA significant heritage building
Stage 3 -	- Lady Lamington	
	Change of Use – Rooming Accommodation (Student d Drink Outlet and Building Work on a State Heritage	
56.	Compliance Assessment – Detailed Demolition	
	Plans	a) Prior to commencing the
	 a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: vi. All floor levels; vii. Roof: viii. All elevations; ix. Detailed cross sections. 	relevant Building Works
	The plans are to be accompanied by a Heritage Impact Statement as specified in Condition 58.	
	The plans are to be accompanied by a 'Hold Points and Heritage Inspection Schedule'. The schedule is to outline 'Hold Points', at which point relevant works cease to enable inspection of the works by a suitably qualified independent reviewer determined by MEDQ.	
	The applicant or their nominated representative must provide at least 5 business days' notice of an upcoming inspection to the Heritage Architect and the independent reviewer as outlined in the approved Schedule. The applicant or their nominated representative will re-confirm the inspection at least 48 hours prior.	
	Following each inspection, within 2 business days both parties must agree the matters discussed in writing. This may include a requirement for the	

applicant to provide updated detailed documentation to resolve issues identified during the inspection, prior to works to the relevant heritage place continuing, to be submitted under part b) of this condition.
 b) Submit to the MEDQ for written approval updated detailed documentation as per the outcome of any Heritage Inspection undertaken in accordance with the Heritage Inspection and Hold Points Schedule approved under part a) of this condition. b) As indicated b) As indicated
 c) Construct the Works in accordance with the plans approved under part a) and b) of this condition. c) As indicated
 d) Submit to the MEDQ a written statement by a registered architect, confirming that the constructed Works are generally in accordance with the plans approved under part a) and b) of this condition. d) Prior to commencing use
Compliance Assessment – Detailed Architectural
Plans
 a) Submit to the MEDQ for Compliance Assessment, detailed architectural floor plans and elevations prepared by a registered architect for: i. All floor levels; ii. Roof: iii. All elevations; iv. Detailed cross sections; and v. Demolition plans.
The detailed plans are to be in accordance with the Herston Quarter PDA Development Scheme, the relevant approved concept plans and are to be accompanied by a Heritage Impact Statement as specified in Condition 59.
The plans are to address the following design parameters: i. Elevations are to provide activation and overlooking to the Fourth Avenue frontage through a range of design features, including glazing, landscape treatment and outdoor dining areas;
 ii. Shop or Food or Drink Outlet tenancies are to be less than 250m2 per tenancy; iii. The design and demolition (if required) must consider heritage nature of the building in accordance with the relevant Conservation Management Plan;
 iv. The main entry into the building from Fourth Avenue will be emphasised through architectural and public realm treatment; v. Details of the proposed materials, colours

58.	Fire Services Report – Lady Lamington Building Submit to the MEDQ a Fire Services Report prepared by a suitably qualified building professional for the PDA significant heritage building identified as the Lady Lamington building. The Fire Services Report is to consider how compliance can be achieved while	Prior to the commencement of Building Work
	 d) Submit to the MEDQ a written statement by a registered architect, confirming that the constructed Works are generally in accordance with the plans approved under part a) and b) of this condition. 	d) Prior to commencing use
	Schedule approved under part a) of this condition.c) Construct the Works in accordance with the plans approved under part a) and b) of this condition.	c) As indicated
	 b) Submit to the MEDQ for written approval updated detailed documentation as per the outcome of any Heritage Inspection undertaken in accordance with the Heritage Inspection and Hold Points 	b) As indicated
	Following each inspection, within 2 business days both parties must agree the matters discussed in writing. This may include a requirement for the applicant to provide updated detailed documentation to resolve issues identified during the inspection, prior to works to the relevant heritage place continuing, to be submitted under part b) of this condition.	
	The applicant or their nominated representative must provide at least 5 business days' notice of an upcoming inspection to the Heritage Architect and the independent reviewer as outlined in the approved Schedule. The applicant or their nominated representative will re-confirm the inspection at least 48 hours prior.	
	The plans are to be accompanied by a 'Hold Points and Heritage Inspection Schedule'. The schedule is to outline 'Hold Points', at which point relevant works cease to enable inspection of the works by a suitably qualified independent reviewer determined by MEDQ.	
	treatments and finishes to all facades where new treatments are proposed; vi. Details of proposed sun shading devices; vii. The location and detailing of all services required to adequately services the site.	

59.	Heritage Impact Statement	
	Submit to the MEDQ a Heritage Impact Statement (HIS) for all building work and Public Realm work proposed and adjacent to the PDA significant heritage building identified as Lady Lamington. The HIS is to demonstrate how the proposed works have regard to the relevant Conservation Management Plan and be prepared by the approved Heritage Architect, as specified in Condition 38 of this approval.	Prior to the commencement of building works or Public Realm works to or adjacent the relevant PDA significant heritage building
Material	– Lady Norman Change of Use – Food and Drink Outlet, Shop, Health ogy Industry, Office, Indoor Sport and Recreation, Sho	
60.	Compliance Assessment – Detailed Demolition	
	Plans	
	 a) Submit to the MEDQ for Compliance Assessment, detailed demolitions plans and elevations prepared by a registered architect for: All floor levels; Roof: 	a) Prior to commencing the relevant Building Works
	iii. All elevations;iv. Detailed cross sections.	
	The plans are to be accompanied by a Heritage Impact Statement as specified in Condition 63.	
	The plans are to be accompanied by a 'Hold Points and Heritage Inspection Schedule'. The schedule is to outline 'Hold Points', at which point relevant works cease to enable inspection of the works by a suitably qualified independent reviewer determined by MEDQ.	
	The applicant or their nominated representative must provide at least 5 business days' notice of an upcoming inspection to the Heritage Architect and the independent reviewer as outlined in the approved Schedule. The applicant or their nominated representative will re-confirm the inspection at least 48 hours prior.	
	Following each inspection, within 2 business days both parties must agree the matters discussed in writing. This may include a requirement for the applicant to provide updated detailed documentation to resolve issues identified during the inspection, prior to works to the relevant heritage place continuing, to be submitted under part b) of this condition.	
	b) Submit to the MEDQ for written approval updated detailed documentation as per the outcome of any Heritage Inspection undertaken in accordance	b) As indicated

	with the Heritage Inspection and Hold Points Schedule approved under part a) of this condition.
	 c) Construct the Works in accordance with the plans c) As indicated approved under part a) of this condition.
	 d) Submit to the MEDQ a written statement by a registered architect, confirming that the constructed Works are generally in accordance with the plans approved under part a) of this condition. d) Prior to commencing use
61.	Compliance Assessment – Detailed Architectural Plans
	 a) Submit to the MEDQ for Compliance Assessment, detailed architectural floor plans and elevations prepared by a registered architect for: i. All floor levels; ii. Roof: iii. All elevations; iv. Detailed cross sections; and v. Demolition plans.
	The detailed plans are to be in accordance with the relevant approved concept plans and are to be accompanied by a Heritage Impact Statement as specified in Condition 63.
	The plans are to address the following design parameters:
	 i. Elevations are to provide activation and overlooking to the Fourth Avenue frontage through a range of design features, including glazing, landscape treatment and outdoor dining areas; ii. Shop or Food or Drink Outlet tenancies are to be less than 250m2 per tenancy; iii. The design and demolition (if required) must consider heritage nature of the building in accordance with the relevant
	Conservation Management Plan; iv. The main entry into the building from Fourth Avenue will be emphasised through architectural and public realm treatment; v. Details of the proposed materials, colours
	 treatments and finishes to all facades where new treatments are proposed; vi. Details of proposed sun shading devices; vii. The location and detailing of all services required to adequately services the site.
	 b) Submit to the MEDQ for written approval updated detailed documentation as per the outcome of any Heritage Inspection undertaken in accordance

	with the Heritage Inspection and Hold Points Schedule approved under part a) of this condition.	
	c) Construct the Works in accordance with the plans approved under part a) and b) of this condition.	c) As indicated
	 d) Submit to the MEDQ a written statement by a registered architect, confirming that the constructed Works are generally in accordance with the plans approved under part a) and b) of this condition. 	d) Prior to commencing use
62.	Fire Services Report – Lady Norman Building	
	Submit to the MEDQ a Fire Services Report prepared by a suitably qualified building professional for the PDA significant heritage building identified as the Lady Norman building. The Fire Services Report is to consider how compliance can be achieved while retaining heritage fabric in situ.	Prior to the commencement of Building Work
63.	Heritage Impact Statement	
	Submit to the MEDQ a Heritage Impact Statement (HIS) for all building work and Public Realm work proposed and adjacent to the PDA significant heritage building identified as Lady Norman. The HIS is to demonstrate how the proposed works have regard to the relevant Conservation Management Plan and be prepared by the approved Heritage Architect, as specified in Condition 38 of this approval.	Prior to the commencement of building works or Public Realm works to or adjacent the relevant PDA significant heritage building

STANDARD ADVICE

Please note that in order to lawfully undertake development, it may be necessary to obtain approvals other than this PDA development approval. For advice on other approvals that may be necessary in relation to your proposal, it is recommended that you seek professional advice.

** End of Package **