

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL



Approval no: DEV2019/1074

Date: 30 October 2020



Acoustic Assessment Report

Carseldine Urban Village – Stage 1

532 Beams Road, Carseldine

Economic Development Queensland

17BRA0109 R02_2 - Stage 1





About TTM

For 30 years, we've been at the centre of the Australian development and infrastructure industry. Our unique combination of acoustics, data, traffic and waste services is fundamental to the success of any architectural or development project.

We have over 50 staff, with an unrivalled depth of experience. Our industry knowledge, technical expertise and commercial insight allow us to deliver an exceptional and reliable service.

T: (07) 3327 9500 F: (07) 3327 9501

E: ttmbris@ttmgroup.com.au







ACOUSTICS

DATA

PLANS AND DOCUMENTS referred to in the PDA **DEVELOPMENT APPROVAL**



Approval no: DEV2019/1074

Date:

30 October 2020

Revision Record

No.	Author	Reviewed/Approved	Description	Date
А	S Yorke		Internal draft	29/07/2019
0	S Yorke	J Fox	Client issue	29/07/2019
1	S Yorke		Client issue	18/03/2020
2	S Yorke		Client issue	31/03/2020



Contents

1	Execut	ve Summary		
2	Introd	duction	6	
	2.1	Background	6	
	2.2	References	6	
	2.3	Scope	6	
3	Site De	Description	7	
	3.1	Site Location	7	
	3.2	Current Site Conditions	7	
4	The Pr	roposed Development	8	
	4.1	Development Description	8	
	4.2	Future Busway	9	
5	Measu	urements	10	
	5.1	Equipment	10	
	5.2	Unattended Noise Monitoring	10	
	5.3	Results of Measurements	11	
		5.3.1 Road Traffic Noise Levels	11	
		5.3.2 Rail Noise Measurements	11	
6	Noise	· Criteria	13	
	6.1	Road Traffic Noise	13	
		6.1.1 Queensland Development Code MP4.4 – Road Traffic Noise	13	
	6.2	Rail Noise	13	
		6.2.1 Fitzgibbon Interim Land Use Plan	13	
		6.2.2 State Development Assessment Provisions (SDAP)	14	
		6.2.3 Queensland Development Code MP4.4 - Rail	15	
7	Analys	rsis – Road Traffic Noise	16	
	7.1	Traffic Volumes	16	
	7.2	Noise Model	16	
		7.2.1 Noise Modelling Parameters	16	
		7.2.2 Noise Model Verification	17	
	7.3	Predicted Noise Levels	17	



8	Rail Nois	e Assessment	20
	8.1	Rail Volumes	20
	8.2	Noise Model	20
		8.2.1 Noise Modelling Parameters	20
		8.2.2 Noise Model Verification	21
	8.3	Predicted Noise Levels - L _{Amax}	21
	8.4	Predicted Noise Levels – L _{Aeq (24hr)}	23
9	Recomm	nendations	24
	9.1	Built Form Treatments	24
		9.1.1 Road Traffic and Rail Noise	24
	9.2	Further Assessment	26
10	Conclusi	on	27
App	endix A	Development Plans	28
•	endix B	Unattended Noise Monitoring Graphs	
		SoundPLAN Noise Modelling	
	endix C	-	
App	endix D	QDC MP4.4 Schedules 1 and 2	42
Tal	ole Ind	ex	
Tabl	e 1: Mea	sured Road Traffic Noise Levels	. 11
Tabl	e 2: Mea	sured Rail Noise Levels (Highest 15)	. 12
Tabl	e 3: Road	Traffic Noise Category Levels – QDC MP4.4 (Schedule 3)	. 13
Tabl	e 4: SDAF	Noise Criteria - Rail Noise	. 14
Tabl	e 5: Rail í	Noise Category Levels – QDC MP4.4 (Schedule 3)	. 15
Tabl	e 6: Traff	ic Volumes used in the Noise Model	. 16
Tabl	e 7: Roac	Traffic Noise Modelling Parameters	. 16
Tabl	e 8: Com	parison of Measured and Predicted Road Traffic Noise Levels	. 17
Tabl	e 9: Rail 1	Noise Modelling Parameters	. 20
Tabl	e 10: Ver	ification of the Rail Noise Model	. 21
Tabl	e 11: QD	C Noise Category Treatments - Combined Road Traffic and Rail Noise	. 24
Tabl	e 12: QD	C Rail Noise Categories and Associated Sound Reduction Requirements (QDC MP4.4 - Schedu	ıle
1)			. 25



Figure Index

Figure 1: Site Locality	7
Figure 2: Site Plan	
Figure 3: Unattended Noise Monitoring Locations	10
Figure 4: Predicted Road Traffic Noise Levels – Ground Level	18
Figure 5: Predicted Road Traffic Noise Levels – First Floor	18
Figure 6: Predicted L _{Amax} Rail Noise Levels – Ground Floor	22
Figure 7: Predicted L _{Amax} Rail Noise Levels – First Floor	22



1 Executive Summary

TTM was engaged by Economic Development Queensland to undertake a noise assessment of Stage 1 of the proposed Carseldine Urban Village development located at 532 Beams Road, Carseldine. The assessment was based upon relevant planning scheme and transport noise development codes.

Unattended noise monitoring was conducted to determine the current road traffic and rail noise levels at the development location. Noise modelling of road traffic noise from Beams Road and rail noise was conducted. Some lots are noise affected by road traffic and rail noise and future dwellings will require acoustic treatment.

A revision to the location of the rail acoustic barrier detailed in the masterplan assessment was included in this analysis. Future stage dwellings were also included in the noise modelling.

Compliance with the relevant planning scheme and State transport noise requirements is predicted based on the implementation of the recommendations outlined in this report.



6

2 Introduction

2.1 Background

TTM was engaged by Economic Development Queensland to undertake a noise assessment of Stage 1 of the proposed Carseldine Urban Village development located at 532 Beams Road, Carseldine. This report will form part of the development application for consideration by Economic Development Queensland (EDQ) and relevant State authorities.

This report is a revision to the previous Stage 1 acoustic report. A revision to the location of the rail acoustic barrier detailed in the masterplan assessment was included in this analysis. Future stage dwellings were also included in the noise modelling.

2.2 References

This report is based on the following:

- Fitzgibbon Urban Development Area Development Scheme.
- Urban Land Development Authority, Fitzgibbon Interim Land Use Plan, July 2008, Version 1.
- State Development Assessment Provisions (SDAP) Version 2.5.
- Queensland Development Code (QDC) MP4.4 *Buildings in a Transport Noise Corridor* (August 2015).
- Development plans shown in Appendix A.
- Site inspection, noise measurements, analysis and calculations conducted by TTM.

2.3 Scope

The assessment includes the following:

- Description of the site.
- Measurement of existing road traffic, rail and ambient noise levels.
- Statement of assessment criteria relating to road traffic and rail noise impacts.
- Prediction of future road traffic and rail noise onto the development.
- Analysis of measured and predicted noise levels.
- Details of noise control recommendations to be incorporated to achieve predicted compliance.

Reference: 17BRA0109 R02_2 - Stage 1



3 Site Description

3.1 Site Location

The site is described by the following:

- Lot 322 SP172124
- 532 Beams Road, Carseldine

The site locality is shown in Figure 1.

Figure 1: Site Locality



3.2 Current Site Conditions

The site is bound by Beams Road to the north, Dorville Road to the west, bushland to the south and a rail line to the east. The current acoustic environment at the site is primarily comprised of noise from road traffic on Beams Road and rail noise from the rail line.




4 The Proposed Development

4.1 Development Description

The Stage 1 proposal is to develop the site into residential townhouses, a designated lot for future retirement living (Lot 3) and associated internal roads. A possible future busway is designated through part of the site. A site plan of the lot subdivision is presented in Figure 2. Further samples of the development plans are shown in Appendix A.

Figure 2: Site Plan





4.2 Future Busway

A possible future busway has been identified as shown in Figure 2. It is currently unknown whether the future busway will be located in this location or whether the busway will be located on Beams Road in conjunction with a future proposed overpass. It is recommended that the assessment of potential future busway noise is undertaken as part of the development assessment of future nearby built form of a sensitive use when busway details are known. Hence no further assessment of the busway was undertaken for this assessment.



5 Measurements

5.1 Equipment

The following equipment was used to measure existing noise levels:

- ARL EL 315 Environmental noise logger (SN#15-302-489) Road traffic noise
- Norsonic Nor140 noise logger (#1406504) Rail noise
- Norsonic Nor131 Sound Level Meter (SN#1313158)
- RION Sound Calibrator type NC73 (SN# TTMNC73-01)

All equipment was calibrated by a National Association of Testing Authorities (NATA) accredited laboratory. The equipment was field calibrated before and after the measurement session. No significant drift from the reference signal was recorded.

5.2 Unattended Noise Monitoring

Unattended noise monitoring was conducted to establish the existing road traffic and rail noise levels between Tuesday 11th July, 2017 to Tuesday 18th July, 2017. The noise monitoring locations are shown in Figure 3. The road traffic noise monitor was placed approximately 17 metres from the edge of Beams Road. The rail noise monitor was located a distance of approximately 17 meters from the centre of the nearest rail line. The monitoring locations were chosen to best represent the relevant noise environment with consideration given to both access and security requirements.

Figure 3: Unattended Noise Monitoring Locations





The microphones were in a free-field location and 1.5m above ground level. The road traffic noise monitor was set to measure statistical noise levels in 'A'-weighting, 'Fast' response, over 15 minute intervals. The rail noise monitor was set to a 5 minute interval.

The rail noise logger was also set up to record audio when a trigger noise level of 75dB(A) or greater was measured. Audio was recorded for 10 - 15 seconds following each trigger event. The audio recordings were used to confirm that the L_{Amax} levels were from a train pass-by event.

Attended noise measurements were undertaken at each noise logger location on Tuesday 11th July 2017 and were used to verify the unattended noise logging data.

Road traffic noise levels were measured in accordance with Australian Standard *AS2702:1984 Acoustics* – *Methods for the measurement of road traffic noise* (AS2702). Rail noise measurements were conducted in accordance with Australian Standard *AS2377:2002 Acoustics* – *Methods for the Measurement of Railbound Vehicle Noise*.

Weather during the monitoring period was generally fine with rainfall on 16th July and temperatures ranging between 9-20°C (source: Bureau of Meteorology). Data affected by rainfall was excluded from the results.

5.3 Results of Measurements

5.3.1 Road Traffic Noise Levels

Table 1 presents the measured road traffic noise levels at the unattended noise monitoring location on Beams Road. Graphical presentation of the measured noise levels is presented in Appendix B.

Table 1: Measured Road Traffic Noise Levels

Location	Road Traffic Noise Descriptor	Time Period	Measured Level dB(A)
	L _{A10,18hr}	6am to midnight	64
	Noisiest day-time L _{Aeq,1 hour}	6pm to 7pm	64
Beams Road	Noisiest night-time L _{Aeq,1 hour}	11pm to 12am	60
Beallis Road	L _{Aeq,24} hour	Midnight to midnight	60
	L ₉₀ , 8 hour	10pm to 6am	41
	L90, 18 hour	6am to midnight	52

5.3.2 Rail Noise Measurements

After analysing the noise logging data and audio recordings, 54 valid train pass-by measurements were captured during a 24 hour period. Measurement data was discarded from the analysis where audio recordings identified inclusion of train horns and other extraneous noise sources. Rail timetables provided by Queensland Rail (QR) indicate approximately 250 trains per day passed the site during the measurement period including approximately 15 freight trains. The Queensland Rail *Code of Practice – Railway Noise*



Management defines the single event maximum (SEM) sound pressure level as the arithmetic average of the highest 15 single maximum noise level events over a 24-hour period.

Table 2 presents the highest 15 free-field L_{Amax} and associated L_{Aeq} rail noise levels during the measured 24-hour period. The calculated $L_{Aeq,24hr}$ is based on these measured L_{Aeq} results (logarithmic average) and number of trains over a 24 hour period, and is therefore a conservative approach. This approach is required as the proximity of road traffic, results in a significant portion of measured road traffic noise and it is not practical to identify and remove all non-train event measurement data over the 24 hour period.

Table 2: Measured Rail Noise Levels (Highest 15)

Train Type	Maximum Noise Level L _{MAX} dB(A)	Noise Level L _{eq} dB(A)	Warning Device
Passenger	89.4	67.0	No
Passenger	89.3	71.2	No
Passenger	88.3	66.9	No
Passenger	87.8	64.7	No
Passenger	87.5	66.3	No
Passenger	87.2	68.7	No
Passenger	85.8	64.5	No
Passenger	84.8	65.0	No
Passenger	83.9	63.2	No
Passenger	83.8	62.7	No
Freight	83.3	63.0	No
Passenger 83.3		63.5	No
Passenger	82.7	66.5	No
Passenger	82.2	63.3	No
Passenger 82.0		64.2	No
Single event maximum noise level (SEM) dB(A)	85.4		
Leq,24hour dB(A)		58.6	



6 Noise Criteria

Assessment criteria for road traffic noise and rail noise are outlined in the following sections.

6.1 Road Traffic Noise

The site is located in the local government transport noise corridor of Beams Road. To ensure a satisfactory level of acoustic amenity is provided for the development, an assessment has been conducted to achieve compliance with the requirements of QDC MP4.4.

6.1.1 Queensland Development Code MP4.4 – Road Traffic Noise

The Queensland Development Code Part MP 4.4 - 'Buildings in a Transport Noise Corridor' August 2015 (QDC) specifies Noise Categories to ensure that habitable rooms of residential buildings are adequately protected from transport noise over a 10-year planning horizon.

The Noise Categories list the minimum acoustic R_W ratings for each building component to comply with the indoor sound levels as outlined in Australian Standard AS2107¹. Details regarding the noise categories and acceptable forms of construction can be found within Schedule 1 and 2 of the QDC document. The triggers for each noise category are summarised in Table 3.

Table 3: Road Traffic Noise Category Levels – QDC MP4.4 (Schedule 3)

Noise Category	Level of Transport Noise* L _{A10,18Hour} for State-Controlled Roads and Designated Local Government Roads	
Category 4	≥ 73 dB(A)	
Category 3	68 – 72 dB(A)	
Category 2	63 – 67 dB(A)	
Category 1	58 – 62 dB(A)	
Category 0	≤ 57 dB(A)	

^{*}Measured at 1 metre from the façade of the proposed or existing building.

6.2 Rail Noise

The assessment of rail noise is considered under the following criteria.

6.2.1 Fitzgibbon Interim Land Use Plan

The Fitzgibbon Interim Land Use Plan specifies acoustic amenity criteria for rail noise in Part 6 section 2(a) as follows:

To the extent determined appropriate by the ULDA, a noise-sensitive use i.e. detached and multi-unit dwellings, child care facility and community facility, within 100m of the north south rail line must meet indoor

13

¹ AS NZS 2107:2016. Acoustics - Recommended design sound levels and reverberation times for building interiors



design level noise criteria to achieve average maximum sound level (10 pm - 6 am) not greater than 50dB(A). The noise criteria should be achieved within bedrooms, living areas and noise-sensitive areas of non residential uses.

We would expect the above stated internal sound level criteria of 50dB(A) L_{max} to take precedence over the SDAP internal criteria.

6.2.2 State Development Assessment Provisions (SDAP)

The noise criteria for land affected by emissions from rail activities are contained in State Code 2 of the State Development Assessment Provisions (SDAP). The criteria are reproduced in Table 4.

Table 4: SDAP Noise Criteria - Rail Noise

Performance Outcomes	Acceptable Outcomes
PO24 Development involving: 1. an accommodation activity; or 2. land for a future accommodation activity minimises noise intrusion from a railway or type 2 multi-modal corridor in habitable rooms.	AO24.1 A noise barrier or earth mound is provided which is designed, sited and constructed: 1. to meet the following external noise criteria at all facades of the building envelope: a. ≤65 dB(A) Leq (24 hour) façade corrected b. ≤87 dB(A) (single event maximum sound pressure level) façade corrected 2. in accordance with the Civil Engineering Technical Requirement – CIVIL-SR-014 Design of noise barriers adjacent to railways, Queensland Rail, 2011. Habitable rooms of relevant residential buildings located within a transport noise corridor must comply with the Queensland Development Code MP4.4 Buildings in a transport noise corridor, Queensland Government, 2015. Transport noise corridors are mapped on the State Planning Policy Interactive Mapping System.
PO25 Development involving an accommodation activity minimises noise intrusion from a railway or type 2 multimodal corridor in outdoor spaces for passive recreation	AO25.1 A noise barrier or earth mound is provided which is designed, sited and constructed: 1. to meet the following external noise criteria in outdoor spaces for passive recreation: a. ≤62 dB(A) Leq (24 hour) free field b. ≤84 dB(A) (single event maximum sound pressure level) free field 2. in accordance with the Civil Engineering Technical Requirement – CIVIL-SR-014 Design of noise barriers adjacent to railways, Queensland Rail, 2011. OR AO26.2 Each dwelling has access to an outdoor space for passive recreation which is shielded from a railway or type 2 multi-modal corridor by a building, a solid gap-free fence, or other solid gap-free structure. AND



Performance Outcomes	Acceptable Outcomes		
	AO26.3 Each dwelling with a balcony directly exposed to noise from a railway or type 2 multi-modal corridor has a continuous solid gap-free balustrade (other than gaps required for drainage purposes to comply with the Building Code of Australia).		

6.2.3 Queensland Development Code MP4.4 - Rail

The *Queensland Development Code Part MP 4.4 - 'Buildings in a Transport Noise Corridor* August 2015 (QDC) specifies Noise Categories to ensure that habitable rooms of residential buildings are adequately protected from transport noise over a 10-year planning horizon.

The Noise Categories list the minimum acoustic R_W ratings for each building component to comply with the indoor sound criteria. Details regarding the noise categories and acceptable forms of construction can be found within Schedule 1 and 2 of the QDC document. The triggers for each noise category are summarised in Table 5.

Table 5: Rail Noise Category Levels – QDC MP4.4 (Schedule 3)

Noise Category	Single event maximum noise* (L _{Amax}) for Railway Land		
Category 4	≥ 85		
Category 3	80 – 84		
Category 2	75 – 79		
Category 1	70 – 74		
Category 0	≤ 69		

^{*} Measured at 1metre from the façade of the proposed or existing building.



7 Analysis – Road Traffic Noise

An assessment of road traffic noise onto the proposed development was conducted to determine the acoustic treatment requirements for predicted compliance with the relevant criteria.

7.1 Traffic Volumes

Existing traffic volumes and growth rates were obtained from Cardno traffic engineers. The traffic volumes used in the noise model are presented in Table 6.

Table 6: Traffic Volumes used in the Noise Model

Road	Traffic Volumes (AADT)			Heavy	Growth Rate
Road	2016	2017	2031	Vehicles (%)	(%)
Beams Road	13,500	13,770	17,261	5.0%	2.0%

The 18 hour traffic volumes used in the noise model are taken to be 95% of the AADT (Annual average daily traffic).

7.2 Noise Model

7.2.1 Noise Modelling Parameters

Road traffic noise predictions were conducted using 'SoundPLAN v8.1', a CoRTN based modelling program. The basis of the 'SoundPLAN' model is presented in Table 7.

Table 7: Road Traffic Noise Modelling Parameters

Description	Value
Noise modelling standard	Cortn (UK)
Grid spacing (noise maps)	2m
Road surface type	Impervious (+0 dB(A))
Ground contours	Natural ground level data from Land Partners
Beams Road Speed limit	60 km/h
Noise source height above grade	0.5m
Floor heights	2.8m
Receiver heights	1.5m above floor level
Façade correction	+2.5 dB(A)



7.2.2 Noise Model Verification

To verify the road traffic noise model, the $L_{A10, 18hour}$ noise levels were modelled and compared to the measured levels as presented in Table 8. As the noise monitor was in a free-field location, the predicted noise level is also shown as free-field.

Table 8: Comparison of Measured and Predicted Road Traffic Noise Levels

Location	Measured L _{A10} , 18 hour	Predicted L _{A10, 18 hour}	Required Correction
Beams Road	64	64	0

The modelled level is within the allowable tolerance of 2 dB(A) of the measured level, therefore no correction is required to the model.

7.3 Predicted Noise Levels

Modelling was conducted to determine road traffic noise levels at the development in the 10 year planning horizon from a forecast completion date of 2021. The predicted future noise levels take into account the 2031 traffic volumes.

Predicted road traffic noise contour maps illustrated as QDC noise categories at the ground floor and first floor are presented in Figure 4 and Figure 5 respectively.

Reference: 17BRA0109 R02_2 - Stage 1







Figure 4: Predicted Road Traffic Noise Levels – Ground Level







Based on the noise modelling results, the development is predicted to be impacted by road traffic noise at QDC noise category 0-3 for ground and first floor levels. SoundPLAN receiver point results are shown in Appendix C.

Facade acoustic treatments will be recommended in order to comply with QDC MP4.4 internal criteria for habitable rooms.

QDC noise categories and associated acoustic treatment requirements for each façade and floor level are detailed in Section 9.



8 Rail Noise Assessment

An assessment of rail noise onto the proposed development was conducted to determine the acoustic treatment requirements for predicted compliance with the relevant criteria.

8.1 Rail Volumes

Rail timetables provided by Queensland Rail (QR) indicate approximately 250 trains per day pass the site (including approximately 15 freight trains). We were advised that all services are subject to alteration, addition and cancellation which may vary the number of actual trains passing daily.

8.2 Noise Model

8.2.1 Noise Modelling Parameters

Rail noise predictions were conducted using 'SoundPLAN' v8.1. The basis of the 'SoundPLAN' model is as follows:

Table 9: Rail Noise Modelling Parameters

Description	Value
Prediction methodology	Nordic Rail Prediction (Kilde Rep. 130)
Grid spacing (noise maps)	2m
Train Frequency (daily) passenger / freight	235 / 15 (approximate)
Train speed	Passenger: 60km/h (estimated) Freight: 80km/h (standard reference speed)
Train length	Passenger: 144m Freight: 1000m Diesel engine: 36m (dual locomotive)
Rail track head height	0.6m above ground
Rail noise source height	0.5m (wheels) and 4.0m (diesel engine) above track head height (includes Kilde +0.5m addition)
L1 train type corrections	Passenger electric: -4.6dB Diesel engine: +4.4dB Freight wagons: -6.5dB
L2 correction (dLtype engine)	-100dB (removes contribution)
Rail noise measurement distance	17m from the nearest line
Ground contours	Elevation data from Land Partners
Floor heights	2.8m
Residential receiver height	1.5m above each floor level
Façade correction	+2.5 dB(A)



8.2.2 Noise Model Verification

The measured single event maximum sound pressure level LAMAX noise level at the monitoring location was verified in the noise model prior to modelling noise impacts at the development. Table 10 presents the results of the rail noise model verification.

Table 10: Verification of the Rail Noise Model

Descriptor	Measured dB(A)	Predicted dB(A)	Required Correction
L _{Amax}	85.4	89.2	-1.8
L _{Aeq,24hr}	58.6	60.5	0

A correction was applied to the L_{Amax} rail noise source to bring the model within +2dB of the measured level. The over prediction is considered to possibly be caused by freight locomotives with a lower engine noise emission on site (ie. notch setting).

8.3 Predicted Noise Levels - L_{Amax}

Predicted rail noise contour maps illustrated as QDC noise categories for ground floor and first floor are presented in the following figures.

An acoustic barrier for rail noise was recommended as part of the previous masterplan noise assessment. A revision to this barrier is included in this assessment. The barrier is located along the length of the eastern boundary of the site (shown in the below figures) with a height of 3.6m above natural ground level. A stepped-in portion of the barrier at the northern end of the eastern boundary is 1.8m high above site design levels. The barrier returns along Beams Road frontage at 1.8m high. Details of the barrier are provided in Appendix A. Dwellings for future stages were also included in the noise model as per draft masterplan in Appendix A.



Figure 6: Predicted L_{Amax} Rail Noise Levels – Ground Floor



Figure 7: Predicted L_{Amax} Rail Noise Levels – First Floor





Based on the noise modelling, the development is predicted to be impacted by rail noise at a level of QDC noise category 0-1 for some ground and first floor levels. Receiver point modelling results are presented in Appendix C.

 L_{Amax} rail noise levels are predicted to comply with the SDAP external façade (PO25.1) and outdoor passive recreation (PO26.1) criteria for all lots.

Facade acoustic treatments will be recommended in order to comply with QDC MP4.4 internal criteria for habitable rooms.

QDC noise categories and associated acoustic treatment requirements for noise affected façades and floor levels are detailed in Section 9.

8.4 Predicted Noise Levels – L_{Aeq (24hr)}

The predicted L_{Aeq (24 hour)} rail noise level at the nearest facade to the rail line is less than 40dB(A) (free-field) based on 250 trains per day. This complies with the SDAP criteria for both external façade and private open space. As compliance is achieved at the nearest facade to the rail line, compliance is also predicted at all other facades.



9 Recommendations

The recommended acoustic treatments are presented in the sections below to achieve predicted compliance with the relevant assessment criteria.

9.1 Built Form Treatments

9.1.1 Road Traffic and Rail Noise

This section summarises the combined building form treatment required for habitable rooms for road traffic and rail noise to achieve compliance with the Queensland Development Code (QDC) MP4.4. For the purposes of the development application, the QDC provides a conservative design approach and is applied for this assessment.

The QDC MP4.4 requires that habitable rooms in residential buildings located in a transport noise corridor are adequately protected from transport noise to safeguard occupant's health and amenity.

In order to achieve the performance requirements of the QDC MP4.4, the external envelope of habitable rooms must comply with the minimum R_W for each building component specified in Schedule 1 to achieve a minimum transport noise reduction level for the relevant noise category by either one of the following:

a. Using materials specified in Schedule 2 of the QDC MP4.4;

OR

b. Using materials with manufacturer's specifications that achieve the minimum R_W value for the relevant building component and applicable noise category.

For application of Point (b), possible alternative constructions can be determined by the glazier (for glazing) and construction manuals such as 'The Red Book' by CSR (for walls and roof/ceiling).

Table 11 presents the acoustic treatment requirements for habitable rooms in accordance with the QDC MP4.4 policy. The treatments are based on the predicted impacts from road traffic and rail noise.

Table 11: QDC Noise Category Treatments - Combined Road Traffic and Rail Noise

Townhouses	Floor Level	Road Traffic and Rail Noise QDC Noise Categories for Habitable Rooms By Façade and Floor			
		E	N	S	W
Terrace 1002 -	Ground	1	2* (1002 only)	0	1
1006	First Floor	1	3 (1002 only)	0	2



Townhouses	Floor Level	Road Traffic and Rail Noise QDC Noise Categories for Habitable Rooms By Façade and Floor			
		E	N	S	W
Terrace 1007 -	Ground	0	0	1	0
1015	First Floor	1 (1015 only)	1	1	1 (1007 only)
Terrace 1016 -	Ground	1	2 (1020 only)	0	1
1020	First Floor	1	2 (1020 only)	1 (1016 only)	1
Terrace 1021 -	Ground	0	1	0	0
1029	First Floor	1 (1021 only)	1	0	0
Terrace 1030 -	Ground	0	0	0	0
1037	First Floor	0	0	0	0
Terrace 1038 -	Ground	0	0	0	0
1046	First Floor	0	0	0	0
Terrace 1047 -	Ground	1	0	0	0
1054	First Floor	1	0	0	0

^{*}If Lot 1001 is constructed prior to Lot 1002 occupation, then the northern façade treatments for Lot 1002 are not required (based on Lot 1001 min. 2 storey and attached construction to Lot 1002)

Details regarding noise categories and associated sound reduction (R_w) requirements for habitable rooms can be found within Schedule 1 of the QDC MP4.4. QDC Schedule 1 is reproduced in Table 12.

Table 12: QDC Rail Noise Categories and Associated Sound Reduction Requirements (QDC MP4.4 - Schedule 1)

QDC Noise	Required Sound Reduction Rating (R _w) for Habitable Rooms				
Category	Glazing > 1.8m ²	Glazing ≤ 1.8m ²	Roof and Ceiling		
Category 4	Rw 43	Rw 43	Rw 52	Rw 45	
Category 3	Rw 38	Rw 35	Rw 47	Rw 41	
Category 2	Rw 35	Rw 32	Rw 41	Rw 38	
Category 1	Rw 27	Rw 24	Rw 35	Rw 35	
Category 0	None	None	None	None	

Details regarding sound reduction ratings (Rw) and acceptable forms of construction can be found within QDC MP 4.4 Schedule 2. QDC Schedule 1 and 2 are provided in Appendix D of this report.



9.2 Further Assessment

It is recommended that further acoustic assessment is conducted for Lot 3 when building plans are available to determine any noise attenuation measures that may be required.



10 Conclusion


TTM was engaged by Economic Development Queensland to undertake a revised noise assessment of Stage 1 of the proposed Carseldine Urban Village development located at 532 Beams Road, Carseldine. The assessment was based upon relevant planning scheme and transport noise development codes.

Compliance with the relevant planning scheme and State transport noise requirements is predicted based on the implementation of the recommendations outlined in this report.



Appendix A Development Plans

ttm



29




Draft layout plan of other Stages – used for dwelling layout in noise model





Revised Rail Noise Acoustic Barrier – used in the noise model





Appendix B Unattended Noise Monitoring Graphs



Road Traffic Noise Monitor











17BRA0109





Appendix C SoundPLAN Noise Modelling



532 Beams Rd, Carseldine Urban Village Assessed receiver levels RTN - Verification 2017

Receiver	FI	L10(18h) Free Field dB(A)	
Logger Receiver - Road	GF	64.0	
Logger Receiver - Road	GF	64.0	
TTM Cons	sulting (Qld) Pty Ltd Level	1 - 129 Logan Rd Woolloongabba, QLD 4102	1

SoundPLAN 7.4



490 Beams Rd, Fitzgibbon Rail - Verification

Lot	LAMax	Leq24hr	
Number	Free Field dB(A)	Free Field dB(A)	
Logger Receiver - Rail (85.4dB)	87.4	60.5	

TTM Consulting Pty Ltd Page



532 Beams Rd, Carseldine Urban Village Road Traffic Noise Assessment RTN - Prediction 2031 - Stage 1

Receiver	Direction	Floor	L10(18h)
			Facade Corrected
			dB(A)
Terrace 1000 - 1006	E	GF	57.4
	_	F 1	59.6
Terrace 1000 - 1006	N	GF	67.4
1		F1	69.3
Terrace 1000 - 1006	S	GF	45.0
1		F1	50.7
Terrace 1000 - 1006	W	GF	60.9
- 1007 1015	_	F1	63.0
Terrace 1007 - 1015	E	GF	55.9
T 4007 4045	N	F1	58.0
Terrace 1007 - 1015	N	GF	53.6
Terrace 1007 - 1015	S	F1 GF	56.3 43.6
Tellace 1007 - 1015	3	F 1	49.3
Terrace 1007 - 1015	w	GF	49.3 56.5
Tellace 1007 - 1015	**	F 1	58.6
Terrace 1016 - 1020	E	GF	59.7
	_	F1	61.8
Terrace 1016 - 1020	N	GF	65.4
1		F 1	67.3
Terrace 1016 - 1020	S	GF	44.9
1		F 1	50.6
Terrace 1016 - 1020	W	GF	55.4
		F1	57.9
Terrace 1021 - 1029	E	GF	53.1
		F 1	55.3
Terrace 1021 - 1029	N	GF	52.9
T 4004 4000		F1	55.0
Terrace 1021 - 1029	S	GF F1	42.0 47.7
Terrace 1021 - 1029	w	GF	47.7 54.0
Tellace 1021 - 1023	**	F1	56.1
Terrace 1030 - 1037	E	GF	44.7
. 5.1400 1000 1001	_	F1	48.7
Terrace 1030 - 1037	N	GF	49.9
		F1	52.9
Terrace 1030 - 1037	S	GF	39.8
		F1	45.6
Terrace 1030 - 1037	W	GF	51.4
		F1	53.6
Terrace 1038 - 1046	E	GF	48.5
<u> </u>		F 1	50.9
Terrace 1038 - 1046	N	GF	45.2

TTM Consulting Pty Ltd	1



532 Beams Rd, Carseldine Urban Village Road Traffic Noise Assessment RTN - Prediction 2031 - Stage 1

Receiver	Direction	Floor	L10(18h)
			Facade Corrected
			dB(A)
		F1	49.2
Terrace 1038 - 1046	S	GF	39.1
		F 1	44.9
Terrace 1038 - 1046	W	GF	49.4
		F 1	51.7
Terrace 1047 - 1054	E	GF	50.5
		F 1	52.8
Terrace 1047 - 1054	N	GF	48.2
		F 1	52.0
Terrace 1047 - 1054	S	GF	39.6
		F 1	45.5
Terrace 1047 - 1054	W	GF	45.1
		F 1	49.3

TTM Consulting Pty Ltd	2



532 Beams Rd, Carseldine Urban Village Assessed receiver levels Rail - Prediction with barrier - Stage 1 with alt barrier

Receiver	Dir	FI	Lmax	Leq,24hr	
Receiver	DII			•	
			Facade corrected	Facade corrected	
			dB(A)	dB(A)	
Terrace 1000 - 1006	E	GF	61.6	39.5	
		F1	67.5	44.5	
Terrace 1000 - 1006	N	GF	69.1	42.9	
		F 1	69.8	44.2	
Terrace 1000 - 1006	S	GF	67.1	40.4	
		F 1	68.6	43.2	
Terrace 1000 - 1006	W	GF	52.8	30.5	
		F1	57.2	34.8	
Terrace 1007 - 1015	Е	GF	68.4	44.5	
T 4007 4045		F1	71.4	46.8	
Terrace 1007 - 1015	N	GF	68.3	40.8	
T 4007 4045		F1	69.5	43.5	
Terrace 1007 - 1015	S	GF	69.9	40.9	
Terrace 1007 - 1015	w	F1 GF	70.7	42.7 30.3	
Terrace 1007 - 1015	VV	F1	51.2 55.5	30.3 34.7	
Terrace 1016 - 1020	E	GF	68.1	43.7	
Terrace 1016 - 1020		F1	71.7	46.4	
Terrace 1016 - 1020	N	GF	71.7	46.0	
Terrace 1016 - 1020	IN	F1	73.3	47.2	
Terrace 1016 - 1020	S	GF	69.3	41.5	
Terrace 1010 - 1020	3	F1	70.6	44.0	
Terrace 1016 - 1020	w	GF	61.7	39.2	
1011400 1010 - 1020		F1	66.9	43.2	
Terrace 1021 - 1029	Е	GF	68.5	44.6	
	_	F1	70.6	46.6	
Terrace 1021 - 1029	N	GF	70.2	40.2	
		F 1	70.8	42.0	
Terrace 1021 - 1029	S	GF	67.4	40.8	
		F1	68.8	43.2	
Terrace 1021 - 1029	W	GF	50.9	30.0	
		F1	55.3	34.3	
Terrace 1030 - 1037	E	GF	59.9	39.2	
		F1	66.2	44.1	
Terrace 1030 - 1037	N	GF	66.3	40.3	
		F1	67.6	42.7	
Terrace 1030 - 1037	S	GF	64.7	39.6	
		F1	66.1	42.3	
Terrace 1030 - 1037	W	GF	50.0	29.1	
		F1	54.2	33.4	
Terrace 1038 - 1046	E	GF	63.7	42.3	
		F1	67.3	44.8	
Terrace 1038 - 1046	N	GF	67.2	39.4	

TTM Consulting (Qld) Pty Ltd Level 8, 369 Ann Street, Brisbane QLD 4000



532 Beams Rd, Carseldine Urban Village Assessed receiver levels Rail - Prediction with barrier - Stage 1 with alt barrier

Receiver	Dir	FI	Lmax	Leq,24hr	
			Facade corrected	Facade corrected	
			dB(A)	dB(A)	
		F1	68.5	42.2	
Terrace 1038 - 1046	S	GF	66.1	42.8	
		F1	66.6	44.0	
Terrace 1038 - 1046	W	GF	48.9	29.1	
		F1	53.2	33.4	
Terrace 1047 - 1054	E	GF	72.4	44.3	
		F1	73.4	46.5	
Terrace 1047 - 1054	N	GF	67.3	41.1	
		F1	68.7	43.5	
Terrace 1047 - 1054	S	GF	65.6	39.8	
		F1	66.6	42.7	
Terrace 1047 - 1054	w	GF	59.2	38.5	
		F1	64.8	42.4	

TTM Consulting (Qld) Pty Ltd Level 8, 369 Ann Street, Brisbane QLD 4000	2



Appendix D QDC MP4.4 Schedules 1 and 2



Schedule 1

Noise category	Minimum transport noise reduction (dB (A)) required for habitable rooms	Component of building's external envelope	Minimum R _w required for each component
		Glazing	43
		External walls	52
Category 4	40	Roof	45
		Floors	51
		Entry doors	35
		Glazing greate (where total area of glazing	38 (where total area of glazing for a <i>habitable room</i> is greater than 1.8m²)
			35 (where total area of glazing for a <i>habitable room</i> is less than or equal to 1.8m²)
Category 3	35		47
		Roof	41
		Floors	45
		Entry doors	33

Version 1.1 Page 7 Publication Date: 17 August 2015

Noise category	Minimum transport noise reduction (dB (A)) required for habitable rooms	Component of building's external envelope	Minimum R⊮required for each component	
		Glazing	35 (where total area of glazing for a <i>habitable room</i> is greater than 1.8m²)	
			32 (where total area of glazing for a <i>habitable room</i> is less than or equal to 1.8m²)	
Category 2	30	External walls	41	
		Roof	38	
		Floors	45	
		Entry doors	33	
		Glazing than 1.8m²) 24	(where total area of glazing for a habitable room is greater	
			24 (where total area of glazing for a habitable room is less than	
Category 1	25	External walls	35	
		Roof	35	
		Entry Doors	28	
Category 0	No additional aco	No additional acoustic treatment required – standard building assessment provisions apply.		

Version 1.1 Page 8 Publication Date: 17 August 2015



Schedule 2

Component of building's external envelope	Minimum R _w	Acceptable forms of construction
	43	Double glazing consisting of two panes of minimum 5mm thick glass with at least 100mm air gap and full perimeter acoustically rated seals.
	38	Minimum 14.38mm thick laminated glass, with full perimeter acoustically rated seals; OR Double glazing consisting of one pane of minimum 5mm thick glass and one pane of minimum 6mm thick glass with at least 44mm air gap, and full perimeter acoustically rated seals
Glazing	35	Minimum 10.38mm thick laminated glass, with full perimeter acoustically rated seals.
	32	Minimum 6.38mm thick laminated glass with full perimeter acoustically rated seals.
-	27	Minimum 4mm thick glass with full perimeter acoustically rated seals
	24	Minimum 4mm thick glass with standard weather seals

Version 1.1 Page 9 Publication Date: 17 August 2015

Component of building's external envelope	Minimum R _w	Acceptable forms of construction
	52	Two leaves of clay brick masonry, at least 270mm in total, with subfloor vents fitted with noise attenuators.
External walls		Two leaves of clay brick masonry at least 110mm thick with: (i) cavity not less than 50mm between leaves; and (ii) 50mm thick mineral insulation or 50mm thick glass wool insulation with a density of 11kg/m³ or 50mm thick polyester insulation with a density of 20kg/m³ in the cavity. OR Two leaves of clay brick masonry at last 110mm thick with: (i) cavity not less than 50mm between leaves; and (ii) at least 13mm thick cement render on each face
	47	Single leaf of clay brick masonry at least 110mm thick with: (i) a row of at least 70mm x 35mm timber studs or 64mm steel studs at 600mm centres, spaced at least 20mm from the masonry wall; and (ii) Mineral insulation or glass wool insulation at least 50mm thick with a density of at least 11 kg/m³ positioned between studs; and (iii) One layer of plasterboard at least 13mm thick fixed to outside face of studs. OR Single leaf of minimum 150mm thick masonry of hollow, dense concrete blocks, with mortar joints laid to prevent moisture bridging.

Version 1.1 Page 10 Publication Date: 17 August 2015



Component of building's external envelope	Minimum R _w	Acceptable forms of construction
	41	Two leaves of clay brick masonry at least 110mm thick with cavity not less than 50mm between leaves OR Single leaf of clay brick masonry at last 110mm thick with: (i) a row of at least 70mm x 35mm timber studs or 64mm steel studs at 600mm centres, spaced at least 20mm from the masonry wall; and (ii) mineral insulation or glass wool insulation at least 50mm thick with a density of at least 11 kg/m³ positioned between studs; and (iii) One layer of plasterboard at least 10mm thick fixed to outside face of studs OR Single leaf of brick masonry at least 110mm thick with at least 13mm thick render on each face OR Concrete brickwork at least 110mm thick OR In-situ concrete at least 100mm thick OR Precast concrete at least 100mm thick and without joints.

Version 1.1 Page 11 Publication Date: 17 August 2015

Component of building's external envelope	Minimum R _w	Acceptable forms of construction
	35	Single leaf of clay brick masonry at least 110mm thick with: (i) a row of at least 70mm x 35mm timber studs or 64mm steel studs at 600mm centres, spaced at least 20mm from the masonry wall; and (ii) One layer of plasterboard at least 10mm thick fixed to outside face of studs OR Minimum 6mm thick fibre cement sheeting or weatherboards or plank cladding externally, minimum 90mm deep timber stud or 92mm metal stud, standard plasterboard at least 13mm thick internally.
Roof	45	Concrete or terracotta tile or sheet metal roof with sarking, acoustically rated plasterboard ceiling at least 13mm thick fixed to ceiling joists, cellulose fibre insulation at least 100mm thick with a density of at least 45kg/m² in the cavity. OR Concrete or terracotta tile or sheet metal roof with sarking, 2 layers of acoustically rated plasterboard at least 16mm thick fixed to ceiling joists, glass wool insulation at least 50mm thick with a density of at least 20kg/m³ in the cavity.
	41	Concrete or terracotta tile or metal sheet roof with sarking, plasterboard ceiling at least 10mm thick fixed to ceiling joists, glass wool insulation at least 50mm thick with a density of at least 11kg/m³ or polyester insulation at least 50mm thick with a density of at least 20kg/m³ in the cavity. OR Concrete suspended slab at least 100mm thick.
	38	Concrete or terracotta tile or metal sheet roof with sarking, plasterboard ceiling at least 10mm thick fixed to ceiling cavity, mineral insulation or glass wool insulation at least 50mm thick with a density of at least 11 kg/m³.

Version 1.1 Page 12 Publication Date: 17 August 2015



Component of building's external envelope	Minimum R _w	Acceptable forms of construction		
	35	Concrete or terracotta tile or metal sheet roof with sarking, plasterboard ceiling at least 10mm thick fixed to ceiling cavity.		
	51	Concrete slab at least 150mm thick.		
Floors	45	Concrete slab at least 100mm thick OR Tongued and grooved boards at least 19mm thick with: (i) timber joists not less than 175mm x 50mm; and (ii) mineral insulation or glass wool insulation at least 75mm thick with a density of at least 11kg/m³ positioned between joists and laid on plasterboard at least 10mm thick fixed to underside of joists; and (iii) mineral insulation or glass wool insulation at least 25mm thick with a density of at least 11kg/m³ laid over entire floor, including tops of joists before flooring is laid; and (iv) secured to battens at least 75mm x 50mm; and (v) the assembled flooring laid over the joists, but not fixed to them, with battens lying between the joists.		
	35	Solid core timber not less than 45mm thick, fixed so as to overlap the frame or rebate of the frame by no less than 10mm, with full perimeter acoustically rated seals.		
Entry Doors	33	Fixed so as to overlap the frame or rebate of the frame by not less than 10mm, fitted with full perimeter acoustically rated seals and constructed of - (i) solid core, wood, particleboard or blockboard not less than 45mm thick; and/or (ii) acoustically laminated glass not less than 10.38mm thick.		

Version 1.1 Page 13 Publication Date: 17 August 2015

Component of building's external envelope	Minimum R _w	Acceptable forms of construction
		Fixed so as to overlap the frame or rebate of the frame, constructed of - (i) Wood, particleboard or blockboard not less than 33mm thick; or
	28	(ii) Compressed fibre reinforced sheeting not less than 9mm thick; or(iii) Other suitable material with a mass per unit area not less than 24.4kg/m²; or
		(iv) Solid core timber door not less than 35mm thick fitted with full perimeter acoustically rated seals.

Version 1.1 Page 14 Publication Date: 17 August 2015