

Department of State Development, Tourism and Innovation

Our ref: DEV2020/1093

18 December 2020

LEG Construction C/- Statewide Survey Group 3/123 Link Road VICTORIA POINT QLD 4165

Attn: Mr Brayden Mason (planning@statewidesurvey.com.au)

Dear Brayden

SECTION 89(1)(a) PDA DEVELOPMENT APPROVAL FOR A PDA DEVELOPMENT APPLICATION FOR A PDA DEVELOPMENT PERMIT FOR A MATERIAL CHANGE OF USE – MULTIPLE DWELLINGS (62 UNITS) AT 3 MOORES ROAD, REDLAND BAY DESCRIBED AS LOT 100 ON SP309514

On 18 December 2020 the Minister for Economic Development Queensland (MEDQ) approved the Priority Development Area (PDA) development application pursuant to s.85(4)(b) of the *Economic Development Act 2012*. The MEDQ has decided to grant all of the PDA development approval applied for, subject to PDA development conditions set out in this PDA decision notice.

The PDA decision notice and approved plans/documents can also be viewed in the MEDQ Development Approvals Register via the Department website <u>www.statedevelopment.qld.gov.au/economic-development-</u> <u>qld/buying-and-developing-land/development-applications-and-assessment/current-applications-and-</u> <u>approvals</u>.

Should you have any queries in relation to this PDA decision notice, please do not hesitate to contact Ms Kari Stephens on 3452 7167 or at kari.stephens@dsdti.qld.gov.au.

Yours sincerely

Jeanine Stone Director Development Assessment Economic Development Queensland

Minister for Economic Development Queensland GPO Box 2202 Brisbane Queensland 4001 Australia **Website** www.edq.qld.gov.au ABN 76 590 288 697

PDA Decision Notice – Approval

Site information			
Name of priority development area	Weinam Creek		
Site address	3 Moores Road, Redland	d Bay	
Lot on plan description	Lot number	Plan description	
	100	SP309514	
PDA development application details			
DEV reference number	DEV2020/1093		
'Properly made' date	6 February 2020		
Type of application	Image: Stream of the second		
Description of proposal applied for	Material change of use (62 multiple dwellings)		

PDA development approval details		
Decision of the MEDQ	The MEDQ has decided to grant all of the PDA development approval applied for, subject to PDA development conditions forming part of this decision notice.	
Decision date	18 December 2020	
Currency period	6 years from Decision date	

Plans and documents

The plans and documents approved by the MEDQ and referred to in the PDA development conditions are detailed in the table below.

2.Site Plan 1 as amended in redDA.01 issue CNovember 20203.Site Plan 2 & Way FindingDA.02 issue CNovember 20204.Site Plan 3DA.03 issue CNovember 20205.Building 1DA.06 issue BJune 20206.Building 2DA.06 issue CNovember 20207.Building 3DA.07 issue BJune 20208.Building 3DA.08 issue CNovember 20209.Building 3DA.09 issue BJune 202010.Building 4DA.10 issue CNovember 202011.Building 4DA.11 issue BJune 202012.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.14 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redC19-323-C09 Rev C5 September 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202018.Landscape concept Plan – Bldg 4 / 5LCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-4 Rev C5 September 202021.Erosin & Sediment Control Management planC19-323-C01 Rev A4 June 202022.Earthworks PlanC19-323-C02 Rev A4 June 202023.Earthworks PlanC19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout Plan <th>Appro</th> <th>oved plans and documents</th> <th>Number (if applicable)</th> <th>Date (if applicable)</th>	Appro	oved plans and documents	Number (if applicable)	Date (if applicable)
3.Site Plan 2 & Way FindingDA.02 issue CNovember 20204.Site Plan 3DA.03 issue CNovember 20205.Building 1DA.05 issue BJune 20206.Building 2DA.06 issue CNovember 20207.Building 3DA.07 issue BJune 20208.Building 3DA.08 issue CNovember 20209.Building 3DA.09 issue BJune 202010.Building 4DA.10 issue CNovember 202011.Building 4DA.11 issue BJune 202012.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.14 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redCP-1 Rev C5 September 202016.Landscape concept plan - Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan - Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept Plan - Bldg 4 / 5LCP-3 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosin & Sediment Control Management planQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks PlanQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C03 Rev A4 June 202025.Stormwater Drainage Layout Plan	1.	Cover Page	DA.00 issue B	June 2020
A.Site Plan 3DA.03 issue CNovember 20205.Building 1DA.05 issue BJune 20206.Building 2DA.06 issue CNovember 20207.Building 3DA.07 issue BJune 20208.Building 3DA.09 issue BJune 20209.Building 4DA.10 issue CNovember 202010.Building 4DA.11 issue BJune 202011.Building 5DA.12 issue BJune 202012.Building 5DA.13 issue BJune 202013.Streetscape and SectionsDA.14 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redC19-323-C09 Rev C18 November 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 4 / 5LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept plan – Bldg 4 / 5LCP-5 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management planC19-323-C01 Rev A4 June 202022.Earthworks detailsC19-323-C02 Rev A4 June 202023.Earthworks detailsC19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanC19-323-C03 Rev B18 November 202025.Stormwate	2.	Site Plan 1 as amended in red	DA.01 issue C	November 2020
5.Building 1DA.05 issue BJune 20206.Building 2DA.06 issue CNovember 20207.Building 2DA.07 issue BJune 20208.Building 3DA.08 issue CNovember 20209.Building 3DA.09 issue BJune 202010.Building 4DA.10 issue CNovember 202011.Building 5DA.11 issue BJune 202012.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.14 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept num ScheduleLCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management planQ19-323-C01 Rev A4 June 202022.Earthworks detailsQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C03 Rev B18 November 202025.Stormwater Drainage Layout PlanQ19-323-C03 Rev B18 November 2020 <t< td=""><td>3.</td><td>Site Plan 2 & Way Finding</td><td>DA.02 issue C</td><td>November 2020</td></t<>	3.	Site Plan 2 & Way Finding	DA.02 issue C	November 2020
Building 2DA.06 issue CNovember 20207.Building 2DA.07 issue BJune 20203.Building 3DA.08 issue CNovember 20209.Building 3DA.09 issue BJune 202010.Building 4DA.10 issue CNovember 202011.Building 5DA.11 issue BJune 202012.Building 5DA.11 issue BJune 202013.Streetscape and SectionsDA.14 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan - Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan - Bldg 4 / 5LCP-3 Rev C5 September 202018.Landscape concept plan - Bldg 4 / 5LCP-4 Rev C5 September 202019.Landscape Finishes, notesLCP-5 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C05 Rev A4 June 202024.Stormwater Drainage Long SectionsQ19-323-C07 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C07 Rev A4 June 202026.Sewer Connection layout planQ19-323-C07 Rev A4 June 20	4.	Site Plan 3	DA.03 issue C	November 2020
7.Building 2DA.07 issue BJune 20203.Building 3DA.08 issue CNovember 20203.Building 3DA.09 issue BJune 202010.Building 4DA.10 issue CNovember 202011.Building 4DA.11 issue BJune 202012.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.14 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan - Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan - Bldg 4 / 5LCP-3 Rev C5 September 202018.Landscape concept plan - Bldg 4 / 5LCP-4 Rev C5 September 202019.Landscape Finishes, notesLCP-5 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C02 Rev A4 June 202022.Earthworks detailsQ19-323-C03 Rev B18 November 202023.Earthworks detailsQ19-323-C06 Rev B18 November 202024.Stormwater Drainage Long SectionsQ19-323-C07 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C07 Rev B18 November 202026.Sewer Connection layout planQ19-323-C07 Rev A4 June 202027.Water Supply layout pl	5.	Building 1	DA.05 issue B	June 2020
Building 3DA.08 issue CNovember 20203.Building 3DA.09 issue BJune 202010.Building 4DA.10 issue CNovember 202011.Building 4DA.11 issue BJune 202012.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.13 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan - Bidg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan - Bidg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan - Bidg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C05 Rev A4 June 202024.Stormwater Drainage Layout PlanQ19-323-C07 Rev B18 November 202025.Sewer Connection layout planQ19-323-C07 Rev B18 November 202026.Sewer Connection layout planQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pa	6.	Building 2	DA.06 issue C	November 2020
A.Building 3DA.09 issue BJune 202010.Building 4DA.10 issue CNovember 202011.Building 4DA.11 issue BJune 202012.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.13 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan – Bidg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bidg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bidg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C05 Rev A4 June 202024.Stormwater Drainage Long SectionsQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C07 Rev B18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 2020	7.	Building 2	DA.07 issue B	June 2020
D.Building 4DA.10 issue CNovember 202011.Building 4DA.11 issue BJune 202012.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.13 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept plan – Bldg 4 / 5LCP-4 Rev C5 September 202020.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202021.Erosin & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks PlanQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C07 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C07 Rev A4 June 202029.Site Plan – Staging & Details <td< td=""><td>8.</td><td>Building 3</td><td>DA.08 issue C</td><td>November 2020</td></td<>	8.	Building 3	DA.08 issue C	November 2020
11.Building 4DA.11 issue BJune 202012.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.13 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept plan – Bldg 4 / 5LCP-4 Rev C5 September 202020.Landscape concept - Plant ScheduleLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks PlanQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev A4 June 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C08 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202029.Site Plan – St	9.	Building 3	DA.09 issue B	June 2020
12.Building 5DA.12 issue BJune 202013.Streetscape and SectionsDA.13 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept plan – Bldg 4 / 5LCP-4 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-5 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C05 Rev A4 June 202025.Stormwater Drainage Long SectionsQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C07 Rev B18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202029.	10.	Building 4	DA.10 issue C	November 2020
13.Streetscape and SectionsDA.13 issue BJune 202014.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape concept - Plant ScheduleLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C02 Rev A4 June 202024.Stormwater Drainage Layout PlanQ19-323-C03 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C06 Rev B18 November 202026.Sewer Connection layout planQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C08 Rev C18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C07 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020 <td>11.</td> <td>Building 4</td> <td>DA.11 issue B</td> <td>June 2020</td>	11.	Building 4	DA.11 issue B	June 2020
14.Design Features DetailsDA.14 issue BJune 202015.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept plan – Bldg 4 / 5LCP-4 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C05 Rev A4 June 202026.Sewer Connection layout planQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C08 Rev C18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A<	12.	Building 5	DA.12 issue B	June 2020
15.Basement carpark layout plan) as amended in redQ19-323-C09 Rev C18 November 202016.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape concept - Plant ScheduleLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C07 Rev A4 June 202026.Sewer Connection layout planQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202020.Site Based Stormwater Management PlanQ19-323-C10 Rev A4 June 202020.Site Based Stormwater Management PlanQ19-323-C10 Rev A4 June 2020	13.	Streetscape and Sections	DA.13 issue B	June 2020
as amended in redLCP-116.Landscape concept plan – Bldg 1 / 2LCP-1 Rev C5 September 202017.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C05 Rev A4 June 202025.Stormwater Drainage Long SectionsQ19-323-C06 Rev B18 November 202026.Sewer Connection layout planQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C08 Rev C18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202020.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	14.	Design Features Details	DA.14 issue B	June 2020
17.Landscape concept plan – Bldg 3 / 4LCP-2 Rev C5 September 202018.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C04 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C05 Rev A4 June 202025.Stormwater Drainage Long SectionsQ19-323-C06 Rev B18 November 202026.Sewer Connection layout planQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	15.		Q19-323-C09 Rev C	18 November 2020
18.Landscape concept plan – Bldg 4 / 5LCP-3 Rev C5 September 202019.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C05 Rev A4 June 202026.Sewer Connection layout planQ19-323-C07 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	16.	Landscape concept plan – Bldg 1 / 2	LCP-1 Rev C	5 September 2020
19.Landscape concept - Plant ScheduleLCP-4 Rev C5 September 202020.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C05 Rev A4 June 202025.Stormwater Drainage Long SectionsQ19-323-C05 Rev A4 June 202026.Sewer Connection layout planQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	17.	Landscape concept plan – Bldg 3 / 4	LCP-2 Rev C	5 September 2020
20.Landscape Finishes, notesLCP-5 Rev C5 September 202021.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C06 Rev A4 June 202026.Sewer Connection layout planQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	18.	Landscape concept plan – Bldg 4 / 5	LCP-3 Rev C	5 September 2020
21.Erosion & Sediment Control Management plan & detailsQ19-323-C01 Rev A4 June 202022.Earthworks PlanQ19-323-C02 Rev A4 June 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C05 Rev A4 June 202026.Sewer Connection layout planQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	19.	Landscape concept - Plant Schedule	LCP-4 Rev C	5 September 2020
& detailsQ19-323-C02 Rev A4 June 202022.Earthworks PlanQ19-323-C03 Rev B18 November 202023.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C05 Rev A4 June 202026.Sewer Connection layout planQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	20.	Landscape Finishes, notes	LCP-5 Rev C	5 September 2020
23.Earthworks detailsQ19-323-C03 Rev B18 November 202024.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C05 Rev A4 June 202026.Sewer Connection layout planQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	21.		Q19-323-C01 Rev A	4 June 2020
24.Stormwater Drainage Layout PlanQ19-323-C04 Rev B18 November 202025.Stormwater Drainage Long SectionsQ19-323-C05 Rev A4 June 202026.Sewer Connection layout planQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	22.	Earthworks Plan	Q19-323-C02 Rev A	4 June 2020
25.Stormwater Drainage Long SectionsQ19-323-C05 Rev A4 June 202026.Sewer Connection layout planQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	23.	Earthworks details	Q19-323-C03 Rev B	18 November 2020
26.Sewer Connection layout planQ19-323-C06 Rev B18 November 202027.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	24.	Stormwater Drainage Layout Plan	Q19-323-C04 Rev B	18 November 2020
27.Water Supply layout planQ19-323-C07 Rev B18 November 202028.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	25.	Stormwater Drainage Long Sections	Q19-323-C05 Rev A	4 June 2020
28.Driveway / Pathway & Carpark layout planQ19-323-C08 Rev C18 November 202029.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	26.	Sewer Connection layout plan	Q19-323-C06 Rev B	18 November 2020
29.Site Plan – Staging & DetailsQ19-323-C10 Rev A4 June 202030.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	27.	Water Supply layout plan	Q19-323-C07 Rev B	18 November 2020
30.Acid Sulfate Soil Investigation1-2252018 May 202031.Site Based Stormwater Management PlanQ1932311 June 2020	28.	Driveway / Pathway & Carpark layout plan	Q19-323-C08 Rev C	18 November 2020
31. Site Based Stormwater Management Plan Q19323 11 June 2020	29.	Site Plan – Staging & Details	Q19-323-C10 Rev A	4 June 2020
	30.	Acid Sulfate Soil Investigation	1-22520	18 May 2020
32. Traffic Engineering Assessment PTT Traffic & Transport 30 July 2020	31.	Site Based Stormwater Management Plan	Q19323	11 June 2020
	32.	Traffic Engineering Assessment	PTT Traffic & Transport	30 July 2020

PREAMBLE

For the purpose of interpreting this approval, including the conditions, the following applies:

ABBREVIATIONS AND DEFINITIONS:

The following is a list of abbreviations utilised in this approval:

- 1. **AILA** means a Landscape Architect registered by the Australian Institute of Landscape Architects.
- 2. **BFP** means Building Format Plan.
- 3. **Certification Procedures Manual** means the document titled *Certification Procedures Manual*, prepared by EDQ, dated April2020 (as amended from time to time).
- 4. **Council** means the relevant local government for the land the subject of this approval.
- 5. **DSDTI** means the Department of State Development, Tourism and Innovation.
- 6. **EDQ** means Economic Development Queensland.
- 7. **EDQ DA** means Economic Development Queensland's Development Assessment team.
- 8. **EDQ TS** means Economic Development Queensland's Technical Services team.
- 9. **IFF** means the Infrastructure Funding Framework, prepared by the Department of State Development, Tourism and Innovation, dated 1 July 2020 (as amended from time to time).
- 10. **MEDQ** means the Minister for Economic Development Queensland.
- 11. **PDA** means Priority Development Area.
- 12. **RPEQ** means Registered Professional Engineer of Queensland.

SUBMITTING DOCUMENTATION TO EDQ:

Where a condition of this approval requires documentation to be submitted to either EDQ DA or EDQ TS, submit the documentation to:

- a) EDQ DA at: <u>pdadevelopmentassessment@dsdmip.qld.gov.au</u>.
- b) EDQ TS at: prepostconstruction@dsdmip.qld.gov.au.

PDA Development Conditions			
No	Condition	Timing	
Gene	ral		
1.	Carry out the approved development Carry out the approved development generally in accordance with the approved plans and documents.	Prior to commencement of use of each stage, or endorsement of the BFP, whichever occurs first	
2.	Maintain the approved development Maintain the approved development generally in accordance with the approved plans and documents.	At all times following commencement of use	
Plann	ning and Urban Design		
3.	Accessible housing Submit to EDQ DA evidence that the approved development delivers a minimum of six accessible units, generally in accordance with the approved plans.	Prior to commencement of use of each stage, or endorsement of the BFP, whichever occurs first	
	NOTE: copies of building work floor plans and an accompanying statement are considered evidence.		
4.	 Window treatments (public realm and overlooking) a) Windows shall be fitted with external privacy screens to a minimum height of 1800mm, measured from floor level, as follows: i. Southern elevation of building 1 (levels 1 and 2); ii. Northern elevation of building 5 (levels 1 and 2). 		

PDA D	evelopment Conditions	
No	Condition	Timing
	 b) Windows adjoining Moores Road car park shall be fitted with external screens and sunhoods, as follows: Western elevation of building 2 (levels 1, 2 and 3); North-western elevation of building 3 (levels 1,2 and 3); North-western elevation of building 4 (levels 1,2 and 3). 	
5.	 Window treatments (privacy) For window located less than 9m from another building face containing windows, those windows shall be treated through the installation of: a) Sill heights at a minimum height of 1.5m above floor level b) Fixed opaque glazing in any part of a window below 1.5m above floor level 	Prior to commencement of use of each stage, or endorsement of the BFP, whichever occurs first
6.	Bin enclosures Provide a roof structure over each bin enclosure that has no more than 25% of the total roof area open to the sky.	Prior to commencement of use for each stage
7.	Clothes Drying Facilities Provide evidence in the Community Management Statement that balconies shall not be used as clothes drying areas.	Prior to the endorsement of the BFP for stage 1, and ongoing
8.	 Minimum Habitable Floor Level Provide evidence that the minimum habitable floor level is at least: a) RL3.52m AHD for buildings 1 and 5; and b) RL4.22 AHD for buildings 2, 3 and 4. 	Prior to the endorsement of the BFP for each stage
Sustai	nability	
9.	Sustainable Energy Rating Submit to EDQ TS evidence that the approved development has been constructed to achieve a NatHERS (Nationwide House Energy Rating Scheme) energy rating of at least 5 stars for individual units and an average of at least 6 stars across all units in the buildings.	Prior to commencement of use for each stage, or endorsement of BFP, whichever occurs first
10.	 Harvesting and Re-use For each stage of the development, submit to EDQ DA, evidence of: a) An energy harvesting system (ie wind, solar etc) with the capacity to meet the ongoing costs of powering the common areas of each stage of the development (lights, lifts, pool filtration etc) b) A rainwater harvesting system capable of capturing rainwater runoff for re-use on the site for irrigation of landscaping 	Prior to commencement of use for each stage, or endorsement of BFP, whichever occurs first
11.	 Electric Vehicle Charging a) Provide a minimum of two electric vehicle charging stations for the development, with each charging station located within a dedicated parking bay. b) Provide updated plans showing the location of the electric vehicle charging stations with the certification. c) Submit to EDQ TS evidence from a suitably qualified professional that the requirements of parts a) and b) of this condition have been met. 	Prior to the commencement of use for Stage 2, or endorsement of BFP, whichever occurs first
	g, Access, Servicing	
12.	 Car Parking a) Provide car parking spaces, delineated and signed generally in accordance with AS2890 – Parking Facilities and the following approved report/plans: Traffic Engineering Assessment report prepared by PTT and dated 30 July 2020; and Basement carpark layout plan Q19-323-C09 Rev C. 	Prior to the commencement of use for Stage 2, or endorsement of BFP, whichever occurs first

PDA I	Development Conditions	
No	Condition	Timing
	 Submit to EDQ TS, certification by a RPEQ demonstrating that the parking facilities have been provided in accordance with part a) of this condition. 	
13.	Tandem spaces Tandem car parking spaces shall be allocated to the same unit	Prior to commencement of use or BFP endorsement for each stage, whichever occurs first
14.	 Bicycle parking Construct, sign and delineate resident and visitor bicycle parking facilities generally in accordance with AS2890.3 – 1993 Bicycle parking facilities as follows: a) a minimum of 16 resident bike parking spaces in the basement area; and b) a minimum of four bike parking spaces for visitors, to be provided at ground level, located either near the entrance/s to buildings 2, 3 and/or 4, or in a conveniently accessible part of the common property. 	Prior to commencement of use or BFP endorsement, whichever occurs first
15.	Refuse Collection Submit to EDQ TS, refuse collection approval from Council or a private waste contractor.	Prior to commencement of use or BFP endorsement, whichever occurs first
Street	scape, Landscape and Environment	
16.	 Landscape Works a) Submit to EDQ TS, detailed landscape plans, certified by an AILA, for landscape works within the proposed development generally in accordance with the following: i) Landscape Concept Plan-BBDG 1/2 Revision C prepared by Mark Baldock Landscape Architect and dated 5/11/2020; and ii) Landscape Concept Plan-BBDG 3/4 Revision C prepared by Mark Baldock Landscape Architect and dated 5/11/2020; and iii) Landscape Concept Plan-BBDG 4/5 Revision C prepared by Mark Baldock Landscape Architect and dated 5/11/2020; and iii) Landscape Concept Plan-BBDG 4/5 Revision C prepared by Mark Baldock Landscape Architect and dated 5/11/2020; and iv) Landscape Concept Plant Schedule Revision C prepared by Mark Baldock Landscape Architect and dated 5/11/2020; and v) Landscape Concept Finish & Notes Revision C prepared by Mark Baldock Landscape Architect and dated 5/11/2020; and v) Landscape Concept Finish & Notes Revision C prepared by Mark Baldock Landscape Architect and dated 5/11/2020; b) Construct the works generally in accordance with the certified plans submitted under part a) of this condition. 	 a) Prior to building works application for stage 1 b) Prior to commencement of use of each stage, or endorsement of the BFP, whichever occurs first and then to be maintained
17.	 Streetscape Works a) Submit to EDQ TS, detailed landscape plans for streetscape works, certified by an AILA registered Landscape Architect. The detailed streetscape plans are to include: i. footpath treatments; ii. details of infrastructure located in the verge; and iii. at least two street trees, including species, size (semi-advanced), spacing and location. 	a) Prior to building works application for stage 1

PDA [Development Conditions	
No	Condition	Timing
	b) Construct the works generally in accordance with the endorsed plans required under part a) of this condition.	 b) Prior to commencement of use for stage 1
	c) Provide 12 months maintenance to the street trees, from the date of written confirmation from EDQ TS that planting is satisfactory.	c) As specified
18.	Footpath reinstatement and extension Following construction of the driveway crossover, reinstate the footpath to match the width and profile of the existing path. The footpath must extend to the property boundaries of both adjoining lots (Lot 21 and Lot 9).	Prior to commencement of use
19.	Outdoor Lighting Outdoor lighting within the site, shall be designed and installed in accordance with AS 4282:1997 Control of the Obtrusive Effects of Outdoor Lighting.	Prior to commencement of use for each stage and then to be maintained
Engin	eering (Infrastructure, Services and Networks)	
20.	Water Connection Connect the development to the existing water reticulation network in accordance with Redland Water current adopted standards.	Prior to commencement of use for each stage
21.	Sewer Connection Connect the development to the existing sewer reticulation network in accordance with Redland Water current adopted standards.	Prior to commencement of use for each stage
22.	Stormwater Lawful point of discharge Connect the development to the existing stormwater discharge point that was provided by the adjacent carpark site in favour of this development.	Prior to commencement of use
23.	 Stormwater Management (Quality) a) Submit to EDQ TS, for detailed engineering design and construction drawings, certified by an RPEQ, prepared with reference to the Site Based Stormwater Management Plan (SBSMP), prepared by Neil McKenzie & Associates dated 11 June 2020. 	a) Prior to commencement of site works
	 The SBSMP and associated design and construction drawings are to: i. Be prepared generally in accordance with: A. PDA Guideline No. 13 Engineering standards – Stormwater quality; B. The WaterByDesign - Bioretention Technical Design Guideline: Version 1.1; and ii. Achieve the stormwater quality criteria in the State Planning Policy 2017, without the need to lift the level of the car park. 	
	b) Construct the works generally in accordance with the SBSMP approved under part a) of this condition.	b) At all times during construction
	c) Submit to EDQ TS, 'as constructed' drawings, including an asset register, certified by a RPEQ, in a format acceptable to the Council, of all stormwater management (quality) works constructed in accordance with this condition.	 Prior to commencement of use for each stage
24.	 Stormwater Management (Quantity) a) Submit to EDQ TS, detailed design plans and hydraulic calculations, certified by a RPEQ, for the proposed stormwater drainage system generally in accordance with the following documents: i. PDA Guideline No. 13 Engineering standards – Stormwater 	a) Prior to commencement of site works

PDA D	Development Conditions	
No	Condition	Timing
	 quantity; and ii. the approved Site Based Stormwater Management Plan required under Conditions of this approval Stormwater Management (Quality). iii. the compliance assessed and approved Engineering Assessment Report, prepared by Neil McKenzie & Associates dated 11 June 2020. i. the compliance assessed and approved Acid Sulfate Soil Investigation report, prepared by Soil Surveys Engineering Pty Ltd and dated 18 May 2020. 	
	b) Construct the works in accordance with the certified plans submitted under part a) of this condition.	 b) At all times during construction
	 c) Submit to EDQ TS, 'as constructed' plans including an asset register and test results, certified by a RPEQ, in a format acceptable to the Council, of all stormwater management (quantity) works constructed in accordance with this condition. 	 c) Prior to commencement of use for each stage
25.	 Electricity Submit to EDQ TS written evidence from Energex confirming: a) that existing underground low-voltage electricity supply is available to the development; OR b) that the applicant has entered into an agreement to provide underground electricity services to the development. 	Prior to commencement of site works for each stage
26.	Telecommunications Submit to EDQ TS documentation from an authorised telecommunication service provider confirming that an agreement has been entered into for the provision of underground telecommunication services to the proposed development.	Prior to commencement of site works for each stage
27.	Broadband Submit to EDQ TS a written agreement from an authorised telecommunications service provider that infrastructure within the development as defined under the <i>Telecommunications Legislation</i> <i>Amendment (Fibre Deployment) Act 2011)</i> can be provided in accordance with the Communications Alliance G645:2017 guideline, to accommodate services which are compliant with the Federal Government's National Broadband Network policy.	Prior to commencement of site works for each stage
28.	 Public Infrastructure – Damage, Repairs and Relocation a) All Works must not damage or compromise the function or performance of any existing public infrastructure. b) Notify, and obtain all necessary approvals from the relevant infrastructure provider where the development requires alterations to existing utility mains, services, Roads, bikeways and footpaths, or other installations prior to commencing works. 	 a) At all times during construction b) Prior to commencement of works
	c) Repair any damage to existing public infrastructure that occurs during Works carried out in association with the Development, within or external to the site, in compliance with the relevant standards and infrastructure provider's requirements. Rectification works are to be completed no later than 20 business days after damage occurs during Works, unless otherwise agreed to in writing by the EDQ TS.	c) At all times

PDA D	Development Conditions	
No	Condition	Timing
Engin	eering (Construction)	
29.	 Appointment of the Project Coordinator a) The Development Proponent must appoint suitably qualified and insured persons to carry out project coordination, certification of works and of other matters required by conditions contained within this PDA development approval. The nominated project coordinator and certifiers must meet the following criteria: i. Project coordinator must have project management skills and demonstrated experience commensurate with the scale of the development. ii. Certifiers must have the required technical qualifications in the discipline being certified and demonstrated experience 	a) Prior to commencement of site works
	commensurate with the scale of the development.b) Submit to EDQ TS for acceptance the relevant qualifications and experience of the project coordinator and certifiers.	 b) Prior to commencement of site works
30.	 Experience of the project coordinator and certifiers. Construction Environmental Management Plan a) Submit to EDQ TS a site-based Construction Environmental Management Plan (CEMP), prepared by the principal site contractor, that manages the following: Noise and dust generated from the site during and outside construction work hours in accordance with the <i>Environmental Protection Act 1994</i>; Stormwater flows around or through the site without increasing the concentration of total suspended solids or Prescribed Water Contaminants (as defined in the <i>Environmental Protection Act 1994</i>), causing erosion, creating any ponding and causing any actionable nuisance to upstream or downstream properties; and Vegetation management measures, including protective fencing and flagging of vegetation to be retained and to restrict construction related vehicles from damaging the root zones of retained vegetation; Site Management Provisions including (where relevant) but not limited to the following: A. Provision for pedestrian management including alternative pedestrian routes, past or around the site; Location of and impacts on any local authority's assets on or external to the site; C. Temporary vehicular access points and frequency of use; D. Provision for loading and unloading materials including the location of any remote loading sites; E. Location of materials, structures, plant and equipment to be stored or placed on the construction site; F. Management of waste generated during the construction activities; G. How materials are to be loaded/unloaded and potential impacts on existing street trees; H. Location of proposed external hoardings and gantries (with clearances to street furniture and other footpath assets); I. Employee and visitor parking areas; J. Anticipated staging, programming; K. Provision for fire exit routes for other uses on the <	a) Prior to commencement of site works

PDA D	evelopment Conditions	
No	Condition	Timing
	 subject or adjoining sites; L. Allowable works times in accordance with those set by the Queensland Environmental Protection Policy (Noise) 2008. The CEMP is to include details of any construction considered necessary to be conducted out of normal business hours (where normal hours are defined as Monday to Saturday between 6.30a.m. and 6.30p.m. excluding public holidays). It is the responsibility of the Contractor to notify and obtain all relevant approvals for out of hours work. 	
	 b) Prior to submitting the CEMP under part a), the CEMP shall be reviewed and approved by a suitably qualified and experienced RPEQ, or other suitably qualified and experienced person responsible for overseeing the construction works. 	 b) Prior to commencement of site works
	c) Undertake all works generally in accordance with the CEMP submitted under part a) of this condition, which is to be current and available on site at all times.	c) At all times during site works
31.	 Groundwater Management Strategy a) Submit to EDQ TS a Site Condition Report, certified an RPEQ to include groundwater risk assessment. 	a) & b) Prior to commencement of site works
	 b) Where the Site Condition Report under part a) identifies a groundwater risk, submit to EDQ TS a Groundwater Management Strategy (GMS), certified by a RPEQ incorporating at a minimum: Strategies for managing groundwater during the staged works phases; An assessment of the groundwater conditions to determine appropriate construction management procedures; Strategies for a situation where the groundwater inflow is excessive and additional pumping is required (i.e. cut-off drain); and Supporting information confirming the GMS was prepared with reference to the relevant documentation prepared in accordance with Condition 4. 	
	 c) Undertake all works in accordance with the GMS certified under part b) of this condition. 	 At all times during construction
32.	 Traffic Management Plan a) Submit to EDQ TS a Traffic Management Plan (TMP), certified by a person holding a current Traffic Management Level 3 qualification or higher. The TMP is to include the following: Provision for the management of traffic around and through the site during and outside of construction work hours; Provision of parking for workers and materials delivery during and outside of construction hours of work; Risk identification, assessment and identification of mitigation measures; Ongoing monitoring, management review and certified updates (as required); and Traffic control plans and/or traffic control diagrams, prepared in accordance with Manual of Uniform Traffic Control Devices (MUTCD), for any temporary part or full road closures of any 	a) Prior to commencement of site works

 TMP submitted under part a) of this condition, which is to be current and available on site at all times. Advice Note - Traffic operational changes such as temporary and permanent lane modifications, footpath closures and alternative kerbside parking alterations, including bus zones, on roads adjoining the site will require separate approval from Council. Batter extension and the extension of the second alternative kerbside parking alterations, including bus zones, on roads adjoining the site will require separate approval from Council. Retaining Walls a) Submit to EDQ TS detailed engineering plans, certified by a material standards; and i. AS4678 - 2002 Earth Retaining Structures and the relevant material standards; and ii. AS4678 - 2002 Earth Retaining Structures. Retaining walls are to be generally in accordance with: i. AS4678 - 2002 Earth Retaining Structures. Retaining walls are to be generally in accordance with PDA Practice Note No. 10 - Plans of development unless otherwise approved by EDQ TS. b) Construct the works generally in accordance with the certified plans required under part a) of this condition. c) Submit to EDQ TS certification from an RPEQ that all retaining wall works 1.0m or greater in height have been constructed generally in accordance with the certified plans submitted under part a) of this condition. Filling and Excavation a) Submit to EDQ TS, detailed earthworks plans, certified by a RPEQ, generally in accordance with AS3798 – 2007 Guidelines on Earthworks for Commercial and Residential Developments and the following plans:	PDA D	Development Conditions		
 b) Undertake all works generally in accordance with the certified TMP submitted under part a) of this condition, which is to be current and available on site at all times. Advice Note - Traffic operational changes such as temporary and permanent lane modifications, footpath closures and alternative kerbside parking alterations, including bus zones, on roads adjoining the site will require separate approval from Council. Retaining Walls a) Submit to EDQ TS detailed engineering plans, certified by a RPEQ, of all retaining walls on lot boundaries 1.0m or greater in height. Retaining walls on lot boundaries 1.0m or greater in height. Retaining walls and/or retention walls shall be designed for a design life of not less than 50 years. The design of the walls shall be in accordance with: i. AS4678 - 2002 Earth Retaining Structures and the relevant material standards; and ii. AS3600 - 2018 Concrete Structures. Retaining walls are to be generally in accordance with PDA Practice Note No. 10 - Plans of development unless otherwise approved by EDQ TS. b) Construct the works generally in accordance with the certified plans required under part a) of this condition. c) Submit to EDQ TS certification from an RPEQ that all retaining wall works 1.0m or greater in height have been constructed generally in accordance with the certified plans submitted under part a) of this condition. d) Prior to commencement use for each stage, or endorsement of the BFF whichever occurs first 34. Filling and Excavation a) Submit to EDQ TS, detailed earthworks plans, certified by a RPEQ, generally in accordance with AS3798 - 2007 Guidelines on Earthworks for Commercial and Residential Developments and the following plans: ii. the compliance assessed and approved Engineering Assessment Report, prepared by Neil McKenzie & Associates dated 11 June 2020. iii. the compliance assessed and approved Engineering P	No	Condition	Timing	
permanent lane modifications, footpath closures and alternative kerbside parking alterations, including bus zones, on roads adjoining the sile will require separate approval from Council. a) 33. Retaining Walls a) Submit to EDQ TS detailed engineering plans, certified by a RPEQ, of all retaining walls on lot boundaries 1.0m or greater in height. Retaining walls and/or retention walls shall be designed for a design life of not less than 50 years. The design of the walls shall be in accordance with: i. AS4678 – 2002 Earth Retaining Structures and the relevant material standards; and ii. AS3600 – 2018 Concrete Structures. Retaining walls are to be generally in accordance with PDA Practice Note No. 10 – Plans of development unless otherwise approved by EDQ TS. b) Construct the works generally in accordance with the certified plans required under part a) of this condition. c) Submit to EDQ TS certification from an RPEQ that all retaining wall works 1.0m or greater in height have been constructed generally in accordance with have been constructed generally in accordance with As3798 – 2007 Guidelines on Earthworks for Commercial and Residential Developments and the following plans:		 b) Undertake all works generally in accordance with the certified TMP submitted under part a) of this condition, which is to be 	b) At all times during site works	
 a) Submit to EDQ TS detailed engineering plans, certified by a RPEQ, of all retaining walls on lot boundaries 1.0m or greater in height. Retaining walls and/or retention walls shall be designed for a design life of not less than 50 years. The design of the walls shall be in accordance with: Astaf78 - 2002 Earth Retaining Structures and the relevant material standards; and AS3600 - 2018 Concrete Structures. Retaining walls are to be generally in accordance with PDA Practice Note No. 10 - Plans of development unless otherwise approved by EDQ TS. b) Construct the works generally in accordance with the certified plans required under part a) of this condition. c) Submit to EDQ TS certification from an RPEQ that all retaining wall works 1.0m or greater in height have been constructed generally in accordance with the certified plans submit to EDQ TS, detailed earthworks plans, certified by a RPEQ, generally in accordance with AS3798 - 2007 Guidelines on Earthworks for Commercial and Residential Developments and the following plans: the compliance assessed and approved Engineering Assessment Report, prepared by Neil McKenzie & Associates dated 11 June 2020. the compliance assessed and approved Acid Sulfate Soil Investigation report, prepared by Soil Surveys Engineering Pty Ltd and dated 18 May 2020. The certified earthworks plans are to: Include a geotechnical soils assessment of the site; Be consistent with the Erosion and Sediment Control plans submitted under the Erosion and Sediment Management 		permanent lane modifications, footpath closures and alternative kerbside parking alterations, including bus zones, on roads adjoining the site will require separate approval from Council.		
 c) Submit to EDQ TS certification from an RPEQ that all retaining wall works 1.0m or greater in height have been constructed generally in accordance with the certified plans submitted under part a) of this condition. 34. Filling and Excavation a) Submit to EDQ TS, detailed earthworks plans, certified by a RPEQ, generally in accordance with AS3798 – 2007 Guidelines on Earthworks for Commercial and Residential Developments and the following plans: ii. the compliance assessed and approved Engineering Assessment Report, prepared by Neil McKenzie & Associates dated 11 June 2020. iii. the compliance assessed and approved Acid Sulfate Soil Investigation report, prepared by Soil Surveys Engineering Pty Ltd and dated 18 May 2020. The certified earthworks plans are to: i. Include a geotechnical soils assessment of the site; ii. Be consistent with the Erosion and Sediment Control plans submitted under the Erosion and Sediment Management 	33.	 a) Submit to EDQ TS detailed engineering plans, certified by a RPEQ, of all retaining walls on lot boundaries 1.0m or greater in height. Retaining walls and/or retention walls shall be designed for a design life of not less than 50 years. The design of the walls shall be in accordance with: AS4678 – 2002 Earth Retaining Structures and the relevant material standards; and AS3600 – 2018 Concrete Structures. Retaining walls are to be generally in accordance with PDA Practice Note No. 10 – Plans of development unless otherwise 	a) Prior to commencement of site works	
 34. Filling and Excavation a) Submit to EDQ TS, detailed earthworks plans, certified by a RPEQ, generally in accordance with AS3798 – 2007 Guidelines on Earthworks for Commercial and Residential Developments and the following plans: ii. the compliance assessed and approved Engineering Assessment Report, prepared by Neil McKenzie & Associates dated 11 June 2020. iii. the compliance assessed and approved Acid Sulfate Soil Investigation report, prepared by Soil Surveys Engineering Pty Ltd and dated 18 May 2020. The certified earthworks plans are to: i. Include a geotechnical soils assessment of the site; ii. Be consistent with the Erosion and Sediment Control plans submitted under the Erosion and Sediment Management 		 plans required under part a) of this condition. c) Submit to EDQ TS certification from an RPEQ that all retaining wall works 1.0m or greater in height have been constructed generally in accordance with the certified plans submitted under 	c) Prior to commencement of use for each stage, or endorsement of the BFP,	
 iii. Provide full detail of areas where dispersive soils will be disturbed, treatment of dispersive soils and their rehabilitation; iv. Provide full details of any areas where surplus soils are to be stockpiled. Provide full details of any areas where surplus soils are to be stockpiled; v. Ensure the protection of adjoining properties and roads from ponding or nuisance stormwater; and 	34.	 Filling and Excavation a) Submit to EDQ TS, detailed earthworks plans, certified by a RPEQ, generally in accordance with AS3798 – 2007 Guidelines on Earthworks for Commercial and Residential Developments and the following plans: ii. the compliance assessed and approved Engineering Assessment Report, prepared by Neil McKenzie & Associates dated 11 June 2020. iii. the compliance assessed and approved Acid Sulfate Soil Investigation report, prepared by Soil Surveys Engineering Pty Ltd and dated 18 May 2020. The certified earthworks plans are to: i. Include a geotechnical soils assessment of the site; ii. Be consistent with the Erosion and Sediment Control plans submitted under the Erosion and Sediment Management condition (condition 36); iii. Provide full detail of areas where dispersive soils will be disturbed, treatment of dispersive soils and their rehabilitation; iv. Provide full details of any areas where surplus soils are to be stockpiled. Provide full details of any areas where surplus soils are to be stockpiled; v. Ensure the protection of adjoining properties and roads from 	a) Prior to commencement of	

PDA I	Development Conditions	
No	Condition	Timing
	vi. Provide for the preservation of all drainage structures from the effects of structural loading generated by the earthworks.	
	b) Carry out the earthworks generally in accordance with the certified plans submitted under part a) of this condition.	 b) Prior to commencement of use
	c) Submit to EDQ TS certification from a RPEQ that all earthworks have been carried out generally accordance with the certified plans submitted under part a) of this condition and that any unsuitable material encountered has been treated or replaced with suitable material.	c) Prior to commencement of use for each stage, or endorsement of the BFP, whichever occurs first
Envire	onment	
35.	Acid Sulfate Soils Excavate, remove and/or treat on-site all acid sulfate soils generally in accordance with the approved Acid Sulfate Soil Investigation report, prepared by Soil Surveys Engineering Pty Ltd and dated 18 May 2020	At all times during construction
36.	 Erosion and Sediment Management a) Submit to EDQ TS an Erosion and Sediment Control Plan (ESCP), certified by a RPEQ or a certified professional in erosion and sediment control (CPESC), generally in accordance with the following guidelines: i. Urban Stormwater Quality Planning Guidelines, dated 2010, prepared by the former Department of Environment and Heritage Protection; and ii. Best Practice Erosion and Sediment Control, dated November 2008, prepared by the International Erosion Control Association Australasia (as amended from time to time). iv. the compliance assessed and approved Engineering Assessment Report, prepared by Neil McKenzie & Associates dated 11 June 2020. v. the compliance assessed and approved Acid Sulfate Soil Investigation report, prepared by Soil Surveys Engineering Pty Ltd and dated 18 May 2020. Given the proximity of the site to sensitive receiving waters, the ESCP is required to demonstrate how the works will: A. Limit clearing to only the area necessary to undertake construction works and shown in the plans; B. Minimise the use of machinery in the waterway; D. Minimise the use of machinery in the waterway; D. Minimise disturbance to the instream bed and banks (e.g. use of geofabric as a work base, or construction of a platform above the substrate); E. Ensure vegetation near waterways is cut no lower than ground level and leaves the root in the ground to aid in soil stabilisation; F. Minimise use of machinery to be no greater than the capacity required for the purpose; G. Control water movement through the site; H. Undertake clearing immediately before construction only; I. Ensure no areas of bare soil unless being actively 	a) Prior to commencement of site works

PDA Development Conditions		
No	Condition	Timing
	 worked; J. Use and maintain sediment barriers such as sediment fences, mulch berms, sediment socks and temporary silt screens and ensure these barriers are functional for the duration of the works; K. Ensure any stockpiles are not in overland flow paths; L. Use bunds to minimise runoff during construction; and 	
	b) Implement the certified ESCP as submitted under part a) of this condition.	 b) At all times during site works.
37.	Disposal of Soil and Removed Vegetation Any soil created, or vegetation removed, as a result of this PDA development approval is:	At all times during site works
	i. not to be disposed of on tidal lands or within waterways; andii. is to be managed to prevent acid soil development.	
Surveying, land dedication and easements		
38.	Easements over Infrastructure Public utility easements are to be provided, in favour of and at no cost to the grantee, over infrastructure that becomes contributed assets.	Prior to commencement of use for each stage, or endorsement of the BFP, whichever occurs first
	The terms of the easements are to be to the satisfaction of the Chief Executive Officer of the authority which ultimately is to takeover and maintain the contributed assets.	
Infras	tructure contributions	
39.	 a) Pay to the MEDQ, infrastructure charges in accordance with the IFF, indexed to the date of payment. b) Prior to the commencement of use for each stage, seek from EDQ DA, a calculation of the payable infrastructure charges for the relevant stage/s c) Certified plans detailing the GFA must be provided at the time of payment. 	In accordance with the IFF

STANDARD ADVICE

Please note that in order to lawfully undertake development, it may be necessary to obtain approvals other than this PDA development approval. For advice on other approvals that may be necessary in relation to your proposal, it is recommended that you seek professional advice.

** End of Package **