PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL



ttm

Approval no: DEV2021/1193

Date: 4 March 2022



Operational Waste Management Plan

Proposed Mixed-Use Development

At 19-25 Campbell Street, Bowen Hills

On Behalf of Dowse Projects





About TTM

For 30 years, we've been at the centre of the Australian development and infrastructure industry. Our unique combination of acoustics, data, traffic and waste services is fundamental to the success of any architectural or development project.

We have over 50 staff, with an unrivalled depth of experience. Our industry knowledge, technical expertise and commercial insight allow us to deliver an exceptional and reliable service.

T: (07) 3327 9500 F: (07) 3327 9501

E: ttmbris@ttmgroup.com.au







Traffic



Acoustics

Data

Waste

Revision Record

No.	Author	Reviewed/Approved	Description	Date
1.	M. Krisanski	S. Kenny	Draft DA Report	20/05/2021
2.	M. Krisanski		DA Report	03/06/2021
3.				
4.				
5.				



Executive Summary

This document is an Operational Waste Management Plan (OWMP) developed for a proposed mixed-use development to be located at 19-25 Campbell Street, Bowen Hills.

The purpose of the OWMP is to provide compliance and design information relating to the handling, storage, and collection of refuse within the proposed development. Compliance relates to alignment with the Brisbane City Council's (BCC) Refuse Planning Scheme Policy (PSP) and associated codes. The content of the OWMP is written with the purpose of providing a guide for the Design, Construction and Operational phases of the development and therefore may be updated to include detailed information as required for each phase. Sections included as "client information only" are removed or amended during the appropriate phase and therefore should not be reviewed as assessable items.

A summary of the proposed waste management processes and equipment is outlined below:

- Equipment:
 - Residential refuse:
 - o 10 x 1100L general waste bins (+ 1 additional bin to remain on equipment during servicing).
 - o 21 x 1100L commingled recycling bins (+ 1 additional bin to remain on equipment during servicing).
 - o A Dual Chute system with hopper doors on residential levels for disposal of waste and recycling.
 - o $2 \times 4 \times 1100$ L bin carousel bin rotation systems (1 system to have a compactor for the compaction of general waste)
 - Commercial Refuse:
 - o 1 x 1100L general waste bin.
 - o 3 x 1100L commingled recycling bins.
- Refuse collection:

All collections will occur via Edgar Street.

- Residential refuse:
 - o Collected by Council via rear-loading RCV's. Collections will occur on-site within the loading area.
 - o 3 collections per week for both general waste and commingled recycling.
- Commercial refuse:
 - o Collected by private contractors using rear-loading RCV's or other vehicles (e.g. tank truck, body truck) as required. Refuse collections will occur on-site within the loading area.
 - o 3-4 collections per week or 7 collections per fortnight for each refuse stream.

2



• Refuse storage:

Residential refuse:

- o Waste and recycling chutes will discharge into 1100L bulk bins stored within the refuse room located on ground floor.
- o All refuse areas are adequately sized to store all appropriate bins.
- o The rotation equipment and is partitioned for safety purposes.
- o Bin washing facilities will be provided within each refuse room.

Commercial refuse:

- o Stored within the commercial refuse room in appropriate bins or equipment as detailed above.
- o Bin washing facilities will be provided within the refuse room.

Refuse transfer:

Residential refuse:

- o Full bins on the rotation equipment will be rotated on a daily basis or as required. Building management will be responsible for bin rotation / changeover.
- o Prior to Council collection, all full waste or recycling bins will be removed from the rotation equipment and placed in the refuse area outside of the partition to be collected directly from refuse room by the BCC Contractor.

Commercial refuse:

o Bins will be collected directly from the commercial refuse room by a private contractor and immediately returned once serviced.

• Refuse disposal:

Residential refuse:

- o Receptacles for storage of at least one day worth of waste and recycling will be provided in each unit.
- o Residents will dispose the material via the waste and recycling chutes accessible via hopper doors on each residential level.
- o As an option, apartment-style composters may be used for separation of food waste.
- o Separation of (drink) containers eligible for a rebate under the container refund scheme is recommended.

Site: 19-25 Campbell Street, Bowen Hills



- Commercial refuse:

- o Each tenancy will be provided with back-of-house bins for disposal to the bulk bins.
- o Staff or cleaners will transfer the waste and recycling materials to the commercial refuse room for disposal into the appropriate bins or equipment.

Site: 19-25 Campbell Street, Bowen Hills



Contents

1	Introdu	ction	8
	1.1.	Background	8
	1.2.	Scope	8
	1.3.	Regulatory Considerations	9
		1.3.1. Council's Refuse Planning Scheme	9
		1.3.2. Waste Levy	13
	1.4.	Site Location	14
	1.5.	Development Summary	16
	1.6.	Development Refuse Profile	16
2	Refuse I	Management	17
	2.1.	Refuse Collection	17
		2.1.1. Bin Quantities	17
		2.1.2. Collection Cycle	17
		2.1.3. RCV Arrangements	18
	2.2.	Refuse Storage	18
	2.3.	Refuse Transfer	18
	2.4.	Refuse Disposal	18
		2.4.1. Residential Refuse	19
		2.4.2. Commercial Refuse	20
		2.4.3. Infrequent Waste	21
3	Recomn	nended Operational Requirements	22
	3.1.	Operational Equipment Summary	22
	3.2.	On-going Management	22
		3.2.1. Safety	22
		3.2.2. Signage	23
		3.2.3. Cleaning and Maintenance	23
		3.2.4. Refuse Minimisation	23
		3.2.5. Education and Communication	24
		3.2.6. Monitoring and Review	24
4	Recomn	nended Design Requirements	25
	4.1.	Bin Servicing Point	25
	4.2.	Refuse Chutes	25
	4.3.	Refuse Rooms	26



4.4.	Bin Carting	27
4.5.	Bin Wash	28
4.6.	Storm Water Prevention and Litter Reduction	28
4.7.	Ventilation	28
Appendix A	Detailed Refuse Calculations	29
A.1	Refuse Calculations	30
A.2	Commercial Refuse Volume to Weight Conversion	31
Appendix B	Site Plans and Drawings	32
B.1	Ground Floor Level	33
Appendix C	Systems and Specifications	35
C.1	Typical Refuse Bins	36
C.2	Typical Refuse Management Equipment	37
C.3	Refuse Transfer and Disposal Methods	39
C.4	Refuse Minimisation Options	40
C.5	Refuse Management Equipment Suppliers	44
C.6	Refuse Management Service Providers	46
Appendix D	Refuse Signage	47
D.1	Refuse Signage	48
D.2	Chute Signage	49
D.3	Other Refuse, Facility and Safety Signage	50
Appendix E	Terms and Abbreviations	51



Table Index

Table 1.1: Scope Items	8
Table 1.2: OWMP Compliance Checklist	
Table 1.3: Development Summary	16
Table 1.4: Residential Refuse Summary	16
Table 1.5: Commercial Refuse Summary	16
Table 2.1: Bins per Collection	
Table 2.2: Estimated Residential RCV Demands	
Table 2.3: Estimated Commercial RCV Demands	
Table 2.4: Residential Refuse Disposal Details	
Table 2.5: Commercial Refuse Disposal Details	
Table 2.6: Disposal of Infrequently Generated Waste	
Table 3.1: Equipment Schedule	
Table 3.2: General Refuse Management Checklist	
Table 3.3: Safety Checklist	
Table 3.4: Signage Checklist	
Table 3.5: Cleaning and Maintenance Checklist	
Table 3.6: Refuse Minimisation Checklist	
Table 3.7: Education and Communication Checklist	
Table 3.8: Monitoring and Review Checklist	
Table A.1: Generation Rates	
Table A.2: Residential Building 1 Refuse Calculations	
Table A.3: Commercial Refuse Calculations	
Table A.4: Commercial Refuse Waste Levy Calculations	31
Figure Index	
Figure 1.1: Site location, Source: Google Maps	
Figure 1.2: Site area, Source: Google Maps	15



1 Introduction

1.1. Background

TTM Consulting has been engaged by Dowse Projects to prepare an OWMP to support the proposed mixed-use development located at 19-25 Campbell Street, Bowen Hills. It is understood that a development application will be lodged with BCC.

1.2. Scope

The content of this OWMP is intended to provide information in reverse order to the typical movement of waste streams from disposal to collection. The reverse order provides context for refuse collection, storage and transfer. Information on refuse disposal and collection points is given for each use within the development.

The items covered within the OWMP are described in Table 1.1. The key information for Council approval can be found in Section 2.

Table 1.1: Scope Items

Item	Description
Refuse streams	Identification of refuse streams & anticipated development refuse volumes likely to be produced
Refuse separation Recommendations for appropriate segregation methods for each refuse stream	
Refuse collections	Assessment of refuse collection vehicle (RCV) access and maneuvering
Refuse storage	Detailed analysis of refuse storage facilities and design
Refuse transfer	Assessment of refuse transfer between refuse storage and collections areas
Refuse disposal	Recommendations for refuse disposal within the development
Refuse management equipment	Identification of recommended and optional refuse management systems and equipment
Refuse management operations	Recommendations for operational efficiency and ongoing management, including refuse minimisation, tenant education and safety
Building design	Recommendations for design of refuse management facilities

Detailed information including refuse calculations, site plans and drawings, recommended refuse management equipment and system specifications, common refuse signage as well as a list of terms and abbreviations are provided in the appendices.

The recommendations in this OWMP relate to the operational phase of the development. Additional requirements for refuse management during or after demolition or construction phases are not included and require a dedicated plan.

The provisions outlined in this OWMP are considered appropriate for this type of development. It is noted that the refuse rooms are suitably sized to accommodate the refuse generated and number of bins proposed based on standard storage and collection methods. The refuse rooms will also accommodate all options for alternate equipment and disposal methods.

Site: 19-25 Campbell Street, Bowen Hills



1.3. Regulatory Considerations

1.3.1. Council's Refuse Planning Scheme

The plan satisfies BCC's requirements by providing the following information:

- Type and quantity of refuse materials that would be generated during the occupancy of the proposed development.
- Refuse collection, storage, transfer and disposal arrangements during occupancy of the completed development.
- Recommended operational requirements for the operational phase of the development, and design requirements for the building and refuse management facilities.

TTM has referred to BCC requirements as outlined in the Refuse PSP. Table 1.2 demonstrates the refuse management items addressed to align with BCC's requirements.

Table 1.2: OWMP Compliance Checklist

BCC S	BCC SC6.26 Refuse Planning Scheme Policy					
Item	ttem Requirement Compliance / Comment					
Sectio	n 3 - Access and Manoeuvrability					
(1)	If refuse collection is from an on-site bin storage area for multiple dwellings or from mobile garbage bins located throughout a development, the pavement/carriageway trafficked by the refuse collection vehicle is a minimum 6.5m wide.	Complies 6.5m is provided.				
(2)	For detached dwellings on rear lots, pavements/carriageways trafficked by a refuse collection vehicle have a minimum width of 5.5m.	N/A				
(3)	The pavement/carriageway has a minimum crossover width of 6.5m and is free from overhanging gardens or trees.	Complies 6.5m is provided.				
(4)	If the collection point is at the kerbside of the internal private road, it is preferred that mobile garbage bins are placed in front of each dwelling. If there are short dead-end streets off the main internal circulating road, sufficient level areas are to be provided beside the main internal circulating road (near the intersection) for a collection point for the mobile garbage bins required for those dwellings.	N/A				
(5)	Turning and manoeuvring facilities for refuse collection vehicles are provided to meet design requirements for the vehicles identified in Table 3.	Complies				
(6)	Subdivision layouts are to provide for the safe and efficient operation and manoeuvring of a side loading refuse collection vehicle. Layouts that require a refuse collection vehicle to reverse more than two truck lengths are to be avoided. If a temporary turnaround is provided, an easement in favour of Brisbane City Council for this purpose will be required over any turning area located within private property. The temporary turnaround is to be constructed to a standard that is satisfactory to Council.	N/A				
(7)	Adequate lift clearances are provided to overhanging trees and wires in accordance with Table 3.	Complies				
(8)	For MGB's, if it is necessary to wheel them to a collection point from a bin storage area: (a) the distance does not exceed 50m; (b) for a retirement facility, the distance does not to exceed 25m;	Complies				

Site: 19-25 Campbell Street, Bowen Hills



	(c) the mobile garbage bin transfer path is free of steps or other obstructions and does not exceed a 1:14 grade.	
(9)	In instances where the gradient of the on-site manoeuvring area is greater than 5% (1:20), the pad that the collection vehicle will stand on while accessing refuse bins at the collection point, is to have a maximum gradient of 2% (1:50).	Complies RCV will stand on 1:20
Section	on 4 - Residential Refuse Collection	
(1)	Residential development is to provide sufficient capacity for 240L of refuse and 240 or 340L of recycling per dwelling, allowing for one collection per week.	Complies – Performance solution of 180L / week for recycling used
(2)	Residential development is to utilise kerbside collection where the locations for both the bin storage area and kerbside collection point can be appropriately accommodated in accordance with section 4.1.	N/A
(3)	a) On-site collection of bulk bins is provided for development comprising greater than 10 dwellings.	Complies
	b) the development comprises greater than 10 dwellings; or where the road verge is not properly shaped to the standard 1:50 gradient and a minimum of 2.5m wide or where the longitudinal road gradient is greater than 1:10.	
(4)	Refuse and recycling collection for a mixed-use development ensures residential and commercial bins are stored separately with separate access to each.	Complies Separate storage areas are provided
Section	on 4.1 - Kerbside Collection (MGB's)	,
(1)	The number and location of mobile garbage bins presented for kerbside collection does not negatively impact on streetscape character, pedestrian and vehicular movement and safety or access for other service providers and utilities (e.g. bus stops).	N/A
(2)	Turnaround facilities for a refuse collection vehicle exist or are provided for where involving staged subdivision developments or where development is located on a no through road.	N/A
(3)	Kerbside collection points for lots with road frontage are to be accommodated on the footpath frontage of the subject site. Each dwelling's collection point is to comprise of a minimum of 2 areas, each with a minimum area of 0.81m2 (i.e. 0.9m x 0.9m) to accommodate mobile garbage bins. These areas can be located together or separately.	N/A
(4)	If a rear lot, the frontage is to include an additional truncated area to provide sufficient space for the servicing of mobile garbage bins. These truncated collection points are to avoid obstructing any driveway or encroachment onto neighbouring frontages. If 2 or more rear lots, no more than 2 adjoining truncated areas are provided for the servicing of mobile garbage bins.	N/A
(5)	Collection points are not located: (a) in a way that obstructs the use or safety of any driveway; (b) within 10m from the tangent point of the kerb radius of a non-signalised intersection or 20m from the tangent point of the kerb radius of a signalised intersection; (c) within 10m from the tangent point of the kerb radius of a roundabout; (d) on arterial road frontages; (e) on verges where the adjacent traffic lane is less than 3m wide; (f) 9m before and 1.5m after a bus stop marker sign; (g) in any other no stopping zone.	N/A
(6)	Where collection is from an internal private road, if there are short no through roads off the main internal circulating road, sufficient level areas are to be provided beside the main internal circulating road (near the intersection) for a collection point for the mobile garbage bins required for those dwellings.	N/A



(7)	The storage area for mobile garbage bins: (a) if contained within the lot: can accommodate 2 areas of 0.81m2 (i.e. 0.9m x	N/A
	0.9m) and is outside the dwelling; or (b) if in a common area: are located in an external enclosure that allows adequate	
	access for residents to all bin(s) and for the bins to be manoeuvred for servicing; or (c) if stored in an enclosed room (other than within a dwelling); are provided with	
	natural or temperature controlled ventilation.	
(8)	Environmental best practices may also include the installation of a trapped waste connection to the sewer system and providing a roof canopy over the designated storage area.	N/A
Section	on 4.2 – On-site Collection (Bulk Bins)	
(1)	In accordance with section 4, development will avoid adverse impacts to residents, pedestrians and roads users by limiting the number of collections required per week while ensuring sufficient refuse and recycling capacity is provided to meet the needs of residents. Table 1 provides details of bulk bin volumes and the number of standard 240L kerbside bins their capacity is equivalent to. These are to be used when identifying the required refuse arrangements.	Complies
(2)	The type of refuse service that is to be used (domestic or commercial) is identified, including whether the refuse collection vehicle is to be front loading, side loading or rear loading (sufficient height must be available).	Complies Rear loading vehicles are proposed.
(3)	A written design proposal for waste collection is to be provided, giving full details of the proposed system, bin sizes, number of bins, storage and collection areas, frequency of collection and the refuse collection vehicle size. Table 2 provides the dimensions and types of bulk bins.	Complies Details are provided within the OWMP.
(4)	The manoeuvring of the refuse collection vehicle is undertaken in a safe and efficient manner, without detrimental impacts to pedestrian amenity or safety, Council or private infrastructure or the function of the road network.	Complies Further details are provided in Section 2 of the OWMP and within the traffic report.
(5)	For multiple dwelling developments fronting a local, neighbourhood, district or suburban road, the refuse collection vehicle may enter the site in a reverse gear in a single movement. An onsite dedicated pedestrian route is provided and is separate from the required vehicle manoeuvring area to ensure pedestrian safety is protected. The pedestrian route is to provide access from the site's frontage to the development and will have a minimum width of 1.2m. The refuse collection vehicle is to leave the site in a forward gear.	Complies RCV's will enter the site via Edgar St and perform a single reversing manoeuvre and exit in a forward gear.
(6)	For multiple dwellings developments fronting an arterial road, or where the refuse collection vehicle cannot reverse onto the site in a single movement, the refuse collection vehicle must enter and leave the site in a forward gear.	N/A
(7)	All entry and exit points are of a width and design that allows for sufficient ingress and egress for the refuse collection vehicle including a 6.5m crossover.	Complies
(8)	To maximise safety, the distance required for refuse collection vehicles to reverse on-site is minimised. Where on-site turnaround of the refuse vehicle cannot be achieved, the bin storage area and collection point is located within 30m of the street frontage.	Complies Reversing distance is limited to the manoeuvring area, adjacent to the storage and collection points.
(9)	Access for a refuse collection vehicle to the collection point is maintained at all times.	Complies RCV access is provided at all times.
(10)	The required vertical and horizontal clearances are provided for the service to operate safely and efficiently. Operational clearance dimensions are shown in Table 3 for various types of collection arrangements.	Complies Operational clearances comply with Table 3 of the Refuse PSP.



(11)	Bulk bins of $1.1 \mathrm{m}^3$ or less are positioned so that collection personnel do not have to move them more than 5m. If a gradient is evident, speed bumps are provided to stop bulk bins from rolling away from the collection point.	Complies Servicing and collection points are located adjacent to each other.
(12)	Bulk bins of 1.5m³ or more are positioned so that front-lift refuse vehicles can drive directly to the container without relocating the bulk bin. If this cannot be achieved due to physical constraints, then the bulk bins are not moved more than 3m from the storage to the collection point.	N/A
(13)	The storage areas for bulk bins are:	Complies
	(a) contained in an enclosure or room of sufficient size for the bulk bin quantity required;	Refer to Sections 2,3 and 4 and Appendix B.
	(b) easily accessible for residents and for the required servicing of bins;	
	(c) screened from neighbouring properties for odour, amenity and noise;	
	(d) protected from the environment;	
	(e) provided with natural or temperature-controlled ventilation if in an enclosed room;	
	(f) kept clear of obstructions, such as fixed bay separators, that impede the ability to change from existing bin sizes or which otherwise limit future refuse collection	
	options;	
	(g) kept clear of other amenities such as air-conditioning units, hot water systems or electrical hubs where located in a bin room.	
(14)	If a refuse or recycling chute is provided:	Complies
	(a) it is to be constructed to allow refuse to fall into the centre of the bin;	Refer to Sections 2,4 and Appendix B.
	(b) it is to have a door / lid to ensure clean changeover of bins;	
	(c) separate chutes and bulk bins are to be used for each waste stream;	
	(d) the room containing the chute and bin or compactor excludes all but authorised personnel.	
(15)	Environmental best practices may also include the installation of a trapped waste connection to the sewer system and providing a roof canopy over the designated storage area.	Complies
Sectio	n 5 – Non-Residential Refuse Collection	
(1)	The requirements for refuse bins or refuse compactors for non-residential	Complies
. ,	development will be assessed case by case, based on the type and amount of waste generated by the development, which is dependent on the operational activities of the development.	TTM has provided this information with input from all consulting disciplines on this project. Commercial and retail waste generation and associated bins are in line with accurate data recently sourced and published, by external LGA's i.e. City of Sydney.
(2)	Sufficient information is provided to demonstrate that refuse collection can occur in an efficient and safe manner on site without adverse impact on amenity (acoustic, odour or visual impacts) and pedestrian and vehicular traffic.	Complies Refer to information detailed within OWMP.
(3)	This information may include evidence from a refuse collection contractor to	Complies
	demonstrate that collection will occur outside normal service/delivery or business times, where seeking permission to allow a refuse collection vehicle to use service bays or parking spaces on the site for access.	Refuse collection contractors can enter the loading dock at anytime however it is likely that timeslots will be assigned by loading dock or facilities management.
(4)	If proposing to use clearances less than the minimum vertical clearances in Table 3, a written confirmation from the proposed waste collection contractor giving full	Complies Operational clearances comply with Table 3 of the Refuse PSP.



	details of the proposed system, bin sizes, number of bins, frequency of collection and the refuse collection vehicle size is to be provided.	
(5)	If the gross floor area of a freestanding food and drink outlet, shop or office is less than 200sqm a dedicated service bay is not required for a refuse collection vehicle.	N/A
(6)	Provision is made for on-site refuse collection for Short-term accommodation if an accommodation hotel or motel.	N/A
(7)	Where disposal of industrial or commercial liquid waste by discharge to a road tanker, the road tanker is to be wholly on-site during collection.	N/A
(8)	The storage areas for industrial bins are to be either within a building or enclosure.	N/A

1.3.2. Waste Levy

The Queensland state government has introduced a levy on commercial wastes sent to landfill. It will normally be applied per tonne of waste and will be passed on by waste collection contractors to customers, possibly based on an assumed volume per bin.

The cost of the levy in the first year is \$75 per tonne, and it will increase by \$5 per tonne each year thereafter. It is anticipated that the development opening year will be 2024 and will therefore have a levy of \$100 per tonne in the first year. This cost will be on top of normal waste collection costs charged by waste collection contractors. Therefore, in order to reduce waste levy costs, waste generators should choose to avoid waste generation through a range of preventative measures, and recycle the waste they do generate as much as possible.

Site: 19-25 Campbell Street, Bowen Hills



1.4. Site Location

The site is located at 19-25 Campbell Street, Bowen Hills, as shown in Figure 1.1 and Figure 1.2. The property description is Lot 10 & 12 on RP144655, Lot 41-45 on RP9895, Lot 1 on RP 151932 and Lot 1 on RP144514.




Figure 1.1: Site location, Source: Google Maps

Site: 19-25 Campbell Street, Bowen Hills





Figure 1.2: Site area, Source: Google Maps



1.5. Development Summary

The mixed-use development is single building consisting of 377 residential units and a combined 382m² of retail GFA.

Table 1.3 provides a summary of the development, including the refuse infrastructure areas as context for the volume information provided in Section 1.6.

Table 1.3: Development Summary

Level	_evel Description		
	Retail	67m ² GFA	
Ground	Retail	78m ² GFA	
	Retail – Food and Beverage	237m ² GFA	
Level 1 - 29	Residential Apartments	377 Units	
Roof	Communal Areas	340m ² + GFA +	

^{*} Areas and unit numbers relevant for refuse calculations only.

1.6. Development Refuse Profile

Table 1.4 and Table 1.5 demonstrate the anticipated volumes for each of the commonly separated refuse streams. All calculations and equipment requirements are based on the development schedules and common waste generation rates as outlined in the detailed information in Appendix A.

Table 1.4: Residential Refuse Summary

Туре	Measure	Quantity	General Waste (L / Week)	Commingled Recycling (L / Week)
All Bedrooms	Units	377	90,480	67,860

Table 1.5: Commercial Refuse Summary

Description	Measure	Quantity	General Waste (L / Week)	All Recycling (L / Week)
Retail	GFA (m²)	382	3,623	10,325

Taking in consideration the waste levy as outlined in Section 1.3.2, examples of additional waste costs for this development are outlined in Appendix A.2. The calculation is based on the anticipated commercial refuse volumes as shown in Table 1.5.

Site: 19-25 Campbell Street, Bowen Hills



2 Refuse Management

This section describes the arrangements for the collection, storage, transfer and disposal of refuse within the development. This includes associated bin quantities, storage capacities, equipment details, collection frequencies and site access details.

2.1. Refuse Collection

2.1.1. Bin Quantities

Table 2.1 below outlines the number of bins per collection. As waste volumes may vary according to the development occupants' attitudes to waste disposal and recycling, bin numbers and sizes may need to be altered to suit the building operation. The table shows the maximum number of bins and equipment expected.

Table 2.1: Bins per Collection

Component	Refuse Stream	Bin / Equipment - Type or Size	Numbers of Bins / Items per Collection
Residential	General Waste	1100L	10 (+1 bin to remain on equipment)
Residential	Commingled Recycling	1100L	21 (+1 bin to remain on equipment)
Camananaial	General Waste	1100L	1
Commercial	Commingled Recycling	1100L	3

2.1.2. Collection Cycle

Table 2.2 and Table 2.3 outline the RCV types and estimated collection frequencies / site entries required to service the site. The type of vehicles allocated, and demand will be subject to final design and potential selection of volume reduction equipment. The figures and days demonstrated apply as an indicative maximum demand.

Table 2.2: Estimated Residential RCV Demands

Residential Refu	se Collections	Day 1	Day 2	Day 3	Day 4	Day 5	Day 6	Day 7	Collections per Week
Compared Master	Collection Days	8		⊘			②		2
General Waste	Vehicle Type	REL RCV		REL RCV			REL RCV		3
Commingled	Collection Days	⊘		⊘		⊘			2
Recycling	Vehicle Type	REL RCV		REL RCV		REL RCV			3
Total Collections per Week		2	0	2	0	1	1	0	6

Site: 19-25 Campbell Street, Bowen Hills



Commercial Collection cycles are based around a 2-day storage for all waste types. This equates to a collection frequency of 3-4 collections per week or 7 collections per fortnight.

Table 2.3: Estimated Commercial RCV Demands

Commercial Refuse Collections		Day 1	Day 2	Day 3	Day 4	Day 5	Day 6	Day 7	Collections per Week
Conoral Waste	Collection Days		\oslash		\oslash		⊘		3
General Waste	Vehicle Type		REL RCV		REL RCV		REL RCV		3
Commingled	Collection Days	③		⊘		⊘		②	4
Recycling	Vehicle Type	REL RCV		REL RCV		REL RCV		REL RCV	4
Total Collections per Week		1	1	0	0	1	1	0	7

2.1.3. RCV Arrangements

All RCV's will enter the site in a forward gear from Edgar Street and perform a single reverse manoeuvre into the loading area, once the service has been completed the RCV will exit the site in a forward gear. The vehicle will stand and service the bins on a flat grade.

All residential collections will be conducted by BCC's waste contractor and commercial / retail collections will be conducted by private contractors. All bins will be collected directly from the respective refuse area / room and returned once serviced.

Further details on vehicle access, egress and on-site manoeuvring can be found in the traffic report.

2.2. Refuse Storage

Residential Units will have 1100L bulk bins stored within the refuse room located on Ground Floor. 4 x 1100L bins will be stored on the automatic rotation equipment for use under the chute systems. Excess bins will be stored in the room.

Commercial / Retail outlets will have 1100L bulk bins stored for use opposite the loading area.

All refuse areas are adequately sized to store all appropriate bins.

A bin wash area will be provided in the refuse rooms and all associate chute discharge / equipment area for residential use will be partitioned for safety purposes.

2.3. Refuse Transfer

Residents will transfer all general waste and recycling to the chutes. Building Management will be responsible to remove full bins from the rotation equipment when full or at regular intervals to prevent overfilling.

All residential and commercial bins will require a minimal transfer distance from the collection area to the servicing area.

2.4. Refuse Disposal

Site: 19-25 Campbell Street, Bowen Hills

The tables in this section summarise general recommended disposal arrangements for frequently generated and infrequently generated refuse for each use within the development. Sections 2.4.1 and 2.4.2 describe



the frequently generated refuse streams that are generated in high volumes for any given period and require significant capacity for storage prior to collections. Section 2.4.3 describes the infrequently generated refuse streams that are generated in relatively low volumes, and where minimal provision for storage can be easily managed by collection frequency.

2.4.1. Residential Refuse

Residents will have receptacles within their units for collection and storage of at least one day of waste and recycling. Once receptacles are full, residents will dispose their waste via dual chute system accessible on each residential level via the hopper doors. The chutes discharge directly into the bulk bins located in the building refuse rooms.

Further details are provided in Table 2.4.

Table 2.4: Residential Refuse Disposal Details

D. C					
Refuse Stream	Disposal Details				
WASTE					
General Waste	Waste bins should always be lined with bags and the bags tied before removal. General waste should weigh approximately 3 kg or less. Waste bins should be accompanied by a commingled recycling bin in order to facilitate separation of general waste and recycling (see below). Residential Apartments Residents will have receptacles within their individual units for collection and storage of at least one day of general waste. Bins are typically placed under the kitchen sink. Additional bins can be placed in other areas as required. Communal Spaces General waste from the communal spaces (e.g. rooftop recreational deck) may include small quantities of food waste, food packaging, drink bottles etc. General waste bins of an appropriate size to accommodate at least one day of waste should be located within the respective areas. Additional bins may be provided for special events.				
Organic (Food) Waste – optional	Separating organic or food waste from general waste may be considered to reduce the total amount of general waste produced. Apartment style equipment such as organic household composter or worm farms are available for use where practical and space allows. Composting should be arranged with the building management. Refer to Appendix C.2 and C.4 for options.				
RECYCLING					
Recycling Comingled, including glass aluminum steel cans tins paper small cardboard semi rigid plastics	Items for recycling must not be bagged and disposed in loose form. Residential Apartments Residents will have receptacles within their individual units for collection and storage of at least one day of recycling. Recycling bins are typically placed under the kitchen sink next to the general waste bin. Additional recycling bins can be placed in other areas as required. Recycling bins will usually be used for all recycling materials (commingled recycling). However, residents are encouraged to make use of the container refund scheme and separate eligible containers from the commingled recycling material (see below). Communal Spaces Recycling from the communal spaces (e.g., residential recreation levels) may consist of recyclable drink containers, food packaging, (clean) paper, cardboard etc. Recycling bins should be located next to waste bins within this area. Extra bins may be provided for special events. Container deposit / refund schemes are currently in place in Queensland. Various models exist including bottle return facilities and (automated) reverse vending machines. Occupants should be encouraged to separate containers that qualify for the schemes from the waste or recycling streams, and send back to a return points.				

Site: 19-25 Campbell Street, Bowen Hills



2.4.2. Commercial Refuse

Bins will be provided for the tenancy. After each day of operation or as required, refuse will be transferred by staff / cleaners to the refuse room and decanted into the appropriate bulk bins. Further details are provided in Table 2.5.

Table 2.5: Commercial Refuse Disposal Details

Refuse Stream	Disposal Details
WASTE	
General Waste	Depending on the type of operations of the individual tenancies, different wastes may be produced. Waste bins should always be lined with bags and the bags tied before removal. Waste bins should be accompanied by a recycling bin in order to facilitate separation of general waste and recycling. For general waste from non-food and beverage outlets, bins of at least 60L capacity should be located in staff rooms, back-of-house or pantry areas. Larger bins an also be placed in areas accessible to the public, e.g. near entrance and exit doors. General waste from food and beverage outlets such as restaurants, takeaways, cafés will be captured by bins typically ranging in size from 30L to 80L that will be placed within the kitchen or back-of-house area to meet the design or layout criteria of the café or restaurant operators.
Organic (Food) Waste — Optional (future)	Separating organic or food waste from general waste is recommended to reduce the total amount of general waste produced. 120L bins can be used in retail and food and beverage outlets, commercial offices should consider benchtop style bin, for disposal of food waste if required. The bins are then transferred to the refuse room for collection. Smaller bins of 120L or 60L caddy bins can be used and the content decanted into bins or food processing equipment in the refuse room. A purpose-built trolley should be used to transfer caddy bins.
Cooking Oil Waste	Waste oils should be disposed separately from general waste if large quantities are produced (e.g. in food and beverage outlets). All waste liquids / oils (e.g. from commercial kitchens) should be separated and stored in clearly labelled containers. Typically, waste oils are removed during delivery of new oils by the supplying contractor. Bunded areas or bunded plastic pallets should be supplied for the storage of liquid waste / oils and stored in a levelled area (e.g. refuse room). Bunded pallets can be stored indoors or purpose built for outdoors. They should be routinely inspected to ensure maintenance of their integrity. Each pallet should be capable of storing of at least one-third of its contents if there is a leak.
RECYCLING	
Commercial Comingled, including: glass aluminum steel cans tins paper / Cardboard small cardboard semi rigid plastics	Depending on the type of operations of the individual tenancies, different recycling materials may be produced. Items for recycling must not be bagged and disposed in loose form. This can be done by decanting the materials from the individual receptacles into a larger container / bin on a trolley for transport to the refuse room. For commingled recycling material from non-food and beverage outlets, bins of at least 60L capacity should be located in staff rooms, back-of-house or pantry areas. Larger bins an also be placed in areas accessible to the public, e.g. near entrance and exit doors. Commingled recycling from food and beverage outlets such as restaurants, takeaways, cafés will be captured by bins up to 240L that will be placed within the kitchen or back-of-house area to meet the design or layout criteria of the cafe or restaurant operators.

Site: 19-25 Campbell Street, Bowen Hills



2.4.3. Infrequent Waste

Table 2.6: Disposal of Infrequently Generated Waste

Refuse Stream	Disposal Details
Green Waste	Green waste is not typically produced from this type of development other than from surrounding landscaped areas or potted plants. Green waste is usually removed by the designated maintenance contractor. The engaged contractor will be required to send this material to a composting or resource recovery facility rather than to a landfill if locally available.
Hard Waste / Bulky Goods	Hard waste may be stored in a designated room which should be located on the loading dock level. Alternatively, collections can be coordinated, and hard waste / bulky goods moved to the loading dock or a designated area for removal prior to collection. When storing bulky goods in a loading dock, it is recommended that items are placed on a pallet for easy loading via a pallet jack or forklift onto the RCV.
Hazardous Waste (paints, batteries and cartridges) Electronic Waste	Where applicable, occupants usually make their own arrangements for the disposal of specialised or hazardous waste and electronic waste such as recycling of toner cartridges and batteries. Please refer to local council and state government websites for disposal options. It is an expectation that the building management assist with disposal of hazardous, electronic or liquid waste and any paint or chemicals as required and requested. Hazardous waste must be handled with due
	care, separated and securely stored for collection by a specialist waste contractor. Please refer to local council and state government websites for further information.

Site: 19-25 Campbell Street, Bowen Hills



3 Recommended Operational Requirements

3.1. Operational Equipment Summary

Equipment required or suitable for use as part of the operational phase of the development is outlined in Table 3.1. Lists of equipment, equipment suppliers and refuse management service providers for use during the operational phase of the development can be found in Appendix C.

Table 3.1: Equipment Schedule

Component	Description	Quantity	Notes
	General Waste Bins (incl. bins under chutes)	11	1100L bins
	Commingled Recycling Bins	22	1100L bins
Residential Refuse	Dual Chute System	2	For waste and recycling disposal. See Appendix C.2 and C.3.
	Carousel Bin Rotation System – 1 with compaction unit for waste	2	See Appendix C.2
	General Waste Bins	1	1100L bins
Commercial Refuse	Commingled Recycling Bins	3	1100L bins
	Refuse Trolleys	TBD	See Appendix C.2 and C.3.

3.2. On-going Management

Responsibilities have to be assigned for all on-going refuse management operations. This is generally done by a building manager, staff and / or cleaners. The following lists (Table 3.2 to Table 3.8) are designed to help managing responsibilities and monitor the refuse operations in order to maintain efficient services and a safe environment.

Table 3.2: General Refuse Management Checklist

Objectives	Checked	Remarks
Organising of weekly pick-ups for all refuse streams.		Liaise with private contractors and Council as required.
Managing daily bin transfers between refuse storage / collection areas if required.		
Check bin fill levels and rotate / swap bins as required, e.g. under chutes.		

3.2.1. Safety

Transferring refuse bins and using refuse management equipment are considered hazardous tasks. Therefore, contractors must ensure that a full risk assessment of equipment, surfaces and related gradients is complete. The contractor must provide procedural documentation to appropriate personnel prior to delivery of equipment and occupancy of the development.

Site: 19-25 Campbell Street, Bowen Hills



Table 3.3: Safety Checklist

Objectives	Checked	Remarks
Abiding by all relevant occupational health and safety legislation, regulations and guidelines to ensure site safety for residents, visitors, staff and contractors.		
Assessment of any manual handling risks and preparation of a manual handling control plan for waste and bin transfers.		
Provision of equipment manuals, training, health and safety procedures, risk assessments and personal protective equipment to staff / contractors in order to control hazards associated with all waste management activities.		

3.2.2. Signage

All receptacles, bins and other refuse management equipment will have adequate signage. Standard signage will be provided in and around waste collection and storage areas (see Appendix D).

Table 3.4: Signage Checklist

Objectives	Checked	Remarks
Ensuring compliance of signage with government local council regulations.		Use signage provided by Council's if available
Ensuring that labelling on bins, refuse room etc. is appropriate and clear and easy to read and updated if required.		

3.2.3. Cleaning and Maintenance

Regular cleaning and maintenance of all refuse management facilities is important to maintain a safe and hygienic environment for residents, visitors, staff and contractors.

Table 3.5: Cleaning and Maintenance Checklist

Objectives	Checked	Remarks
General cleaning of all refuse holding and transfer areas including Refuse bins, rooms and storage areas		Frequency depends on refuse generation and building operation.
 Refuse transfer areas including lifts and staircases Refuse chutes and hopper doors Any other refuse management equipment 		
Coordination of specialised cleaning contractors as required.		
Maintenance and servicing of refuse management equipment as per schedule.		Frequency depends on equipment and building operation.
Coordination of specialised equipment contractors as required.		

3.2.4. Refuse Minimisation

Refuse minimisation is an important part of any site operation. At a minimum, the following should be implemented. Additional refuse minimisation options can be found in Appendix C.

Site: 19-25 Campbell Street, Bowen Hills



Refuse minimisation requires regular reviewing to ensure operational sustainability of refuse volumes, equipment and economic feasibility. It is recommended that refuse weights and movements are noted and reviewed. An external review is usually conducted 12 to 18 months after the implementation of the plan.

Table 3.6: Refuse Minimisation Checklist

Objectives	Checked	Remarks
Regular review of material quantities to avoid over-ordering.		
Consideration of secondary and recycled materials where possible.		
Encouraging refuse minimisation through education and signage (see below).		
Reduce refuse through continuous monitoring and review (see below).		

3.2.5. Education and Communication

On-going education is important to ensure people continue to use the facilities as originally intended. All body corporate and leasing contracts should contain clauses pertaining to waste management arrangements and use of any associated equipment.

Table 3.7: Education and Communication Checklist

Objectives	Checked	Remarks
Communication of refuse management arrangements to residents, staff and contractors as required.		
Consideration of promotional opportunities for any successes e.g. awards programs.		

3.2.6. Monitoring and Review

Regular monitoring and inspections of waste and related equipment and facilities from the development should be conducted by building management or designated staff for maintenance and sustainability.

Table 3.8: Monitoring and Review Checklist

Objectives	Checked	Remarks
Continual monitoring of equipment uses and scheduling to ensure best operational outcomes.		
Regular review of refuse management equipment and facilities such as bin volumes, refuse storage capacities and stormwater management arrangements.		

Site: 19-25 Campbell Street, Bowen Hills



4 Recommended Design Requirements

This section lists general recommended design requirements for the building and refuse management facilities. They should be considered for optimal refuse management within the development, and to comply with relevant regulations and Council requirements. Further details can be found in BCC's Refuse PSP.

4.1. Bin Servicing Point

The RCV's will park in the loading bay area as detailed in Section 2.1.3 for refuse collections. The bin service point will have the following features:

- Has sufficient access and clearance for the waste and recycling collection vehicles to service the bins, including no overhead obstructions.
- Allows bins to be serviced safely while minimising the impediment to vehicle movements during servicing.
- Is clearly separated from car parking bays, footpaths and pedestrian access.
- Is of sufficient size to accommodate the bins.
- Is devoid of stairs, lips or ramps and allows bins to be manoeuvred easily.
- Does not block the entry and exit to the property.
- Is not adjacent to a kitchen or eating area for public use.
- Is over 5m from any door, window or fresh air intake within the development or any adjoining site.
- Is screened sufficiently to minimise the view of bins from neighbouring properties or passing vehicles and pedestrian traffic external to the site.
- Is positioned away from entrances to shops or residential premises.

4.2. Refuse Chutes

The requirements for a waste removal system incorporating waste chutes are as follows:

- Adequate strength for its purpose, including additional reinforcing where necessary at joints, bends and hopper intersections.
- Insect and vermin proof.
- Constructed and installed to prevent the following during use and operation of the system:
 - Transmission of vibration to the structure of the premises.
 - Excessive odour and noise to the occupants of the building.
- Installed in a fire rated duct and ventilated in compliance with building requirements of the Building Code of Australia.

Site: 19-25 Campbell Street, Bowen Hills



- Comply with the waste chute manufacturer's technical specifications and / or operational limitations, including installation design features and ancillary equipment required to prevent blockages and noise disturbances.
- Fitted with a shutter at the base of the chute for closing off the chute manually during bin exchange and automatically in the case of fire.
- Discharge centrally above the waste containers in the waste storage room.
- Chute hoppers to be:
 - Provided on each (residential) floor and be located in a freely ventilated position in the open air or in a dedicated room or compartment.
 - Be easily accessed by the occupants of each unit.
 - Be separate from any habitable room or place used in connection with food preparation or living areas.
 - Be designed and installed to:
 - o Close off the service opening in the chute when the device is open for loading.
 - o Be between 1.0m and 1.5m above floor level.
 - o Automatically return to the closed position after use.
 - o Permit free flow into the chute.
 - o Not project into the chute.
 - o Allow easy cleaning of the device and the connection between the service opening and the
 - Have the largest dimension of the service opening (the diagonal of a rectangular opening) not exceeding 0.75m diameter of the chute with which the hopper is connected.
 - Have a surround on the wall around the hopper that is at least 300mm wide and made of glazed tiling or other impervious material that can easily be cleaned.
 - Have a floor adjacent to the hopper that is paved with hard impervious materials with a smooth finished surface.
 - Be ventilated and finished with an impervious material covered at all angles, if located within a waste disposal room.

4.3. Refuse Rooms

The refuse rooms will have the following features in order to minimise odours, deter vermin, protect surrounding areas, and make it a user-friendly and safe area:

- Be insect and vermin proof.
- Fire rated and ventilated in accordance with the National Construction Code Building Code of Australia.

Site: 19-25 Campbell Street, Bowen Hills



- Doors must be wide enough to allow for the easy removal of the largest container to be stored.
- The walls, ceilings, floors and equipment are to be designed and constructed of impervious material with a smooth finish to allow for easy cleaning.
- The floors to be graded to fall to a drainage point.
- Drainage points connected to sewer in accordance with trade waste requirements.
- A hose cock must be provided inside the room for cleaning bins and the rooms.
- Adequate artificial lighting.
- Not located adjacent to or within any habitable portion of a building or place used in connection with food preparation (including food storage).
- Permit unobstructed access for removal of the containers to the service point and for positioning the containers correctly in relation to the chutes.
- Will be attractively designed to minimise their visual impact on the surrounding areas.
- Does not have any steps or lips.
- Is enclosed on all sides except for the gated entrance to ensure bins are not visible from a public place, neighbouring properties, passing vehicles or pedestrian traffic external to the site.
- Is of sufficient size to accommodate the bins with sufficient clearance around the combined bin area.
- Is positioned away from entrances to shops or residential premises.
- The height of the bin storage area allows for waste bins to be opened and closed.

4.4. Bin Carting

The bin carting route will the following features:

- Is via hard stand pathways.
- Allows bins to be easily manoeuvred.
- Does not impede traffic flow.
- Does not extend through any habitable parts of a building or food premises.
- Does not have any lips, stairs or steps for bins to be manoeuvred easily.

Site: 19-25 Campbell Street, Bowen Hills



4.5. Bin Wash

A bin wash-down facility will be provided in each refuse room. It will have the following features:

- Constructed hardstand with a solid concrete base.
- Roofed and designed to prevent entry to rainwater.
- Graded to fall to a drainage point that is connected to sewer in accordance with trade waste requirements.
- Provided with a hosecock for cleaning.
- Is in a well-ventilated portion of the basement and not within 10m of an opening to a food premises or food handling area.

4.6. Storm Water Prevention and Litter Reduction

Designated staff / cleaners are responsible for on-site storm water pollution and litter reduction. To limit the impact on the environment and site, the following measures should be taken into account:

- Providing adequate signage to promote litter control.
- Providing sufficient refuse bins in appropriate areas.
- Preventing unauthorised entry to waste areas.
- Monitoring waste and prevent waste overflow.
- Promoting best practices for waste minimisation.
- Installing litter traps in car parks for any unwanted discharge.

4.7. Ventilation

Natural or mechanical ventilation must be provided to waste storage areas unless refrigerated below 4° C. Natural ventilation means unobstructed, permanent openings direct to external air no less than one-twentieth (1/20) of floor area. Mechanical ventilation requires a minimum rate of 100L/s and 5L/m² exhaust rate.

Site: 19-25 Campbell Street, Bowen Hills



Appendix A Detailed Refuse Calculations

Site: 19-25 Campbell Street, Bowen Hills



A.1 Refuse Calculations

The residential generation rates used for the calculation of refuse produced has been applied using the BCC – WaRRS new required rates.

The retail/commercial generation rates used for the calculation of refuse produced has been generally applied from the City of Sydney's 'Guidelines for Waste Management in New Developments'

These generation rats are based on data from the Commercial Waste Data Review commissioned by the City of Sydney, document dated 22 February 2017. General waste (uncompacted putrescible) and co-mingled recycling waste density factors are applied according to Western Australia Waste Authority figures. All applied generation rates are indicated in Table A.1.

Table A.1: Generation Rates

Туре	Measure	General Waste	Commingled Recycling	Source
Residential				
Residential Units	L / Unit / Week	240	180	BCC – WaRRS (new requirements)
Commercial				
Food and Beverage	L / 100m² / Day	200	500	City of Sydney – Food and Beverage
Retail	L / 100m² / Day	30	200	City of Sydney - Retail

^{*}Food waste service is not initially being considered; therefore, food waste generation volumes have been added to general waste for the purpose of calculations.

Residential waste volumes indicated include compaction. Recycling compaction is prohibited and therefore has not been applied. All commercial volumes are calculated based on a seven-day operation.

Table A.2: Residential Building 1 Refuse Calculations

Description	Quantity	Measure	General Waste (L/Week)	Commingled Recycling (L/Week)
1, 2 & 3 bedroom	Units	377	90,480	67,860
Compacted Volumes (L / Wo	eek)		30,160	N/A
Volumes per Collection (L / Collection)		12,926	29,083	
Collections Per Week		eek	3	3
	Storage Capacity Equipment Size Equipment Quantity Required (min) Equipment Quantity Provided **		3 Days	3 Days
Collection and Equipment Details			1100L	1100L
Details			10 Bins	21 Bins
			11 Bins	22 Bins

^{* 1} spare bin to be provided for equipment while all full bins are presented for collection.

Site: 19-25 Campbell Street, Bowen Hills



Table A.3: Commercial Refuse Calculations

Description	Quantity	Measure	General Waste (L/Week)	Commingled Recycling (L/Week)
Retail 1	GFA m ²	78	164	1,092
Retail 2	GFA m ²	67	141	938
Retail 3 – Food and Beverage	GFA m ²	237	3,318	8,295
Total Volume per Week (L / Week)		3,623	10,325	
Volumes per Collection (L / Collection)		1,035	2,950	
	Collections Pe	r Week	3.5 or (7 per fortnight)	3.5 or (7 per fortnight)
Collection and Equipment	Storage Capac	city	2 Days	2 Days
Collection and Equipment Details	Equipment Size		1100L	1100L
	Equipment Quantity Required (min)		1 Bin	3 Bins

^{** 1} spare waste bin to be provided under the chutes when all full bins are presented for collection.

A.2 Commercial Refuse Volume to Weight Conversion

Table A.4: Commercial Refuse Waste Levy Calculations

Description	Measure	General Waste	Commingled Recycling
Total Volumes	L / Week	3,623	10,325
Total volumes	m³ / Week	3.6	10.3
Conversion Factor *	kg / m³	150	63
Tonnes	T / Week	0.5	0.7
Tonnes per Year	T / Year	28.3	33.9
Diversion Potential	-	46%	54%
Waste Levy **	\$ / Year	\$2,124.98	\$1,271.91

^{*} Applies to uncompacted volumes.

Site: 19-25 Campbell Street, Bowen Hills

^{**} If 100% of food waste will be diverted from general waste, the waste levy can be significantly reduced.




Appendix B Site Plans and Drawings


Site: 19-25 Campbell Street, Bowen Hills



B.1 Ground Floor Level



Source: Nettletontribe, drawing 11703_SK101, revision 8, dated 25/05/2021 – Ground Floor Plan



Glerk

Project Name
BOWEN HILLS
RESIDENTIAL
Project Address
19- 25 Campbell
Street, Bowen Hills

GROUND FLOOR PLAN

<u>ν</u>	101	03 SK101	11703
1:200	Sheet Slave A1	MH	No

nettletontribe

EDAS SECTIONOM STREET



Appendix C Systems and Specifications

Site: 19-25 Campbell Street, Bowen Hills



C.1 Typical Refuse Bins

Bin Types	Waste Streams	Examples	Information
Residential unit bins	General waste and recycling		Various options and sizes. Built and standalone bin available. Examples: https://www.bunnings.com.au
Back-of- house bins	General waste, recycling, food waste, paper / cardboard		Various options and sizes available. Tenant to supply depending on preference and space available. Example: 60L metro bins Dimensions approx. 559 x 279 x 635mm (L x W x H) Examples: https://www.spacepac.com.au
240L bins	General waste, paper, recycling, green waste		Dimensions approx. 740 x 580 x 1080mm (L x W x H) (dimensions may depend on contractor) Examples: http://www.justwheeliebins.com.au , http://wheeliebinsonline.com.au
1100L bins	General waste, recycling, paper / cardboard	SULO	Dimensions approx. 1070 x 1240 x 1330mm (L x W x H) (dimensions depend on contractor) Examples: http://www.justwheeliebins.com.au, https://www.australianwaste management.com.au

Site: 19-25 Campbell Street, Bowen Hills



C.2 Typical Refuse Management Equipment

Systems	Waste Streams	Examples	Information
Organics Household Composting, Worm Farm, Digesters	Food waste / organics	State of the state	Organics / food waste separation, composting and digesting; household-type and commercial grade equipment available Examples Urban Composter https://www.urbancomposter .com.au Closed Loop https://closedloop.com.au/ upcycling-products ORCA https://www.feedtheorca.com
Food Waste Processing, Storage and Disposal	Food waste / organics	ANICS PROCESSION ORGANICS ORGANICS ORGANICS ORGANICS	Volume reduction and organics / food waste recycling through food waste separation and macerating Examples: Pulpmaster Food Processing and Storage https://pulpmaster.com.au Under-sink food waste macerators and disposers https://www.insinkerator.com.au (household type macerators) https://insinkerator.emerson.com (commercial-grade macerators)
Cooking oil storage and recycling	Used cooking oil	Crist?	Cooking oil recycling Example: https://www.cookers.com.au Cooking oil delivery, used oil collection and provision of required equipment
		Cookers PH I IUO 882299	

Site: 19-25 Campbell Street, Bowen Hills



Systems	Waste Streams	Examples	Information
Bunded pallets	Liquid Waste		Spill containment, e.g. for waste cooking oil containers Example: https://www.tradeenviro .com.au/bunded-pallets https://www.materialshandling .com.au/products/bunded-pallet
Trolleys	General waste, recycling, food waste, paper / cardboard		Assisted manual transfer of refuse Examples: https://rubbermaidcommercial .com.au/products/waste- management/mega-brute https://www.materialshandling .com.au/products/deluxe-compact- cleaning-carts
Chute systems	General waste, recycling, food waste	BIN CHUTE	Refuse disposal in multi-storey buildings through refuse chutes: single chute for waste only, or single chute with diverter system or dual chute for disposal of waste and recycling Examples: https://www.wastech.com.au/products/chutes https://www.elephantsfoot.com.au/products/chutes
Bin tugs	-	No.	Dimensions: 650mm L x 609mm W Assisted transfer of refuse Examples: http://ev.spacepac.com.au /categories/tugger, https://www.spacepac.com.au /product/wheelie-bin-aluminum- steel-trailers
Bin Trailers	-		Dimensions: 2100mm L x 600mm W

Site: 19-25 Campbell Street, Bowen Hills



C.3 Refuse Transfer and Disposal Methods

	fuse Transfer and Disposal Methods	
Method	Examples	Description
Manual transfer / disposal		 Manual transfer is simply the process of physically carrying waste bags, food waste receptacles or recycling boxes and crates without assistance. From a safety perspective, this is acceptable for small quantities and initial disposal into refuse chutes, refuse compartments or, in the case of ground level activities, directly into the refuse storage room. Waste material should be bagged prior to any transfer from apartments, suites, offices, back-of-house areas etc. to waste storage compartments or rooms. Food waste should be placed in receptacles such as a caddy style bin or bucket which will not allow leakage during transfer. Recycling material should be placed in boxes or crates prior to transfer. Cardboard and paper items can be placed within another cardboard box for transfer. Examples: https://www.alamy.com
Assisted manual transfer		Assisted manual transfer includes the use of any wheeled container, wheelie bin or trolley with a capacity to carry refuse items with a combined weight of 20kg and above. The equipment bares the weight of the material, but it still requires physical force and or balance to move the bin or trolley. From a safety perspective, this type of equipment should be a minimum requirement for transfer of material greater than 20kg and when transferring between individual levels to the refuse storage room or loading areas. Use of enclosed or caged equipment will also eliminate 'litter or leakage trails' which can occur when using open or unsealed equipment. Examples: https://www.justwheeliebins.com.au , https://www.materialshandling.com.au
Gravity transfer / disposal		Gravity transfer describes the use of refuse chutes. This typically includes access at all floors and discharging in bulk bins in ground floor or basement refuse rooms. Examples: https://www.elephantsfoot.com.au/products/chutes , https://www.wastech.com.au/products/chutes
Assisted transfer		Assisted transfer includes the use of any container with capacity to carry 20kg or more, pushed or towed by mechanical or electrical self-propelling equipment.

Site: 19-25 Campbell Street, Bowen Hills



C.4 Refuse Minimisation Options

Refuse Minimisation Options – Waste

Systems	Description
Food rescue	OzHarvest and Second Bite are food rescue organisations working throughout Australia. The organisation collects surplus foods from businesses (including Woolworths, Coles, Goodman Fielder and other smaller companies) and redistributes the foods to welfare agencies. They provide regular scheduled collections or adhoc / on call collections, and they have refrigerated vehicles. Other accepted items include fresh fruit and vegetables, tinned goods, cold meats and deli items, and readymade meals (which will only be accepted frozen). Where food rescue organisations are available, consideration may be given to suitable space for the temporary storage of food stuffs, including dry storage and the placement of a small fridge if cold room space is not available. There is no associated collections cost. Hence, it can be considered a zero-cost option for disposal of what would otherwise be food waste, and it supports the community at the same time.
Composting	Food waste composing is an option of reducing the amount of general waste going to landfill where organic waste can create methane gas due to anaerobic digestion, which contributes to global warming. Systems of different scales exist from small benchtop composters for individual households or apartments to commercial size systems. Examples are shown below. The process usually involves breaking down organic food scraps through natural processes. This includes systems such as worm farms or composters where microbes break down the food waste, with or without the aid of compost additives. The composted products are rich in nutrients and good bacteria, and they can be added to flower bed or gardens. Most food wastes and other organic (garden) material can be composted including meat, fish, vegetables, fruit, dairy, coffee or wilted flowers. However, large bones, excessive liquids such as cooking oil or seafood shells should not be placed in the composers. Sources: https://closedloop.com.au/upcycling-products , https://www.teedtheorca.com
Food waste separation and collection	When considering separation of organic food waste, the handling and potential for volume reduction should also be considered. As an example, the Pulpmaster system can be used to reduce the stored volume of food waste produced, and to prepare the material for re-use. Typically, the system is placed in proximity to sink areas in the kitchen, particularly where food preparation waste or plate scrapings can be easily disposed. This provides a fully sealed transfer system for storage and collection. Pulping systems can also be placed back-of-house spaces for

Site: 19-25 Campbell Street, Bowen Hills



Systems Description

restaurants and cafes or placed within a refuse room for centralisation to multiple users. Pulped food waste is pumped into holding tanks for storage and collection via a 50mm pipe and collected by a liquid vacuum tanker.

The images below provide visual context of the connection from pulping machine to storage tank and the option for decanting 120L bins into the machine via a bin lifter and auger feed. The tank may be up to 20m away from the pulping machine. The distance is increased when including vertical drops from upper levels of the building. The storage tank may be up to 30m from a loading area, with the only requirement being a service pipe with camlock end connection placed within proximity of the loading area. Collections are completed by a vacuum tanker which may range in size depending on the size of the storage tanks and the distance of the tank from the loading area.









Source: http://pulpmaster.com.au

Waste Conversion

Converting waste by reducing its volume and weight means less material to be disposed of, which results in fewer refuse collection vehicle kilometres. This allows cost savings in logistics and has a positive environmental effect due to less fuel used per amount of waste to be disposed.

As an example, OMPECO provide a solution for converting general and medical waste into a sterilised, dehydrated ground material as shown below. The process involves loading the sterilisation chamber with waste material and crushing / shredding of the material by rotors to produce a fine ground. During the process, the material is heated by friction to 100°C which causes the moisture in the waste material to evaporate. After evaporation, the material is heated further to sterilisation or pasteurisation. The ground material is then cooled down to be unloaded from the converter. The final product has excellent long-term handling and storage properties, the it has up to 80% less volume and 50% less weight than the original waste material. It can be used in waste to energy systems as it is comparatively dry with a high calorific value.







Source: http://www.ompeco.com/italian/language/en/home-2/#

Waste compaction

Various compaction equipment exists for reducing the volume of (general) waste. As a result, less bins and / or fewer bin collections and service vehicle trips are required, which helps to reduce costs and environmental impact.

Site: 19-25 Campbell Street, Bowen Hills

41



Systems Description Examples of typical waste compaction equipment include the following: Under chute compactors can be installed in developments with waste chutes. This allows to compact waste material before it is discharged from the chute into the waste bins. Bin presses can be used to annually compress waste material in bins of different sizes. For public spaces, litter bins are available with a built-in compaction mechanism that reduces the volume of waste material in the bins. An innovative example is the solar compactor shown below. Energy produced by a solar panel on top of the bin is used to operate a fill level sensor and automated internal compaction mechanism, allowing up to eight times more waste to be stored in the bin before collection is required. In addition, notification about the fill level of the bins can be sent out in order to monitor bins and manage collection frequencies. Sources: https://www.wastech.com.au/products/compactors, https://www.wastech.com.au/products/chutes/ecopac-compactor, https://wasteinitiatives.com.au/products/waste-compactors, https://www.solarbins.com.au/features/bigbelly-solar-bin Charity A good way of minimising waste is to reuse items that are still good to use. Several charity organisations exist donations that accept items such clothing, shoes, bedding, books, toys, furniture, kitchenware and other household items. The donated items must not be torn, damaged or broken. Electrical appliances such as white goods are usually not accepted. Common organisations operating in Australia include Saint Vincent de Paul Society (Vinnies) and Lifeline (see images below). Items can be placed into the organisations' charity / donation bins located in various public spaces such as near community or shopping areas. Alternatively, they can be dropped off at the organisations' shops during opening hours. Refer to https://www.lifeline.org.au or https://www.vinnies.org.au for further information. For larger developments and precincts where large amounts of donation items can be expected, the placement of charity bins within the development should be taken into consideration. /innies **Vinnies**

Sources: https://www.vinnies.org.au, https://lifelinesouthcoast.org.au

Site: 19-25 Campbell Street, Bowen Hills Reference: 21BRW0002



Refuse Minimisation Options - Recycling

Systems Description Container Container deposit / refund schemes are currently in place in several states in Australia. Various models exist including bottle return facilities and (automated) reverse vending machines. deposit schemes Residents, tenants, staff and cleaners should be encouraged to separate containers that qualify for the schemes from the waste or recycling streams, and return them to one of the return points. Storage space or dedicated bins within tenancies, apartments or communal areas should be provided. For larger developments or precincts where large amounts of empty containers are expected, consideration may be given to an on-site return point. The return points should be located near recycling bins so that cardboard boxes or plastic bags that have been used to transfer the empty containers to the return point can be disposed appropriately. This can prevent cluttering of the area around the return point. The images below show a typical return point and containers that commonly qualify for a deposit refund. Sources: https://returnandearn.org.au, https://envirobank.com.au/bottle-and-can-recycling-queensland, https://www.containersforchange.com.au/how-it-works

Site: 19-25 Campbell Street, Bowen Hills



5 Sorting Equipment Bin Cleaning Equipment \bigcirc \sum Bins (General), Bin Stands 5 Smoking Management Waste Cooking Oil Systems Composting Pulping, Digestors \ Nacuum Systems, Food Waste Management **Drain Protection** 5 \bigcirc \sum Response, Absorbents, Spill Containment, Spill \mathcal{E} Weighing Systems Bin Rotation \bigcirc 5 Bin Lifters / Tippers Equipment \mathcal{S} > Trolleys / Manual Handling 5 5 Bin Tugs / Trailers \bigcirc 5 Chutes \mathcal{S} \mathcal{E} Glass Crushers 5 5 Shredders 5 \sum \mathcal{S} > Compactors 5 5 \mathcal{S} \bigcirc **Balers** https://www.materialshandling.com.au **Elephants Foot Recycling Solutions** http://www.elephantsfoot.com.au Waste Management Equipment http://www.absorbenviro.com.au http://www.electrodrive.com.au http://www.tradeenviro.com.au https://wasteinitiatives.com.au http://www.spacepac.com.au http://www.bottlecycler.com http://ev.spacepac.com.au http://www.miltek.com.au Electrodrive / Lift Master www.spillstation.com.au http://wastech.com.au http://pakmor.com.au https://draffin.com.au Trade Environmental Spillstationaustralia Spacepac Solutions **Materials Handling** Waste Initiatives Absorbenviro BottleCycler Spacepac Wastech Pakmor Miltek Draffin

Refuse Management Equipment Suppliers

Site: 19-25 Campbell Street, Bowen Hills

	_	
Ì		
_	7	
	Ξ	

				ı		ı	ı	ı	ı	ı	
Sorting Equipment											
Bin Cleaning Equipment											
Bins (General), Bin Stands									<u></u>	<u></u>	\(\)
Smoking Management									\bigcirc		
Waste Cooking Oil Systems								<u>></u>			
Composting				\bigcirc	S	S	S			S	
Food Waste Management \ Vacuum Systems, Pulping, Digestors	(S)	\bigcirc	<u>S</u>								
Spill Containment, Spill Response, Absorbents, Drain Protection									\bigcirc		
Weighing Systems											
Bin Rotation											
Sin Lifters \ Tippers											\bigcirc
Trolleys / Manual Handling Equipment									\bigcirc	<u>></u>	
Bin Tugs / Trailers											
Setud											
Glass Crushers											
Shredders											
Compactors											
Balers											
Waste Management Equipment	Pulpmaster http://pulpmaster.com.au	Australian Vacuum Systems http://www.australianvacuumsystems.c om.au	Meiko https://www.meiko.com.au	Closed Loop Organics https://closedloop.com.au/upcycling- products_	Compost Revolution https://compostrevolution.com.au	Urban Composter https://www.urbancomposter.com.au	ORCA Digester https://www.feedtheorca.com	Cookers https://www.cookers.com.au	Rubbermaid https://rubbermaidcommercial.com.au/ products/waste-management	Sulo http://www.sulo.com.au	Australian Waste Management https://www.australianwastemanageme nt.com.au/products



C.6 Refuse Management Service Providers

Specialist Waste Services	Food Waste	Waste Cooking Oil	Hazardous Waste	Liquid Waste	Electronic Waste	Industrial Waste	Construction & Demolition Waste	Waste Water	Secure Document Destruction
Cleanaway * https://www.cleanaway.com.au		\bigcirc	\bigcirc				\bigcirc	\bigcirc	
JJ Richards * https://www.jjrichards.com.au		\bigcirc	\bigcirc	\bigcirc		\bigcirc	\bigcirc	\bigcirc	
Veolia * https://www.veolia.com/anz			\bigcirc	\bigcirc	\bigcirc		\bigcirc	\bigcirc	\bigcirc
Suez * https://www.suez.com.au				\bigcirc	\bigcirc		\bigcirc	\bigcirc	
SecondBite https://www.secondbite.org	\bigcirc								
OZ Harvest https://www.ozharvest.org	\bigcirc								
Cookers https://www.cookers.com.au		\bigcirc							
ToxFree https://www.toxfree.com.au			\bigcirc		\bigcirc	\bigcirc			
AceWaste https://www.acewaste.com.au			\bigcirc			\bigcirc			

Site: 19-25 Campbell Street, Bowen Hills



Appendix D Refuse Signage

Site: 19-25 Campbell Street, Bowen Hills



D.1 Refuse Signage

Waste signage guideline are provided by the Queensland government: https://www.qld.gov.au/environment/pollution/management/waste/recovery/recycling/signage.

General Refuse Signage









Other Refuse Signage









48



D.2 Chute Signage



49



D.3 Other Refuse, Facility and Safety Signage

Various signage including refuse area, safety and facility signage should be arranged through certified signage providers. Example signs can be found at http://www.signblitz.com.au, https://www.smartsign.com.

Example Refuse Room Signage

WASTE RECYCLE ROOM CLEANERS ROOM

GARBAGE ROOM STORAGE ROOM

Example Facility Signage









Example Safety Signage





COMPACTOR RULES

- All trash must be securely bagged prior to disposal.
- Comply with all recycling regulations.
- NO toxic or combustible materials.
- NO auto batteries, oils, or petroleum.
- NO furniture or large

KEEP AREA CLEAN AND LITTER-FREE!



50

Site: 19-25 Campbell Street, Bowen Hills



Appendix E Terms and Abbreviations

Site: 19-25 Campbell Street, Bowen Hills



In this OWMP, a term or abbreviation has the following meaning unless indicated otherwise:

TERM	ABBREVIATION	DEFINITION
Equipment		
Bin (Refuse Bin)		A plastic or steel container for disposal and temporary storage of waste or recycling items. Various types and sizes exist for different items and purposes. Examples include residential unit bins, bulk bins, MGB, steely bins and specialised for medical waste or cigarette butts.
Bin Storage Area		An enclosed area designated for storing on-site refuse bins or a refuse compactor within the property.
Bulk Bin		A galvanized or steel bin receptacle that is greater than 360L in capacity generally ranging from 1.00m³ to 4.50m³ used for the storage of refuse that is used for on-site refuse collection.
Bulk Mobile Garbage Bin	Bulk MGB	A plastic (polypropylene) receptacle that is greater than 360L in capacity generally ranging from 660L to 1100L used for the storage of refuse.
Chute Discharge		The point at which refuse exits from the refuse chute.
Chute Discharge Room		An enclosed area / room housing the discharge and associated equipment for the refuse chute.
Collection Point		An identified position where refuse bins are stored for collection and emptying. The collection point can also be the bin storage area.
Compactor		A receptacle that provides for the mechanical compaction and temporary storage of refuse. It allows to reduce bin numbers and collection frequency.
Composter		A container or machine used for composting specific food scraps and/or organic materials.
Food Waste Recycling System		Defined as a vacuum or pump-based system for shredding, macerating or pulping of food waste. The food waste is transferred through pressure (service) pipes to sealed liquid storage tanks.
Green Waste		All vegetated organic material such as small branches, leaves and grass clippings, tree and shrub pruning, plants and flowers.
Hopper		A fitting into which waste is placed and from which it passes into a chute or directly into a waste container. It consists of a fixed frame and hood unit (the frame) and a hinged or pivoted combined door and receiving unit, and it is typically mounted on a wall.
Liquid Waste		Non-hazardous liquid waste generated by commercial premises should be connected to sewer or collected for treatment and disposal by a liquid waste contractor (including grease trap waste).
Mobile Garbage Bin	MGB	A plastic (polypropylene) bin or bins used for the temporary storage of refuse that is up to 360L in capacity and may be used in kerbside refuse collection or on-site collection.
Putrescible Waste		Putrescible waste is the component of the waste stream liable to become putrid and usually breaks down in a landfill to create landfill gases and leachate. Typically applies to food, animal and organic products.
Recycling		Recycling contains all material suitable for re-manufacture or re-use, e.g. glass bottles and jars; plastics such as PET, HDPE and PVC; aluminium aerosol and steel cans and lids; milk and juice cartons; soft drink, milk and shampoo containers; paper, cardboard, junk mail, newspapers and magazines.
Refuse		Refuse is material generated and discarded from residential and commercial buildings including general waste, recyclables, green waste and bulky items.

Site: 19-25 Campbell Street, Bowen Hills



TERM	ABBREVIATION	DEFINITION
Refuse Chute		A ventilated, essentially vertical pipe passing from floor to floor of a building for the purpose of refuse disposal, with openings as required to connect with hoppers and normally terminating at its lower end at the roof of a central refuse room.
Refuse Collection Vehicle	RCV	A vehicle specifically designed for collecting and emptying refuse bins and refuse compactors.
Refuse Storage Room		An area identified for storing on-site MGBs or Bulk Bins within the property.
Refuse Tolley		A cart on wheels that can be used to collect smaller quantities of refuse from different areas or rooms of a building or site, and wheel the collected refuse to a (bulk) bin storage area where it is disposed. Refuse trolleys are commonly used in hotels or offices.
Regulated Waste		Regulated waste is waste prescribed under legislation as regulated waste.
Transfer (Manual Transfer)		Manual transfer means physical transfer of refuse material and associated bulk bins or trolleys without assistance.
Waste		Waste is referred to as refuse material with the exclusion of recycling, green waste, hazardous waste, special waste, liquid waste and restricted solid waste.
Waste (General Waste)		General waste is generally referred to as material free of any actual or apparent contamination such as pathological / infectious, radioactive materials and / or hazardous chemical. Reporting use is for material considered to be free of food waste.
Wheelie Bin		A MGB of up to 360L, usually with 2 wheels for easy transfer. A common type is a 240L wheelie bin used for kerbside collection in many residential areas.
Measures		
Cubic Metre	m ³	Volume in cubic metre(s) related to refuse management equipment.
Ground Floor Area	GFA	The GFA of all storeys of a building is measured from the outside of the external walls or the centre of a common wall. It is commonly measured in square metres.
Kilogram	kg	Kilogram(s) related to refuse weight.
Litre	L	Litre(s) related to refuse volumes.
Square Metre	m ²	Square metre(s) related to refuse areas.
Ton	Т	Ton(s) related to refuse weight.
Collection Vehicles		
Body Truck		A conventional heavy vehicle with a covered loading area. It is generally not specifically designed for emptying the content of bins into the truck during refuse collections, but can be used to carry entire (full) bins for servicing by bin swap-over.
Rear-End-Loading Refuse Collection Vehicle	REL RCV	A truck specially designed to collect municipal solid waste and recycling, typically 240L wheelie bins to 1100L bulk bins, from rear loading mechanism and haul the collected waste to a solid waste treatment facility.
Tank Truck		An RCV that is specifically designed to collect liquid wastes such as waste cooking oil and food waste pulp. The waste is typically pumped from a waste storage tank into the truck via a hose. Liquid waste management equipment is often provided by the contractor who collects the waste and operates the truck.

Site: 19-25 Campbell Street, Bowen Hills