

1. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL PROVIDE TO THE SUPERINTENDENT A COPY OF THE CONSTRUCTION PROGRAM DETAILING THE DATES OF COMMENCEMENT AND COMPLETION FOR EACH STAGE.
2. PRIOR TO COMMENCING WORK, THE CONTRACTOR SHALL PREPARE AND FORWARD TO THE SUPERINTENDENT A REPORT ON THE CONDITION OF EXISTING INFRASTRUCTURE IN THE VICINITY OF THE WORKS SITE. THE REPORT SHALL LIST THE LOCATION AND EXTENT OF ANY EXISTING DAMAGE. THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR ALL DAMAGED ASSETS THAT ARE NOT REPORTED PRIOR TO THE COMMENCEMENT OF WORKS.
3. PRIOR TO THE COMMENCEMENT OF EARTHWORKS, THE CONTRACTOR SHALL SUBMIT AN EROSION AND SEDIMENT CONTROL PLAN FOR APPROVAL BY THE SITE SUPERINTENDENT.
4. THE CONTRACTOR SHALL USE AN APPROVED SECURITY FENCE TO ISOLATE UNSAFE AREAS AS MUTUALLY AGREED UPON BY THE CONTRACTOR AND SUPERINTENDENT.
5. DO NOT SCALE OFF DRAWINGS.
6. ALL DIMENSIONS AND LEVELS TO BE SITE CHECKED AND ANY DISCREPANCY REPORTED TO THE SUPERINTENDENT.
7. ANY VARIATION TO THE DETAILS SHOWN ON THE DRAWING MUST BE AUTHORISED BY THE SUPERINTENDENT PRIOR TO FABRICATION AND/OR CONSTRUCTION.
8. CONSTRUCTION WORK SHALL BE CARRIED OUT STRICTLY IN ACCORDANCE WITH THE QLD WORKPLACE HEALTH AND SAFETY ACT (1995) AND THE WORKPLACE HEALTH AND SAFETY REGULATION (2008).
9. ALL PROPRIETARY PRODUCTS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
10. ALL DIMENSIONS ARE IN MM UNLESS NOTED OTHERWISE.
11. ALL R.L.S AND F.S.L.S ARE IN M AHD.
12. THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL EXISTING SERVICES WITH RELEVANT AUTHORITIES BEFORE COMMENCING CONSTRUCTION.
13. ALL ASSETS MODIFIED OR DAMAGED BY THE PROPOSED WORKS SHALL BE REINSTATED TO THE SATISFACTION OF THE SUPERINTENDENT.
14. THE CONTRACTOR SHALL REMOVE ALL STRUCTURES, DEBRIS AND FENCES FROM THE SITE TO THE SATISFACTION OF THE SUPERINTENDENT. THE CONTRACTOR SHALL NOTIFY THE SUPERINTENDENT PRIOR TO COMMENCEMENT OF DEMOLISHING ANY EXISTING STRUCTURES WITHIN THE SITE AREAS.

THE SUPERINTENDENT AND WETLAND DESIGNERS ARE REQUIRED TO INSPECT THE WETLAND CONSTRUCTION AND PROVIDE SIGNOFF AND CERTIFICATION IN ACCORDANCE WITH THE CONSTRUCTION SPECIFICATION AND CONSTRUCTION AND ESTABLISHMENT GUIDELINES - CONSTRUCTED WETLANDS, BIORETENTION SYSTEMS AND SWALES (WATER BY DESIGN, 2010). IN ORDER TO FULFIL THIS REQUIREMENT, THE CONTRACTOR SHALL REQUEST THAT THE SUPERINTENDENT ARRANGE INSPECTIONS BY THE DESIGN TEAM AT THE FOLLOWING MILESTONES:

- ## VEGETATION PROTECTION AND WEED MANAGEMENT

- ## SOIL AND GROUNDWATER MANAGEMENT

- PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL



Queensland
Government

- ### HIGH FLOW CONTINGENCIES


- ## EARTHWORKS

- ### DRAINAGE PIPES AND PITS

- ### TOLERANCES



- ## ACCESS ROADS

1. ACCESS TRACKS SHALL BE CONSTRUCTED IN ACCORDANCE WITH RELEVANT STANDARD SPECIFICATIONS (QUEENSLAND DEPARTMENT OF TRANSPORT AND MAIN ROADS AND TCC).
2. ROAD BASE MATERIAL SHALL BE TYPE 2.3 WITH 2% CROSSFALL.
3. WHERE DICTED, ROAD BASE MATERIAL SHALL BE CEMENT STABILISED OR APPROVED EQUIVALENT.




30mm ASPHALTIC CONCRETE
110mm BASE COURSE (TYPE 2.1, CBR 80)
140mm SUB-BASE COURSE (TYPE 2.3, CBR 45)
SUBGRADE REPLACEMENT AS REQUIRED (TYPE 2.5, CBR 15)
DESIGN ESA = 1.1×10^5


Queensland
Government



A1	Drawing No 17-268-05	Revision B
----	-------------------------	---------------



A1	Drawing No 17-268-07	Revision B
----	-------------------------	---------------



PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2022/1292


Date: 12 December 2022



DO NOT SCALE THIS DRAWING
IF IN DOUBT - ASK!



LOCALITY PLAN



REVISIONS

[illegible]

	Associated Consultants



Project



Approved - RPEQ 12805

Drawing Title
EROSION AND SEDIMENT CONTROL
LAYOUT PLAN

Drawn CWH	Designed CWH	Checked RM	Date JAN 1
Scale AS SHOWN			Sheet 08 of
A1	Drawing No 17-268-08		Revision B

LEGEND

-
- STAGE BOUNDARY
- FINISHED SURFACE CONTOURS 36.0
- NATURAL SURFACE CONTOURS 36.0
- EXISTING ROAD CENTRELINE
- EXISTING KERB AND CHANNEL
- EXISTING STORMWATER DRAINAGE SW
- EXISTING SEWER MAIN TS
- EXISTING TRUNK SEWER MAIN
- EXISTING WATER MAIN
- EXISTING IRRIGATION IRR 200
- SEDIMENT AND DIVERSION FENCE (TEMP)
- EXISTING FENCE

NOTE :-
EROSION AND SEDIMENT CONTROL DESIGN
IS IDENTICAL FOR CONSTRUCTION PHASE
AND POST-CONSTRUCTION PHASE.

SCALE  1 : 500 (A1 UNREDUCED)

- THIS PROGRAM AND ASSOCIATED PLANS SHOULD BE READ IN CONJUNCTION WITH THE MANAGEMENT SPECIFICATION INCORPORATED IN THE CONTRACT DOCUMENTS. THE PROVISIONS OF THE SPECIFICATION ARE TO BE STRICTLY ADHERED TO.
2. THE BASIC OBJECTIVES OF THE EROSION AND SEDIMENT CONTROL ARE:
 - I. IDENTIFY CRITICAL AREAS AND PROVIDE APPROPRIATE ATTENTION TO THOSE AREAS.
 - II. PLAN SITE LAYOUTS SO THAT ACCESS TO ALL REQUIRED DRAINAGE EROSION AND SEDIMENT CONTROL MEASURE IS MAINTAINED.
 - III. LIMIT EXPOSURE TIME BY PROGRAMMING TO MINIMISE THE AREA OF LAND EXPOSED TO POTENTIALLY ADVERSE WEATHER CONDITIONS AT ANY ONE TIME. I.E. PROGRESSIVELY CLEAR AND REVEGETATE.
 - IV. PROVIDE CONTROL MEASURES INCLUDING TEMPORARY AND PERMANENT DRAINAGE, EROSION AND SEDIMENT CONTROLS.
3. THE EROSION AND SEDIMENT CONTROL SHALL COMPLY WITH BEST PRACTICE FOR EROSION AND SEDIMENT CONTROL, THE POLLUTION CONTROL MANUAL FOR URBAN STORMWATER MANAGEMENT, THE QUEENSLAND URBAN DRAINAGE MANUAL, AND THE SOIL EROSION AND SEDIMENT CONTROL - ENGINEERING GUIDELINES FOR QUEENSLAND (CURRENT EDITIONS).
4. CONSTRUCTION SEQUENCE THE CONSTRUCTION SEQUENCE WILL GENERALLY BE:
 - I. OBTAIN ALL NECESSARY PERMITS AND APPROVALS BEFORE SITE ESTABLISHMENTS.
 - II. HOLD A PRE-CONSTRUCTION CONFERENCE.
 - III. STABILISE ALL CONSTRUCTION ACCESS ROUTES AND ENTRY/EXIT POINTS.
 - IV. ESTABLISH SEDIMENT CONTROL STRUCTURES AND TEMPORARY DRAINAGE CONTROL MEASURES AS NECESSARY.
 - V. CARRY OUT BULK EARTHWORKS.
 - VI. MAINTAIN AND REPAIR DRAINAGE, EROSION AND SEDIMENT CONTROL MEASURES.
 - VII. REMOVE SEDIMENT CONTROL MEASURES WHEN THE SITE IS STABILISED. I.E. >70% GROUND COVER
 - VIII. THE CONTRACTOR SHALL PREPARE A SUPPLEMENTARY EROSION AND SEDIMENT CONTROL PLAN TO SUIT HIS/HER CONSTRUCTION METHODOLOGY, AND SUBMIT THIS PLAN FOR APPROVAL TO THE SUPERINTENDENT. IT SHOULD BE NOTED THAT ANY SIGNIFICANT VARIATION TO THIS PLAN MAY REQUIRE RESUBMISSION TO COUNCIL FOR APPROVAL. THE CLIENT SHALL NOT BE RESPONSIBLE FOR ANY SUCH ASSOCIATED DELAY.
5. ALL ESC DEVICES ARE TO BE INSPECTED WEEKLY, PRIOR TO EXPECTED AND AFTER RAINFALL. ANY DAMAGE IS TO BE REPAIRED AS REQUIRED TO MAINTAIN THEIR EFFICACY.
6. ALL TEMPORARY EROSION AND SEDIMENT CONTROL (ESC) MEASURE TO BE MAINTAINED AND FULLY OPERATIONAL DURING THE MAINTENANCE PERIOD AND ARE TO BE REMOVED AFTER THE SATISFACTORY COMPLETION OF AN OFF-MAINTENANCE INSPECTION BY COUNCIL AND PRIOR TO FORMAL ACCEPTANCE "OFF MAINTENANCE" BY COUNCIL.
7. PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, THE CONTRACTOR IS TO PROVIDE A DETAILED PROGRAM TO THE SUPERINTENDENT SHOWING THE TIMING FOR ALL WORKS ASSOCIATED WITH THE PROJECT, NOMINATING, IN PARTICULAR, THE PROGRAM FOR INSTALLATION OF SOIL AND EROSION CONTROL SYSTEMS.
8. EARTHWORKS SHALL BE CARRIED OUT IN SUCH A MANNER THAT THE SITE IS MAINTAINED IN A WELL DRAINED CONDITION, AREAS OF LOOSE SOIL ARE MINIMISED AND CONCENTRATIONS OF STORMWATER ARE MINIMISED. BULK EARTHWORKS WILL BE CARRIED OUT OVER THE ENTIRE SITE IN ONE STAGE.
9. A SHAKE DOWN AS DETAILED ON THE PLAN COMPRISING FINE DRAINAGE GRAVEL SHALL BE LOCATED ADJACENT TO THE POINT OF ACCESS WHERE VEHICLES CAN BE WASHED DOWN PRIOR TO EXIT TO THE STREET SYSTEM IF REQUIRED. THE WASH DOWN AREA SHALL BE KEPT FREE OF MUD.
10. FOR DETAILS OF ENTRY/EXIT SEDIMENT PAD REFER TO BEST PRACTICE EROSION & SEDIMENT CONTROL BOOK 1, PAGE 2.48, FIGURE 2.6.
11. SUPPLEMENTARY EROSION AND SEDIMENT CONTROL DEVICES MAY BE REQUIRED AT THE DISCRETION OF THE SUPERINTENDENT.
12. SEDIMENTATION FENCES TO BE PLACED AS SHOWN. FOR DETAILS OF SEDIMENT FENCE REFER BEST PRACTICE EROSION & SEDIMENT CONTROL BOOK 1, PAGE 2.50, FIGURE 2.8.
13. WHERE SEDIMENT FENCES ARE SHOWN TO BE CONSTRUCTED IN AREAS OF SIGNIFICANT EARTHWORKS, ERECTION OF THE FENCE MAY BE DEFERRED UNTIL COMPLETION OF THE BULK EARTHWORKS, SUBJECT TO ABSENCE OF RAIN.

1. ENSURE COMPLIANCE WITH THE REQUIREMENTS OF AS4970 – TREES ON CONSTRUCTION SITES. THIS MAY REQUIRE CONSULTATION AND GUIDANCE FROM A CLASS V CERTIFIED ARBORIST AS TREES OUTSIDE THE IMMEDIATE WORK AREA MAY BE AFFECTED.

1. NO DISTURBED AREA IS TO REMAIN DENUDE LONGER THAN 60 DAYS.
2. ALL EROSION AND SILTATION CONTROL MEASURES ARE TO BE PLACED PRIOR TO OR AS THE FIRST STEP IN CLEARING AND GRUBBING OR ANY OTHER EARTHWORKS OR TRENCHING.
3. ALL STORMWATER, SEWER LINE AND SERVICES TRENCHES NOT IN STREETS ARE TO BE MULCHED AND SEEDED WITHIN 15 DAYS AFTER BACKFILL, NO MORE THAN 150 METRES ARE TO BE OPEN AT ANY ONE TIME.
4. ALL TEMPORARY EARTH BANKS, DIVERSIONS AND SEDIMENT DAM EMBAKMENTS ARE TO BE MACHINE-COMPACTED, SEEDED AND MULCHED FOR TEMPORARY VEGETATIVE COVER WITHIN 10 DAYS AFTER GRADING. STRAW OR HAY MULCH IS REQUIRED.
5. ALL FILL EMBAKMENTS ARE TO BE LEFT WITH A LIP AT THE TOP OF THE SLOPE AT THE END OF EACH DAYS OPERATION.
6. ALL CUT AND FILL BATTERS ARE TO BE SEEDED AND MULCHED WITHIN 10 DAYS OF COMPLETION OF GRADING.
7. ADDITIONAL SILT AND EROSION CONTROLS MAY BE REQUIRED AS ORDERED ON SITE BY THE SUPERVISING ENGINEER.
8. ALL CONTROLS ARE TO BE INSPECTED AFTER EACH STORM EVENT AND MAINTAINED AS REQUIRED. CONTROLS ARE TO BE MAINTAINED UNTIL THE DISTURBED AREAS ARE PERMANENTLY STABILIZED OR UNTIL NO LONGER REQUIRED.

CONSTRUCT AND MAINTAIN SILT FENCES, STRAW BALE TRAPS, ALLOTMENT DRAINAGE BANKS, CATCH DRAINS AND HYDROMULCHING WHICH CONTROL SEDIMENT AND EROSION DURING CLEARING AND BULK EARTHWORKS.

CONSTRUCT AND MAINTAIN SILT FENCES, STRAW BALE TRAPS, ALLOTMENT DRAINAGE BANKS AND CATCH DRAINS WHICH CONTROL SEDIMENTATION AND EROSION DURING TRENCHING WORK.

CONSTRUCT AND MAINTAIN SILT FENCES, STRAW BALE TRAPS, ALLOTMENT DRAINAGE BANKS, GULLY INLET PROTECTION, AND PIPE INLET/OUTLET PROTECTION WHICH CONTROL SEDIMENTATION AND EROSION DURING PAVEMENT CONSTRUCTION. SAND BAGGING TO BE PLACED ACROSS PAVEMENT TO CONTROL RUNOFF IN PAVEMENT BOXING AS DIRECTED ON SITE.

CONSTRUCT AND MAINTAIN CONTROLS AND VEGETATIVE TREATMENTS WHICH CONTROL SEDIMENTATION AND EROSION PRIOR TO THE ESTABLISHMENT OF GRASS COVER. PROVIDE 600mm WIDE GRASS FILTER STRIPS BEHIND KERB AND CHANNEL.

ALL VEHICLES EXITING FROM THE SITE ARE TO BE CLEANED AND TREATED TO PREVENT MATERIAL BEING TRACKED OR DEPOSITED ONTO PUBLIC ROADS.
IF MATERIAL IS ACCIDENTALLY DEPOSITED ONTO PUBLIC ROADS IT SHALL BE REMOVED WITHOUT DELAY. IF THE SHAKEDOWN DEVICE PROVES TO BE INEFFECTIVE THE CONTRACTOR IS TO USE OTHERS MEANS TO PREVENT MATERIAL BEING DEPOSITED ONTO PUBLIC ROADS.

1. STRIP AND STOCKPILE AVAILABLE TOPSOIL (ASSUMED AVERAGE DEPTH 150mm) FROM ALL DISTURBED AREAS PRIOR TO BULK EARTHWORKS. GRADE EVENLY BETWEEN ALLOTMENT FINISHED SURFACE LEVELS AND ENSURE LOTS ARE FREE DRAINING.
2. MINIMUM SLOPE ACROSS ALLOTMENTS TO BE 1%.
3. ALL FOOTPATHS, BATTERS, AND EARTHWORKS AFFECTED ALLOTMENTS ARE TO BE TOPSOILED TO A MINIMUM DEPTH OF 150mm (LIGHTLY COMPACTED) AND TURFED WHERE SPECIFIED.

1. SEDIMENT FENCES TO BE PLACED AS SHOWN. SEDIMENT FENCED TO BE REPAIRED AND EXCESSIVE SEDIMENT DEPOSITS SHALL BE REMOVED ONCE CAPACITY FALLS BELOW 75%.
2. FOR DETAILS OF SEDIMENT FENCE REFER BEST PRACTICE EROSION & SEDIMENT CONTROL BOOK 1, PAGE 250, FIGURE 2.8.
3. SEDIMENT FENCES TO BE REPAIRED AS REQUIRED AND EXCESSIVE SEDIMENT DEPOSITS SHOULD BE REMOVED.
4. INSTALL KERB INLETS WITH GRAVEL RANGING FROM 50mm TO 75mm IN SIZE SHALL BE INSTALLED AT ALL COMPLETED INLETS. REFER IPWEAQ STANDARD DRAWING D-0041. THESE SHALL BE MAINTAINED IN A CLEAN CONDITION. IN THE EVENT OF HEAVY RAIN THEY SHALL BE REMOVED TO MINIMISE THE POTENTIAL FOR FLOODING.
5. CHECKS OF SILT CONTROL DEVICES ARE TO BE MADE WEEKLY, OR AFTER ANY SIGNIFICANT STORM EVENT TO ENSURE INTEGRITY AND PERFORMANCE.

1. PROVIDE TURFING TO ENTIRE WIDTH OF ALL SWALES, FOOTPATHS, AND 1 IN 4 CUT AND FILL BATTERS.
2. FOOTPATH BATTERS ARE TO BE STABILISED WITH TOPSOIL (AND TURFED) AS SOON AS PRACTICAL AFTER THE BATTERS HAVE BEEN COMPLETED.


1. TOPSOIL STOCKPILES SHALL BE LESS THAN 1m DEEP AND UNCOMPACTED. A SEDIMENTATION FENCE SHALL BE CONSTRUCTED ON THE D/S SIDE, OR THE STOCKPILE STABILISED WITH VEGETATION, MULCH, OR A SOIL STABILISER.
2. SEDIMENTATION FENCES TO BE PLACED AS SHOWN.
3. REGULARLY INSPECT BANKS AND REPAIR ANY SLUMPS, WHEEL TRACK DAMAGE OR LOSS OF FREEBOARD.
4. REMOVE SEDIMENT TO AVOID PONDING FROM CATCH DRAINS.
5. REMOVE EXCESSIVE SEDIMENT FROM UPSTREAM OF CHECK DAM.
6. ROAD RESERVE TO BE USED AS HAUL ROAD.
7. A CATCH DRAIN OR DIVERSION BANK IS TO BE PROVIDED ON THE TOP SIDE OF ALL CUTS, WITH DISCHARGE EITHER TO UNDISTURBED GRASS LANDS OR TO THE CROSS ROAD DRAINAGE.
8. SUPPLEMENTARY EROSION AND SEDIMENT CONTROL DEVICES MAY BE REQUIRED AT THE DISCRETION OF THE ENGINEER.
9. WATER QUALITY SAMPLES MUST BE TAKEN AND ANALYSED PRIOR TO THE RELEASE OF ANY WATER FROM A POND. WATER QUALITY MUST SATISFY THE FOLLOWING CRITERIA: TSS-50MG/L PH BETWEEN 6.5 AND 8.
10. ALL WATER QUALITY DATA INCLUDING DATES OF RAINFALL, TESTING AND WATER RELEASE MUST BE MAINTAINED IN AN ON-SITE REGISTER. THIS REGISTER IS TO BE MAINTAINED FOR THE DURATION OF THE APPROVED WORKS AND BE AVAILABLE ON SITE FOR INSPECTION BY COUNCIL OFFICERS ON REQUEST.
11. EXPOSED AREAS ON LOTS ARE TO BE SEEDED AND MULCHED (E.G. HYDROMULCHED). MULCH SHALL BE APPLIED AT A MINIMUM RATE OF 257/Ha. ALTERNATIVELY THEY SHALL BE DRILL-SEEDED AND IRRIGATED SO AS TO ENSURE ~70% GROUND COVER WITHIN 14 DAYS FROM NOVEMBER TO APRIL, OR 30 DAYS FROM MAY TO OCTOBER.

1. SEDIMENTATION FENCES TO BE MAINTAINED UNTIL TURFING IS COMPLETED.
2. SEDIMENT BASINS TO BE CHECKED AFTER EVERY SIGNIFICANT STORM AND DESILTED ONCE THE SETTLEMENT LIMIT HAS BEEN REACHED.


A1	Drawing No 17-268-09	Revision A
----	-------------------------	---------------




SCALE  1 : 500 (A1 UNREDUCED)




SITE ACCESS POINT SHAKEDOWN FACILITY
N.T.S.




SITE ACCESS POINT ENTRY/EXIT PAD
N.T.S.




TURF STRIP DETAIL
N.T.S.




SANDBAG CHECK DAM
N.T.S.




SEDIMENT FENCE
N.T.S.





PLAN VIEW
N.T.S.




ON GRADE GULLY INLET
N.T.S.



SILT FENCE DETAILS
N.T.S.



DIVERSION DRAINAGE BANK
N.T.S.



CATCHMENT DRAIN
N.T.S.

DO NOT SCALE THIS DRAWING
IF IN DOUBT - ASK!

NORTH

LOCALITY PLAN

CAMP CREEK ROAD

YARRABILBA PRECINCT 3

YARRABILBA

WILLABONG

TRAILHEAD ROAD

REVISIONS

No	Description	Date	By
A	FOR APPROVAL	JAN 18	CWH

Associated Consultants

RPS

RPS Australia East Pty Ltd
ACN 140 252 762
ABN 44 140 252 762
Suite 4, Indrala East Drive, Corporate Park
(North Building) 34-36 Glenferrie Drive, Rostov
PO Box 1048 Rostov VIC 3108-0228
T +61 7 555 36500
F +61 7 555 36599
www.rpsgroup.com.au

Client

lendlease

Project

YARRABILBA

STEELE ROAD TRAILHEAD ACCESS

KN GROUP PTY LTD
CONSULTING ENGINEERS

LEVEL 2 - 71 GREY STREET
SOUTH BRISBANE
QUEENSLAND 4101
PHONE 07 3017 1900
FAX 07 3017 1911
EMAIL kn@knpl.com.au
ABN 35 112 053 611

Approved - IPTG 12803

Drawing Title

EROSION AND SEDIMENT CONTROL DETAILS

Drawn	Designed	Checked	Date
CWH	CWH	RM	JAN 18

Scale

AS SHOWN

Sheet 10 of 11

Drawing No

17-268-10

Revision

A

PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

Approval no: DEV2022/1292
Date: 12 December 2022



SCALE

10 5 0 10 20 30 40 50m

1 : 500 (A1 UNREDUCED)

Date: 12 December 2022

Date: 19th February 2018
Date: 19th February 2018

Drawn CWH	Designed CWH	Checked RM	Date JAN 18
Scale AS SHOWN			Sheet 11 of 11
A1	Drawing No 17-268-11		Revision A