

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2024/1491

Date: 7 May 2025


Queensland Government

Yield Breakdown		
Lot Type	Overall	
	Yield	%
25m Deep Product		
Villa 10m Allotment	13	6.2%
Premium Villa 12.5m Allotment	23	11.0%
Courtyard 14m Allotment	22	10.5%
Premium Courtyard 16m Allotment	2	1.0%
Premium Traditional 20m Allotment	4	1.9%
Possible Multiple Residential Allotment	1	0.5%
Subtotal	65	31.0%
28m Deep Terrace Product		
Terrace 7.5m Allotment	9	4.3%
Terrace 9.5m Allotment	4	1.9%
Subtotal	13	6.2%
30m Deep Product		
Villa 10m Allotment	30	14.3%
Premium Villa 12.5m Allotment	51	24.3%
Courtyard 14m Allotment	39	18.6%
Premium Courtyard 16m Allotment	6	2.9%
Traditional 18m Allotment	—	0.0%
Premium Traditional 20m Allotment	6	2.9%
Possible Multiple Residential Allotment	—	0.0%
Subtotal	132	62.9%
Total Residential Allotments	210	100.0%
Residential Net Density	15.5 dw/ha	
Super Lots		
Child Care	1	
Sub Total	1	
Total Allotments	211	
Maximum Potential Residential Dwellings (Includes Multiple Residential Allotments)	211	
Maximum Potential Net Residential Density	15.5 dw/ha	

Land Use	Overall	
	Area	%
Stage Area		
	16.967 ha	100.0%
Saleable Area		
Residential Allotments	7.934 ha	46.8%
Child Care	0.301 ha	1.8%
Total Area of Allotments	8.235 ha	48.5%
Road		
North South Arterial Dedication (incl. batters)	3.079 ha	18.1%
Trunk Connector 2 Lanes (23.7m)	—	0.0%
Neighbourhood Connector (20.2m)	0.598 ha	3.5%
Neighbourhood Access Street (16.5m)	3.513 ha	20.7%
Laneway (6.5m)	0.075 ha	0.4%
Pedestrian Linkages	0.132 ha	0.8%
Total Area of New Road	7.397 ha	43.6%
Open Space		
Conservation Buffer	—	0.0%
Corridor Park / Conservation	—	0.0%
Stormwater Management	0.555 ha	3.3%
Regional Sports	—	0.0%
District Sports	—	0.0%
Neighbourhood Recreation Park	0.539 ha	3.2%
Local Recreation Park	—	0.0%
Local Linear Recreation Park	0.241 ha	1.4%
Total Open Space	1.335 ha	7.9%

Legend

General

Application Boundary

Stage Boundary

Sub Stage Boundary

Possible Multiple Residential Allotment (Max. no. of dwellings)

Existing Q100

Concept Design Contours (1m)

Bus Stop Catchment (400m)

Indicative Indented Bus Stop Location

Neighbourhood Park Catchment (400m)

Note:
All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.
Dimensions have been rounded to the nearest 0.1 metres.
Areas have been rounded down to the nearest 5m².
The boundaries shown on this plan should not be used for final detailed engineers design.

Source Information:
Site boundaries: Veris.
Adjoining information: Veris.
Design Contours: Colliers (29-08-2024).
Environment constraints: Saunders Havill Group.
Q100: Engeny.
North South Arterial Alignment: Colliers.

Yield Breakdown													
Lot Type	Stage 10A	Stage 10B	Stage 10C	Stage 10D	Stage 10E	Stage 10F	Stage 10G	Stage 10H	Stage 10I	Stage 10J	Stage 10T	Overall	
	Yield	Yield	Yield	Yield	Yield	Yield	Yield	Yield	Yield	Yield	Yield	Yield	%
25m Deep Product													
Villa 10m Allotment	—	5	—	—	—	2	6	—	—	—	—	13	6.2%
Premium Villa 12.5m Allotment	5	4	—	—	—	5	9	—	—	—	—	23	11.0%
Courtyard 14m Allotment	4	1	—	—	—	11	6	—	—	—	—	22	10.5%
Premium Courtyard 16m Allotment	1	—	—	—	—	1	—	—	—	—	—	2	1.0%
Premium Traditional 20m Allotment	2	—	—	—	—	2	—	—	—	—	—	4	1.9%
Possible Multiple Residential Allotment	—	1	—	—	—	—	—	—	—	—	—	1	0.5%
Subtotal	12	11	—	—	—	21	21	—	—	—	—	65	31.0%
28m Deep Terrace Product													
Terrace 7.5m Allotment	—	—	—	—	—	—	—	—	9	—	—	9	4.3%
Terrace 9.5m Allotment	—	—	—	—	—	—	—	—	4	—	—	4	1.9%
Subtotal	—	—	—	—	—	—	—	—	13	—	—	13	6.2%
30m Deep Product													
Villa 10m Allotment	6	4	6	—	—	8	5	—	—	1	—	30	14.3%
Premium Villa 12.5m Allotment	12	3	16	—	—	6	6	—	—	8	—	51	24.3%
Courtyard 14m Allotment	5	5	6	—	—	4	3	—	—	16	—	39	18.6%
Premium Courtyard 16m Allotment	1	3	—	—	—	—	—	—	—	2	—	6	2.9%
Traditional 18m Allotment	—	—	—	—	—	—	—	—	—	—	—	—	0.0%
Premium Traditional 20m Allotment	—	3	2	—	—	—	—	—	—	1	—	6	2.9%
Possible Multiple Residential Allotment	—	—	—	—	—	—	—	—	—	—	—	—	0.0%
Subtotal	24	18	30	—	—	18	14	—	—	28	—	132	62.9%
Total Residential Allotments	36	29	30	—	—	39	35	—	13	28	—	210	100.0%
Residential Net Density	17.7 dw/ha	18.7 dw/ha	14.3 dw/ha	—	—	17.7 dw/ha	20.4 dw/ha	—	16.9 dw/ha	13.2 dw/ha	—	15.5 dw/ha	
Super Lots													
Child Care	—	—	—	1	—	—	—	—	—	—	—	1	
Sub Total	—	—	—	1	—	—	—	—	—	—	—	1	
Total Allotments	36	29	30	1	—	39	35	—	13	28	—	211	
Maximum Potential Residential Dwellings (Includes Multiple Residential Allotments)	36	30	30	—	—	39	35	—	13	28	—	211	
Maximum Potential Net Residential Density	17.7 dw/ha	19.3 dw/ha	14.3 dw/ha	—	—	17.7 dw/ha	20.4 dw/ha	—	16.9 dw/ha	13.2 dw/ha	—	15.5 dw/ha	

Land Budget													
Land Use	Stage 10A	Stage 10B	Stage 10C	Stage 10D	Stage 10E	Stage 10F	Stage 10G	Stage 10H	Stage 10I	Stage 10J	Stage 10T	Overall	
	Area	Area	Area	Area	Area	Area	Area	Area	Area	Area	Area	Area	%
Stage Area	2.038 ha	1.554 ha	2.096 ha	0.301 ha	0.539 ha	2.199 ha	1.714 ha	0.555 ha	0.771 ha	2.121 ha	3.079 ha	16.967 ha	100%
Saleable Area													
Residential Allotments	1.371 ha	1.114 ha	1.237 ha	—	—	1.427 ha	1.213 ha	—	0.294 ha	1.278 ha	—	7.934 ha	46.8%
Child Care	—	—	—	0.301 ha	—	—	—	—	—	—	—	0.301 ha	1.8%
Total Area of Allotments	1.371 ha	1.114 ha	1.237 ha	0.301 ha	—	1.427 ha	1.213 ha	—	0.294 ha	1.278 ha	—	8.235 ha	48.5%
Road													
North South Arterial Dedication (incl. batters)	—	—	—	—	—	—	—	—	—	—	3.079 ha	3.079 ha	18.1%
Trunk Connector 2 Lanes (23.7m)	—	—	—	—	—	—	—	—	—	—	—	—	0.0%
Neighbourhood Connector (20.2m)	—	—	—	—	—	—	—	—	—	0.598 ha	—	0.598 ha	3.5%
Neighbourhood Access Street (16.5m)	0.667 ha	0.440 ha	0.588 ha	—	—	0.742 ha	0.501 ha	—	0.402 ha	0.173 ha	—	3.513 ha	20.7%
Laneway (6.5m)	—	—	—	—	—	—	—	—	0.075 ha	—	—	0.075 ha	0.4%
Pedestrian Linkages	—	—	0.030 ha	—	—	0.030 ha	—	—	—	0.072 ha	—	0.132 ha	—
Total Area of New Road	0.667 ha	0.440 ha	0.618 ha	—	—	0.772 ha	0.501 ha	—	0.477 ha	0.843 ha	3.079 ha	7.397 ha	43.6%
Open Space													
Conservation Buffer	—	—	—	—	—	—	—	—	—	—	—	—	0.0%
Corridor Park / Conservation	—	—	—	—	—	—	—	—	—	—	—	—	0.0%
Stormwater Management	—	—	—	—	—	—	—	0.555 ha	—	—	—	0.555 ha	3.3%
Regional Sports	—	—	—	—	—	—	—	—	—	—	—	—	0.0%
District Sports	—	—	—	—	—	—	—	—	—	—	—	—	0.0%
Neighbourhood Recreation Park	—	—	—	—	0.539 ha	—	—	—	—	—	—	0.539 ha	3.2%
Local Recreation Park	—	—	—	—	—	—	—	—	—	—	—	—	0.0%
Local Linear Recreation Park	—	—	0.241 ha	—	—	—	—	—	—	—	—	0.241 ha	1.4%
Total Open Space	—	—	0.241 ha	—	0.539 ha	—	—	0.555 ha	—	—	—	1.335 ha	7.9%

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2024/1491

Date: 7 May 2025





FLAGSTONE CA3 SOUTH


STAGE 10 OVERALL

STATISTICS

Yield Breakdown						
	Stage 10A	Stage 10B	Stage 10C	Stage 10D	Overall	
Lot Type	Yield	Yield	Yield	Yield	Yield	%
25m Deep Product						
Villa 10m Allotment	—	5	—	—	5	5.3%
Premium Villa 12.5m Allotment	5	4	—	—	9	9.5%
Courtyard 14m Allotment	4	1	—	—	5	5.3%
Premium Courtyard 16m Allotment	1	—	—	—	1	1.1%
Premium Traditional 20m Allotment	2	—	—	—	2	2.1%
Possible Multiple Residential Allotment	—	1	—	—	1	1.1%
Subtotal	12	11	—	—	23	24.2%
28m Deep Terrace Product						
Terrace 7.5m Allotment	—	—	—	—	—	0.0%
Terrace 9.5m Allotment	—	—	—	—	—	0.0%
Subtotal	—	—	—	—	—	0.0%
30m Deep Product						
Villa 10m Allotment	6	4	6	—	16	16.8%
Premium Villa 12.5m Allotment	12	3	16	—	31	32.6%
Courtyard 14m Allotment	5	5	6	—	16	16.8%
Premium Courtyard 16m Allotment	1	3	—	—	4	4.2%
Traditional 18m Allotment	—	—	—	—	—	0.0%
Premium Traditional 20m Allotment	—	3	2	—	5	5.3%
Possible Multiple Residential Allotment	—	—	—	—	—	0.0%
Subtotal	24	18	30	—	72	75.8%
Total Residential Allotments	36	29	30	—	95	100.0%
Residential Net Density	17.7 dw/ha	18.7 dw/ha	14.3 dw/ha	—		
Super Lots						
Child Care	—	—	—	1	1	
Sub Total	—	—	—	1	1	
Total Allotments	36	29	30	1	96	
Maximum Potential Residential Dwellings (Includes Multiple Residential Allotments)	36	30	30	0	96	
Maximum Potential Net Residential Density	17.7 dw/ha	19.3 dw/ha	14.3 dw/ha	—		

Land Budget						
	Stage 10A	Stage 10B	Stage 10C	Stage 10D	Overall	
Land Use	Area	Area	Area	Area	Area	%
Stage Area	2.038 ha	1.554 ha	2.096 ha	0.301 ha	5.989 ha	100.0%
Saleable Area						
Residential Allotments	1.371 ha	1.114 ha	1.237 ha	—	3.722 ha	62.1%
Child Care	—	—	—	0.301 ha	0.301 ha	5.0%
Total Area of Allotments	1.371 ha	1.114 ha	1.237 ha	0.301 ha	4.023 ha	67.2%
Road						
North South Arterial Dedication (incl. batters)	—	—	—	—	—	0.0%
Trunk Connector 2 Lanes (23.7m)	—	—	—	—	—	0.0%
Neighbourhood Connector (20.2m)	—	—	—	—	—	0.0%
Neighbourhood Access Street (16.5m)	0.667 ha	0.440 ha	0.588 ha	—	1.695 ha	28.3%
Landeway (6.5m)	—	—	—	—	—	0.0%
Pedestrian Linkages	—	—	0.030 ha	—	0.030 ha	0.5%
Total Area of New Road	0.667 ha	0.440 ha	0.618 ha	—	1.725 ha	28.8%
Open Space						
Conservation Buffer	—	—	—	—	—	0.0%
Corridor Park / Conservation	—	—	—	—	—	0.0%
Stormwater Management	—	—	—	—	—	0.0%
Regional Sports	—	—	—	—	—	0.0%
District Sports	—	—	—	—	—	0.0%
Neighbourhood Recreation Park	—	—	—	—	—	0.0%
Local Recreation Park	—	—	—	—	—	0.0%
Local Linear Recreation Park	—	—	0.241 ha	—	0.241 ha	4.0%
Total Open Space	—	—	0.241 ha	—	0.241 ha	4.0%





PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2024/1491

Date: 7 May 2025



- Legend**
- General**
- Application Boundary
 - Stage Boundary
 - Sub Stage Boundary
 - Concept Design Contours (1m)
 - Bus Stop Catchment (400m)
 - Indicative Indented Bus Stop Location
 - Neighbourhood Park Catchment (400m)

Note:

All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.

Dimensions have been rounded to the nearest 0.1 metres.

Areas have been rounded down to the nearest 5m².

The boundaries shown on this plan should not be used for final detailed engineers design.

Source Information:

Site boundaries: Veris.

Adjoining information: Veris.

Design Contours: Colliers (29-08-2024).

Environment constraints: Saunders Havill Group.

Q100: Engeny.


North South Arterial Alignment: Colliers.


Land Budget

Land Use	Stage 10E	Stage 10G	Stage 10I	Stage 10J	Overall	
	Area	Area	Area	Area	Area	%
Stage Area	0.539 ha	1.714 ha	0.771 ha	2.121 ha	5.145 ha	100.0%
Saleable Area						
Residential Allotments	—	1.213 ha	0.294 ha	1.278 ha	2.785 ha	54.1%
Child Care	—	—	—	—	—	0.0%
Total Area of Allotments	—	1.213 ha	0.294 ha	1.278 ha	2.785 ha	54.1%
Road						
North South Arterial Dedication (incl. batters)	—	—	—	—	—	0.0%
Trunk Connector 2 Lanes (23.7m)	—	—	—	—	—	0.0%
Neighbourhood Connector (20.2m)	—	—	—	0.598 ha	0.598 ha	11.6%
Neighbourhood Access Street (16.5m)	—	0.501 ha	0.402 ha	0.173 ha	1.076 ha	20.9%
Laneway (6.5m)	—	—	0.075 ha	—	0.075 ha	1.5%
Pedestrian Linkages	—	—	—	0.072 ha	0.072 ha	1.4%
Total Area of New Road	—	0.501 ha	0.477 ha	0.843 ha	1.821 ha	35.4%
Open Space						
Conservation Buffer	—	—	—	—	—	0.0%
Corridor Park / Conservation	—	—	—	—	—	0.0%
Stormwater Management	—	—	—	—	—	0.0%
Regional Sports	—	—	—	—	—	0.0%
District Sports	—	—	—	—	—	0.0%
Neighbourhood Recreation Park	0.539 ha	—	—	—	0.539 ha	10.5%
Local Recreation Park	—	—	—	—	—	0.0%
Local Linear Recreation Park	—	—	—	—	—	0.0%
Total Open Space	0.539 ha	—	—	—	0.539 ha	10.5%

KEY MAP

Scale: 1 : 7,500





Legend

General

- Application Boundary
- Stage Boundary
- Sub Stage Boundary
- Concept Design Contours (1m)
- Bus Stop Catchment (400m)
- Indicative Indented Bus Stop Location
- Neighbourhood Park Catchment (400m)

KEY MAP

Scale: 1 : 7,500

Note:

All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.

Dimensions have been rounded to the nearest 0.1 metres.

Areas have been rounded down to the nearest 5m².

The boundaries shown on this plan should not be used for final detailed engineers design.

Source Information:

Site boundaries: Veris.
Adjoining information: Veris.
Design Contours: Colliers (29-08-2024).
Environment constraints: Saunders Havill Group.
Q100: Engeny.
North South Arterial Alignment: Colliers.

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2024/1491
Date: 7 May 2025



Yield Breakdown

Lot Type	Stage 10F		Overall	
	Yield	Yield	Yield	%
25m Deep Product				
Villa 10m Allotment	2	2	2	5.1%
Premium Villa 12.5m Allotment	5	5	5	12.8%
Courtyard 14m Allotment	11	11	11	28.2%
Premium Courtyard 16m Allotment	1	1	1	2.6%
Premium Traditional 20m Allotment	2	2	2	5.1%
Possible Multiple Residential Allotment	—	—	—	0.0%
Subtotal	21	21	21	53.8%
28m Deep Terrace Product				
Terrace 7.5m Allotment	—	—	—	0.0%
Terrace 9.5m Allotment	—	—	—	0.0%
Subtotal	—	—	—	0.0%
30m Deep Product				
Villa 10m Allotment	8	8	8	20.5%
Premium Villa 12.5m Allotment	6	6	6	15.4%
Courtyard 14m Allotment	4	4	4	10.3%
Premium Courtyard 16m Allotment	—	—	—	0.0%
Traditional 18m Allotment	—	—	—	0.0%
Premium Traditional 20m Allotment	—	—	—	0.0%
Possible Multiple Residential Allotment	—	—	—	0.0%
Subtotal	18	18	18	46.2%
Total Residential Allotments	39	39	39	100.0%
Residential Net Density	17.7 dw/ha			
Super Lots				
Child Care	—	—	—	—
Sub Total	—	—	—	—
Total Allotments	39	39	39	
Maximum Potential Residential Dwellings (Includes Multiple Residential Allotments)	39		39	
Maximum Potential Net Residential Density	17.7 dw/ha			

Land Budget

Land Use	Stage 10F	Stage 10H	Stage 10T	Overall	
	Area	Area	Area	Area	%
Stage Area	2.199 ha	0.555 ha	3.079 ha	5.833 ha	100.0%
Saleable Area					
Residential Allotments	1.427 ha	—	—	1.427 ha	24.5%
Child Care	—	—	—	—	0.0%
Total Area of Allotments	1.427 ha	—	—	1.427 ha	24.5%
Road					
North South Arterial Dedication (incl. batters)	—	—	3.079 ha	3.079 ha	52.8%
Trunk Connector 2 Lanes (23.7m)	—	—	—	—	0.0%
Neighbourhood Connector (20.2m)	—	—	—	—	0.0%
Neighbourhood Access Street (16.5m)	0.742 ha	—	—	0.742 ha	12.7%
Laneway (6.5m)	—	—	—	—	0.0%
Pedestrian Linkages	0.030 ha	—	—	0.030 ha	0.5%
Total Area of New Road	0.772 ha	—	3.079 ha	3.851 ha	66.0%
Open Space					
Conservation Buffer	—	—	—	—	0.0%
Corridor Park / Conservation	—	—	—	—	0.0%
Stormwater Management	—	0.555 ha	—	0.555 ha	9.5%
Regional Sports	—	—	—	—	0.0%
District Sports	—	—	—	—	0.0%
Neighbourhood Recreation Park	—	—	—	—	0.0%
Local Recreation Park	—	—	—	—	0.0%
Local Linear Recreation Park	—	—	—	—	0.0%
Total Open Space	—	0.555 ha	—	0.555 ha	9.5%

PLAN REF: 110056 – 577

Rev No: B
DATE: 12 DECEMBER 2024
CLIENT: PEET
DRAWN BY: JC / MM
CHECKED BY: MD



FLAGSTONE CA3 SOUTH
STAGE 10F, 10H & 10T
PLAN OF SUBDIVISION

PEET

URBAN DESIGN
Level 8
31 Duncan Street
PO Box 1559
Fortitude Valley QLD 4006
T +61 7 3539 9500
W rpsgroup.com

rps

A TETRA TECH COMPANY

© COPYRIGHT
Unauthorised reproduction or amendment not permitted. Please contact the author.

0 20 40 60 80 100 1 : 1,500 @ A3



Plan of Development Table	Rear Loaded Terrace Allotments		Villa Allotments		Premium Villa Allotments		Courtyard Allotments		Premium Courtyard Allotments		Traditional Allotments		Premium Traditional Allotments		Multiple Residential Allotments (MR)	
	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor
Front/Primary Frontage	2.4m	2.4m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	4.5m	4.5m	4.5m	4.5m	3.0m	3.0m
Garage	n/a	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a
Rear	0.9m	0.9m	0.9m	0.9m	1.0m	1.0m	1.0m	1.5m	1.0m	1.5m	1.5m	2.0m	1.5m	2.0m	1.5m	1.5m
Side - General Lots																
Built to Boundary	0.0m	0.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	n/a	n/a	n/a	n/a	n/a	n/a
Maximum BTB Wall Length (% of boundary length)	90%		70%		65%		65%		60%		n/a		n/a		n/a	
Non Built to Boundary	0.9m	0.9m	0.9m	0.9m	1.0m	1.0m	1.0m	1.5m	1.0m	1.5m	1.5m	2.0m	1.5m	2.0m	1.0m	1.5m
Corner Lots - Secondary Frontage	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	2.0m	1.5m	2.0m	1.5m	1.5m
Laneway Lots																
Rear of Lot (from laneway boundary including garage)	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	n/a	n/a	n/a	n/a	n/a	n/a
Site Cover	75%		65%		60%		60%		60%		60%		60%		75%	

Notes:
General

1. All development is to be undertaken in accordance with the Development Approval, and Queensland Development Code (QDC), except as varied below.
2. The maximum height of buildings shall not exceed two (2) storeys.
3. Maximum building location envelopes are subject to future proposed easements and/or other underground services.
4. All lots subject to an acoustic assessment to determine level of acoustic treatments.
5. Buildings shall be constructed in accordance with Bushfire AS3959.
6. Secondary dwellings are not permitted on lots less than 400m².
7. Provisions in this POD do not relate to the following allotments: the District Centre allotment (lot 50032); the Ambulance allotment (lot 50033); the Child Care Allotments (lot 50034, 50036, 50037); the State Primary School allotment (lot 30015); the Local Centre Allotments (lots 50038 and 50040); the Community Facility Allotment (lot 50039); or Medium Density Allotments (lot 50041, 50042 and 50043). A separate MCU application will need to be submitted for development on these lots.
8. Approved uses are House, Multiple Residential, Home Based Business, Display Home and Sales Office.
9. Approved uses also includes 'Other Residential' - where limited to accommodation for disadvantaged persons, accommodation for persons who are being nursed, require ongoing supervision/support or are convalescing or crisis accommodation (including persons escaping domestic violence). A separate MCU application will need to be submitted for Residential care facility or retirement facility uses.
10. Advertising Devices, where associated with a display home/village and temporary in nature, are Exempt Development.

Setbacks

11. Setbacks are as per the Plan of Development Table unless otherwise dimensioned. If a lot is not developed for a Multiple Residential (MR) site, then the equivalent size detached lot setbacks will apply.
12. The location of the built to boundary walls are indicated on the Plan of Development. Where built to boundary walls are not adopted side setbacks shall be in accordance with the Plan of Development Table.
13. Boundary setbacks are measured to the wall of the structure.
14. Front verandah and covered areas to the front door are permitted to extend into the front setback on the condition that the roofed area is not enclosed. For front setbacks, this roofed area can extend to 1.0m from the front property line.
15. Eaves cannot encroach (other than where buildings are built to boundary) closer than 450mm to the lot boundary.
16. If a retaining wall which exceeds 2.0m in height is present along the rear boundary of an allotment (single face wall construction), a 2.5m rear setback must be adopted.
17. If a terraced retaining wall is adopted at the rear boundary of a property, the lower face is to be a maximum of 1.0m from the property boundary, and a 2.5m rear setback must be adopted.
18. A corner lot, for the purposes of determining setbacks, is a lot that adjoins the intersection of two streets. This excludes those lots that abut a shared access driveway, laneway or a pedestrian link/ landscape buffer and therefore in these cases a secondary frontage setback does not apply.
19. In the case of corner allotments an additional setback from the street corner is applicable. The setback applies to any building or structure greater than 2m high as follows:

In the case of Terrace and Villa Corner Lots, the setback is measured as the line that joins the points on the front and side street boundaries of the lot that are located 6m back from the point of intersection of these two boundaries.

In the case of Premium Villa, Courtyard, Premium Courtyard, Traditional, Premium Traditional, Ridgetop Allotments and Multiple Residential Corner Lots, the setback is measured as the line that joins the points on the front and side street boundaries of the lot that are located 9m back from the point of intersection of these two boundaries.

Private Open Space

20. Private open space must measure a minimum of 10m² with a minimum dimension in any direction of 2.4 metres.
21. Private open space must be directly accessible from a living space.

On-site car parking and driveways

22. On-site car parking is to be provided in accordance with the following minimum requirements:

For lots <12.5 metres wide - 1 covered space per dwelling;

For lots 12.5 metres wide or greater - 2 covered spaces per dwelling;

For Multiple Residential sites, at least 1 covered space per dwelling, plus 0.5 spaces per dwelling (can be uncovered).
23. Garages for any single storey dwelling on a Lot between 10.0m and 12.49m in width must adhere to the following design criteria:

The front facing building wall, which comprises the garage door, must not exceed an external width of 5.7m

The garage door:

Width must not exceed 4.8m

Must have a minimum 450mm eave above it

Must be setback a minimum of 240mm behind the pillar of the garage door, and

Must have a sectional, tilt or roller door.

The front façade of the dwelling must be forward of the alignment of the garage wall, and must include the following:

A front entrance door with glass inserts and / or windows or with a sidelight where the front door is solid. If the front facade includes a habitable room with window, a sidelight is not required.

A front verandah, portico or porch located over the front entrance, which extends a minimum of 1600mm forward of the entrance door

The verandah, portico or porch is to include front piers with distinct materials and/or colours.

Driveways cannot exceed 3.0m across the verge on Lots between 10.0m and 12.49m wide.”
24. Double car garages are permitted on any double storey dwelling built on a Lot between 10.0m and 12.49m or a laneway dwelling.
25. Driveways are to accord with Logan City Council's (LCC) standards. Prior to construction, approval from LCC for Vehicular Access to Residential Premises is required.
26. The maximum width of a driveway at the lot boundary shall be 4.8 metres for a lot with a double car width garage and 3.0 metres for a lot with a single car width garage.
27. Garages and carports accessed from a Laneway must be built setback 0.9 metres from the boundary unless otherwise dimensioned on the Plan of Development. Ingress/egress must be achieved for a B99 Vehicle.
28. Maximum of one driveway per dwelling unless it is a MR lot.
29. Minimum distance of a driveway from an intersection of one street with another street is 6.0 metres. The Driveway must be laid at the grade of the adjacent verge area. No grade changes to the verge for the driveway will be allowed.
30. Where there is a footpath within the verge, the footpath should be cut at the nearest joint and the footpath reinstated to the driveway without compromising the structural integrity of the footpath.
31. Driveways must be completed prior to occupation of the dwelling.

Fencing

32. Fencing erected by Peet must not be altered, modified or removed without prior written approval from Peet.
33. Fencing on all open space and/or street frontages has a maximum height of 1.2 metres where solid or has a maximum height of 1.8 metres where containing openings that make the fence more than 50% transparent. This does not apply to side boundary fencing that abuts open space.
34. Fencing on all park or street frontages is constructed with visible posts, which are at least 120mm x 120mm and 100mm higher than the infill palings or panels.
35. Fencing on lanes can be screen fencing at 1.8m high where along private open space, carparking and service areas.
36. Fencing on corner lots is to be designed as front fences addressing both streets (rather than a front and a side fence).
37. Notwithstanding the above, solid front fences and walls may be 1.8 metres in height if the dwelling has a frontage to a street with traffic volumes in excess of, or projected to exceed, 10,000 vehicles per day.

38. Fencing on shared side boundaries of lots 4134-4138 and 4189-4130 to comply with the following:

1.8m high good neighbour style fencing permitted for the first 30 metres of the side boundary to ensure privacy between dwellings, measured from the primary street frontage. Good neighbour style fencing must not protrude forward of the front building

No side fencing or timber post and rail rural style fencing for the remainder of the side boundary.

Timber post and rail rural style fencing is to be 1200mm high sanded and stained hard wood posts at 2400mm intervals with rails at 600mm and 1100mm. Both rails must be level. Transparent infill panels of chainmesh are permitted - if adopted, a bottom rail must be incorporated which follows the angle of the ground and spaced 50mm above ground level.
39. Fencing on the rear boundaries of lots 4111-4115, 4125-4133, 4139-4144 and 4147-4188 must be 1.8m high good neighbour style fencing and adopt one consistent and uniform design to ensure allotments with multiple neighbours have consistent fencing.

Retaining Walls

40. For retaining walls **not** constructed by the developer:

Retaining walls must not exceed more than 1.0m where fronted to a public street or park. Retaining walls to side and rear boundaries (which are not adjoining a public street or park) can be up to 2.0m. Retaining in excess of this must use terraced retaining.

Where retaining walls are terraced, the lower face is to be a maximum of 1.0m from the property boundary.
41. No timber retaining walls over 1.0m or adjoining parks or public streets.
42. Walls over 1.0m require RPEQ certification.

Building Articulation

43. All buildings with a width of more than 10 metres that are visible from a street or park are to include articulation to reduce the mass of the building by one or more of the following:

Windows recessed into the façade or bay windows;

Balconies, porches or verandahs;

Articulation of roof lines

Window hoods; and/or

Use of multiple cladding materials
44. Where adjoining an area of open space, housing design must facilitate passive surveillance of the open space, which can be achieved through the incorporation of at least one (1) habitable room orientated towards the open space.
45. Carports and garages are to be compatible with the main building design in terms of height, roof form, detailing, materials and colours.
46. All building materials must be suitably coloured, stained or painted, including retaining, fences, walls and roofs. Untreated materials, such as zinc coated steel, bare metal, concrete block or masonry panels are not permitted.
47. Air-conditioners, gas bottles, hot water systems, clothes lines and other household services must be screened and/or located to minimise visual impact to public streets or parks.
48. Homes must include a clearly identifiable and addressed front door and undercover point of entry.
49. Screened drying and rubbish bins area must be behind the main face of the dwelling.
50. At least two openings to all habitable rooms to facilitate cross flow ventilation are required.

Slope and Building Footings

51. Buildings on sloping sites must be built to the boundary on the low side of the lot and the footing must be projected deep enough to be below the adjoining property building pad level.
52. If the nominated pad level is not provided, the pad level is to be assumed as the average of the four corners of the adjacent block, using the as constructed levels.
53. Building footings are to be designed in accordance with the appropriate Australian Standard. Building footings are to be designed to ensure that there are no adverse impacts (functional, financial or construction limitations) on adjoining allotments, particularly in relation to retaining walls.

Electric Vehicle Readiness

54. All dwellings are to have a dedicated electrical circuit from the circuit board to the garage for at least one Basic (slow) EVSE charger per home, in accordance with the Australian Wiring Rules AS/NZS 3000: 2018. The circuit is to be fitted with a minimum 20 Amp GPO outlet which can be replaced by a dedicated 7kW EVSE of the occupant's choice. Where not used for Electric Vehicle Supply Equipment, the circuit is to be terminated at an isolator.

Additional Criteria for Steep Residential Allotments

55. Steep Residential Allotments controls relate to all allotments within Stages 13A, 13B, 13C, 13G and 13H.
56. Building design and construction techniques are to minimise cut and fill of sloping sites through site responsive home designs that consider:

Stepped floor levels to take up the site slope withing the building;

Split level home designs; and/or

Part slab / part posts and been construction; and/or

Pole home construction.
57. Building design, cut and/or fill on site must not negatively impact the conveyance of stormwater or adversely affect neighbouring properties
58. Building design should consider the retention of existing vegetation outside of the BLE.
59. Any views into the undercroft of the home from the public street or park must be screened through architectural elements, such as vertical or horizontal battens or alttice screening that complements the aesthetic of the home.
60. Class 10 buildings or structures are permitted within the prescribed building envelope and contribute towards site cover percentage.
61. Refer to POD Note 38 and 39 for additional fencing controls.

Additional Criteria for Multiple Residential Allotments (excluding Lots 50041, 50042 & 50043)

62. Buildings must address all street frontages with driveways, pedestrian entries or both.
63. All dwellings must have a clearly identifiable front door, which is undercover.
64. Drying and rubbish bin areas must be located behind the main face of the dwelling or suitably screen from public streets and park frontages.
65. Maximum number of dwellings on each multiple residential lot is annotated on the Plan of Development.

Additional Criteria for Secondary Dwellings

66. Floor area must be between a minimum of 45m² and 75m².
67. Materials, detailing, colours and roof form are consistent with those of the primary house.
68. Outdoor living space must measure a minimum of 9m² with a minimum dimension in any direction of 3 metres.
69. Outdoor living space must be directly accessible from the main living space and can be combined with the primary dwelling outdoor space.
70. Outdoor living space on a corner allotment must be suitably screened if located within the secondary street boundary setback.
71. A minimum of one (5m x 3m) car parking space must be provided for the secondary dwelling, in addition to parking for the primary dwelling.
72. The driveway must be shared with the primary house, however on corner allotments a separate driveway may be provided with a minimum width of 3 metres and a maximum width of 5 metres.
73. Corner allotments must provide dedicated pedestrian entry and a visible door from and addressing the secondary street to the secondary dwelling.
74. Corner allotments must provide a minimum of one habitable room, with large windows or balconies, fronting the secondary street.
75. Subdivision of Secondary Dwellings is not permitted.

Definitions

Laneway Allotment - Allotments serviced by a laneway.

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2024/1491

Date: 7 May 2025



PLAN REF: 110056 – 579

Rev No: B

DATE: 12 DECEMBER 2024

CLIENT: PEET

DRAWN BY: JC

CHECKED BY: MD



FLAGSTONE CA3 SOUTH
STAGE 10 OVERALL
PLAN OF DEVELOPMENT NOTES



URBAN DESIGN
Level 8
31 Duncan Street
PO Box 1559
Fortitude Valley QLD 4006
T +61 7 3539 9500
W rpsgroup.com




© COPYRIGHT
Unauthorised reproduction or amendment not permitted. Please contact the author.

A TETRA TECH COMPANY



0 20 40 60 80 100 1 : 2,000 @ A3

Plan of Development Table	Rear Loaded Terrace Allotments		Villa Allotments		Premium Villa Allotments		Courtyard Allotments		Premium Courtyard Allotments		Traditional Allotments		Premium Traditional Allotments		Multiple Residential Allotments (MR)	
	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor
Front/Primary Frontage	2.4m	2.4m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	4.5m	4.5m	4.5m	4.5m	3.0m	3.0m
Garage	n/a	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a
Rear	0.9m	0.9m	0.9m	0.9m	1.0m	1.0m	1.0m	1.5m	1.0m	1.5m	1.5m	2.0m	1.5m	2.0m	1.5m	1.5m
Side - General Lots																
Built to Boundary	0.0m	0.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	n/a	n/a	n/a	n/a	n/a	n/a
Maximum BTB Wall Length (% of boundary length)	90%		70%		65%		65%		60%		n/a		n/a		n/a	
Non Built to Boundary	0.9m	0.9m	0.9m	0.9m	1.0m	1.0m	1.0m	1.5m	1.0m	1.5m	1.5m	2.0m	1.5m	2.0m	1.0m	1.5m
Corner Lots - Secondary Frontage	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	2.0m	1.5m	2.0m	1.5m	1.5m
Laneway Lots																
Rear of Lot (from laneway boundary including garage)	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	n/a	n/a	n/a	n/a	n/a	n/a
Site Cover	75%		65%		60%		60%		60%		60%		60%		75%	





Plan of Development Table	Rear Loaded Terrace Allotments		Villa Allotments		Premium Villa Allotments		Courtyard Allotments		Premium Courtyard Allotments		Traditional Allotments		Premium Traditional Allotments		Multiple Residential Allotments (MR)	
	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor
Front/Primary Frontage	2.4m	2.4m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	4.5m	4.5m	4.5m	4.5m	3.0m	3.0m
Garage	n/a	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a
Rear	0.9m	0.9m	0.9m	0.9m	1.0m	1.0m	1.0m	1.5m	1.0m	1.5m	1.5m	2.0m	1.5m	2.0m	1.5m	1.5m
Side - General Lots																
Built to Boundary	0.0m	0.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	n/a	n/a	n/a	n/a	n/a	n/a
Maximum BTB Wall Length (% of boundary length)	90%		70%		65%		65%		60%		n/a		n/a		n/a	
Non Built to Boundary	0.9m	0.9m	0.9m	0.9m	1.0m	1.0m	1.0m	1.5m	1.0m	1.5m	1.5m	2.0m	1.5m	2.0m	1.0m	1.5m
Corner Lots - Secondary Frontage	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	2.0m	1.5m	2.0m	1.5m	1.5m
Laneway Lots																
Rear of Lot (from laneway boundary including garage)	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	n/a	n/a	n/a	n/a	n/a	n/a
Site Cover	75%		65%		60%		60%		60%		60%		60%		75%	



- Legend**
- General**
- Application Boundary
 - Stage Boundary
 - Sub Stage Boundary
 - Concept Design Contours (1m)
 - 2m High Noise Barrier
- Open Space**
- Stormwater Detention
 - Linear Connections
- Allotment Details**
- Split Level Allotments
 - Preferred Private Open Space Location
 - Maximum Building Location Envelope
 - Mandatory Built to Boundary Wall
 - Optional Built to Boundary Wall
 - Preferred Double Garage Location
 - Preferred Single Garage Location
 - Lot Impacted by Potential Acoustic Requirements

Note:
All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.
Dimensions have been rounded to the nearest 0.1 metres.
Areas have been rounded down to the nearest 5m².
The boundaries shown on this plan should not be used for final detailed engineers design.

Source Information:
Site boundaries: Veris.
Adjoining information: Veris.
Design Contours: Colliers (29-08-2024).
Environment constraints: Saunders Havill Group.
Q100: Engeny.
North South Arterial Alignment: Colliers.

Plan of Development Table	Rear Loaded Terrace Allotments		Villa Allotments		Premium Villa Allotments		Courtyard Allotments		Premium Courtyard Allotments		Traditional Allotments		Premium Traditional Allotments		Multiple Residential Allotments (MR)	
	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor	Ground Floor	First Floor
Front/Primary Frontage	2.4m	2.4m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	3.0m	4.5m	4.5m	4.5m	4.5m	3.0m	3.0m
Garage	n/a	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a	5.0m	n/a
Rear	0.9m	0.9m	0.9m	0.9m	1.0m	1.0m	1.0m	1.5m	1.0m	1.5m	1.5m	2.0m	1.5m	2.0m	1.5m	1.5m
Side - General Lots																
Built to Boundary	0.0m	0.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	0.0m	1.0m	n/a	n/a	n/a	n/a	n/a	n/a
Maximum BTB Wall Length (% of boundary length)	90%		70%		65%		65%		60%		n/a		n/a		n/a	
Non Built to Boundary	0.9m	0.9m	0.9m	0.9m	1.0m	1.0m	1.0m	1.5m	1.0m	1.5m	1.5m	2.0m	1.5m	2.0m	1.0m	1.5m
Corner Lots - Secondary Frontage	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	1.5m	2.0m	1.5m	2.0m	1.5m	1.5m
Laneway Lots																
Rear of Lot (from laneway boundary including garage)	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	0.9m	n/a	n/a	n/a	n/a	n/a	n/a
Site Cover	75%		65%		60%		60%		60%		60%		60%		75%	

All Lot Numbers, Dimensions and Areas are approximate only, and are subject to survey and Council approval.

Areas have been rounded down to the nearest 5m².

Source Information:

Site boundaries: Veris.


Adjoining information: Veris.

Contours: Qspatial.

Environment constraints: Saunders Havill Group.

Q100: Engeny.

North South Arterial Alignment: Colliers.



Typical Indented Parking Bay Arrangement
(In accordance with AS2890)
Scale 1 : 200

Total On-Street Visitor Parking Spaces Provided	162
Total Residential Dwellings	210
Total On-Street Visitor Parking Spaces Required	158
(based on 0.75 per dwelling)	

4



PEET

URBAN DESIGN
Level 8
31 Duncan Street
PO Box 1559
Fortitude Valley QLD 4006
T +61 7 3539 9500
W rpsgroup.com

© COPYRIGHT **A TETRA TECH COMPANY**
Unauthorised reproduction or amendment not permitted. Please contact the author.



A TETRA TECH COMPANY