Our ref: DEV2024/1491

7 May 2025

Peet Flagstone City Pty Ltd C/-RPS AAP Consulting Pty Ltd Att: Nick Meadows Level 8, 31 Duncan Street FORTITUDE VALLEY QLD 4006

Email: nick.meadows@rpsconsulting.com

Dear Mr Meadows

S89(1)(a) Approval of PDA Development Application

Development Permit for Reconfiguring a Lot – 4 lots into 1,631 residential lots, 9 non-residential lots, open space, new roads, balance lots, and associated Plan of Development at New Beith and Everdell Roads, New Beith described as Lot 1 on RP35155, Lot 989 on RP854074, Lot 908 on SP335853 and Lot 911 on SP340300

On 7 May 2025, pursuant to s.85(4)(b) of the *Economic Development Act 2012*, the Minister for Economic Development Queensland (MEDQ) decided to grant **all** of the PDA development application applied for, in accordance with the attached PDA decision notice.

The PDA decision notice and approved plans / documents can also be viewed in the MEDQ Development Approvals Register via the website at <u>Current applications and approvals</u>.

If you require any further information, please contact Gabrielle Shepherd, Principal Planner, Development Assessment, in Economic Development Queensland, by telephone on (07) 3452 7914 or at gabrielle.shepherd@edq.qld.gov.au, who will assist.

Yours sincerely

Amandă Dryden

Director

Development Assessment

Economic Development Queensland



PDA Decision Notice

Site information			
Name of priority development area (PDA)	Greater Flagstone		
Site address	New Beith and Everdell Roads, New Beith		
Lot on plan description	Lot number	Plan description	
	Lot 1	RP35155	
	Lot 989	RP854074	
	Lot 908	SP335853	
	Lot 911	SP340300	
PDA development application details			
DEV reference number	DEV2024/1491		
'Properly made' date	20 March 2024		
Type of application	 ☑ PDA development application for: ☐ Material change of use ☐ Preliminary approval ☐ Development permit ☑ Reconfiguring a lot ☐ Preliminary approval ☑ Development permit ☐ Operational work ☐ Preliminary approval ☐ Development permit ☐ Application to change PDA development approval ☐ Application to extend currency period 		
Proposed development	1631 residential lots, 9 non-re new roads, balance lots, and Development		
PDA development approval details			
Decision of the MEDQ	The MEDQ has decided to gradevelopment approval applied development conditions formi	for, subject to PDA	
Decision date	7 May 2025		
Currency period	4 years from the date of the decision		
Assessment Team			
Assessment Manager (Lead)	Gabrielle Shepherd, Principal Planner		
Manager	Leila Torrens, Manager		
Engineer	Jack Landsberg, Principal Technical Officer		
Delegate	Amanda Dryden, Director		

Approved plans and documents

The plans and documents approved by the MEDQ and referred to in the PDA development conditions for the PDA development approval are detailed below.

oved plans and documents	Number	Date
•		12/12/2024
Subdivision, prepared by RPS	110000 000 Nev B	12/12/2027
Flagstone CA3 South Stages 8-14 Overall Plan of Subdivision Statistics, prepared by RPS	110056-640 Rev B	12/12/2024
Flagstone CA3 South Stage 14 Overall Plan of Subdivision, prepared by RPS	110056–623 Rev B	12/12/2024
Flagstone CA3 South Stage 14 Plan of Subdivision, prepared by RPS	110056–624 Rev B	12/12/2024
Flagstone CA3 South Stage 14A-14D Overall Plan of Subdivision, prepared by RPS	110056–625 Rev B	12/12/2024
Flagstone CA3 South Stage 14E-14G & 14I Plan of Subdivision, prepared by RPS	110056-626 Rev B	12/12/2024
Flagstone CA3 South Stage 14L, 14M - 14O Plan of Subdivision, prepared by RPS	110056-627 Rev B	12/12/2024
Flagstone CA3 South Stage 4J, 14K & 14P Plan of Subdivision, prepared by RPS	110056-628 Rev B	12/12/2024
Flagstone CA3 South Stage 14H, 14Q-2, 14Q-3 & 14R Plan of Subdivision, prepared by RPS	110056-629 Rev B	12/12/2024
Flagstone CA3 South Stage 14S-1 - 14S-5 Plan of Subdivision, prepared by RPS	110056-630 Rev B	12/12/2024
Flagstone CA3 South Stage 14 Overall Plan of Development, prepared by RPS	110056–631 Rev B	12/12/2024
Flagstone CA3 South Stage 14 Overall Plan of Development Notes, prepared by RPS	110056–632 Rev B	12/12/2024
Flagstone CA3 South Stage 14a - 14d Plan of Development, prepared by RPS	110056–633 Rev B	12/12/2024
Flagstone CA3 South Stage 14E - 14G & 14I Plan of Development, prepared by RPS	110056-634 Rev B	12/12/2024
Flagstone CA3 South Stage 14L, 14M - 14O Plan of Development, prepared by RPS	110056–635 Rev B	12/12/2024
Flagstone CA3 South Stage 14J, 14K & 14P Plan of Development, prepared by RPS	110056–636 Rev B	12/12/2024
Flagstone CA3 South Stage 14H – 14R Plan of Development, prepared by RPS	110056–637 Rev B	12/12/2024
Flagstone CA3 South Stage 14 Parking Management Plan, prepared by RPS	110056–638 Rev B	12/12/2024
Flagstone CA3 South Stage 14 Plan of Subdivision, prepared by RPS	110056-639 Rev B	12/12/2024
	Flagstone CA3 South Stages 8-14 Overall Plan of Subdivision, prepared by RPS Flagstone CA3 South Stages 8-14 Overall Plan of Subdivision Statistics, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14 Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14A-14D Overall Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14E-14G & 14I Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14L, 14M - 14O Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14L, 14K & 14P Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 4J, 14K & 14P Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14H, 14Q-2, 14Q-3 & 14R Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14S-1 - 14S-5 Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Development, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Development Notes, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Development Notes, prepared by RPS Flagstone CA3 South Stage 14E - 14G & 14I Plan of Development, prepared by RPS Flagstone CA3 South Stage 14E - 14G & 14I Plan of Development, prepared by RPS Flagstone CA3 South Stage 14L, 14M - 14O Plan of Development, prepared by RPS Flagstone CA3 South Stage 14J, 14K & 14P Plan of Development, prepared by RPS Flagstone CA3 South Stage 14J, 14K & 14P Plan of Development, prepared by RPS Flagstone CA3 South Stage 14J, 14K & 14P Plan of Development, prepared by RPS Flagstone CA3 South Stage 14 Parking Management Plan, prepared by RPS Flagstone CA3 South Stage 14 Plan of Subdivision,	Flagstone CA3 South Stages 8-14 Overall Plan of Subdivision, prepared by RPS Flagstone CA3 South Stages 8-14 Overall Plan of Subdivision Statistics, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14 Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14 Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14E-14G & 14I Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14L, 14M - 14O Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14L, 14M - 14O Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14H, 14Q-2, 14Q-3 & 14R Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14S-1 - 14S-5 Plan of Subdivision, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Development, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Development, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Development, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Development, prepared by RPS Flagstone CA3 South Stage 14 Overall Plan of Development, prepared by RPS Flagstone CA3 South Stage 14B - 14B

	<u></u>		
20.	Flagstone CA3 South Stage 13 Overall Plan of Subdivision, prepared by RPS	110056–607 Rev B	12/12/2024
21.	Flagstone CA3 South Stage 13 Overall Statistics, prepared by RPS	110056–608 Rev B	12/12/2024
22.	Flagstone CA3 South Stage 13A, 13C & 13M Plan of Subdivision, prepared by RPS	110056–609 Rev B	12/12/2024
23.	Flagstone CA3 South Stage 13B & 13H Plan of Subdivision, prepared by RPS	110056–610 Rev B	12/12/2024
24.	Flagstone CA3 South Stage 13D - 13F Plan of Subdivision, prepared by RPS	110056–611 Rev B	12/12/2024
25.	Flagstone CA3 South Stage 13J-2, 13J-3, 13J-4, 13K & 13L Plan of Subdivision, prepared by RPS	110056–612 Rev B	12/12/2024
26.	Flagstone CA3 South Stage 13B & 13G Plan of Subdivision, prepared by RPS	110056–613 Rev B	12/12/2024
27.	Flagstone CA3 South Stage 13 Overall Plan of Development, prepared by RPS	110056–614 Rev B	12/12/2024 Amended in Red 07/05/2025
28.	Flagstone CA3 South Stage 13 Overall Plan of Development Notes, prepared by RPS	110056–615 Rev B	12/12/2024 Amended in Red 07/05/2025
29.	Flagstone CA3 South Stage 13A, 13C & 13M Plan of Development, prepared by RPS	110056–616 Rev B	12/12/2024 Amended in Red 07/05/2025
30.	Flagstone CA3 South Stage 13B & 13H Plan of Development, prepared by RPS	110056–617 Rev B	12/12/2024 Amended in Red 07/05/2025
31.	Flagstone CA3 South Stage 13D - 13F Plan of Development, prepared by RPS	110056–618 Rev B	
32.	Flagstone CA3 South Stage 13K & 13L Plan of Development, prepared by RPS	110056–620 Rev B	
33.	Flagstone CA3 South Stage 13B & 13G Plan of Development, prepared by RPS	110056–621 Rev B	12/12/2024 Amended in Red 07/05/2025
34.	Flagstone CA3 South Stage 13 Overall Parking Management Plan, prepared by RPS	110056–622 Rev B	12/12/2024
35.	Flagstone CA3 South Stage 12 Overall Plan of Subdivision, prepared by RPS	110056–596 Rev B	12/12/2024
36.	Flagstone CA3 South Stage 12 Overall Statistics, prepared by RPS	110056–597 Rev B	12/12/2024
37.	Flagstone CA3 South Stage 12A - 12B Plan of Subdivision, prepared by RPS	110056–598 Rev B	12/12/2024
38.	Flagstone CA3 South Stage 12C - 12E Plan of Subdivision, prepared by RPS	110056–599 Rev B	12/12/2024
39.	Flagstone CA3 South Stage 12F - 12I Plan of Subdivision, prepared by RPS	110056–600 Rev B	12/12/2024
		· · · · · · · · · · · · · · · · · · ·	

40.	Flagstone CA3 South Stage 12 Overall Plan of Development, prepared by RPS	110056–601 Rev B	12/12/2024
41.	Flagstone CA3 South Stage 12 Overall Plan of Development Nites, prepared by RPS	110056–602 Rev B	12/12/2024
42.	Flagstone CA3 South Stage 12A - 12B Plan of Development, prepared by RPS	110056-603 Rev B	12/12/2024
43.	Flagstone CA3 South Stage 12C - 12E Plan of Development, prepared by RPS	110056-604 Rev B	12/12/2024
44.	Flagstone CA3 South Stage 12F - 12I Plan of Development, prepared by RPS	110056-605 Rev B	12/12/2024
45.	Flagstone CA3 South Stage 12 Overall Parking Management Plan, prepared by RPS	110056-606 Rev B	12/12/2024
46.	Flagstone CA3 South Stage 11 Overall Plan of Subdivision, prepared by RPS	110056–584 Rev B	12/12/2024
47.	Flagstone CA3 South Stage 11 Overall Statistics, prepared by RPS	110056–585 Rev B	12/12/2024
48.	Flagstone CA3 South Stage 11A - 11E Plan of Subdivision, prepared by RPS	110056–586 Rev B	12/12/2024
49.	Flagstone CA3 South Stage 11B – 11D Plan of Subdivision, prepared by RPS	110056–587 Rev B	12/12/2024
50.	Flagstone CA3 South Stage 11F - 11H Plan of Subdivision, prepared by RPS	110056–588 Rev B	12/12/2024
51.	Flagstone CA3 South Stage 11I - 11J Plan of Subdivision, prepared by RPS	110056–589 Rev B	12/12/2024
52.	Flagstone CA3 South Stage 11I & 11J Plan of Subdivision, prepared by RPS	110056–590 Rev B	12/12/2024
53.	Flagstone CA3 South Stage 11A - 11E Plan of Development, prepared by RPS	110056–591 Rev B	12/12/2024
54.	Flagstone CA3 South Stage 11 Overall Plan of Development Notes, prepared by RPS	110056–592 Rev B	12/12/2024
55.	Flagstone CA3 South Stage 11A - 11E Plan of Development, prepared by RPS	110056–593 Rev B	12/12/2024
56.	Flagstone CA3 South Stage 11B – 11D Plan of Development, prepared by RPS	110056–594 Rev B	12/12/2024
57.	Flagstone CA3 South Stage 11 Parking Management Plan, prepared by RPS	110056–595 Rev B	12/12/2024
58.	Flagstone CA3 South Stage 10 Overall Plan of Subdivision, prepared by RPS	110056–573 Rev B	12/12/2024
59.	Flagstone CA3 South Stage 10 Overall Statistics, prepared by RPS	110056–574 Rev B	12/12/2024
60.	Flagstone CA3 South Stage 10A - 10D Plan of Subdivision, prepared by RPS	110056–575 Rev B	12/12/2024
61.	Flagstone CA3 South Stage 10E - 10G & 10I Plan of Subdivision, prepared by RPS	110056–576 Rev B	12/12/2024

62.	Flagstone CA3 South Stage 10F, 10H & 10T Plan of Subdivision, prepared by RPS	110056–577 Rev B	12/12/2024
63.	Flagstone CA3 South Stage 10 Overall Plan of Development, prepared by RPS	110056–578 Rev B	12/12/2024
64.	Flagstone CA3 South Stage 10 Overall Plan of Development Notes, prepared by RPS	110056–579 Rev B	12/12/2024
65.	Flagstone CA3 South Stage 10A - 10D Plan of Development, prepared by RPS	110056–580 Rev B	12/12/2024
66.	Flagstone CA3 South Stage 10E - 10G & 10I Plan of Subdivision, prepared by RPS	110056–581 Rev B	12/12/2024
67.	Flagstone CA3 South Stage 10F, 10H & 10T Plan of Development, prepared by RPS	110056–582 Rev B	12/12/2024
68.	Flagstone CA3 South Stage 10 Parking Management Plan, prepared by RPS	110056–583 Rev B	12/12/2024
69.	Flagstone CA3 South Stage 9 Overall Plan of Subdivision, prepared by RPS	110056–558 Rev B	12/12/2024
70.	Flagstone CA3 South Stage 9 Overall Statistics, prepared by RPS	110056–559 Rev B	12/12/2024
71.	Flagstone CA3 South Stage 9A-2, 9B, 9C-1 & 9C-2 Plan of Subdivision, prepared by RPS	110056–560 Rev B	12/12/2024
72.	Flagstone CA3 South Stage 9E & 9H Plan of Subdivision, prepared by RPS	110056–561 Rev B	12/12/2024
73.	Flagstone CA3 South Stage 9D-1, 9D-2, 9G & 9I Plan of Subdivision, prepared by RPS	110056–562 Rev B	12/12/2024
74.	Flagstone CA3 South Stage F, 9G, 9J - 9L Plan of Subdivision, prepared by RPS	110056–563 Rev B	12/12/2024
75.	Flagstone CA3 South Stage 9A-1, 9M & 9N Plan of Subdivision, prepared by RPS	110056–564 Rev B	12/12/2024
76.	Flagstone CA3 South Stage 9 Overall Plan of Subdivision, prepared by RPS	110056–565 Rev B	12/12/2024
77.	Flagstone CA3 South Stage 9 Overall Plan of Development Notes, prepared by RPS	110056–566 Rev B	12/12/2024
78.	Flagstone CA3 South Stage 9A-2, 9B, 9C-1 & 9C-2 Plan of Development, prepared by RPS	110056–567 Rev B	12/12/2024
79.	Flagstone CA3 South Stage 9E & 9H Plan of Development, prepared by RPS	110056–568 Rev B	12/12/2024
80.	Flagstone CA3 South Stage 9D-1, 9D-2, 9E - 9I Plan of Development, prepared by RPS	110056–569 Rev B	12/12/2024
81.	Flagstone CA3 South Stage 9F, 9G, 9J - 9L Plan of Development, prepared by RPS	110056–570 Rev B	12/12/2024
82.	Flagstone CA3 South Stage 9M & 9N Plan of Development, prepared by RPS	110056–571 Rev B	12/12/2024
83.	Flagstone CA3 South Stage 9 Parking Management Plan, prepared by RPS	110056–572 Rev B	12/12/2024

84.	Flagstone CA3 South Stage 8 Plan of Subdivision, prepared by RPS	110056–557 Rev B	12/12/2024
85.	Flagstone Context Area 3 Landscape Master Plan, prepared by RPS	Rev B	02/09/2024
86.	Fauna Management Plan, Flagstone Context Area 3 (CA3) south, prepared by Saunders Havill Group	Job No. 9850 Issue D	30/08/2024
87.	Vegetation Management Plan - Context Plan 3 Area - Phase 1 Bulk Earthworks, prepared by Saunders Havill Group	9850 E 02 CP3 Stage 1 VMP A – Vegetation Clearing Notes	5 March 2024
88.		9850 E 03 CP3 Stage 1 VMP C – Key Plan	27 August 2024
89.		9850 E 04-82 CP3 Stage 1 VMP C – Detail Sheets	30 August 2024
90.		9850 E 83 CP3 Stage 1 VMP C – Clearing Direction	27 August 2024
91.		Appendix A – Stage CP3 Phase 1 Tree Schedule	27 August 2024
92.	Flagstone Development, Context Area 3 (CA3) South Road Traffic Noise Intrusion Assessment, Stages 8-14, prepared by SLR	620.v10512.02002 Rev 2	18 March 2024
93.	Geotechnical Site Investigation & Landslide Risk Assessment @ Context 3, New Beith Road Flagstone QLD 4280, prepared by Qualtest Geotechnical and Laboratory	6464 – 24-338	22/08/2024
94.	Bushfire management plan, prepared by LEC	24020 FINAL	2 October 2024
95.	Flagstone City Context Area 3 South Traffic & Transport Assessment, prepared by Bitzios Consulting	P2300.001R Flagstone City CA3 South TIA	14/02/2025
96.	Flagstone City CA3 South Site-Based Stormwater Management Plan, prepared by Engeny	QC4012_002-REP- 004-2 Rev 2	23/08/2024
97.	Trunk Sewer Cover Plan, prepared by Colliers	20-0211-DA-0600 Rev A	22/08/2024
98.	Trunk Sewer Overall Layout Plan, prepared by Colliers	20-0211-DA-0610 Rev A	22/08/2024
99.	Trunk Sewer Layout Plan Sheet 1 of 7, prepared by Colliers	20-0211-DA-0611 Rev A	22/08/2024
100.	Trunk Sewer Layout Plan Sheet 2 of 7, prepared by Colliers	20-0211-DA-0612 Rev A	22/08/2024
101.	Trunk Sewer Layout Plan Sheet 3 of 7, prepared by Colliers	20-0211-DA-0613 Rev A	22/08/2024

102	Trunk Sewer Layout Plan Sheet 4 of 7, prepared by	20-0211-DA-0614	22/08/2024
102.	Colliers	Rev A	22/00/2024
103.	Trunk Sewer Layout Plan Sheet 5 of 7, prepared by Colliers	20-0211-DA-0615 Rev A	22/08/2024
104.	Trunk Sewer Layout Plan Sheet 6 of 7, prepared by Colliers	20-0211-DA-0616 Rev A	22/08/2024
105.	Trunk Sewer Layout Plan Sheet 7 of 7, prepared by Colliers	20-0211-DA-0617 Rev A	22/08/2024
106.	Trunk Sewer Longitudinal Sections Sheet 1 of 6, prepared by Colliers	20-0211-DA-0620 Rev A	22/08/2024
107.	Trunk Sewer Longitudinal Sections Sheet 2 of 6, prepared by Colliers	20-0211-DA-0621 Rev A	22/08/2024
108.	Trunk Sewer Longitudinal Sections Sheet 3 of 6, prepared by Colliers	20-0211-DA-0622 Rev A	22/08/2024
109.	Trunk Sewer Longitudinal Sections Sheet 4 of 6, prepared by Colliers	20-0211-DA-0623 Rev A	22/08/2024
110.	Trunk Sewer Longitudinal Sections Sheet 5 of 6, prepared by Colliers	20-0211-DA-0624 Rev A	22/08/2024
111.	Trunk Sewer Longitudinal Sections Sheet 6 of 6, prepared by Colliers	20-0211-DA-0625 Rev A	22/08/2024
112.	Trunk Sewer Cover Plan, prepared by Colliers	20-0211-500	
113.	General Notes & Live Works, prepared by Colliers	20-0211-501	
114.	Trunk Sewer Layout Plan Sheet 1, prepared by Colliers	20-0211-502	
115.	Trunk Sewer Layout Plan Sheet 2, prepared by Colliers	20-0211-503	
116.	Trunk Sewer Layout Plan Sheet 3, prepared by Colliers	20-0211-504	
117.	Trunk Sewer Layout Plan Sheet 4, prepared by Colliers	20-0211-505	
118.	Trunk Sewer Layout Plan Sheet 5, prepared by Colliers	20-0211-506	
119.	Trunk Sewer Longitudinal Sections Sheet 1, prepared by Colliers	20-0211-507	
120.	Trunk Sewer Longitudinal Sections Sheet 2, prepared by Colliers	20-0211-508	
121.	Trunk Sewer Longitudinal Sections Sheet 3, prepared by Colliers	20-0211-509	
122.	Trunk Sewer Longitudinal Sections Sheet 4, prepared by Colliers	20-0211-510	
123.	Trunk Sewer Cover Plan	23-0202-1700	
124.	General Notes & Live Works	23-0202-1700	
125.	Trunk Sewer Overall Layout Plan	23-0202-1710	
126.	Trunk Sewer Layout Plan Sheet 1 of 5	23-0202-1711	
127.	Trunk Sewer Layout Plan Sheet 2 of 5	23-0202-1712	

128.	Trunk Sewer Layout Plan Sheet 3 of 5	23-0202-1713	
129.	Trunk Sewer Layout Plan Sheet 4 of 5	23-0202-1714	
130.	Trunk Sewer Layout Plan Sheet 5 of 5	23-0202-1715	
131.	Trunk Sewer Longitudinal Sections Sheet 1 of 4	23-0202-1716	
132.	Trunk Sewer Longitudinal Sections Sheet 2 of 4	23-0202-1717	
133.	Trunk Sewer Longitudinal Sections Sheet 3 of 4	23-0202-1718	
134.	Trunk Sewer Longitudinal Sections Sheet 4 of 4	23-0202-1719	
135.	Typical Bored and Embedment Detail	23-0202-1720	
136.	Sewer Trunk Main M.H. Construction Notes Sheet 1 of 2	23-0202-1721	
137.	Sewer Trunk Main M.H. Construction Notes Sheet 2 of 2	23-0202-1722	
138.	Flagstone City Area 3 South – Pipe Sizes, prepared by Digital Water Solutions	J0000347 Map No: SEW-DIA	6/02/2025 amended in red 6/05/2025
139.	Flagstone Development – water mains diameter (mm)	J0000347 Map No: Diameter	19/02/2025
140.	Concept Bulk Earthworks Overall Layout	DA-0100, Rev C	13 February 2025
141.	Concept Bulk Earthworks Layout Plan Sheet 1 of 31	DA-0101, Rev D	26 March 2025
142.	Concept Bulk Earthworks Layout Plan Sheet 2 of 31	DA-0102, Rev C	13 February 2025
143.	Concept Bulk Earthworks Layout Plan Sheet 3 of 31	DA-0103, Rev C	13 February 2025
144.	Concept Bulk Earthworks Layout Plan Sheet 4 of 31	DA-0104, Rev C	13 February 2025
145.	Concept Bulk Earthworks Layout Plan Sheet 5 of 31	DA-0105, Rev C	13 February 2025
146.	Concept Bulk Earthworks Layout Plan Sheet 6 of 31	DA-0106, Rev C	13 February 2025
147.	Concept Bulk Earthworks Layout Plan Sheet 7 of 31	DA-0107, Rev C	13 February 2025
148.	Concept Bulk Earthworks Layout Plan Sheet 8 of 31	DA-0108, Rev C	13 February 2025
149.	Concept Bulk Earthworks Layout Plan Sheet 9 of 31	DA-0109, Rev C	13 February 2025
150.	Concept Bulk Earthworks Layout Plan Sheet 10 of 31	DA-0110, Rev C	13 February 2025
151.	Concept Bulk Earthworks Layout Plan Sheet 11 of 31	DA-0111, Rev C	13 February 2025
152.	Concept Bulk Earthworks Layout Plan Sheet 12 of 31	DA-0112, Rev C	13 February 2025
153.	Concept Bulk Earthworks Layout Plan Sheet 13 of 31	DA-0113, Rev C	13 February 2025
154.	Concept Bulk Earthworks Layout Plan Sheet 14 of 31	DA-0114, Rev C	13 February 2025
155.	Concept Bulk Earthworks Layout Plan Sheet 15 of 31	DA-0115, Rev C	13 February 2025
156.	Concept Bulk Earthworks Layout Plan Sheet 16 of 31	DA-0116, Rev C	13 February 2025
157.	Concept Bulk Earthworks Layout Plan Sheet 17 of 31	DA-0117, Rev C	13 February 2025
158.	Concept Bulk Earthworks Layout Plan Sheet 18 of 31	DA-0118, Rev C	13 February 2025
159.	Concept Bulk Earthworks Layout Plan Sheet 19 of 31	DA-0119, Rev C	13 February 2025
160.	Concept Bulk Earthworks Layout Plan Sheet 20 of 31	DA-0120, Rev C	13 February 2025
161.	Concept Bulk Earthworks Layout Plan Sheet 21 of 31	DA-0121, Rev C	13 February 2025

162.	Concept Bulk Earthworks Layout Plan Sheet 22 of 31	DA-0122, Rev C	13 February 2025
163.	Concept Bulk Earthworks Layout Plan Sheet 23 of 31	DA-0123, Rev C	13 February 2025
164.	Concept Bulk Earthworks Layout Plan Sheet 24 of 31	DA-0124, Rev C	13 February 2025
165.	Concept Bulk Earthworks Layout Plan Sheet 25 of 31	DA-0125, Rev C	13 February 2025
166.	Concept Bulk Earthworks Layout Plan Sheet 26 of 31	DA-0126, Rev C	13 February 2025
167.	Concept Bulk Earthworks Layout Plan Sheet 27 of 31	DA-0127, Rev C	13 February 2025
168.	Concept Bulk Earthworks Layout Plan Sheet 28 of 31	DA-0128, Rev C	13 February 2025
169.	Concept Bulk Earthworks Layout Plan Sheet 29 of 31	DA-0129, Rev C	13 February 2025
170.	Concept Bulk Earthworks Layout Plan Sheet 30 of 31	DA-0130, Rev C	13 February 2025
171.	Concept Bulk Earthworks Layout Plan Sheet 31 of 31	DA-0131, Rev C	13 February 2025
172.	Concept Bulk Sections Sheet 1 of 3	DA-0150, Rev C	13 February 2025
173.	Concept Bulk Sections Sheet 2 of 3	DA-0151, Rev C	13 February 2025
174.	Concept Bulk Sections Sheet 3 of 3	DA-0152, Rev C	13 February 2025
175.	Concept Roadworks and Drainage Layout Plan Sheet 1 of 31	DA-0200, Rev C	13 February 2025
176.	Concept Roadworks and Drainage Layout Plan Sheet 2 of 31	DA-0201, Rev C	13 February 2025
177.	Concept Roadworks and Drainage Layout Plan Sheet 3 of 31	DA-0202, Rev C	13 February 2025
178.	Concept Roadworks and Drainage Layout Plan Sheet 4 of 31	DA-0203, Rev C	13 February 2025
179.	Concept Roadworks and Drainage Layout Plan Sheet 5 of 31	DA-0204, Rev C	13 February 2025
180.	Concept Roadworks and Drainage Layout Plan Sheet 6 of 31	DA-0205, Rev C	13 February 2025
181.	Concept Roadworks and Drainage Layout Plan Sheet 7 of 31	DA-0206, Rev C	13 February 2025
182.	Concept Roadworks and Drainage Layout Plan Sheet 8 of 31	DA-0207, Rev C	13 February 2025
183.	Concept Roadworks and Drainage Layout Plan Sheet 9 of 31	DA-0208, Rev C	13 February 2025
184.	Concept Roadworks and Drainage Layout Plan Sheet 10 of 31	DA-0209, Rev C	13 February 2025
185.	Concept Roadworks and Drainage Layout Plan Sheet 11 of 31	DA-0210, Rev C	13 February 2025
186.	Concept Roadworks and Drainage Layout Plan Sheet 12 of 31	DA-0211, Rev C	13 February 2025
187.	Concept Roadworks and Drainage Layout Plan Sheet 13 of 31	DA-0212, Rev C	13 February 2025
188.	Concept Roadworks and Drainage Layout Plan Sheet 14 of 31	DA-0213, Rev C	13 February 2025
		•	

189.	Concept Roadworks and Drainage Layout Plan Sheet 15 of 31	DA-0214, Rev C	13 February 2025
190.	Concept Roadworks and Drainage Layout Plan Sheet 16 of 31	DA-0215, Rev C	13 February 2025
191.	Concept Roadworks and Drainage Layout Plan Sheet 17 of 31	DA-0216, Rev C	13 February 2025
192.	Concept Roadworks and Drainage Layout Plan Sheet 18 of 31	DA-0217, Rev C	13 February 2025
193.	Concept Roadworks and Drainage Layout Plan Sheet 19 of 31	DA-0218, Rev C	13 February 2025
194.	Concept Roadworks and Drainage Layout Plan Sheet 20 of 31	DA-0219, Rev C	13 February 2025
195.	Concept Roadworks and Drainage Layout Plan Sheet 21 of 31	DA-0220, Rev C	13 February 2025
196.	Concept Roadworks and Drainage Layout Plan Sheet 22 of 31	DA-0221, Rev C	13 February 2025
197.	Concept Roadworks and Drainage Layout Plan Sheet 23 of 31	DA-0222, Rev C	13 February 2025
198.	Concept Roadworks and Drainage Layout Plan Sheet 24 of 31	DA-0223, Rev C	13 February 2025
199.	Concept Roadworks and Drainage Layout Plan Sheet 25 of 31	DA-0224, Rev C	13 February 2025
200.	Concept Roadworks and Drainage Layout Plan Sheet 26 of 31	DA-0225, Rev C	13 February 2025
201.	Concept Roadworks and Drainage Layout Plan Sheet 27 of 31	DA-0226, Rev C	13 February 2025
202.	Concept Roadworks and Drainage Layout Plan Sheet 28 of 31	DA-0227, Rev C	13 February 2025
203.	Concept Roadworks and Drainage Layout Plan Sheet 29 of 31	DA-0228, Rev C	13 February 2025
204.	Concept Roadworks and Drainage Layout Plan Sheet 30 of 31	DA-0229, Rev C	13 February 2025
205.	Concept Roadworks and Drainage Layout Plan Sheet 31 of 31	DA-0230, Rev C	13 February 2025
206.	Concept Road Types Layout	DA-0250, Rev C	13 February 2025
207.	Concept Road Typical Cross Sections	DA-0251, Rev C	13 February 2025
208.	Concept Major Roads Layout Plan	DA-0300, Rev C	13 February 2025
209.	Concept Road 1 Longitudinal Section Sheet 1 of 3	DA-0301, Rev C	13 February 2025
210.	Concept Road 1 Longitudinal Section Sheet 2 of 3	DA-0302, Rev C	13 February 2025
211.	Concept Road 1 Longitudinal Section Sheet 3 of 3	DA-0303, Rev C	13 February 2025
212.	Concept Road 2 Longitudinal Section	DA-0304, Rev C	13 February 2025
213.	Concept Road 3 Longitudinal Section	DA-0305, Rev C	13 February 2025

214.	Concept Bio Retention Overall Layout Plan	DA-0400, Rev C	13 February 2025
215.	Concept Sewerage and Water Reticulation Overall Layout	DA-0500, Rev C	13 February 2025
216.	Concept Sewerage and Water Reticulation Layout Plan Sheet 1 of 32	DA-0501, Rev C	13 February 2025
217.	Concept Sewerage and Water Reticulation Layout Plan Sheet 2 of 32	DA-0502, Rev C	13 February 2025
218.	Concept Sewerage and Water Reticulation Layout Plan Sheet 3 of 32	DA-0503, Rev C	13 February 2025
219.	Concept Sewerage and Water Reticulation Layout Plan Sheet 4 of 32	DA-0504, Rev C	13 February 2025
220.	Concept Sewerage and Water Reticulation Layout Plan Sheet 5 of 32	DA-0505, Rev C	13 February 2025
221.	Concept Sewerage and Water Reticulation Layout Plan Sheet 6 of 32	DA-0506, Rev C	13 February 2025
222.	Concept Sewerage and Water Reticulation Layout Plan Sheet 7 of 32	DA-0507, Rev C	13 February 2025
223.	Concept Sewerage and Water Reticulation Layout Plan Sheet 8 of 32	DA-0508, Rev C	13 February 2025
224.	Concept Sewerage and Water Reticulation Layout Plan Sheet 9 of 32	DA-0509, Rev C	13 February 2025
225.	Concept Sewerage and Water Reticulation Layout Plan Sheet 10 of 32	DA-0510, Rev C	13 February 2025
226.	Concept Sewerage and Water Reticulation Layout Plan Sheet 11 of 32	DA-0511, Rev C	13 February 2025
227.	Concept Sewerage and Water Reticulation Layout Plan Sheet 12 of 32	DA-0512, Rev C	13 February 2025
228.	Concept Sewerage and Water Reticulation Layout Plan Sheet 13 of 32	DA-0513, Rev C	13 February 2025
229.	Concept Sewerage and Water Reticulation Layout Plan Sheet 14 of 32	DA-0514, Rev C	13 February 2025
230.	Concept Sewerage and Water Reticulation Layout Plan Sheet 15 of 32	DA-0515, Rev C	13 February 2025
231.	Concept Sewerage and Water Reticulation Layout Plan Sheet 16 of 32	DA-0516, Rev C	13 February 2025
232.	Concept Sewerage and Water Reticulation Layout Plan Sheet 17 of 32	DA-0517, Rev C	13 February 2025
233.	Concept Sewerage and Water Reticulation Layout Plan Sheet 18 of 32	DA-0518, Rev C	13 February 2025
234.	Concept Sewerage and Water Reticulation Layout Plan Sheet 19 of 32	DA-0519, Rev C	13 February 2025
235.	Concept Sewerage and Water Reticulation Layout Plan Sheet 20 of 32	DA-0520, Rev C	13 February 2025
		•	•

236.	Concept Sewerage and Water Reticulation Layout Plan Sheet 21 of 32	DA-0521, Rev C	13 February 2025
237.	Concept Sewerage and Water Reticulation Layout Plan Sheet 22 of 32	DA-0522, Rev C	13 February 2025
238.	Concept Sewerage and Water Reticulation Layout Plan Sheet 23 of 32	DA-0523, Rev C	13 February 2025
239.	Concept Sewerage and Water Reticulation Layout Plan Sheet 24 of 32	DA-0524, Rev C	13 February 2025
240.	Concept Sewerage and Water Reticulation Layout Plan Sheet 25 of 32	DA-0525, Rev C	13 February 2025
241.	Concept Sewerage and Water Reticulation Layout Plan Sheet 26 of 32	DA-0526, Rev C	13 February 2025
242.	Concept Sewerage and Water Reticulation Layout Plan Sheet 27 of 32	DA-0527, Rev C	13 February 2025
243.	Concept Sewerage and Water Reticulation Layout Plan Sheet 28 of 32	DA-0528, Rev C	13 February 2025
244.	Concept Sewerage and Water Reticulation Layout Plan Sheet 29 of 32	DA-0529, Rev C	13 February 2025
245.	Concept Sewerage and Water Reticulation Layout Plan Sheet 30 of 32	DA-0530, Rev C	13 February 2025
246.	Concept Sewerage and Water Reticulation Layout Plan Sheet 31 of 32	DA-0531, Rev C	13 February 2025
247.	Concept Sewerage and Water Reticulation Layout Plan Sheet 32 of 32	DA-0532, Rev C	13 February 2025
Supp	porting plans and documents		
248.	Flagstone City Masterplan Flood Management Strategy	QC4012_002-REP- 001-4 Rev 4	26 August 2024
249.	New Beith Road – Flagstone, Road Functional Package Homestead Drive, Flagstone, prepared by Colliers	Project No: 22-0145 P100-P133 Rev A P140-P159 Rev A P170-P185 Rev A P190-P222 Rev A P300-P313 Rev A	12/09/2024
250.	New Beith Road – Flagstone, Road Functional Package Homestead Drive, Flagstone, prepared by Colliers	Project No: 19-0158 100 Rev 3 101-107 Rev 4 110-115 Rev 3	6/10/2022

Preamble, abbreviations, and definitions

ABBREVIATIONS AND DEFINITIONS

The following is a list of abbreviations utilised in this approval:

AILA means a Landscape Architect registered by the Australian Institute of Landscape Architects.

CERTIFICATION PROCEDURES MANUAL means the document titled *Certification Procedures Manual*, prepared by EDQ, dated April 2020 (as amended from time to time).

CONTRIBUTED ASSET means an asset constructed under a PDA development approval or Infrastructure Agreement that will become the responsibility of an External Authority. For the purposes of operational works for a Contributed Asset, the following definitions apply:

- a) External Authority means a public-sector entity other than the MEDQ;
- b) **Parkland** means carrying out operational work related to the provision of parkland infrastructure;
- c) **Roadworks** means carrying out any operational work within existing or proposed road(s), to a depth of 1.5m measured from the top of kerb, and includes Streetscape Works;
- d) **Sewer Works** means carrying out any operational work related to the provision of wastewater infrastructure;
- e) **Streetscape Works** means carrying out any operational work within the verge of a road, including footpath surface treatments, street furniture, street lighting and landscaping;
- f) **Stormwater Works** means carrying out any operational work related to the provision of stormwater infrastructure: and
- g) **Water Works** means carrying out any operational work related to the provision of water infrastructure.

COUNCIL means the relevant local government for the land the subject of this approval.

EDQ means Economic Development Queensland.

EDQ DA means Economic Development Queensland's – Development Assessment team.

EDQ IS means Economic Development Queensland's – Infrastructure Solutions team.

EP Act means the Environmental Protection Act 1994.

ICID means the {"Yarrabilba PDA" OR "Greater Flagstone PDA"} Implementation Charge Infrastructure Deed {developer name confirmed by EDQ infrastructure} in effect on 24 May 2019 (as amended from time to time).

IFF means the Infrastructure Funding Framework, prepared by the Department of State Development, Tourism and Innovation, dated 1 July 2020 (as amended from time to time).

LTA means Land Title Act 1994.

MEDQ means the Minister for Economic Development Queensland.

PDA means Priority Development Area.

RPEQ means Registered Professional Engineer of Queensland.

SRIA means the Yarrabilba PDA & Greater Flagstone PDA Sub-regional Infrastructure Agreement in effect on 24 May 2019 (as amended from time to time).

Compliance assessment

Where a condition of this approval requires Compliance Assessment, Compliance Assessment is required in accordance with the following:

- a) The applicant must:
 - i) pay to MEDQ at the time of submission the relevant fee for Compliance Assessment, including any third party peer review costs which will be charged on a 100% cost recovery basis. The Compliance Assessment fees are set out in EDQ Development Assessment Fees and Charges Schedule¹ (as amended from time to time).
 - ii) submit to EDQ DA a duly completed Compliance Assessment form².
 - iii) submit to EDQ DA the documentation as required under the relevant condition.
- b) Where EDQ is satisfied the documentation submitted for Compliance Assessment meets the requirements of the relevant condition (or element of the condition), EDQ will endorse the documentation and advise by written notice.
- c) Compliance Assessment and endorsement can be repeated where a different design or solution, to that already endorsed, is sought.
- d) The process and timeframes that apply to Compliance Assessment are as follows:
 - i) applicant submits items required under a) above to EDQ DA for Compliance Assessment.
 - ii) within 20 business days EDQ assesses the documentation and:
 - 1. if satisfied, endorses the documentation; or
 - 2. if not satisfied, notifies the applicant accordingly.
 - iii) if the applicant is notified under ii.2. above, revised documentation must be submitted **within 20 business days** from the date of notification.
 - iv) within 20 business days EDQ assesses the revised documentation and:
 - 1. if satisfied, endorses the revised documentation; or
 - 2. if not satisfied, notifies the applicant accordingly.
 - v) where EDQ notifies the applicant as stated under iv.2. above, repeat steps iii. and iv. above. If either party is not satisfied by the outcome of this process, that party can elect to enter into a mediation process with an independent mediator agreed to by both parties.

Despite note v. above, the condition (or element of the condition) is determined to have been met only when EDQ endorses relevant documentation.

¹ The EDQ Development Assessment Fees and Charges Schedule is available at EDQ's website.

² The Compliance Assessment form is available at EDQ's website. It sets out how to submit documentation for Compliance Assessment and how to pay Compliance Assessment fees.

Submitting documentation to EDQ

Where a condition of this approval requires documentation to be submitted to either EDQ DA or EDQ IS, use the following email addresses:

- a) EDQ DA: pdadevelopmentassessment@edq.qld.gov.au
- b) EDQ IS: <u>PrePostConstruction@edq.qld.gov.au</u>

PDA	PDA Development Conditions – Reconfiguring a Lot						
No	Condition	Timing					
Gen	General						
1.	Carry out the approved development						
	Carry out the approved development generally in accordance with: a) the approved plans and documents; and b) any other documentation endorsed via Compliance Assessment as required by these conditions.	Prior to survey plan endorsement for the relevant sub-stage					
2.	Street naming						
	Submit to EDQ DA a schedule of street names approved by Council.	Prior to survey plan endorsement for the relevant sub-stage					
3.	Entry walls or features						
	The provision of entry walls or features is prohibited on road and open spaces unless otherwise approved by EDQ Development Assessment.	As indicated					
Con	struction						
4.	Hours of Work - Construction						
	Unless otherwise endorsed, via Compliance Assessment for out of hours work, construction hours for the approved development are limited to Monday to Saturday between 6:30am to 6:30pm, excluding public holidays.	During construction unless otherwise endorsed					
5.	Out of Hours Work - Compliance Assessment						
	Where out of hours work is proposed, submit to EDQ DA, for Compliance Assessment, an out of hours work request. The out of hours work request must include a duly completed out of hours work request form ³ .	Minimum of 10 business days prior to proposed out of hours work commencement date					
6.	Certification of Operational Work						
	Carry out all Operational Work under this approval in accordance with the Certification Procedures Manual.	At all times					
7.	Certification of Operational Work for Contributed Assets						
	Carry out all Operational Work, for Contributed Assets, under this approval in accordance with the <i>Certification Procedures Manual</i> .	At all times					
8.	Construction Management Plan						
	a) Submit to EDQ IS, a site-based Construction Management Plan (CMP), prepared by the principal site contractor and reviewed by a suitably qualified and experienced person responsible for overseeing the site works, to manage construction impacts, including:	a) Prior to commencing work for the relevant substage					

³ The out of hours work request form is available at EDQ's website.

16

PDA	PDA Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
		Timing			
	 A copy of the CMP submitted under part a) of this condition must be current and available on site. 	b) During construction			
	 c) Carry out all construction work generally in accordance with the CMP submitted under part a) of this condition. 	c) During construction			
9.	Erosion and Sediment Management				
	 a) Submit to EDQ IS, an Erosion and Sediment Control Plan (ESCP), certified by a suitably qualified RPEQ or an accredited professional in erosion and sediment control, and prepared generally in accordance with the following: i) construction phase stormwater management design objectives of the State Planning Policy 2017 (Appendix 2 Table A); ii) Healthy Land and Water Technical Note: Complying with the SPP – Sediment Management on Construction Sites. 	a) Prior to commencing work for the relevant sub- stage			
	b) Implement the certified ESCP submitted under part a) of this condition.	b) During construction			
	Note : Temporary erosion and sediment control measures are not to result in removal of additional vegetation beyond approved development footprint				
10.	Traffic Management Plan				
	 a) Submit to EDQ IS, a Traffic Management Plan (TMP), certified by a person holding a current Traffic Management Design qualification. The TMP must include the following: 	a) Prior to commencing work for the relevant sub-stage			

PDA	PDA Development Conditions – Reconfiguring a Lot					
No	Condition	Timing				
	 i) provision for the safe and functional management of traffic around and through the site during and outside of construction work hours; 					
	 ii) provision for the safe and functional management of pedestrian traffic, including alternative pedestrian routes past, through or around the site; 					
	iii) provision of parking for workers and materials delivery;iv) risk identification, assessment and identification of mitigation measures;					
	 v) ongoing monitoring, management review and certified updates (as required); and vi) traffic control plans and/or traffic control diagrams, prepared in 					
	accordance with Austroads Guide to Temporary Traffic Management, for any temporary part or full road closures.					
	 b) Carry out all construction work generally in accordance with the certified TMP submitted under part a) of this condition, which is to be current and available on site. 	b) During construction				
	NOTE : Operational traffic changes, such as temporary and permanent lane modifications, relaxation of clearway zone hours or footpath closures may require authorisation from Council or DTMR as road manager. It is recommended that applicants engage directly with the applicable road manager.					
11.	Public Infrastructure (Damage, Repairs and Relocation)					
	Repair any damage to existing public infrastructure caused by works carried out in association with the approved development.	a) Prior to survey plan endorsement for the relevant sub-stage				
	b) Where existing public infrastructure require repair or relocation, due to the approved development and/or works associated with the approved development, repair and/or relocate the public infrastructure at no cost to others and in accordance with statutory requirements and adopted design standards.	b) Prior to survey plan endorsement for the relevant sub-stage				
	NOTE : It is recommended applicants record their own dated photographic evidence of the condition of relevant existing public infrastructure both before and after works carried out in association with the approved development.					
12.	Fencing					
	Fences to be constructed by the developer along the common boundaries to all rear draining residential lots and those with multiple neighbours in Stage 13.	Prior to survey plan endorsement for the relevant sub-stage				
	Fencing is not to prejudice outcomes related to condition 32 (Stormwater – quantity)					
	nworks and Retaining Walls					
13.	Earthworks					
	 a) Submit to EDQ IS detailed earthworks plans, certified by a RPEQ, and designed generally in accordance with: i) Australian Standard AS3798 – 2007 Guidelines on Earthworks for Commercial and Residential Developments and ii) the approved plans. 	a) Prior to commencing earthworks for the relevant sub-stage				
	The certified earthworks plans are to:					
	The solution out the plane are to.					

PDA	A Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
	 i) include a geotechnical soils assessment of the site; ii) accord with the Erosion and Sediment Control Plans, as required by condition 9 – Erosion and sediment management; iii) include the location and finished surface levels of any cut and/or fill; iv) detail areas where dispersive soils will be disturbed, treatment of dispersive soils and their rehabilitation; v) provide details of any areas where surplus soils are to be stockpiled; vi) detail protection measures to: 1. ensure adjoining properties and roads are not impacted by ponding or nuisance stormwater resulting from earthworks associated with the approved development; 2. preserve all drainage structures from structural loading impacts resulting from earthworks associated with the approved development. 				
	 b) Carry out earthworks generally in accordance with the certified plans submitted under part a) of this condition. 	b) Prior to survey plan endorsement for the relevant sub-stage			
	 c) Submit to EDQ IS RPEQ certification that: all earthworks have been carried out generally in accordance with the certified plans submitted under part a) of this condition; and any unsuitable material encountered has been treated or replaced with suitable material. 	c) Prior to survey plan endorsement for the relevant sub-stage			
14.	Compliance assessment - Earthworks				
	a) Submit to EDQ IS for compliance assessment, detailed earthworks plans for the proposed batter between CH420-540 of Road 4 located on Concept Bulk Earthworks plan DA-0120 Rev C (Sheet 20 of 31). This batter is to be modified to be a single tier retaining wall/batter hybrid to minimise impact on existing vegetation.	a) Prior to commencing earthworks for the relevant sub-stage			
	b) Submit to EDQ IS for compliance assessment, detailed earthworks plans for the area in proximity to Waterway C to the west and northwest of Road 1 located on Concept Bulk Earthworks plans DA-0101 Rev C (Sheet 1) and DA-0105 Rev C (Sheet 5). The earthworks plans are to display the extent of environmental constraints of the mapped waterway.	b) Prior to any vegetation clearing in Stage 14 and adjacent green space areas.			
	 The plans are to be certified by a suitably qualified RPEQ, and designed generally in accordance with: i) Australian Standard AS3798 – 2007 Guidelines on Earthworks for Commercial and Residential Developments and ii) the approved earthworks/functional layout plans. 				
	 The certified earthworks plans are to: i) include a geotechnical soils assessment of the site; ii) accord with the Erosion and Sediment Control Plans, as required by condition 9 – Erosion and sediment management; iii) include the location and finished surface levels of any cut and/or fill; iv) detail areas where dispersive soils will be disturbed, treatment of dispersive soils and their rehabilitation; v) provide details of any areas where surplus soils are to be stockpiled; vi) detail protection measures to: 				

PDA	PDA Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
	 ensure adjoining properties and roads are not impacted by ponding or nuisance stormwater resulting from earthworks associated with the approved development; preserve all drainage structures from structural loading impacts resulting from earthworks associated with the approved development. 				
	 c) Carry out earthworks generally in accordance with the certified plans submitted under part a) of this condition. 	c) Prior to survey plan endorsement for the relevant sub-stage			
	 d) Submit to EDQ IS RPEQ certification that: i) all earthworks have been carried out generally in accordance with the certified plans submitted under part a) of this condition; and ii) any unsuitable material encountered has been treated or replaced with suitable material. 	d) Prior to survey plan endorsement for the relevant sub-stage			
15.	Compliance assessment - Retaining Walls				
	 a) Submit to EDQ IS for compliance assessment, detailed earthworks plans for the proposed batter between CH420-540 of Road 4 located on Concept Bulk Earthworks plan DA-0120 Rev C (Sheet 20 of 31). This batter is to be modified to be a single tier retaining wall/batter hybrid to minimise impact on existing vegetation. The plans are to be certified by a suitably qualified RPEQ, for all retaining walls 1m or greater in height. Retaining walls must be: i) certified to achieve a minimum 50-year design life; ii) designed generally in accordance with AS4678 – Earth Retaining Structures and relevant material standards (e.g. AS3600 – Concrete Structures); iii) located and designed generally in accordance with the approved earthworks/functional layout plans. 	a) Prior to commencing earthworks for the relevant sub-stage			
	 b) Construct retaining walls generally in accordance with the certified plans required under part a) of this condition. 	b) Prior to survey plan endorsement for the relevant sub-stage			
	c) Submit to EDQ IS certification from an RPEQ that all retaining wall works 1.0m or greater in height have been constructed generally in accordance with the certified plans submitted under part a) of this condition.	c) Prior to survey plan endorsement for the relevant sub-stage			
16.	Retaining Walls				
	 a) Submit to EDQ IS detailed engineering plans, certified by a RPEQ, of all retaining walls 1m or greater in height. Retaining walls must be: i) certified to achieve a minimum 50 year design life; ii) designed generally in accordance with AS4678 – Earth Retaining Structures and relevant material standards (e.g. AS3600 – Concrete Structures); iii) located and designed generally in accordance with the approved plans. 	a) Prior to commencing earthworks for the relevant sub-stage			
	 b) Construct retaining walls generally in accordance with the certified plans required under part a) of this condition. 	b) Prior to survey plan endorsement for the relevant sub-stage			

PDA	PDA Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
	c) Submit to EDQ IS certification from an RPEQ that all retaining wall works 1.0m or greater in height have been constructed generally in accordance with the certified plans submitted under part a) of this condition.	c) Prior to survey plan endorsement for the relevant sub-stage			
	works, urban servicing and stormwater management				
17.	Roadworks - Internal				
	a) Submit to EDQ IS, detailed engineering plans, certified by a suitably qualified RPEQ, for all roadworks, including parking bays, indented bus bays, traffic devices and footpaths. The certified engineering plans must be designed generally in accordance with PDA Guideline No. 13 Engineering standards, and the approved Functional Layout Plans.	a) Prior to commencing roadworks			
	 b) Construct roadworks generally in accordance with the certified plans submitted under part a) of this condition. 	b) Prior to survey plan endorsement for the relevant sub-stage			
	 c) Submit to EDQ IS: i) certification from a suitably qualified and experienced RPEQ that all roadworks have been constructed generally in accordance with the certified plans submitted under part b) of this condition; and ii) all documentation as required by the <i>Certification Procedures Manual</i>. iii) as-constructed drawings, asset register and test results, certified by a suitably qualified RPEQ, in a format acceptable to the end asset owners for all roadworks constructed under this condition. 	c) Prior to survey plan endorsement for the relevant sub-stage			
18.	Compliance Assessment – Secondary Access – New Beith Road – Internal to the PDA (north of and including Flagstonian Dr intersection)				
	a) Submit to EDQ IS for compliance assessment, detailed design plans interim road layout plans certified by a suitably qualified RPEQ for the upgrade of New Beith Road between the development boundary and the northern PDA boundary.	a) Prior to commencement of works			
	The interim 2 lane road layout on the ultimate alignment shall generally include the following: i) Two (2) lane (interim) upgrade of New Beith Road ((R004A, R008A and R007A on Map 3: Transport (roads) – DCOP Map June 2022), from the northern boundary of the PDA to (and including) the New Beith Road/Flagstonian Drive intersection (at the location for R1005A shown on Map 4: Transport (intersections) – DCOP Map June 2022), including earthworks, and bridge RB001A on New Beith Road (as shown on Map 5: Transport (structures) – DCOP Map June 2022); ii) culverts RC001A and RC011A on New Beith Road (as shown on Map 5: Transport (structures) – DCOP Map June 2022), for the interim (two (2) lane) design for the New Beith Road upgrade in paragraph (i) above; iii) New Beith Road/Flagstonian Drive priority controlled intersection (RI005A on Map 4: Transport (intersections) – DCOP Map June 2022),				
	Including all infrastructure that is: i) ancillary to, and services related to, the infrastructure identified in paragraphs (i)-(iii) above, to the extent reasonably required for the provision of that infrastructure; and				

PDA	Development Conditions – Reconfiguring a Lot	
No	Condition	Timing
	ii) required by an Approval to be delivered as part of, or to interrelate with, the infrastructure identified in paragraphs (i)-(iii) above.	
	b) Submit to EDQ IS for compliance assessment, detailed design plans for the ultimate functional road layout, including intersections and culverts, certified by a suitably qualified RPEQ for the upgrade of New Beith Road.	b) Prior to commencement of works
	The interim 2 lane road layout on the ultimate alignment shall generally include the following: . 32m road reserve width . 4 x 3.5m wide traffic lanes . 5m median	
	2 x 6.35m verge (including 2.4m cycleway & 1.5m footpath)	
	c) Construct the works generally in accordance with the RPEQ certified plans required under parts a) and b) of this condition.	c) Prior to 30 November 2026
	d) Submit to EDQ IS 'as constructed' drawings, asset register and test results, certified by a suitably qualified RPEQ, in a format acceptable to the Council of all road works constructed in accordance with this condition.	d) Prior to 30 November 2026
19.	Dedication of new road reserve – New Beith Rd - South of Flagstonian Dr intersection to Lot 1 on SP351245 (formerly Lot 3 on RP45236)	
	Dedicate stages 11L-1 and 11L-2 as road reserve.	Prior to endorsement of the 200 th lot of this approval
20.	Compliance Assessment – Secondary Access – New Beith Road – Internal to the PDA (South of Flagstonian Dr intersection to Gateway Drive Intersection) and intersections	
	a) Submit to EDQ IS for compliance assessment, detailed design plans interim road layout plans certified by a suitably qualified RPEQ for the upgrade of New Beith Road south of Flagstonian Drive intersection to Lot 3 on RP45236.	a) Prior to endorsement of the 150 th lot of this approval
	The interim 2 lane road layout on the ultimate alignment shall generally include the following: i) Two (2) lane (interim) upgrade of New Beith Road (R022A and R013A on Map 3: Transport (roads) – DCOP Map June 2022), from the south of Flagstonian Dr intersection to and including the intersection at the location for Rl007A shown on Map 4: Transport	
	(intersections) – DCOP Map June 2022, including earthworks; ii) culverts RC010A on New Beith Road (as shown on Map 5: Transport (structures) – DCOP Map June 2022), for the interim (two (2) lane) design for the New Beith Road upgrade in paragraph (i) above;	
	iii) New Beith Road priority controlled intersection (RI007A on Map 4: Transport (intersections) – DCOP Map June 2022)	
	Including all infrastructure that is: i) ancillary to, and services related to, the infrastructure identified in paragraphs (i)-(iii) above, to the extent reasonably required for the provision of that infrastructure; and	
	 required by an Approval to be delivered as part of, or to interrelate with, the infrastructure identified in paragraphs (i)-(iii) above. 	

PDA	PDA Development Conditions – Reconfiguring a Lot				
No	Со	ndition	Timing		
	b)	Submit to EDQ IS for compliance assessment detailed design plans for the ultimate functional road layout including intersections and culverts, certified by a suitably qualified RPEQ for the upgrade of New Beith Road.	b) Prior to commencement of works		
		The interim 2 lane road layout on the ultimate alignment shall generally include the following: . 32m road reserve width . 4 x 3.5m wide traffic lanes . 5m median			
		2 x 6.35m verge (including 2.4m cycleway & 1.5m footpath)			
	c)	Construct the works generally in accordance with the RPEQ certified plans required under part a) of this condition.	c) Prior to commencement of use of Lot 50033 or Lot 30015 (whichever occurs first)		
	d)	Submit to EDQ IS 'as constructed' drawings, asset register and test results, certified by a suitably qualified RPEQ, in a format acceptable to the Council of all road works constructed in accordance with this condition.	d) Prior to commencement of use of Lot 50033 or Lot 30015 (whichever occurs first)		
21.	Inte	mpliance Assessment – Secondary Access – New Beith Road – ernal to the PDA (Gateway Drive Intersection to Lot 1 on SP351245 rmerly Lot 3 on RP45236))			
	a)	Submit to EDQ IS for compliance assessment, detailed design plans interim road layout plans certified by a suitably qualified RPEQ for the upgrade of New Beith Road south of Flagstonian Drive intersection to Lot 3 on RP45236/ Lot 1 on SP351245.	a) Prior to endorsement of the 150 th lot of this approval		
		The interim 2 lane road layout on the ultimate alignment shall generally include the two (2) lane (interim) upgrade of New Beith Road (R022A and R013A on Map 3: Transport (roads) – DCOP Map June 2022), from the south of Flagstonian Dr intersection to Lot 3 on RP45236/Lot 1 on SP351245, including earthworks.			
		 Including all infrastructure that is: i) ancillary to, and services related to, the infrastructure identified in paragraph (i) above, to the extent reasonably required for the provision of that infrastructure; and ii) required by an Approval to be delivered as part of, or to interrelate with, the infrastructure identified in paragraph (i) above. 			
	b)	Submit to EDQ IS for compliance assessment detailed design plans for the ultimate functional road layout including intersections and culverts, certified by a suitably qualified RPEQ for the upgrade of New Beith Road.	b) Prior to commencement of works		
		The interim 2 lane road layout on the ultimate alignment shall generally include the following: 32m road reserve width 4 x 3.5m wide traffic lanes 5m median 2 x 6.35m verge (including 2.4m cycleway & 1.5m footpath)			

PDA	PDA Development Conditions – Reconfiguring a Lot					
No	Condition	Timing				
	c) Construct the works generally in accordance with the RPEQ certified plans required under part a) of this condition.	c) Prior to the survey plan endorsement of the 1500 th lot of this approval				
	d) Submit to EDQ IS 'as constructed' drawings, asset register and test results, certified by a suitably qualified RPEQ, in a format acceptable to the Council of all road works constructed in accordance with this condition.	d) Prior to the survey plan endorsement of the 1500 th lot of this approval				
22.	Street Lighting					
	Comply with either parts a) or parts b) and c) of this condition.					
	 a) Design and install a Rate 2 street lighting system, certified by a suitably qualified RPEQ, to all roads, including footpaths/bikeways within road reserves. The design of the street lighting system must: i) meet the relevant standards of Energex; ii) be endorsed by Energex as 'Rate 2 Public Lighting'; iii) be endorsed by Council as the Energex 'billable customer'; iv) be generally in accordance with Australian Standards AS1158 – 'Lighting for Roads and Public Spaces. 	a) Prior to survey plan endorsement for the relevant sub-stage				
	 b) Design and install a Rate 3 street lighting system, certified by a suitably qualified and experienced RPEQ, to all roads, including footpaths/bikeways within road reserves. The design of the street lighting system must: i) be in accordance with Australian Standards AS1158 – 'Lighting for Roads and Public Spaces' ii) meet the requirements of AS3000 – 'SAA Wiring Rules'. iii) meet the requirements of Energex for unmetered supply iv) be endorsed by the relevant ownership authority. 	b) Prior to survey plan endorsement for the relevant sub-stage				
	c) Submit to EDQ IS 'as-constructed' plans and test documentation, certified by a suitably qualified RPEQ, in a format acceptable to Council.	c) Prior to on-maintenance for the relevant sub-stage				
23.	Compliance Assessment – Water Pump Station					
	a) Submit to EDQ IS for compliance assessment, detailed design plans and report certified by a RPEQ, for a proposed variable speed pump station, including back-up generator and standby pumping units to ensure continuity of supply, to service the development, generally in accordance with PDA Guideline No. 13 Engineering standards.	a) Prior to commencement of works of the first stage				
	 b) Construct the pump station generally in accordance with the endorsed plans required under part a) of this condition. 	b) Prior to survey plan endorsement for the first stage				
	 c) Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of the water pump station constructed in accordance with this condition, including an asset register, commissioning report and test results in accordance with: i) Council's current adopted standards; and ii) the SEQ Water Supply and Sewerage Design and Construction Code - Asset Information. 	c) Prior to survey plan endorsement for the first stage				
	Note: the water pump station will establish a temporary booster supply zone to service lots within the proposed demand management area DM2. Once the Round Mountain Reservoir HLZ 2 is constructed, the water pump station with the downstream DN300 will be converted to the dedicated feed to the HLZ reservoir.					

PDA	DA Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
24.	Compliance Assessment – Interim Pressure management zone for Stage 11		<u> </u>		
	Prior to the Round Mountain Reservoir and associated trunk main are constructed in accordance with condition 26 of this approval:				
	a) Submit to EDQ IS for compliance assessment, detailed design plans and report certified by a RPEQ, for the water supply infrastructure to service to Stage 11, generally in accordance with <i>PDA Guideline No. 13 Engineering standards.</i>	a)	Prior to commencement of works of the first sub- stage within Stage 11		
	The water infrastructure shall ensure that the maximum pressure to the properties within the low-lying areas of Stage 11, is generally in accordance with the adopted Council's DSS. At minimum, the report shall at minimum assessing the following options: i) servicing the low-lying areas of Stage 11 with a parallel water main connected upstream of the proposed booster pump station ii) installation of temporary pressure reducing valve to ensure the DSS maximum pressure requirement is met during the supply of the temporary booster supply arrangement.				
	b) Construct the water supply infrastructure generally in accordance with the endorsed plans required under part a) of this condition.	b)	Prior to commencement of works of the first sub- stage within Stage 11		
	 c) Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of the water pump station constructed in accordance with this condition, including an asset register, commissioning report and test results in accordance with: i) Council's current adopted standards; and ii) the SEQ Water Supply and Sewerage Design and Construction Code - Asset Information. 	c)	Prior to commencement of works of the first sub- stage within Stage 11		
25.	Compliance Assessment – DN300 trunk main				
	a) Submit to EDQ IS for compliance assessment, detailed design plans certified by a RPEQ, for the proposed DN300 trunk main from the trunk network within New Beith Road to the western boundary of the land subject to this approval, generally in accordance with PDA Guideline No. 13 Engineering standards.	a)	Prior to survey plan endorsement for the relevant sub-stage		
	 b) Construct the works generally in accordance with the endorsed plans required under part a) of this condition. 	b)	Prior to survey plan endorsement for the relevant sub-stage		
	 Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of the water pump station constructed in accordance with this condition, including an asset register, commissioning report and test results in accordance with: Council's current adopted standards; and the SEQ Water Supply and Sewerage Design and Construction Code - Asset Information. 	c)	Prior to survey plan endorsement for the relevant sub-stage		
	Note: the water pump station will establish a temporary booster supply zone to service lots within the proposed demand management area DM2 through the DN300 main. Once the Round Mountain Reservoir HLZ 2 is constructed, the water pump station with the downstream DN300 will be converted to the dedicated feed to the HLZ reservoir.				

PDA	DA Development Conditions – Reconfiguring a Lot					
No	Со	ndition	Timing			
26.		mpliance Assessment – Round Mountain High Level Reservoir and sociated trunk mains				
	a)	Submit to EDQ IS, for compliance assessment preliminary design plans and report for the proposed HLZ reservoir with a bottom water level of 145m AHD and associated trunk mains, generally in accordance with PDA Guideline No. 13 Engineering standards.	a)	Prior to survey plan endorsement of the 500 th lot of this approval		
		 The preliminary design report shall include: reservoir siting assessment study, including identification of suitable access arrangement preliminary plans for proposed dedicated feed main and outlet main to the development Preliminary plans for the two proposed PRVs, considering opportunity of colocation, for the proposed district metered areas DM1 and DM2. Changes required to the water pump station and downstream network to switch from the interim booster supplied zone to the 				
	b)	ultimate gravity fed zone. Submit to EDQ IS, for compliance assessment, detailed design plans, certified by a RPEQ, for the HLZ1 reservoir and associated trunk mains and change to the water pump station in accordance with the endorsed preliminary design plans required under part a) of this condition and PDA Guideline No. 13 Engineering standards – Sewer and Water.	b)	Prior to survey plan endorsement of the 1000 th lot of this approval		
	c)	Construct the works generally in accordance with the endorsed plans required under part b) of this condition.	c)	Prior to survey plan endorsement of the 1500 th lot of this approval		
	d)	Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of the reservoir and associated trunk mains and PRVs, constructed in accordance with this condition, including an asset register, commissioning report and test results in accordance with: i) Council's current adopted standards; and ii) the SEQ Water Supply and Sewerage Design and Construction Code - Asset Information.	d)	Prior to survey plan endorsement of the 1500 th lot of this approval		
27.	Co	mpliance Assessment - Relocation of trunk water main				
	a)	Submit to EDQ IS, for compliance assessment detailed design plans, certified by a RPEQ for the relocation of the existing DN375 trunk water main within Stage 10 and 11 to the New Beith Road reserve, generally in accordance with PDA Guideline No. 13 Engineering standards.	a)	Prior to commencement of works for Stage 10 and 11		
	b)	Construct water reticulation works generally in accordance with the endorsed plans submitted under part a) of this condition.	b)	Prior to survey plan endorsement of any lots within Stage 10 and 11		
	c)	Submit to EDQ IS 'as constructed' plans, certified by a RPEQ, of all water reticulation infrastructure constructed in accordance with this condition, including an asset register, pressure and bacterial test results in accordance with: i) Council's current adopted standards; and ii) the SEQ Water Supply and Sewerage Design and Construction Code - Asset Information.	c)	Prior to survey plan endorsement of any lots within Stage 10 and 11		

PDA	DA Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
	Note : the relocation of the existing DN375 trunk main is triggered by the proposed development layout and therefore the relocation will be a full developer's cost.				
28.	Water Reticulation				
	 a) Submit to EDQ IS detailed water reticulation design plans, certified by a RPEQ. The certified water reticulation design plans must be designed generally in accordance with: i) PDA Guideline No. 13 Engineering standards; and ii) the approved Water Mains diameter plan prepared by DWS and dated 4/2/25 	a)	Prior commencing water reticulation work for the relevant sub-stage		
	 b) Construct water reticulation works generally in accordance with the certified plans submitted under part a) of this condition. 	b)	Prior to survey plan endorsement for the relevant sub-stage		
	 c) Submit to EDQ IS 'as constructed' plans, certified by a RPEQ, of all water reticulation infrastructure constructed in accordance with this condition, including an asset register, pressure and bacterial test results in accordance with: i) Council's current adopted standards; and ii) The SEQ Water Supply and Sewerage Design and Construction Code - Asset Information. 	c)	Prior to survey plan endorsement for the relevant sub-stage		
29.	Compliance Assessment – Augmentation of existing DN225 sewer				
	a) Submit to EDQ DA, for compliance assessment detailed design plans certified by a RPEQ, for the augmentation of the existing DN225 trunk sewer from MH 3/6 to MH 3/1 to provide additional 588 EP capacity, generally in accordance with the DCOP and the <i>PDA Guideline No. 13 Engineering standards – Sewer and</i> Water.	a)	Prior to the plan sealing of the first lot within Stage 10		
	b) Construct the works generally in accordance with the endorsed plans required under part b) of this condition.	b)	Prior to the plan sealing of the first lot within Stage 10		
	 c) Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of all sewer reticulation infrastructure constructed in accordance with this condition, including an asset register, pressure and CCTV results in accordance with: i) Council's current adopted standards; and ii) the SEQ Water Supply and Sewerage Design and Construction Code - Asset Information. 	c)	Prior to the plan sealing of the first lot within Stage 10		
	Note: the augmentation of the existing DN225 sewer is required to provide additional capacity to service Stage 10. The augmentation may be addressed with the redirection of the reticulation sewer connected to MH 3/6.				
30.	Compliance Assessment – Sandy Creek Trunk Sewer				
	a) Submit to EDQ IS, for compliance assessment detailed design plans and report certified by a RPEQ, for the extension of the Sandy Creek Trunk Sewer from Stage 5 to the future connection to the reticulation network for Stage 11, generally in accordance with the DCOP and the PDA Guideline No. 13 Engineering standards – Sewer and Water. The detailed design plans and report shall include:	a)	Prior to commencement of works of Stage 8, 9 and 11		
	 Route selection to minimise impact to existing vegetation, while maintaining a cost-effective conveyance solution 				

PDA	Development Conditions – Reconfiguring a Lot		
No	Condition	Tir	ning
	Preliminary plans to upstream further extend to demonstrating adequate level to service upstream catchments.		
	b) Construct the works generally in accordance with the endorsed plans required under part a) of this condition.	b)	Prior to survey plan endorsement of any lots within Stage 8, 9 and 11
	 c) Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of all sewer reticulation infrastructure constructed in accordance with this condition, including an asset register, pressure and CCTV results in accordance with: i) Council's current adopted standards; and ii) the SEQ Water Supply and Sewerage Design and Construction 	c)	Prior to survey plan endorsement of any lots within Stage 8, 9 and 11
	Code - Asset Information.		
31.	Compliance Assessment – Flagstone Creek Trunk Sewer		
	a) Submit to EDQ IS, for compliance assessment detailed design plans and report certified by a RPEQ, for the extension of the Sandy Creek Trunk Sewer from MH 4/1, near the pump station FC4, to the future connection of the reticulation network for Stage 14, generally in accordance with the DCOP and the PDA Guideline No. 13 Engineering standards – Sewer and Water.	a)	Prior to commencement of works of Stage 12, 13 and 14
	 The detailed design plans and report shall include: i) Route selection to minimise impact to existing vegetation, while maintaining a cost-effective conveyance solution ii) Preliminary plans to upstream further extend to demonstrating adequate level to service upstream catchments. 		
	b) Construct the works generally in accordance with the endorsed plans required under part a) of this condition.	b)	Prior to survey plan endorsement of the relevant sub-stage
	 c) Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of all sewer reticulation infrastructure constructed in accordance with this condition, including an asset register, pressure and CCTV results in accordance with: i) Council's current adopted standards; and ii) the SEQ Water Supply and Sewerage Design and Construction Code - Asset Information. 	c)	Prior to survey plan endorsement of of the relevant sub-stage
32.	Sewer Reticulation for Stage 8, 9, 10 and 11		
	 a) Submit to EDQ IS detailed sewer reticulation design plans, certified by a RPEQ. The certified sewer reticulation design plans must be designed generally in accordance with: i) PDA Guideline No. 13 Engineering standards; and ii) The approved Sewerage Network Pipe Sizes plan 	a)	Prior the commencing sewer reticulation work relevant sub-stage
	 b) Construct sewer reticulation works generally in accordance with the certified plans submitted under part b) of this condition. 	b)	Prior to survey plan endorsement relevant sub-stage
	c) Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of all sewer reticulation infrastructure constructed in accordance with this condition, including an asset register, pressure and CCTV results in accordance with:	c)	Prior to survey plan endorsement relevant sub-stage

PDA	Development Conditions – Reconfiguring a Lot	
No	Condition	Timing
	 i) Council's current adopted standards; and ii) The SEQ Water Supply and Sewerage Design and Construction Code - Asset Information. 	
33.	Compliance Assessment - Sewer Reticulation for Stage 12, 13 and 14	
	 a) Submit to EDQ IS for compliance assessment, an updated sewerage network plan, certified by a RPEQ, for Stage 12, 13 and 14. The plan shall include i) Ultimate sewerage connections to the municipal network ii) Any proposed interim servicing solution, including maximum EP capacity and timing for decommission 	a) Prior to commencement of works for Stage 12, 13 and 14
	 b) Submit to EDQ IS detailed sewer reticulation design plans, certified by a RPEQ. The certified sewer reticulation design plans must be designed generally in accordance with: i) PDA Guideline No. 13 Engineering standards; and ii) the endorsed catchments plan required under part a) of this condition. 	b) Prior the commencing sewer reticulation work relevant sub-stage
	c) Construct sewer reticulation works generally in accordance with the certified plans submitted under part b) of this condition.	c) Prior to survey plan endorsement relevant sub-stage
	 d) Submit to EDQ IS 'as constructed' plans, certified by an RPEQ, of all sewer reticulation infrastructure constructed in accordance with this condition, including an asset register, pressure and CCTV results in accordance with: i) Council's current adopted standards; and ii) The SEQ Water Supply and Sewerage Design and Construction Code - Asset Information. 	d) Prior to survey plan endorsement relevant sub-stage
	Note to applicant: any interim servicing solution endorsed by EDQ will be subject to an uncompleted works bonding agreement to ensure timely delivery of the ultimate infrastructure.	
34.	Compliance Assessment - Stormwater Management (Quality)	
	a) Submit to EDQ IS detailed engineering drawings, certified by a suitably qualified RPEQ, for stormwater treatment devices designed generally in accordance with <i>PDA Guideline No. 13 Engineering standards</i> – Stormwater quality, relevant IMPs and OSSs (as updated from time to time) and the approved plans and documents.	a) Prior to commencing stormwater work
	 b) Construct stormwater works generally in accordance with the certified plans submitted under part a) of this condition. 	b) Prior to survey plan endorsement for the relevant sub-stage
	c) Submit to EDQ IS "as constructed" plans, certified by a suitably qualified RPEQ, including an asset register, in a format acceptable to Council.	c) Prior to survey plan endorsement for the relevant sub-stage
35.	Compliance Assessment - Stormwater Management (Quantity)	
	a) Submit to EDQ IS for compliance assessment, detailed engineering drawings and hydraulic calculations, certified by a suitably qualified RPEQ, for the stormwater drainage system designed generally in accordance with PDA Guideline No. 13 Engineering standards –	a) Prior to the first stage discharging to the stormwater detention device or;

PDA	PDA Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
	Stormwater quantity, relevant IMPs and OSSs (as updated from time to time), and the approved plans and documents These plans are to include any inter-allotment drainage and proposed easements. In particular, the plans are to address overland flow from rear draining lots within Stage 13.	Provide an RPEQ certified technical memo demonstrating the allowable limit of construction before stormwater runoff exceeds predevelopment flows.			
	 b) Construct stormwater works generally in accordance with the certified plans submitted under part a) of this condition. 	b) Prior to survey plan endorsement for the relevant sub-stage			
	c) Submit to EDQ IS "as constructed" plans, certified by a suitably qualified RPEQ including an asset register in a format acceptable to Council.	c) Prior to survey plan endorsement for the relevant sub-stage			
36.	Compliance Assessment - Stormwater - Infrastructure Masterplan				
	Submit to EDQ IS for compliance assessment, an updated infrastructure master plan for stormwater infrastructure.	Prior to lodgement of first CA for SW quality and quantity			
	In addition to the requirements set out in condition 3 of the DEV2012/209 Approval, this infrastructure master plan must include the following: i) a Flooding Report that includes an appropriate flood model to determine a flood assessment of the pre and post development scenario. The report is to demonstrate no worsening impact on state infrastructure. Consideration must be given to the current Logan City Council's Temporary Local Planning Instrument ii) a Stormwater Management Report detailing measures to be implemented to ensure the integrity and values of waterways is maintained and enhanced by providing appropriate management of water quality and water quantity iii) a waterway condition assessment which demonstrates how creek stability and ongoing waterway health is to be achieved and sustained iv) a groundwater management strategy which includes assessment of the inter-relationship between existing groundwater conditions and proposed development design and v) demonstrate how the proposed infrastructure and other actions will contribute towards the achievement of an overarching site strategy for TWCM. NOTE: This condition is considered to be complied with if a SWIMP has been endorsed under another approval.				
07	endorsed under another approval				
37.	Compliance Assessment - Total water cycle management (TWCM)				
	Submit to EDQ IS for compliance assessment, an updated overarching site strategy for TWCM.	Prior to lodgement of first CA for SW quality and quantity			
	 In addition to the requirements set out in condition 4 of the DEV2012/209 Approval, this overarching site strategy must: address all elements of the water cycle, separately and in combination, in order to deliver water infrastructure and management strategies in a way that optimises social and environmental benefits and minimises costs. This includes water supply, sewage, stormwater, flooding and receiving water quality and include strategies for sewage, potable water, stormwater management and water self-sufficiency. 				

PDA	PDA Development Conditions – Reconfiguring a Lot				
No	Condition	Tir	ning		
	This overarching site strategy, as amended from time to time, will guide future development decisions in relation to the site.				
	Include a monitoring program that on a yearly basis, commencing from the date of this approval, provides a report that analyses the achievement against the set targets. Should the monitoring program identify that delivery differs from the target in any reporting period, a mitigation plan, setting out how the target will be achieved in the next review period must accompany the report.				
	 NOTES: i) Offsets against the Implementation charge may be applicable for the costs of implementing this overarching site strategy where clear innovations initiatives are implemented. ii) This condition is considered to be complied with if a SWIMP has been endorsed under another approval 				
38.	Electricity				
	Submit to EDQ IS a Certificate of Electricity Supply from ENERGEX for the provision of electricity supply to the approved development.	a)	Prior to survey plan endorsement for the relevant sub-stage		
	b) Connect the approved development in accordance with the Certificate of Electricity Supply submitted under part a) of this condition.	b)	Prior to on maintenance for the relevant sub-stage		
39.	Telecommunications				
	a) Submit to EDQ IS documentation from an authorised telecommunication service provider confirming that an agreement has been entered into for the provision of underground telecommunication services to the approved development.	a)	Prior to survey plan endorsement for the relevant sub-stage		
	 b) Connect the approved development in accordance with the documentation submitted under part a) of this condition. 	b)	Prior to on maintenance for the relevant sub-stage		
40.	Broadband				
	a) Submit to EDQ IS written agreement, from an authorised telecommunications service provider, confirming that fibre-ready pit and pipe infrastructure designed to service the approved development can accommodate services compliant with <i>Industry Guideline G645:2017 Fibre-Ready Pit and Pipe Specification for Real Estate Development Projects</i> .	a)	Prior to survey plan endorsement for the relevant sub-stage		
	b) Construct the fibre-ready pit and pipe infrastructure specified in the agreement submitted under part a) of this condition.	b)	Prior to on maintenance for the relevant sub-stage		
Land	scape and environment				
41.	Streetscape Works (compliance assessment d)-g))				
	Either: a) Submit to EDQ DA detailed landscape plans for streetscape works, including a schedule of assets, certified by an AILA, generally in accordance with Council's Infrastructure Planning Scheme Policy – Landscaping.	a)	Prior to commencement of site works for each stage		
	The location and size of stormwater treatment devices proposed within the road reserve are required to be certified by an RPEQ.				

PDA	DA Development Conditions – Reconfiguring a Lot				
No	Condition	Tir	ming		
	 b) Construct the works generally in accordance with the certified plans submitted under part a) of this condition. 	b)	Prior to survey plan endorsement for each stage		
	 Submit to EDQ DA 'As Constructed' plans and asset register in a format acceptable to Council. 	c)	Prior to survey plan endorsement for each stage		
	Or:				
	d) Where the streetscape works do not comply with Council's Infrastructure Planning Scheme Policy – Landscaping, submit to EDQ DA for compliance assessment detailed streetscape works drawings, including a schedule of proposed standard and non-standard assets (with justification) to be donated to Council certified by an AILA.	d)	Prior to commencement of site works for each stage		
	The detailed functional layout plans are to include where applicable:				
	 location and type of street lighting; footpath treatments, ensuring any embellishments within do not obstruct maintenance operations. (e.g. proposed boulders are spaced accordingly to allow for mowing or are located in landscaped beds) location and types of streetscape furniture; 				
	4. location and size of stormwater treatment devices, certified by an REPQ; and5. street trees, including species, size and location generally in accordance with Council adopted planting schedules and guidelines.				
	e) Submit to EDQ IS detailed streetscape works plans certified by an AILA generally in accordance with the endorsed plans required under part d) of this condition.	e)	Prior to commencement of site works for each sub-stage		
	f) Construct the works generally in accordance with the endorsed streetscape plans as required under part d) of this condition.	f)	Prior to survey plan endorsement for each sub-stage		
	g) Submit to EDQ IS 'as constructed' plans and asset register in a format acceptable to Council.	g)	Prior to survey plan endorsement for each sub-stage		
10	Note: footpath treatments are to ensure any embellishments do not obstruct maintenance operations.				
42.	Compliance Assessment - Landscape Works (Parks and Open Space)				
	 a) Submit to EDQ IS, for Compliance Assessment, detailed landscape plans, certified by an AILA, for proposed landscape works within parks and open space. The certified plans must include a schedule of proposed standard and non-standard Contributed Assets to be transferred to Council and landscaping designed generally in accordance with: i) PDA Guideline No. 12 – Park planning and design; and ii) the approved plans. The certified plans are to include, where relevant: ii) existing contours or site levels, services and features: 	a)	Prior to commencement of landscape work for the relevant sub-stage and use		
	 existing contours or site levels, services and features; 				

PDA	Development Conditions – Reconfiguring a Lot	
No	Condition	Timing
	 ii) proposed finished levels, including sections across and through the open space at critical points (e.g. interface with roads or water bodies, retaining walls or batters); iii) location of proposed drainage and stormwater works within open space, including cross-sections and descriptions; iv) locations of electricity and water connections to parks; v) location and details of vehicle barriers/bollards/landscaping along park frontages to prevent unauthorised vehicular access; vi) details and locations of any proposed building works including bridges, park furniture, picnic facilities, play equipment, public amenities, car parking, driveways, footpaths and cycling paths; vii) trees and plants, including species, size and location generally in accordance with Council's adopted planting schedules and guidelines. 	
	 b) Construct landscape works generally in accordance with the plans endorsed under part a) of this condition. 	b) Prior to survey plan endorsement for the relevant sub-stage
	 c) Submit to EDQ IS, 'as constructed' plans, certified by an AILA, and asset register in a format acceptable to Council. Note: Landscape concept plans for the sport parks will be required with the 	c) Prior to survey plan endorsement for the relevant sub-stage
	submission of MCU's to establish the use.	
43.	Compliance Assessment - Waterway Rehabilitation and Stabilisation – all identified waterways	
	a) Submit to EDQ IS for compliance assessment a waterway rehabilitation and stabilisation strategy certified by a suitably qualified professional for all identified waterways (Flagstone Creek limited to the southern side of the creek and Sandy Creek limited to the northern side of the creek or as otherwise required for tie-in purposes).	Prior to commencement of works for the relevant sub-stage
	 The water stabilisation strategy shall include: i) an assessment of geotechnical conditions of the site, ii) proposed locations of detention and bio-retention basins and other infrastructure iii) full details of areas where dispersive soils will be disturbed, their treatment, rehabilitation and stabilisation, where appropriate. 	
	 b) Submit to EDQ IS detailed waterway rehabilitation and stabilisation plans for the southern portion of Flagstone Creek certified by a suitably qualified professional generally in accordance with the waterway stability strategy endorsed under part a) of this condition generally documenting where applicable the following: i) Existing contours or site levels, services and features; ii) Proposed finished levels, including sections across and through the waterway at critical points; iii) Vegetation management; iv) Details and locations of any proposed structures, including: weirs, bridges and artificial bank stabilisation (eg: gabions); v) Trees and plants, including species, size and location generally in accordance with Council's adopted planting schedules and guidelines. 	b) Prior to commencement of works for the relevant sub-stage

Development Conditions – Reconfiguring a Lot	
· · · · · · · · · · · · · · · · · · ·	Timing
c) Carry out the works generally in accordance with the certified plans required under part b) of this condition.	c) Prior to survey plan endorsement for the relevant sub-stage
d) Submit to EDQ IS 'as constructed' plans and asset register in a format acceptable to the Council certified by a suitably qualified professional.	d) Prior to survey plan endorsement for the relevant sub-stage
Compliance Assessment - Ecological sustainability and innovation	
Submit to EDQ IS the outcomes of the monitoring program included in the endorsed Ecological Sustainability and Innovation OSS on a yearly basis from the date of this approval. The report is to provide analyses of the achievement against the set targets. Should the monitoring program identify that delivery differs from the target in any reporting period, a mitigation plan, setting out how the target will be achieved in the next review period must accompany the report.	At the time of the Total Water Cycle Management Plan submission.
Note : Offsets against the Implementation charge may be applicable for the costs of implementing this overarching site strategy.	
Vegetation Management and Clearing	
 a) Carry out vegetation clearing generally in accordance with the relevant approved plans/documents. 	a) Prior to survey plan endorsement for the relevant stage
b) Submit to EDQ IS certification from a suitably qualified ecologist or arborist (AQF Level 5 or above that vegetation clearing has been carried out in accordance with part a) of this condition.	b) Prior to survey plan endorsement for the relevant stage
Compliance Assessment - Rehabilitation Plan	
 a) Submit for compliance assessment an updated rehabilitation plan. The rehabilitation plan must: Outline the rehabilitation works required to rehabilitate areas identified in Map 1 – Proposed Rehabilitation Areas (refer to Attachment 2) Identify the rehabilitation works, including (but not limited to): the establishment of a 10m (minimum) vegetated buffer from top of bank that is consistent with the pre-clearing ecosystem on identified watercourses rehabilitate identified fauna corridors rehabilitate the environmental protection zone and the establishment of vegetative ground covers to promote regeneration of native plant species. The ground covers must be designed to not inhibit native species generation nor introduce exotic or pest species into the area. Identify the staging associated with the required rehabilitation works to ensure the long-term success. Be prepared in accordance with the methods outlined in the Guideline and Manual components of the SEQ Ecological Restoration Framework to return the vegetation to a self-sustaining ecosystem as defined in the SEQ Ecological Restoration Framework. 	a) Prior to survey plan endorsement of the first sub-stage
	d) Submit to EDQ IS 'as constructed' plans and asset register in a format acceptable to the Council certified by a suitably qualified professional. Compliance Assessment - Ecological sustainability and innovation Submit to EDQ IS the outcomes of the monitoring program included in the endorsed Ecological Sustainability and Innovation OSS on a yearly basis from the date of this approval. The report is to provide analyses of the achievement against the set targets. Should the monitoring program identify that delivery differs from the target in any reporting period, a mitigation plan, setting out how the target will be achieved in the next review period must accompany the report. Note: Offsets against the Implementation charge may be applicable for the costs of implementing this overarching site strategy. Vegetation Management and Clearing a) Carry out vegetation clearing generally in accordance with the relevant approved plans/documents. b) Submit to EDQ IS certification from a suitably qualified ecologist or arborist (AQF Level 5 or above that vegetation clearing has been carried out in accordance with part a) of this condition. Compliance Assessment - Rehabilitation Plan a) Submit for compliance assessment an updated rehabilitation plan. The rehabilitation plan must: i) Outline the rehabilitation works required to rehabilitate areas identified in Map 1 – Proposed Rehabilitation Areas (refer to Attachment 2) ii) Identify the rehabilitation works, including (but not limited to): 1. the establishment of a 10m (minimum) vegetated buffer from top of bank that is consistent with the pre-clearing ecosystem on identified watercourses 2. rehabilitate identified fauna corridors 3. rehabilitate identified fauna corridors 4. the establishment of vegetative ground covers to promote regeneration of native plant species. The ground covers must be designed to not inhibit native species generation nor introduce exotic or pest species into the area. iii) Identify the staging associated with the required rehabilita

PDA	PDA Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
	 Following the EDQ's endorsement of the rehabilitation plan outlined in (a) complete rehabilitation works in accordance with the endorsed rehabilitation plan. 	b) Prior to survey plan endorsement for the relevant sub-stage			
	c) Submit certification from an ALIA registered professional, that the works have been completed in accordance with part b of this condition	c) Prior to survey plan endorsement for the relevant sub-stage			
47.	Koala Habitat Contribution				
	Pay to the MEDQ \$150 for each approved dwelling to be developed in accordance with the approved plan of development NOTE: The contribution required by this condition is for the purposes of managing	Prior to survey plan endorsement for the relevant stage			
	koala habitat and is levied in accordance with PDA Guideline No. 17 – Remnant vegetation and koala habitat obligations in Greater Flagstone and Yarrabilba PDAs.				
48.	Bushfire Management				
	a) Carry out bushfire management works as recommended in the approved Bushfire Management Report	a) Prior to survey plan endorsement for the relevant sub-stage			
	b) Submit to EDQ DA verification from a suitably qualified professional that the works required for bushfire management and mitigation within the relevant stages have been carried out generally in accordance with the relevant approved plans and documents.	b) Prior to survey plan endorsement for the relevant sub-stage			
49.	Acoustic Treatments (Noise Barrier)				
	a) Submit to EDQ IS detailed engineering plans, certified by a suitably qualified RPEQ for the approved noise barrier(s). The noise barrier(s) must be designed generally in accordance with PDA Engineering Guideline No. 13 – Engineering standards - Acoustic treatments, and the recommendations of the approved acoustic report.	a) Prior to commencement of noise barrier works for the relevant stage			
	 b) Construct barrier(s) works generally in accordance with the certified plans submitted under part a) of this condition. 	b) Prior to survey plan endorsement for the relevant sub-stage			
	c) Submit to EDQ IS 'as constructed' plans, certified by a suitably qualified RPEQ and an asset register.	c) Prior to survey plan endorsement for the relevant sub-stage			
	eying, Land Transfers and Easements				
50.	Land Transfers - Drainage				
	Transfer, in fee simple, to Council as trustee any lots containing drainage infrastructure (e.g., stormwater detention basins), where such infrastructure is not contained within a road reserve.	At registration of survey plan for the relevant sub-stage			
	The plans and terms of the easement/s must be to the satisfaction of the Chief Executive Officer of the authority.				
51.	Land Transfers – Water pump station				
	Transfer, in fee simple, to Council as trustee, any lot containing the water pump station.	At registration of survey plan for the relevant sub-stage			
	The plans and terms of the easement/s must be to the satisfaction of the Chief Executive Officer of the authority.				

PDA	PDA Development Conditions – Reconfiguring a Lot				
No	Condition	Timing			
52.	Land Transfers – Park and Open Space				
	Transfer, in fee simple, to Council as trustee Lots 91409, 91407, 91408, 91411, 91401, 91303, 91304, 91301, 91305, 91302, 91002, 90904, 91001, 90903, 91106, 91104, 91103, 91101, 91102, 90901, 90902, as shown on the approved plans for park and open space purposes.	At registration of survey plan for the relevant sub-stage			
53.	Land Transfers - Major and District Sports Parks				
	Transfer, in fee simple, to Council as trustee Lots 91105 and 91410 as shown on the approved plans for Major and district sports parks purposes.	At registration of survey plan for the relevant sub-stage			
54.	Land Transfers – Local Community Facilities				
	Transfer, in fee simple, to Council as trustee, Lot 50039 as shown on the approved plans for local community centre purposes. Lots to be transferred under this condition must be serviced in accordance with the Community Facilities IMP as amended from time to time.	At registration of survey plan for the relevant sub-stage			
55.	Land Transfers – State Community Facilities				
	Transfer, in fee simple, to the State of Queensland (represented by the Department of Education and Queensland Ambulance Services), Lot 30015 (Department of Education), and Lot 50033 (Queensland Ambulance Service) as shown on the approved plans. Lots to be transferred under this condition must be serviced in accordance with Community Facilities IMP.	At registration of survey plan for the relevant sub-stage			
56.	Easements over Infrastructure				
	Provide public utility easements, in favour of and at no cost to the grantee, over infrastructure located in land (other than road) for Contributed Assets. The terms of public utility easements are to be to the satisfaction of the	At registration of survey plan for the relevant sub-stage			
	Chief Executive Officer of the authority which is to accept and maintain the Contributed Assets.				
57.	High Density Development Easements (lots ≤300m² in area)				
	a) Submit to EDQ DA high density development easement documentation, in a registerable form, for approved lots ≤300m² in area and involving common wall construction.	a) At or prior to survey plan endorsement for the relevant sub-stage			
	 Register all high density development easements required under part a) of this condition. 	b) At registration of survey plan for the relevant substage			
58.	Reciprocal Easements (lots >300m² in area)				
	 a) Submit to EDQ DA reciprocal easement documentation, in a registerable form, for approved lots >300m² in area and involving common wall construction. 	a) At or prior to survey plan endorsement for the relevant sub-stage			
	 Register all reciprocal easements required under part a) of this condition. 	b) At registration of survey plan for the relevant substage			
	NOTE : For the purposes of this condition, common wall construction includes the circumstances listed under section 94(2) (a) of the LTA (e.g. terrace housing on standard format lots).				

PDA	PDA Development Conditions – Reconfiguring a Lot			
No	Condition	Timing		
Infra	structure Charges			
59.	Municipal & State Charges The applicant will pay to the MEDQ the Municipal & State Charges in accordance with the DCOP, indexed to the date of payment.	In accordance with the DCOP.		
60.	Implementation Charge			
	 a) If the ICID applies to the development, the applicant will pay to the MEDQ the ID Implementation Charge (calculated in accordance with the ICID); or 	a) In accordance with the ICID; or		
	b) If the ICID does not apply to the development, the applicant must pay the MEDQ the relevant charges calculated in accordance with the DCOP, indexed to the date of payment.	b) In accordance with the DCOP		
61.	Sub-Regional & Value Capture Charges			
	a) If the SRIA or DSRCIA applies to the development, the applicant will provide the MEDQ with a copy of an invoice from Logan City Council (the Council) for the IA Sub-regional charges (calculated in accordance with the SRIA) and written evidence that those charges have been paid to the Council; or	a) In accordance with the SRIA, DSRCIA; or		
	b) If the SRIA or DSRCIA do not apply to the development, the applicant must pay to the MEDQ the Sub-regional and Value Capture charges in accordance with the DCOP, indexed to the date of payment.	b) In accordance with the DCOP		

Deve	Development Conditions – Plan of Development (POD)				
No	Condition	Timing			
Deve	elopment in accordance with a POD				
62.	Carry out the approved development Carry out the approved development generally in accordance with:	Prior to commencement of			
	a) the approved POD; andb) any documentation endorsed via Compliance Assessment as required by these conditions.	use			
63.	Maintain the approved development Maintain the approved development generally in accordance with any documentation endorsed via Compliance Assessment as required by these	At all times following commencement of use			
	conditions.				
64.	Submit to EDQ DA, for Compliance Assessment, documentation for MULTIPLE RESIDENTIAL development for three or more units, excluding lots 50041, 50042 and 50043, for assessment against the approved POD.	a) Prior to commencement of building works			
	 b) The documentation submitted under part a) of this condition is to detail and/or include the following: i) site location; ii) lot size and configuration; iii) building height; iv) plot ratio, gross floor area (GFA) and site cover; v) number and size, using GFA, of dwellings; 	b) Prior to commencement of building works			

Deve	elopment Conditions – Plan of Development (POD)	
No	Condition	Timing
	 vi) interface with adjoining dwellings; vii) built-form including floor plans, sections, elevations and details of materials; viii) landscaping and open space provision; ix) on-site parking, access and servicing; x) urban servicing arrangements including sewer, water, stormwater connections; and xi) an assessment of compliance with the approved POD. 	
Cons	struction of development in accordance with a POD	
65.	Out of hours of work – construction	
	Unless otherwise endorsed, via Compliance Assessment for out of hours work, construction hours for the approved development are limited to Monday to Saturday between 6:30am to 6:30pm, excluding public holidays.	During construction unless otherwise endorsed
66.	Out of hours work - Compliance Assessment	
	Where out of hours work is proposed, submit to EDQ DA, for Compliance Assessment, an out of hours work request. The out of hours work request must include a duly completed out of hours work request form ⁴ .	Minimum of 10 business days prior to proposed out of hours work commencement date
67.	Certification of Operational Work	
	Carry out all Operational Work, for a use permitted under the approved POD, in accordance with the <i>Certification Procedures Manual</i> .	At all times
68.	Public infrastructure (damage, repairs and relocation)	
	Repair any damage to existing public infrastructure caused by works carried out in association with the approved development.	a) Prior to commencement of use or endorsement of a Building Format Plan, whichever occurs first
	 b) Should existing public infrastructure require repair or relocation, due to the approved development and/or works associated with the approved development, repair and/or relocate the public infrastructure at no cost to others and in accordance with statutory requirements and adopted design standards. NOTE: It is recommended applicants record their own dated photographic evidence of the condition of relevant existing public infrastructure both before and after works carried out in association with the approved development. 	b) Prior to commencement of use or endorsement of a Building Format Plan, whichever occurs first
69.	Municipal & State Charges	
	The applicant will pay to the MEDQ the Municipal & State Charges in accordance with the DCOP, indexed to the date of payment.	In accordance with the DCOP.
70.	Implementation Charge	
	a) If the ICID applies to the development, the applicant will pay to the MEDQ the ID Implementation Charge (calculated in accordance with the ICID); or	a) In accordance with the ICID; or
	b) If the ICID does not apply to the development, the applicant must pay the MEDQ the relevant charges calculated in accordance with the DCOP, indexed to the date of payment.	b) In accordance with the DCOP

 $^{^{\}rm 4}$ The out of hours work request form is available at EDQ's website.

Development Conditions – Plan of Development (POD)		
No	Condition	Timing
71.	Sub-Regional & Value Capture Charges	
	a) If the SRIA or DSRCIA applies to the development, the applicant will provide the MEDQ with a copy of an invoice from Logan City Council (the Council) for the IA Sub-regional charges (calculated in accordance with the SRIA) and written evidence that those charges have been paid to the Council; or	a) In accordance with the SRIA, DSRCIA; or
	b) If the SRIA or DSRCIA do not apply to the development, the applicant must pay to the MEDQ the Sub-regional and Value Capture charges in accordance with the DCOP, indexed to the date of payment.	b) In accordance with the DCOP

STANDARD ADVICE

- Please note that to lawfully undertake development, it may be necessary to obtain approvals other than this PDA development approval. For advice on other approvals that may be necessary in relation to your proposal, it is recommended that you seek professional advice.
- The Natural Environment OSS was endorsed in 2015. It is recommended that the document is updated under 2012/209 to ensure it reflects current mapping and policy positions.

** End of Package **