

**CIVIL ENGINEERING REPORT
44 EDISON CRESCENT YARRABILBA
PROPOSED INDUSTRIAL BUILDING**

REVISION B
OUR REF: 25584

REVISION	DATE	AMENDMENTS
A	19/05/25	-
B	28/07/25	Revised Layout

Prepared For:	Black Diamond Building & Construction
Prepared By:	Richard Leonard
Release Date	28/07/2025
Job Number:	25584
Document Name:	Civil Engineering Report
	44 Edison Crescent Yarrabilba
Revision:	A

Approved for release by

A handwritten signature in black ink, appearing to read 'CLL', is positioned above the printed name and title.

Campbell Leonard
FIEAust CPEng NPER3
RPEQ 4293
Director

Contents

1.	Introduction	4
2.	Site Information	4
3.	Engineering Assessment	5
3.1	Erosion and Sediment Control	5
3.2	Bulk Earthworks	5
3.3	Vehicular Access	5
3.4	Stormwater Drainage	6
3.5	Sewer Connection	6
3.6	Water Connection	6
4.	Conclusion	7

Figures

1. Introduction

This Civil Engineering Report has been in order to accompany an application for a material change of use.

The objectives of this report are to assess the following in the context of the proposed development:

- Erosion and sediment control
- Bulk Earthworks
- Vehicular Access
- Stormwater Drainage
- Sewer Connection
- Water Connection
- Electrical and telecommunications connections

2. Site Information

The site is located at 44 Edison Crescent Yarrabilba (Lot 24 SP333769). This lot was created as part of Stage 2 of Precinct 5 of the Yarrabilba Priority Development Area (PDA). The site has a frontage to Edison Crescent to the west and south. It grades generally from the north east to the south west at generally 2.0%. The area of the site is 2,168m² in size, and it is currently vacant.




Figure 1 Aerial Photo of Site (Copyright Qld Globe)

The proposal for the site is for the construction of a building with two tenancies, with associated car parking.

3. Engineering Assessment

3.1 Erosion and Sediment Control

During the course of the construction, the following processes are expected:

- Bulk earthworks
- Detailed earthworks to trim lot to final levels
- Construction

Management of stormwater runoff from the exposed earthwork surfaces will be based on containment, diversion and retention. At all stages of construction, current standards of building practices will be adhered to. These include:

- Placement of sediment fences
- Vehicle shakedown to prevent suspended solids being exported from site and consequently into surrounding stormwater infrastructure
- Sediment traps to field inlet pits and gullies

An Erosion and Sediment Control Plan has been prepared, refer to CLA Consultants Drawing 25584 - 002 in Figures. It will be the responsibility of the contractor to ensure that these and any other sedimentation and erosion controls are carried out.

3.2 Bulk Earthworks

The development of the site will require earthworks to level the site to provide the building pad. This process will result in a cut from the site of approximately 80m³. Drawing 25584 - 003 provides details of the earthworks proposed on the site.

3.3 Vehicular Access

It is proposed that access to the site for vehicles will be provided by a single crossover to Edison Crescent. These will be constructed as 'General Wide' or 'General Wide Flared' crossovers as per IPWEA standard drawing RS-051.

The service vehicle for the development is a Heavy Rigid Vehicle (HRV). A Traffic Engineering Report will be provided for assessment separately.

3.4 Stormwater Drainage

As discussed above, the subject site lies within a new subdivision. As part of the subdivision works, stormwater management has been provided within the downstream network through a series of bio-retention filters with additional ponding. As such, no treatment in terms of stormwater quantity is required within the site. It is proposed however to install SQIDEP approved Gross Pollutant Traps (Atlan Stormsacks or similar) to all field inlet pits. This will manage the release of gross pollutants and coarse sediments into the downstream infrastructure.

Stormwater from roofs and car park areas will be collected in a new internal stormwater drainage system. This system will use the existing stormwater pit on the site as the lawful point of discharge. The stormwater layout is shown on Drawing 25584 - 004, and the stormwater drainage longitudinal sections and catchment plan/calculations are shown at Drawings 25584 - 005 and 006 respectively.

3.5 Sewer Connection

The proposed sewer connection point will be the existing property connection to the south west of the site. CLA Consultants Drawing 25584 - 004 shows the location of this connection point.

3.6 Water Connection

A new private water meter assembly will be provided to the site from the existing 150mm diameter PVC-M water main which runs within the verge on the opposite side of Edison Crescent. The size and final location of this connection will be nominated by the hydraulic consultant prior to application for Plumbing and Drainage approval.

3.7 Electrical and Telecommunications Connections

The existing energex pillar boxes will be used as the connection point for the site. There is existing telstra infrastructure outside the site, this will be the connection point for communications purposes.

5. Conclusion

This report has assessed the following:

- Erosion and sediment control
- Bulk Earthworks
- Vehicular Access
- Stormwater Drainage
- Sewer Connection
- Water Connection
- Electrical and telecommunications connections

The proposed development is able to be serviced by all required infrastructure, and in accordance with the relevant local government requirements.

Figures

Site Survey Stewart McIntyre & Associates

CLA Consultants Drawings

25584 – 001 – Site Plan, Drawing Schedule & Notes

25584 – 002 – Erosion and Sediment Control Plan

25584 – 003 – Bulk Earthworks Plan


25584 – 004 – Grading & Drainage Plan

25584 – 005 – Stormwater Drainage Long Section


25584 – 006 – Stormwater Catchment Plan and Calculations



- GENERAL NOTES
1. ALL WORK TO BE CARRIED OUT IN ACCORDANCE WITH LOGAN CITY COUNCIL'S SPECIFICATIONS. CONTRACTOR TO OBTAIN AND RETAIN A COPY ON SITE DURING THE COURSE OF THE WORKS.
 2. ALL NEW WORKS ARE TO BE MADE A SMOOTH JUNCTION WITH EXISTING CONDITIONS, AND HARRY IN A WORKMANLIKE MANNER.
 3. THE CONTRACTOR IS TO VERIFY THE LOCATION OF ALL SERVICES WITH EACH RELEVANT AUTHORITY. ANY DAMAGE TO SERVICES SHALL BE RECTIFIED BY THE CONTRACTOR OR THE RELEVANT AUTHORITY AT THE CONTRACTOR'S EXPENSE. SERVICES SHOWN ON THESE PLANS ARE ONLY THOSE EVIDENT AT THE TIME OF SURVEY OR AS DETERMINED FROM SERVICE DIAGRAMS. CLAs LIABILITY IS LIMITED TO THE INFORMATION PROVIDED AND THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY INFORMATION AND FOR THE ACCURACY OF THE DATA.
 4. SERVICES CROSSING THE SITE BOUNDARY SHALL BE MARKED AND DEPTH NOTED IN WORKING ORDER FOR ALL WORKS DURING CONSTRUCTION.
 5. SERVICES CROSSING THE SITE BOUNDARY SHALL BE MARKED AND DEPTH NOTED IN WORKING ORDER FOR ALL WORKS DURING CONSTRUCTION.
 6. SERVICES CROSSING THE SITE BOUNDARY SHALL BE MARKED AND DEPTH NOTED IN WORKING ORDER FOR ALL WORKS DURING CONSTRUCTION.
 7. SERVICES CROSSING THE SITE BOUNDARY SHALL BE MARKED AND DEPTH NOTED IN WORKING ORDER FOR ALL WORKS DURING CONSTRUCTION.
 8. SERVICES CROSSING THE SITE BOUNDARY SHALL BE MARKED AND DEPTH NOTED IN WORKING ORDER FOR ALL WORKS DURING CONSTRUCTION.
 9. SERVICES CROSSING THE SITE BOUNDARY SHALL BE MARKED AND DEPTH NOTED IN WORKING ORDER FOR ALL WORKS DURING CONSTRUCTION.
 10. PROPERTIES AFFECTED BY THE WORKS ARE TO BE NOTIFIED IN ADVANCE WHERE DISRUPTION TO EXISTING ACCESS IS LIKELY.



VEHICULAR CROSSOVER GRADING DETAILS
150 @ A3



DRAWING SCHEDULE	
NUMBER	TITLE
25584 - 001	SITE PLAN, DRAWING SCHEDULE & NOTES
25584 - 002	EROSION & SEDIMENT CONTROL PLAN
25584 - 003	BULK EARTHWORKS PLAN
25584 - 004	SITE GRADING & DRAINAGE PLAN SHEET
25584 - 005	STORMWATER DRAINAGE LONGITUDINAL SECTIONS
25584 - 006	STORMWATER CATCHMENT PLAN & CALCULATIONS

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2025/1650

Date: 7 August 2025


Queensland Government


CLA CONSULTANTS
CIVIL ENGINEERS
10/11-13/15
GOLD COAST QLD 4226
P: 0414 888 321
F: 07 5520 1077
r.leonard@claconsultants.com.au

CLIENT
BLACK DIAMOND BUILDING

PROJECT
44 EDISON CRESCENT YARRABILBA

PROPERTY DESCRIPTION
LOT 24 SP333769

DESIGNED
RC LEONARD

DRAWN
RC LEONARD

REVIEWED
CB LEONARD

DATE
19 MAY 2025

APPROVED

RC LEONARD
Professional Engineer (PEng) 4290

PROJECT REF.	DRAWING NO.	REVISION
25584	001	B





PLACE PORTABLE KERB SEDIMENT TRAP AS PER DETAIL AT ALL GULLY PITS AFFECTED BY SITE CONSTRUCTION WORKS

- LEGEND
- SILT FENCE
- VEHICLE SHAKEDOWN
- INLET SEDIMENT TRAP


PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2025/1650


Date: 7 August 2025

Queensland Government


- Sedimentation and Erosion Control
- Sedimentation and erosion control implementation and maintenance shall be in accordance with the Local Government of Moreton Bay Council's "Management Practices". The Contractor shall make himself aware of the prevailing weather conditions and shall take all necessary precautions to secure the site at the completion of each day's work, and whenever else is considered necessary.
 - Sedimentation and erosion control measures shall be provided as required to prevent the movement of dust and/or silt from the site.
 - Sediment and erosion control measures shall be installed downstream of any work area prior to the commencement of work in that area.
 - Erosion and sedimentation control measures shall be installed prior to the commencement of work in that area.
 - Topsoil shall be stripped in accordance with the specification and stockpiles at locations as agreed by the superintendent and Council's designated representative, and grass seeded, mulched, re-vegetated etc within 7 days of the completion of work.
 - All sediment control measures and devices shall be inspected for structural damage after each rainfall event and at the completion of each day's work. All trapped sediment shall be removed to an approved location on site for re-use on site or for subsequent removal from the site. Site disposal will only be approved when it can be demonstrated that no sediment erosion can be attributed to the site.
 - Sediment and erosion control measures around stockpiles shall include but not necessarily be limited to:
 - Provision of a silt fence below the stockpile, as indicated by the natural slopes of the land.
 - Provision of grass cover if stockpile is to remain in place for more than 30 days.
 - Provision of a silt fence and a wind erosion control mat to prevent wind erosion.
 - Place 600mm width turf at both top and toes of retaining walls and tops of new kerb.
 - Water areas of construction regularly as required to obviate potential for dust nuisance to adjoining properties and the site generally.
- Construction Traffic Shakedown
- Provide construction traffic shake down device at all relevant site exit points. Clean out and maintain shake down device regularly to ensure efficient operation.




PORTABLE GRAVEL KERB SEDIMENT TRAP



INLET SEDIMENT TRAP



VEHICLE SHAKEDOWN AREA



SILT FENCE

CIA CONSULTANTS
CIVIL ENGINEERS
PO BOX 1234
GOLD COAST QLD 4226
P: 0414 888 121
F: 07 5520 1077
c.leonard@ciaconsultants.com.au

CLIENT
BLACK DIAMOND BUILDING

PROJECT
44 EDISON CRESCENT YARRABILBA

PROPERTY DESCRIPTION
LOT 24 SP333769

DESIGNED
RC LEONARD

DRAWN
RC LEONARD

REVIEWED
CB LEONARD

DATE
19 MAY 2025

APPROVED

REV	DESCRIPTION	BY	DATE	APPROVED
B	REV LAYOUT	RCL	26/07/25	CBL
A	LOWER FILES	RCL	9/07/25	CBL

NAME
EROSION & SEDIMENT CONTROL PLAN

PROJECT REF.	DRAWING NO.	REVISION
25584	002	B



1500 @ A3

1:250 @ A3



CLIENT
BLACK DIAMOND
BUILDING


PROPERTY DESCRIPTION	LOT 24 SP333769
DESIGNED	RC LEONARD
DRAWN	RC LEONARD
REVIEWED	CB LEONARD
DATE	19 MAY 2025

APPROVED

[illegible]

PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

Approval no: **DEV2025/11**
Date: **7 August 2025**



[illegible]

2

PIT TYPE	FI - STORMSACK	EXISTING	ADD STORMSACK	EXISTING
GRATE/LID	GRATE (D)			
PIT SIZE	900 x 600			
FLOW (LIT /SEC)	121667	170.668		
VELOCITY (m/s)	3.593	2.618		
HGL LEVEL (m)	52.780	51.685	51.104	50.964


DATUM RL 49.25	300ø PVC	EXISTING 375ø
DIAMETER (mm)	300	375
SLOPE/GRADE	3.40%	2.45%
DEPTH (m)	1.69.38	1.40.87
INVERT LEVEL (m)	50.890	50.750
TOP OF PIT LEVEL	52.500	52.000
FINAL SURFACE LEVEL	52.000	14.728
ROAD CHANNAGE	14.728	5.722
CHAINAGE	0.000	20.450

1



 CLA CONSULTANTS CIVIL ENGINEERS PO BOX 5342 GOLD COAST MCC QLD 9726 P: 0418 888 321 F: 07 5520 1077 rleonard@claconsultants.com.au					
CLIENT	BLACK DIAMOND BUILDING				
PROJECT	44 EDISON CRESCENT YARRABILBA				
PROPERTY DESCRIPTION	LOT 24 SPR33769				
DESIGNED	RC LEONARD				
DRAWN	RC LEONARD				
REVIEWED	CB LEONARD				
DATE	19 MAY 2025				
APPROVED	 RICHARD CHIEFFO RPEQ 1290				
A.	LOWER PILES	REL	0.07/25	CHL	
REV	DESCRIPTION	BY	DATE	APPROV	
NAM					
STORMWATER DRAINAGE LONG SECTIONS					
PROJECT REF	DRAWING NO	REVISION			
25584	005	A			

DRAINAGE CALCULATIONS - Return Period: 100yrs

[illegible]

 CLA CONSULTANTS CIVIL ENGINEERS PO BOX 5342 GOLD COAST MC QLD 9726 P: 0414 888 321 F: 07 5520 1077 e:leonard@claconsultants.com.au									
CLIENT		BLACK DIAMOND BUILDING							
PROJECT		44 EDISON CRESCENT YARRABILBA							
PROPERTY DESCRIPTION	LOT 24 SP33749								
DESIGNED	RC LEONARD								
DRAWN	RC LEONARD								
REVIEWED	CB LEONARD								
DATE	19 MAY 2025								
APPROVED	 RC LEONARD, CHIEF PRG, 0295 929 929								
B	REV. LAUNCH	REL	26.07.25	CHL					
A	LOWER PDS	REL	0.07.25	CHL					
NAME		STORMWATER CATCHMENT PLAN & CALCULATIONS							
PROJECT REF	DRAWING NO	REVISION							
25584	006	B							


PLANS AND DOCUMENTS
 referred to in the PDA
DEVELOPMENT APPROVAL
 Approval no: **DEV/2025/1650**
 Date: **7 August 2025**