



PROPOSED INDUSTRIAL SUBDIVISION 702-742 GREENBANK RD, NORTH MACLEAN

TRAFFIC IMPACT ASSESSMENT

15 JULY 2025

PREPARED FOR
GREAT WALL PROPERTY GROUP



PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

Approval no: DEV2023/1425/2
Date: 8 September 2025



DOCUMENT CONTROL RECORD

DOCUMENT						
Report Title:		702-742 Greenbank Road, North Maclean - Traffic Impact Assessment				
Client:		Great Wall Property Group				
Project Number:		24-209				
REV	PURPOSE	DATE	AUTHOR	REVIEWER	APPROVED	SIGNED
A	FINAL	DEC-23	CG	JPG	JPG RPEQ 22233	
B	FINAL	FEB-24	CG	JPG	JPG RPEQ 22233	
C	FINAL	JUL-25	CG	JPG	JPG RPEQ 22233	

COPYRIGHT

This work is copyright. Apart from any use permitted under the Copyright Act 1968, no part may be produced without prior permission. Requests and inquiries concerning reproduction and rights should be directed to:

The Director

Pekol Traffic and Transport

Level 2, 62 Astor Terrace

Spring Hill QLD 4000

DISCLAIMER

This document is produced solely for the benefit of and use by our client in accordance with the terms and conditions of our appointment. PTT does not accept liability to third parties arising from their use of or reliance upon the contents of this report.

TABLE OF CONTENTS

1.0 INTRODUCTION	3
1.2 Aim	3
1.3 Scope of Report	3
2.0 EXISTING CONDITIONS	4
2.1 Subject Site	4
2.2 Access	4
2.3 Road Network	4
2.4 Active and Public Transport	5
2.5 Greater Flagstone PDA	5
3.0 PROPOSED DEVELOPMENT	7
3.1 Overview	7
3.2 Access	7
3.3 Parking	9
3.4 Servicing	9
3.5 Future Road Planning	10
4.0 TRAFFIC OPERATIONS	12
4.1 Development Staging	12
4.2 Traffic Generation	12
4.3 Directional distribution	12
4.4 Turn Warrants Assessment	13
4.5 Traffic Impact	15
5.0 CONCLUSIONS AND RECOMMENDATIONS	16
5.1 Conclusions	16
5.2 Recommendations	16
APPENDIX A: PLANS OF DEVELOPMENT	
APPENDIX B: GREENBANK ROAD SITE ACCESS DRAWINGS	
APPENDIX C: TURNING MOVEMENT FORECASTS	

1.0 INTRODUCTION

In October 2023, PTT was commissioned by Great Wall Property Group to undertake a traffic engineering assessment in support of a proposed one into two industrial lot subdivision at 702-742 Greenbank Road, North Maclean. The location of the subject site is shown in Figure 1.1.

The proposed sub-division plan has been revised, and the potential development area over proposed Lot 1 has reduced significantly. Given that the expected peak traffic generation associated with Lot 1 has also reduced significantly, revised turn treatments at the site access are proposed, as discussed in Section 4 of this revised traffic engineering assessment (Revision C). No changes to the temporary access location, parking recommendations and servicing arrangements are proposed, nor are any changes considered necessary.

Figure 1.1: SITE LOCALITY



1.2 AIM

The aim of this assessment is to evaluate the proposed development in terms of its access, parking and servicing arrangements, pedestrian / cyclist facilities, peak hour traffic generation and impact on the surrounding road network.

1.3 SCOPE OF REPORT

This report begins by summarising the characteristics of the existing road network (Chapter 2), followed by a description of the scope and scale of the development, including a consideration of the site access, parking provision and design, servicing arrangements and pedestrian / cyclist facilities (Chapter 3). The expected peak hour traffic generation of the site is quantified, with the development's likely impact assessed qualitatively (Chapter 4). The report concludes with a summary of key findings and recommendations (Chapter 5).


2.0 EXISTING CONDITIONS

2.1 SUBJECT SITE

The subject site is located at 702-742 Greenbank Road, North Maclean and is formally described as Lot 3 on 209351. According to the Logan Planning Scheme, the site is within a Priority Development Area (ie Greater Flagstone). A single residential dwelling and associated buildings are currently on the site, as shown in Figure 2.1.

The site is bounded by rural residential properties to the north and south, vacant land to the east and Greenbank Road to the west. The surrounding area is predominately rural residential.

Figure 2.1: SUBJECT SITE



2.2 ACCESS

Access to the subject site is currently provided via a single crossover on Greenbank Road, as indicated in Figure 2.1.

2.3 ROAD NETWORK

Greenbank Road is an undivided road with one lane of traffic in each direction and has a posted speed of 80km/h. According to Logan City Council's (LCC) Road Hierarchy, it is classified as a Rural Collector (ie major road).

Traffic count data collected at the Mount Lindesay Highway / Greenbank Road intersection (approximately 2km south-east of the site) in March 2023 indicates that existing traffic volumes

on Greenbank Road is in the order of 760vph and 905vph during the weekday morning and evening peak hours, respectively.

Given the extensive development expected throughout the Greater Flagstone PDA, Greenbank Road will be upgraded in the future to cater for increased traffic generated by the PDA.


2.4 ACTIVE AND PUBLIC TRANSPORT

There are no formalised pedestrian and facilities in proximity to the site, nor are there any public bus stops.

2.5 GREATER FLAGSTONE PDA

The subject site forms part of the Greater Flagstone PDA, specifically the North Maclean Industry and Business Precinct. The latest revision of the of the PDA general planning layout was endorsed by Economic Development Queensland (EDQ) in 2021 and is shown in Figure 2.2. According to the general planning layout, the subject site is zoned for industry and business uses.


Figure 2.2: GREATER FLAGSTONE GENERAL PLANNING LAYOUT



The general planning layout shown in Figure 2.2 includes an indicative road network through the subject site, that connects Greenbank Road to an approved 12-lot industrial sub-division to the east of the site (Application Number: DEV2015/727), as well as future development to the south of the site. A new T-intersection on Greenbank Road at the southern corner of the subject site would facilitate access to the future road network, with the road network also accessed from Willowbrook Road East via the approved 12-lot sub-division.

The approved sub-division layout is shown in Figure 2.3. Despite being approved in 2016, it is understood that the approval is still valid. As shown, the approved site is accessed via a new T-intersection on Greenbank Road (ie to align with the ultimate Willowbank Road East shown in Figure 2.2), with each individual lot accessed via a new 24m wide road. It is expected that this new road would be extended to the west as part of future development over the subject site.

Figure 2.3: APPROVED 12-LOT SUB-DIVISION




3.0 PROPOSED DEVELOPMENT

3.1 OVERVIEW

The development application seeks approval for a Reconfiguration of Lot (ROL) from one lot into two lots on the subject site. It is understood that Lot 1 would comprise future industrial uses and Lot 2 would cater for an environmental conservation zone. A separate Material Change of Use (MCU) application will be submitted to EDQ in the future to establish industrial uses over Lot 1. It is expected that Lot 1 would cater for warehouse or low impact / light industry uses. Future development over Lot 1 would be expected to accommodate approximately 10,260m² gross floor area (GFA).

The proposed ROL subdivision layout, including future road corridor, is included in Appendix A and shown in Figure 3.1.

Figure 3.1: PROPOSED SITE LAYOUT



3.2 ACCESS

3.2.1 Location

Vehicular access to Lot 1 is proposed from Greenbank Road via a private driveway, located at the south-western corner of the site. The proposed access would be located as far as possible from an existing horizontal curve on Greenbank Road (ie north of the access location). The proposed access location would not encroach existing intersections and neighbouring driveways. It is therefore our view that the proposed Greenbank Road access location is appropriate.

Ultimately, the site would also be accessed via a secondary driveway on the eastern side of the site and future road connections to the neighbouring sites to the east and south, noting that an industrial subdivision was approved at 820 Greenbank Road which accounted for future road connectivity to the subject site. This additional access location is shown in Figure 3.1. It is

understood that this ultimate additional access (via future road connections to sites to the east and south) would facilitate flood-free site access.

3.2.2 Design

Proposed Lot 1 would cater for heavy vehicles movements and thus, it is recommended that the all site accesses be designed in accordance with Institute of Public Works Engineering Australasia (IPWEA) Standard Drawing RS-102. It is expected that more detailed plans of the access driveway would be prepared in the future as part of future MCU applications.

3.2.3 Turn Treatments


Based on a turn warrants assessment provided in Section 4.3, it is recommended that the Greenbank Road access design incorporates the following turn treatments:

- a 55m short auxiliary left-turn deceleration lane (AUL(s)) on Greenbank Road
- an 80m short channelised right-turn lane (CHR(s)) on Greenbank Road

The AUL(s) and CHR(s) treatments will minimise the disruption to through traffic on Greenbank Road and are considered appropriate interim treatments, noting that (a) the site will ultimately be accessed via the adjacent site to the east and (b) Greenbank Road will eventually be upgraded to cater for expected development in the PDA.

A concept functional layout of the Greenbank Road access, including recommended turn treatments is shown in Figure 3.2 and included in Appendix B.

Figure 3.2: GREENBANK ROAD ACCESS FUNCTIONAL LAYOUT




3.2.4 Sight Distance

We estimate there is approximately 205m safe intersection sight distance (SISD) to the north of the proposed Greenbank Road access and in excess of 250m SISD to the south of the access (measured approximately 5.0m back from the through carriageway), as shown in Figure 3.3. Based on 90km/h design speed (ie posted speed plus 10km/h), the Austroads Guide to Road Design Part 4A: Unsignalised and Signalised Intersections identifies a desirable SISD of 214m (based on a two second reaction time) and an absolute minimum SISD of 201m (based on a 1.5 second reaction time). Thus, the available sight distance to the south of the Greenbank Road access achieves the minimum desirable sight distance required by Austroads.

Given that there is a horizontal curve to the north of the access, it is expected that vehicles approaching the access from the north would be travelling at or below the posted speed (ie 80km/h). For an 80km/h posted speed, Austroads requires a desirable SISD of 181m. We are therefore of the view that sufficient sight distance would be available to the north of the access, noting that the proposed Greenbank Road access location achieves the desirable SISD for an 80km/h posted speed and the absolute minimum SISD for a 90km/h design speed.

Figure 3.3: AVAILABLE SISD AT GREENBANK ROAD ACCESS



3.3 PARKING

In accordance with Greater Flagstone PDA Development Scheme, it is recommended that future development over Lot 1 provides sufficient parking in accordance with Division 5 Parking and Servicing Code of the Beaudesert Shire Planning Scheme 2007.

3.4 SERVICING

The section of Greenbank Road along the site frontage is not an approved B-double route. However, given that Greenbank Road will eventually be upgraded to facilitate primary access to the PDA, which is expected to cater for industrial uses, it is likely that Greenbank Road will eventually cater for B-Doubles.

The recommended CHR treatment shown in Figure 3.2 has been designed to cater for the storage of a 25m long B-double. Furthermore, it is expected that the Greenbank Road access could be readily designed to cater for the access/egress of a B-double, as demonstrated in drawing 24-209-003 included in Appendix B.

It is expected that the ultimate access design would be determined as part of future MCU applications over the site. It is recommended that the ultimate access design sufficiently caters for B-double access and egress.

3.5 FUTURE ROAD PLANNING

As shown in Figure 2.2, the Greater Flagstone general planning layout indicatively shows a future road running through the subject site, between Greenbank Road and the approved internal road network over the adjacent sub-division to the east. This new road would meet Greenbank Road at a T-intersection, generally located as per the Greenbank Road Lot 1 access shown in Figure 3.2. However, it is understood that the section of Greenbank Road, immediately adjacent to the subject site, is within a high hazard flood zone as shown in Figure 3.4 and so it would seem reasonable to relocate this future T-intersection elsewhere on the network (ie to a location on Greenbank Road that is not in a high flood zone).

Figure 3.4: FLOOD MAPPING GREENBANK ROAD





Figure 3.5 demonstrates that a cohesive future road network could be readily provided over sites to the east and south, without requiring a direct through connection to Greenbank Road through the subject site. Instead, a land dedication would be provided on the eastern side of the site to facilitate a future road connection between the approved sub-division to the east and future development over sites to the south. This dedication is approximately 34m which more than adequately cater for EDQ's preferred Industrial Collector cross-section.

We are of the view that the revised road network generally achieves the same level of accessibility and connectivity as the EDQ endorsed context plan. We recommend that the re-located T-intersection on Greenbank Road (ie provided in lieu of a T-intersection within the bounds of the subject site) be located approximately 300m north of the future Greenbank Road / Willowbrook Road East intersection. This would (a) ensure the T-intersection is located outside of the high hazard flood zone and (b) achieves the minimum intersection separation required in EDQ's Street and Movement Network Guidelines for Trunk Collector / Industrial Collector Roads.

Figure 3.5: REVISED INDICATIVE FUTURE ROAD NETWORK LAYOUT



4.0 TRAFFIC OPERATIONS

4.1 DEVELOPMENT STAGING

4.1.1 Assessment Scenarios

It is standard practice when analysing future year traffic operations to adopt a ten-year design horizon from the year of full occupation. Therefore, the following development staging has been adopted:

—	Traffic Survey:	2023
—	Development Application:	2025
—	Construction and Occupation:	2027
—	Occupation plus 10 years:	2037

4.1.2 Background Traffic Growth

The Department of Transport and Main Road's (TMR) Annual Average Daily Traffic (AADT) data for the Mount Lindesay Highway in the vicinity of the subject site (Counter Site: 10098) indicates an average traffic growth rate of 2.1% per annum over the most recent 10-year period for which data is available (ie 2012-2022). Accordingly, a background traffic growth rate of 2.1% per annum has been adopted. The application of this rate equates to a 29.4% increase in traffic volumes over the next 14 years (ie 2023 to 2037).

4.2 TRAFFIC GENERATION

Proposed Lot 1 is expected to cater for warehouse / low impact industry uses. The New South Wales Transport Roads and Maritime Services (RMS) Guide to Traffic Generating Developments (including the 2013 Updated Traffic Surveys) and TMR's Road Planning and Design Manual (1st Edition) recommends the following trip rates be adopted:

—	Warehouse:	0.5 trips per 100m ² GFA
—	Low Impact Industry:	0.9 trips per 100m ² GFA

TMRs' Road Planning and Design Manual identifies that the gross floor area (GFA) of industrial uses is typically around 45% of the site area, as considerable space has to be devoted to parking, servicing and manoeuvring. The total building pad / developable area over Lot 1 equates to approximately 22,800m². Thus, the total GFA over Lot 1 is expected to be in order of 10,260m².

Conservatively adopting the higher of the two trip rates listed above, future development over Lot 1 could generate in the order of 92 two-way vehicle trips during the morning and evening peak hours.

4.3 DIRECTIONAL DISTRIBUTION

The distribution of development related traffic on the existing road network has been estimated based on the directional split inherent in the traffic surveys collected at the nearby Mount Lindesay Highway / Greenbank Road intersection. The adopted directional distribution at the Lot 1 Greenbank Road access is summarised in Appendix C.

The expected turning forecasts at the site access during the opening and future year peak hours is summarised in Figures 4.1 and 4.2.

Figure 4.1: OPENING YEAR TURNING VOLUMES





Figure 4.2: FUTURE YEAR TURNING VOLUMES




4.4 TURN WARRANTS ASSESSMENT

The proposed Greenbank Road access included in the previous sub-division layout is supported by a full-length 100m long Auxiliary Left-turn (AUL) treatment and 150m Channelised Right-turn Lane (CHR). However, given that the revised layout seeks to significantly reduce development traffic, it is our view that these turn treatments would be excessive to support the revised proposal.

Future traffic volumes at the Greenbank Road access, under the revised sub-division design, are summarised in Figures 4.1 and 4.2. Application of the Normal Design Domain (NDD) warrants included in Austroads Guide to Traffic Management Part 6: Intersections, Interchanges and

Crossings, suggests that an AUL and CHR would still be warranted under the revised proposal, despite the significant decrease in traffic generation, as shown in Figure 4.3. However, the revised proposal is at the lower end of the threshold to trigger these treatments, which suggests that the requirement for these higher order treatments is mainly driven by the high through volumes on Greenbank Road.

Figure 4.3: NDD TURN WARRANTS ASSESSMENT – FUTURE YEAR



Section C9.2 of the Austroads Guide to Traffic Management Part 6: Intersections, Interchanges and Crossings deals with the application of warrants for turn lanes. With respect to the use of these warrants, Austroads states that they are based on the construction of new intersections on new roads (ie greenfield sites) and:

“although not intended for direct application to accesses and driveways, they may be used as a reference for such”


This confirms that the warrants are a guide only and are primarily for the construction of intersections on new roads. Austroads does not mandate the application of the warrants for turn lanes with respect to the site access driveways. This guidance is accepted by the TMR Road Planning and Design Manual 2nd Edition (RPDM).

Given the significant reduction in development traffic proposed under the revised sub-division, we have revised the turn warrants assessment at the proposed Greenbank Road access, in accordance with Extended Design Domain (EDD) warrants included in Austroads Guide To Road Design Part 6. The EDD warrants have been applied because:

- the warrants are not strictly required at property accesses
- the subject site will ultimately be accessed via future local road connections through adjacent sites to the east and south, as outlined in the submitted traffic report
- Greenbank Road is expected to be upgraded in the future to cater for the PDA, as outlined in the submitted traffic report

The results of the EDD turn warrants assessment for the 2037 post-development weekday morning and evening peak hour scenarios is shown in Figure 4.4. A short auxiliary left-turn treatment (AUL(s)) and short channelised right-turn treatment (CHR(s)) is warranted.

Figure 4.4: NDD TURN WARRANTS ASSESSMENT – FUTURE YEAR



A functional layout of the Greenbank Road access is shown in Figure 3.2 and included in Appendix B and includes a 50m AUL(s) and 80m CHR(s) designed in accordance with Austroads Guide to Road Design Part 4A: Unsignalised and Signalised Intersections.

4.5 TRAFFIC IMPACT

In terms of additional traffic, the proposal could generate up to 92 two-way vehicle trips. Greenbank Road is currently classified as a Rural Collector. However, as sites within the Greater Flagstone PDA are development, it is expected the Greenbank Road would operate similar to a Trunk Connector (ie given they carry relatively high through traffic volumes).

Excluding traffic generated by the subject development, Greenbank Road is expected to carry in the order of 9,830 vehicles per day in 2027 and 11,740 vehicles per day in 2037. Post development daily traffic volumes on Greenbank Road are expected to be in the order of 10,750 vehicles and 12,660 vehicles during 2027 and 2037, respectively. According to EDQ's Street and Movement Network Guidelines, a two-lane Trunk Connector has a carrying capacity of up to 18,000vpd. Accordingly, it is expected that the adjacent section of Greenbank Road would have sufficient spare carrying capacity to cater for the proposed development. Therefore, additional traffic analyses are not considered necessary.

5.0 CONCLUSIONS AND RECOMMENDATIONS

5.1 CONCLUSIONS

The proposed development at 702-742 Greenbank Road, North Maclean has been evaluated in terms of the site access arrangements, parking provision and design, servicing arrangements, pedestrian / cyclist facilities and likely traffic impact. The main points to note are:


- the development application seeks approval for a one into two lot sub-division
- separate MCU applications would be lodged over Lot 1 to establish future warehouse / low impact industry uses
- the site would be temporarily accessed via an all-movements access on Greenbank Road, with the ultimate access arrangement including a future access on the eastern side of the site
- ultimate flood-free access would be provided via future road connections to the east and south of the subject site and future alternative access driveway on the eastern side of the site
- a 50m AUL(s) and 80m CHR(s) treatment would be provided at the Greenbank Road all-movements access to cater for the increase in entry turn movements, as shown in Figure 3.2
- sufficient sight distance would be achieved at the Greenbank Road access, in accordance with Austroads
- the proposal seeks to revise EDQ's indicative future road network and the proposed sub-division would not hinder the ability to implement a cohesive and functional future road network surrounding the site
- the proposal could generate up to 92 two-way vehicle movements during the weekday morning and evening peak hours
- the recommended turn treatments at the temporary site access have reduced from an AUL/CHR to a AUL(s)/CHR(s)
- the adjacent section of Greenbank Road is expected to have sufficient spare capacity to cater this additional traffic

5.2 RECOMMENDATIONS

Based on our review, it is recommended that:

- all site accesses are designed in accordance with IPWEA Standard Drawing RS-102 and cater for B-double access and egress
- that future development over Lot 1 provides sufficient parking in accordance with Division 5 Parking and Servicing Code of the Beaudesert Shire Planning Scheme 2007

APPENDIX A: PROPOSED SUB-DIVISION PLAN



Legend

Subject site (lot 3 on RP209351)

Proposed lots

Lot 1

Lot 2

Areas

Developable Area

Laydown Area

Development free buffer covenant area

Road corridor

Future road corridor within proposed lot 1

Future road corridor within adjoining lots

Proposed driveway access

Logan Flood Study

1% AEP

Cadastral boundary

REFERENCES

Cadastrre - (c) The State of Queensland (DNRM DCDB)

Coordinate System: GDA2020 MGA Zone 56

Images are not orthorectified, overlays are best fit. Features are based on topographical data and may vary.

Logan Flood Study georeference from Logan Flood Portal as at 24 April, 2025 (indicative only).

Nearmap imagery 11 April 2023.

Indicative only.

Date: 5/06/2025

N

1:2,500

02550100

M


TITLE

Reconfiguration Plan

PROJECT



702-742 Greenbank Road,
North Maclean

PROPOSED LOT 1
Covenant area - 0.41 ha
Proposed developable area - 2.28 ha
Proposed laydown area - 2.51 ha
Proposed driveway - 0.73 ha
Stage 2 future road corridor - 0.44 ha
Proposed Lot 1 total area - 6.37 ha



REEL PLANNING
Urban & Rural Strategies


APPENDIX B: GREENBANK SITE ACCESS DRAWINGS



B	REDUCED SCALE OF DEVELOPMENT	CG	09/07/25
A	INITIAL PLANS FOR DA	CG	21/12/23
REV.	AMENDMENTS	DRN	DATE

PROJECT TITLE:	702-742 GREENBANK ROAD, NORTH MACLEAN
DRAWING TITLE:	LOT 1 ACCESS FUNCTIONAL LAYOUT

CLIENT:					GREATWALL PROPERTY GROUP												
DATE:		09/07/2025		SCALE:		AS SPECIFIED		DRAWN:		CG		APPROVED:		JPG			
DRAWING NO.				24-209-001				REV		B		JOB NO.				24-209	






PTT
TRAFFIC & TRANSPORT ENGINEERING

ABN 96 067 593 962
P 07 3839 6771 WWW.PTT.COM.AU
Level 2, 62 Astor Tce, Spring Hill QLD 4000


B	REDUCED SCALE OF DEVELOPMENT	CG	09/07/25
A	INITIAL PLANS FOR DA	CG	21/12/23
REV.	AMENDMENTS	DRN	DATE



B-DOUBLE 25M			
	metres		
Traction Width	: 2.50	Look to Lock Time	: 6.0
Traction Width	: 2.50	Steering Angle	: 20.7
Traction Width	: 2.50	Articulating Angle	: 70.0
Traction Width	: 2.50		



SCALE 1:750




SCALE 1:500


B	REDUCED SCALE OF DEVELOPMENT	CG	09/07/25		
A	INITIAL PLANS FOR DA	CG	21/12/23		
REV.	AMENDMENTS	DRN	DATE		


PROJECT TITLE:	702-742 GREENBANK ROAD, NORTH MACLEAN
DRAWING TITLE:	B-DOUBLE ACCESS/EGRESS

CLIENT:					GREAT WALL PROPERTY GROUP		
DATE:		SCALE:		DRAWN:		APPROVED:	
09/07/2025		1:500@A3		CG		JPG	
DRAWING NO.		REV		JOB NO.			
24-209-003		B		24-209			


APPENDIX C: TURNING MOVEMENT FORECASTS










Client		GreatWall Property Group	Project) Greenbank Road, North Maclean Revis
Date	10/07/2025	Figure	Figure 3	Job No. 26-011
2027 Pre-Development Morning Peak Hour				






PTT
ABN 96 067 593 962
P 07 3839 6771 WWW.PTT.COM.AU
Level 2, 62 Astor Tce, Spring Hill QLD 4000

Client		GreatWall Property Group	Project) Greenbank Road, North Maclean Revis
Date	10/07/2025	Figure	Figure 5	Job No. 26-011
2037 Pre-Development Morning Peak Hour				




PTT
ABN 96 067 593 962
P 07 3839 6771 WWW.**PTT**.COM.AU
Level 2, 62 Astor Tce, Spring Hill QLD 4000

Client		GreatWall Property Group	Project	Greenbank Road, North Maclean Revis
Date	10/07/2025	Figure	Figure 6	Job No. 26-011
2037 Pre-Development Evening Peak Hour				




PTT
ABN 96 067 593 962
P 07 3839 6771 WWW.PTT.COM.AU
Level 2, 62 Astor Tce, Spring Hill QLD 4000


Client		GreatWall Property Group		Project) Greenbank Road, North Maclean Revis					
Date		10/07/2025		Figure		Figure 7		Job No.		26-011	
Development Traffic Distribution - Morning Peak Hour											




Client		GreatWall Property Group		Project) Greenbank Road, North Maclean Revis					
Date		10/07/2025		Figure		Figure 8		Job No.		26-011	
Development Traffic Distribution - Evening Peak Hour											



Client		GreatWall Property Group		Project		3 Greenbank Road, North Maclean Revis					
Date		10/07/2025		Figure		Figure 9		Job No.		26-011	
Development Traffic Generation - Morning Peak Hour											





Client		GreatWall Property Group	Project) Greenbank Road, North Maclean Revis	
Date	10/07/2025	Figure	Figure 11	Job No.	26-011
2027 Post-Development Morning Peak Hour					

