

PLANS AND DOCUMENTS  
referred to in the PDA  
DEVELOPMENT APPROVAL

Approval no: DEV2025/1674

Date: 15 September 2025



# Engineering and Stormwater Report

Retire Australia - Parkside Yeronga  
70 Park Road, Yeronga



Stantec Australia Pty Ltd

Prepared for:  
Retire Australia

Prepared by:  
Jun Tan & Katherine Leggett

Date:  
24 July 2025

Project/File:  
301051102

## Revision Schedule

Revision No.	Date	Description	Prepared by	Independent Reviewer	Approved by
A	15/07/2025	Draft Engineering and Stormwater Report	JTAN & KJL	JFB	KJL
B	22/07/2025	Engineering and Stormwater Report	KJL	JFB	KJL
C	24/07/2025	Updated Architectural Drawings	KJL	JFB	KJL

Checked and approved by RPEQ

Name: Katherine Leggett (RPEQ 27100)

Signature: 

## Disclaimer

The conclusions in the report are Stantec's professional opinion, as of the time of the report, and concerning the scope described in the report. The opinions in the document are based on conditions and information existing at the time the document was published and do not take into account any subsequent changes. The report relates solely to the specific project for which Stantec was retained and the stated purpose for which the report was prepared. The report is not to be used or relied on for any variation or extension of the project, or for any other project or purpose, and any unauthorized use or reliance is at the recipient's own risk.

Stantec has assumed all information received from the client and third parties in the preparation of the report to be correct. While Stantec has exercised a customary level of judgment or due diligence in the use of such information, Stantec assumes no responsibility for the consequences of any error or omission contained therein.

This report is intended solely for use by the client in accordance with Stantec's contract with the client. While the report may be provided to applicable authorities having jurisdiction and others for whom the client is responsible, Stantec does not warrant the services to any third party. The report may not be relied upon by any other party without the express written consent of Stantec, which may be withheld at Stantec's discretion.



## Table of Contents

<b>1</b>	<b>Introduction .....</b>	<b>3</b>
1.1	Application History .....	1
<b>2</b>	<b>General Site Characteristics .....</b>	<b>2</b>
2.1	Property Details.....	2
2.2	Existing Site Conditions .....	2
2.3	Topography .....	3
2.4	Vegetation .....	3
2.5	Bulk Earthworks .....	4
<b>3</b>	<b>Site Access .....</b>	<b>5</b>
3.1	Site Vehicular Access .....	5
3.2	Pedestrian Access .....	5
3.3	On Street Loading Bay.....	5
<b>4</b>	<b>Flooding and Overland Flow Impacts .....</b>	<b>6</b>
4.1	Known Existing Flooding and Strategy .....	6
4.2	External Catchments .....	6
<b>5</b>	<b>Environmental Considerations .....</b>	<b>7</b>
5.1	Acid Sulfate Soils .....	7
5.2	Erosion and Sediment Control .....	7
<b>6</b>	<b>Stormwater Management .....</b>	<b>8</b>
6.1	Requirements.....	8
6.2	Stormwater Quantity .....	8
6.2.1	Existing Stormwater Regime and Lawful Point of Discharge.....	8
6.2.2	Stormwater Detention and Discharge .....	8
6.3	Stormwater Quality.....	9
6.3.1	Stormwater Management Strategy – Operational Phase .....	9
6.3.2	Maintenance Tasks and Responsibilities .....	9
<b>7</b>	<b>Water Infrastructure .....</b>	<b>10</b>
<b>8</b>	<b>Sewerage Infrastructure .....</b>	<b>11</b>
<b>9</b>	<b>Electrical and Communications Infrastructure .....</b>	<b>12</b>
<b>10</b>	<b>Gas Network Infrastructure .....</b>	<b>13</b>
<b>11</b>	<b>Conclusions and Suggestions .....</b>	<b>14</b>

### List of Tables

Table 1: Stormwater Quality and Quantity Targets

Table 2 - Summary of SQID Maintenance Responsibility

### List of Figures

Figure 1 - Site Location Aerial (Source: Nearmap, Dated 8 May 2025 )

Figure 2 - Contour & Detail Survey (Source: survey by Therefor Group, dated 27 June 2025)

Figure 3 - Flood Mapping (Source: Brisbane City Council Flood Awareness Mapping)

Figure 4 - ASS Mapping (Source: Brisbane City Council Interactive Mapping)

Figure 5 – Water Infrastructure Mapping (Source: Urban Utilities infrastructure interactive GIS mapping)

Figure 6 - Sewer Infrastructure Mapping (Source: Urban Utilities infrastructure interactive GIS mapping)

Figure 7 - Existing Energex Infrastructure (BYDA)

Figure 8 - Existing Gas Infrastructure (BYDA)



# **Engineering and Stormwater Report**

## **1 Introduction**

### **List of Appendices**

**Appendix A – Feature Survey and Sub-Surface Utility Information**

**Appendix B – BCC Floodwise Property Report**

**Appendix C – Erosion Hazard Assessment Form**

**Appendix D – Proposed Engineering Development Plans**

**Appendix E – Proposed Architectural Plans**

**Appendix F – Parkside Yeronga subdivision documentation**

**Appendix G – Before You Dig Records**

**Appendix H – Geotech Report**





# 1 Introduction

This Engineering and Stormwater Report has been prepared for Retire Australia for the purposes of outlining the existing engineering constraints pertinent to the proposed Retirement Facility and Care Co-located Uses development over land currently described as 70 Park Road, Yeronga. The real property description of this lot is Lot 1 on SP328496.

It is further noted that Lot 1 SP328496 will be subject to a realignment of lots, such that a Volumetric Lot is created over the Pedestrian Accessway being provided to support DDA access connectivity from Villa Street to Currawong Crescent. For clarity, the wider Retirement Facility development will be located on *Lot 101*, and the Volumetric Lot containing the Accessway will be located on *Lot 102*.

This report outlines the provision of Civil infrastructure services, stormwater management, the bulk earthworks strategy proposed for the development site and demonstrates the principles which will be adopted in regard to the proposed development application. This Engineering and Stormwater Report specifically addresses the site's existing and proposed characteristics in a preliminary format, with reference to the following:

- Site topography and vegetation;
- Bulk Earthworks;
- Roadways and site access;
- Flooding and overland flow;
- Environmental considerations;
- Stormwater infrastructure and management;
- Water infrastructure;
- Sewerage infrastructure;
- Electrical infrastructure;
- Communications infrastructure; and
- Gas network infrastructure.



The existing services information, existing site characteristics and environmental considerations have been retrieved from, and informed by, a variety of resources, as outlined below.

- Yeronga Priority Development Area Development Scheme (dated August 2019);
- Economic Development Queensland PDA Guideline No. 13 for Engineering standards (dated September 2017);
- Economic Development Queensland PDA Guideline No. 15 for Protection from flood and storm tide inundation (dated May 2015);
- Preliminary Approval documentation for Parkside Yeronga PDA, and subsequent updates:
  - » Parkside Yeronga Site Based Stormwater Management Plan, prepared by Stantec (reference 301048272-RE-02\_C, dated 14/02/2022);
  - » Updated engineering plans, dated 25/02/2022;
- Feature survey information, provided by Therefor Group (dated 27<sup>th</sup> June, 2025);
- Preliminary tree advice contained within the draft AIA provided by Consult Arborist (dated 25<sup>th</sup> June 2025);
- Site Geotechnical Investigation, provided by Douglas Partners (dated February 2022)
- Brisbane City Council Planning Scheme and associated interactive mapping showing zones and overlays;
- Brisbane City Council Floodwise Property Report;
- Before you Dig Australia information.

## 1.1 Application History

The proposed development is to be assessed against the Yeronga Priority Development Area Development Scheme August 2019, unless amended by the Preliminary Approval Framework under Economic Development Queensland (EDQ) Development Application Ref: DEV2021/1221. The Preliminary Approval Framework (DEV2021/1221) was originally approved by EDQ with conditions on 3<sup>rd</sup> May 2022, with a subsequent Minor Change request approved on 6<sup>th</sup> December 2023.

A Services Advice Notice application to Urban Utilities was lodged on 12<sup>th</sup> June 2025 (ref: 25-SAN-81975), for UU to verify that there is suitable capacity within the water and sewer network to service the site (different demand assumptions were used within the PDA Masterplan, when Lot 1 was originally contemplated for commercial purposes). The SAN application is with Urban Utilities for assessment at the time of writing this report.



## 2 General Site Characteristics

### 2.1 Property Details

Address: 70 Park Road, Yeronga, QLD, 4104

Real Property Description: Lot 1 on SP328496

Total Site Area: 2,273m<sup>2</sup> (0.2273ha)

As seen in Figure 1 below, the proposed development site is bound by Currawong Crescent to the North, the Yeronga Community Centre on Lot 11 SP328496 to the East, Villa Street to the South, and Park Road to the West.

The development site is currently vacant with trees to the Southern and Western boundaries, and grass cover spreading over the site. There is a temporary stockpile of material located on the lot, which was sourced from other lots within the wider Yeronga PDA subdivision. At the time of writing this report, the stockpile was being removed from the site.

Refer to Appendices D and E for the proposed engineering development and Architectural layouts.



Figure 1 - Site Location Aerial (Source: Nearmap, Dated 8 May 2025 )

### 2.2 Existing Site Conditions

The proposed site originally formed part of the Yeronga TAFE site until it closed in 2010. All former TAFE buildings and driveways were cleared by late-2019, leaving the parent lot as vacant land. The site



has since been developed to establish the Yeronga PDA subdivision, with this report being prepared to support the subsequent development of one of those created lots.

## 2.3 Topography

According to survey completed by Therefor Group in June 2025, the change in topography across the site ranges from circa 22.25m AHD on the Villa Street interface to 18m AHD at Currawong Crescent, with the site generally falling from the Southern boundary, towards to the North. There is an existing retaining wall located along the Southern and Western boundaries, which flattens the existing lot surface levels.

The site currently has a temporary stockpile of material located on the lot, which was sourced from other lots within the wider Yeronga PDA subdivision. At the time of writing this report, the stockpile was being removed from the site to enable the future construction of this development.

Refer to Appendix A for the Survey.




Figure 2 - Contour & Detail Survey (Source: survey by Therefor Group, dated 27 June 2025)

## 2.4 Vegetation

An Arboricultural Impact Assessment (AIA) has been completed by Consult Arborist. The report has identified that there are trees to the North-Western corner of the site boundary to be retained and will include the requirements for exclusion and no-go zones, to ensure the existing trees remain protected during the development of the Retirement Facility. Refer to the separately submitted AIA for commentary on the existing vegetation management requirements.





## **2.5 Bulk Earthworks**

The proposed development will require earthworks of varying degrees to facilitate construction, ranging from trimming and surface grading and service trenching, through to bulk earthworks for basement excavation. The proposed development works (and thus the earthworks) are contained within the site, with the exception of some small sections of the surrounding verge areas to be regraded, to ensure compliant verge grades are achieved at the development interfaces.

Given the project is only at the Development Approval Stage, full detailed design and documentation of the basement retention system has not been completed. We can, however, provide some preliminary information to help EDQ with the assessment of this application. A site-specific, detailed Geotechnical report for the proposed Retirement Facility will be completed to inform the detailed design phase, so the below advice has been informed by a geotechnical report prepared for the wider Yeronga PDA subdivision development works. This report was completed by Douglas Partners (dated 7th February 2022), and is deemed to be suitable for use to inform this Development Approval phase of the project. Refer to Appendix H for the Geotech report prepared for the wider Yeronga PDA subdivision development works.

Based on the above-mentioned Geotechnical report, it is anticipated that the retention system would comprise of two potential options:

1. If ground water is not encountered on site, 600dia soldier piles at a maximum 1.2m spacings, with 200mm thick shotcrete walls can be installed. Temporary ground anchors are to be installed if required.
2. If groundwater is encountered on site, a secant pile system consisting of 600dia piles will be required.

The above options would be designed in conjunction with advice from a Geotechnical Engineer, AS4678 (Earth Retaining Structures), AS3600 (Concrete Structures Code), AS3798 (Guidelines on Earthworks for Commercial and Residential Developments), and any other applicable codes as determined during the detailed design phase.

The Earthworks Shading Plan contained within in Appendix D provides indicative bulk earthworks requirements for the proposed development, and shows the conceptual earthworks levels and extent of cut and fill volumes indicatively required to undertake the works (generally in relation to the basement structures).

Note, given the preliminary nature of the earthworks design, the shading plan does not provide complete guidance on areas where only surface trimming and grading will occur to help facilitate stormwater management, surface grading and equitable access requirements. We note that the bulk earthworks plan does show indicative surface levels that will likely be established to the Northern, Southern and Western verges to ensure the adjoining verge areas fall towards the adjoining roadways. All of these elements, and design for the DDA Accessway, will be further refined in conjunction with the Structural, Landscape and Architectural Consultant teams, as the design develops.



## 3 Site Access

### 3.1 Site Vehicular Access

The Retirement Facility site will have street frontage to Currawong Crescent along the Northern site boundary, Villa Street along the Southern site boundary and via Park Road to the Western site boundary.

Fronting the site, Currawong Crescent has an approximate sealed pavement width of min 5.2m, Villa Street has an approximate sealed pavement width of 11.3m, and Park Road has an approximate sealed pavement width of 9.9m. The site side verge fronting Currawong Crescent varies along the full site boundary, while Villa Street has a verge width of approximately 6m, and Park Road has a verge width of approximately 7.2m.

An 8m wide crossover was constructed as part of the wider Yeronga PDA subdivision, from Currawong Crescent. The existing access from Currawong Crescent will be retained and used as the site construction vehicle access / egress point. Reconstruction of this crossover access will be required, given it will be used to provide construction access to the lot in the interim, and the resultant condition of the crossover is not considered to reflect the new build aesthetic of the development.

### 3.2 Pedestrian Access

The Currawong Crescent site frontage has a 1.8m wide concrete footpath constructed along part of the site boundary, which connects the Park Road footpath to the existing 8m wide site crossover. There are existing concrete footpaths along the full site frontages to Park Road and Villa Street, of width 1.8m.

The footpath connection within the Currawong Crescent verge will be continued further East as part of the development, to connect Lot 1 to the remainder of the wider PDA subdivision footpath network.

Internal to the site, a DDA compliant pedestrian Accessway will be constructed to provide suitable pedestrian connectivity between Villa Street and Currawong Crescent. Refer to the Landscape Consultant's DA documentation for the proposed Accessway details. The wider Retirement Facility development will be located on Lot 101, and a Volumetric Lot will be created as part of the development to contain the Accessway, which will be located on Lot 102.

### 3.3 On Street Loading Bay

A loading bay was constructed on Currawong Crescent as part of the wider Yeronga PDA subdivision, which fronts the proposed development site to the North-West.

It is proposed to use this loading bay to suit the various loading requirements of the development. If required by EDQ of Brisbane City Council, the existing bay can be conditioned to be widened and amended to suit the vehicular swept paths. The civil drawings captured within Appendix D reflect the potential works to upgrade the existing loading bay, if required by EDQ or Brisbane City Council.

Further information on the site access arrangements and loading bay swept paths can be found within the submitted DA Traffic Report.



## 4 Flooding and Overland Flow Impacts

### 4.1 Known Existing Flooding and Strategy

BCC Interactive Mapping, Flood Awareness Interactive Mapping and the Floodwise Property Reports identify that the site is not impacted by Brisbane River flooding, creek/waterway flooding and overland flow overlays.

Refer to Appendix B for the BCC Floodwise Property Report.



Figure 3 - Flood Mapping (Source: Brisbane City Council Flood Awareness Mapping)

### 4.2 External Catchments

The surrounding area has been investigated to determine the likely impact of existing external stormwater catchments on the proposed development site. By examining contours of the surrounding area, it has been established that the site is not affected by external catchments.



## 5 Environmental Considerations

## 5.1 Acid Sulfate Soils

Acid sulfate soils are typically encountered in Holocene sediment and below 5mAHD. The lowest existing surface level of the site is approximately RL18mAHD at the Northern site boundary, with proposed excavations for the basement extending down to circa RL12.25mAHD. The site is subject to the Brisbane City Council acid sulfate soil overlay for land above 5mAHD to 20mAHD for potential acid sulfate soils (PASS) and actual acid sulfate soils (AASS). No bulk earthworks or pipe trenching works are expected to be undertaken below the 5mAHD contour.

The Parkside Yeronga SBSMP (Refer Appendix F) provided for the PDA Preliminary Approval indicates that acid sulfate soils testing was completed on site, with acidic soils encountered. The acidic soils were not considered to be acid sulfate soils, and as such, no Acid Sulfate Soils Management Plan is proposed.




Figure 4 - ASS Mapping (Source: Brisbane City Council Interactive Mapping)

## 5.2 Erosion and Sediment Control

An Erosion Hazard Assessment has been completed for the proposed development and is attached in Appendix C.

The site was assessed to be a medium Erosion and Sediment Control risk. The medium risk was triggered by land disturbance area greater than 1000m2.

Soil testing has not yet been undertaken for the development to determine the Emersion Class of the soil. As such, this testing will be completed during the detailed geotechnical investigation phase to inform the proposed erosion and sediment control methodology.

A Conceptual Erosion and Sediment Control (ESC) Management Plan will be required at the time of construction to demonstrate that the proposed development can accommodate the necessary devices to mitigate the sediment and erosion risks associated with the construction phase of the development. The plan will be prepared with reference to the International Erosion Control Association (IECA) Best Practice Erosion and Sediment Control. Prior to works commencement on-site, the ESC Plans will be reviewed, amended, and endorsed by a Certified Professional in Erosion and Sediment Control (CPESC).





## 6 Stormwater Management

### 6.1 Requirements

There is a requirement that stormwater strategies prepared for development purposes provide for the achievement of best practice water quality performance objectives. This requires the use of stormwater treatment measures that improve the quality and reduce the flow of water discharged to waterways. Pollution reduction targets, as detailed in the State Planning Policy (July 2017) are outlined in Table 1 below.

The table also outlines the proposed stormwater quantity design level of serviceability that will be provided within the stormwater drainage system as per guidance within the BCC City Plan, the relevant Australian Standard (AS3500.3), and the Queensland Urban Drainage Manual (2016).

Table 1: Stormwater Quality and Quantity Targets

Pollutant	Pollution Reduction Target
Total Suspended Solids (TSS)	80%
Total Phosphorous (TP)	60%
Total Nitrogen (TN)	45%
Total Gross Pollutants >5mm (GP)	90%
Quantity Design Storm	AEP
Minor Design storm	10% AEP
Major Design storm	1% AEP
Stormwater Detention	Not Required

### 6.2 Stormwater Quantity

#### 6.2.1 Existing Stormwater Regime and Lawful Point of Discharge

It is a requirement that every development must have a lawful point of stormwater discharge. A lawful point of discharge to service the proposed Retirement Facility site has been constructed as part of the wider Yeronga PDA subdivision works and is located to the North-Eastern corner of the proposed development site. The wider Yeronga PDA subdivision ultimately discharges to the North.

The private internal stormwater lines will need to be designed and connected to the lawful point of discharge for the development, as part of future design phases.

#### 6.2.2 Stormwater Detention and Discharge

A Parkside Yeronga PDA SBSMP was prepared by Stantec for the purpose of supporting the Preliminary Approval application for the Yeronga PDA. As discussed in the Parkside Yeronga PDA SBSMP, the percent impervious area in the post development phase (being a fully developed PDA area) is not greater than the pre-development condition, being the Yeronga TAFE.

Given that the indicative masterplan indicates that the percent impervious area has not increased from the existing Yeronga TAFE conditions, which also correlates to the percent impervious area proposed by the Retirement Facility, the stormwater flow at the PDA outlet point will be non-worsening from pre-development conditions. As such, no stormwater detention mitigation is proposed at a site development level or within the wider PDA.

Refer to Appendix F for the Parkside Yeronga PDA subdivision documentation.



## 6.3 Stormwater Quality

### 6.3.1 Stormwater Management Strategy – Operational Phase

It is a requirement that the proposed development manages stormwater in such a way that in the long term, the development achieves industry standard Water Quality Objectives, thus reducing the impact the development has on receiving waters.

The Parkside Yeronga PDA SBSMP was prepared by Stantec for the purpose of supporting the Preliminary Approval application for the Yeronga PDA. As discussed in the Yeronga PDA SBSMP, a subdivision wide bioretention basin is proposed to treat runoff from the proposed lots and roads. Given that the subdivision wide bioretention basin caters for the treatment of stormwater runoff from proposed Lot 1, no on-site treatment measures are proposed.

Additional best practice Water Sensitive Urban Design elements may be utilised within the landscaping areas, and these will be investigated during the natural progression of detailed design phases for the Retirement Facility. These will be captured within the landscaping documentation.

### 6.3.2 Maintenance Tasks and Responsibilities

To ensure that the proposed stormwater quality treatment train maintains its treatment effectiveness, maintenance is imperative to be undertaken, including monitoring and rectification as required. The maintenance requirements are included in Table 2. This maintenance regime will be the responsibility of the local Council.

*Table 2 - Summary of SQID Maintenance Responsibility*

Stormwater Quality Improvement Devices	Ongoing Maintenance Responsibility
Subdivision Bioretention System	<p>Council are the owner of the bioretention basin constructed as part of the wider Yeronga PDA subdivision.</p> <p>It is the contractor's responsibility during construction of the proposed Retirement Facility to ensure that sediment does not enter into the drainage network constructed under the PDA subdivision. If sediment does end up in the bioretention basin as a result of the Retirement Facility construction works, the contractor is to appropriately reinstate the bioretention basin.</p>



## 7 Water Infrastructure

The proposed development is within the Urban Utilities service connection area.

As part of the wider Yeronga PDA subdivision works, water reticulation mains were constructed to service the subdivision and ultimately the proposed Retirement Facility lot. The water main constructed as part of the subdivision works is located in the Southern verge of Currawong Crescent, which fronts the development site.

The connection point to service Lot 1 will be via the DN180 PE water main located in the Southern verge of Currawong Crescent, with the new water connection to be metered in accordance with current Urban Utilities standards and via a direct application to Urban Utilities. A separate water connection could be provided to the proposed Volumetric Lot, if required.

A Services Advice Notice (ref: 25-SAN-81975) application was lodged with Urban Utilities on 12th June 2025 to verify if there is suitable capacity within the existing water network to service the proposed Retirement Facility development, as there were different demand assumptions used within the wider Yeronga PDA Masterplan design, when Lot 1 was originally contemplated for commercial purposes. The SAN application is with Urban Utilities for assessment at the time of writing this report.

The SAN will also confirm whether separate water connections and meters are to be established to service proposed Lot 101 and Volumetric Lot 102.

The size of the proposed water property connection for the domestic and fire servicing is to be confirmed by the Hydraulic Consultant in future detailed design phases.

Refer to the Proposed Development Plans in Appendix D for the proposed water network and connection location.




Figure 5 – Water Infrastructure Mapping (Source: Urban Utilities infrastructure interactive GIS mapping)



## 8 Sewerage Infrastructure

The proposed development is within the Urban Utilities service connection area.

As part of the wider Yeronga PDA subdivision works, sewer reticulation mains were constructed to service the subdivision and ultimately the proposed Retirement Facility lot. The sewer mains constructed as part of the subdivision works are located in the Eastern verge of Currawong Crescent, to the North-Eastern corner of the development site.

A DN160 sewer property connection to the existing sewer infrastructure was provided as part of the subdivision works, and is located in the North-Eastern corner of the site. Connection to the infrastructure is to be in accordance with Urban Utilities standards and via a direct application to Urban Utilities. Confirmation of constructed sewer property connection position and levels is required to ensure the required site serviceability is achieved via the gravity sewer network in accordance with the SEQCode.

A Services Advice Notice (ref: 25-SAN-81975) application was lodged with Urban Utilities on 12<sup>th</sup> June 2025 to verify if there is suitable capacity within the existing sewer network to service the proposed Retirement Facility development, as there were different demand assumptions used within the wider Yeronga PDA Masterplan design, when Lot 1 was originally contemplated for commercial purposes. The SAN application is with Urban Utilities for assessment at the time of writing this report.

The SAN will also confirm whether separate sewer connections are to be established to service proposed Lot 101 and Volumetric Lot 102. It is however noted that Lot 102 does not require a sewer connection for site serviceability of the Accessway Lot, but could be provided to the Volumetric Lot if required.

Refer to the Proposed Development Plans in Appendix D for the proposed water network and connection location.




Figure 6 - Sewer Infrastructure Mapping (Source: Urban Utilities infrastructure interactive GIS mapping)



## 9 Electrical and Communications Infrastructure

The local electricity authority is Energex.

Communications networks surrounding the wider PDA area are NBN, Telstra, Pipe networks and Optus, so it is envisioned a communications connection will be supplied by one of these providers.

Electrical and communications infrastructure was delivered as part of the wider Yeronga PDA subdivision, and as such, it is anticipated that the power supply and communications requirements for the Retirement Facility have been taken into consideration in the subdivision design stage. A separate Electrical connection can also be provided to the proposed Volumetric Lot, if required.

A padmount transformer is assumed to be required to service the proposed development, and has been nominated to be in the North-Western corner of the site, fronting Currawong Crescent.

Refer to the Dial Before You Dig information found in Appendix G for details on the existing electrical and telecommunication infrastructure.




Figure 7 - Existing Energex Infrastructure (BYDA)



## 10 Gas Network Infrastructure

There is a DN63 PE existing gas main along the western verge of Park Road next to the development site.

No gas reticulation was required to be installed within the wider Yeronga PDA subdivision development, nor is it perceived that Retire Australia require a gas connection to support the proposed development.




Figure 8 - Existing Gas Infrastructure (BYDA)

## **11 Conclusions and Suggestions**

This Engineering and Stormwater Report has been prepared to support the Development Application for the proposed Retirement Facility at 70 Park Road, Yeronga, which is part of the wider Yeronga PDA subdivision site.

The report has demonstrated a civil infrastructure servicing solution to ensure that all services will be available to the development and construction of the development will not adversely impact adjoining properties.

This report has confirmed that the stormwater water quality objectives for the site will be met by the establishment of the wider PDA bioretention basin proposed to be constructed as part of the subdivision works.

The report has also confirmed that runoff from the proposed development will not create worsening downstream of the site, since the overall PDA wide post development impervious area will not increase the percent impervious area in the predevelopment scenario. As such, no on-site detention mitigation is proposed.

Therefore, we recommend Economic Development Queensland support the Development Application from an engineering perspective.



# Appendices






## **Appendix A – Feature Survey and Sub-Surface Utility Information**







This Detail Survey is a compilation of surveys conducted by Therefor Group Pty Ltd in 2021 & 2025, survey data from 2023/2024 supplied by Stantec on 01-07-2025 and survey data supplied by Marchese Partners on 24-06-2025.  
Quality B information should be verified before use.

- 1. Building Finished Floor Level
- 2. Electrical Light Pole
- 3. Electrical Pillar
- 4. Electrical Pit
- 5. Electrical Pole
- 6. Fence Gate
- 7. Sewer Manhole
- 8. Telecomms Manhole
- 9. Telecomms Pit
- 10. Topo Surface Level
- 11. Traffic Light
- 12. Traffic Pit
- 13. Traffic Sign
- 14. Water Valve
- 15. Water Valve (Supplied) Yeronga PDA
- 16. Water Meter
- 17. Water Meter (Supplied) Yeronga PDA
- 18. Water Fire Hydrant
- 19. Water Fire Hydrant (Supplied) Yeronga PDA
- 20. Veg Tree

	Building Line
	Building Retaining Wall Base
	Building Retaining Wall Top
— E OH	Electrical Overhead
— E (B)	Electrical Located - Quality Level 'B' Surveyed 2021
— E (D)	Electrical Located - Quality Level 'D'
	Electrical Staywire
— F — F — F	Fence Line
	Fence Handrail
— GAS (B)	Gas Located - Quality Level 'B' Surveyed 2021
— GAS (D)	Gas Located - Quality Level 'D'
	Road Crown
	Road Driveway
	Road Kerb Back
	Road Kerb Face
	Road Kerb Invert
	Road Kerb Lip
	Road Line Marking - Dashed
	Road Line Marking - Solid
— S (B)	Sewer Located - Quality Level 'B' Surveyed 2021
	Telecomms Pit (Strung)
— C (B)	Telecomms Located - Quality Level 'B' Surveyed 2021
— C (D)	Telecomms Located - Quality Level 'D'
—	Topo Change of Grade
	Topo Concrete
	Traffic Sign (Strung)
— T (B)	Traffic Located - Quality Level 'B' Surveyed 2021
— T (D)	Traffic Located - Quality Level 'D'
	Veg Garden Edge
— W (B)	Water Located - Quality Level 'B' Surveyed 2021
— W (D)	Water Located - Quality Level 'D'

(1) **MAP GRID OF AUSTRALIA**  
This plan is on GD94, MGA Zone 56 with ground distances.

(2) This plan was prepared by Therefor Group Pty Ltd and surveyed on 15-06-2025, for the purpose and the exclusive use of Retire Australia, to be used for design work. This plan is not to be used without the supplied digital information. This information is not to be used for any other purpose or by any other person or corporation.

(3) The contours and levels shown on this plan are suitable only for the purpose for which this plan was prepared and should not be used for any other purpose. The contour interval shown herein is 0.25 metres.

(4) **Property Boundaries**  
The subject lot boundaries and dimensions shown on this plan have been determined by a Cadastral Survey as defined by the Surveying and Mapping Infrastructure Act 2003 and Surveyors Act 2003, for more details refer to SP328498.

(5) Only visible features of underground services were located. Positions of stormwater mains, sewer mains & water mains that have been plotted are indicative only and as such should not be relied upon for detailed engineering design and construction. Contact relevant authorities before any excavation.

(6) **UNDERGROUND SERVICES**

This plan generally complies with Australian Standard 5488: Classification of Subsurface Utility Information (SUI).

**Definitions**  
**Quality Level A (QL-A):** Meets location accuracy standards for minimum risk when excavating. Features or points on alignments that have been positively identified, measured directly and have a maximum horizontal and vertical tolerance of 50mm or less.

Quality Level B (QL-B): Significant risk reduction. Points on alignments that have been remotely detected. These points have a maximum horizontal tolerance of +/- 300mm and a maximum vertical tolerance of +/- 500mm.

Quality Level C (QL-C): Low accuracy and a high risk of damage. Alignments determined using a combination of existing records and site survey of visible evidence. E.g. surveyed location of pit lids but the actual position of underground connection between pits is still assumed.

Quality Level D (QL-D): Least accurate data and if used on its own has a high risk of damage.  
Includes Alignments that have been scaled or digitized from service provider's records.

Only information with Quality Level A should be relied upon for detailed design. For more information see AS5488.

(7) This plan may not be copied unless this note is included

DISCLAIMER This design and drawing is subject to Copyright and intellectual property laws and may not be reproduced for any purpose without the consent of Theifer Group Pty Ltd. The information contained within this document is confidential and recipients of this document are prohibited from disclosing the information to any person nor be used contrary to the purpose of the issue without the written approval of Theifer Group Pty Ltd. Conceptual plans are not intended to be used for any purpose other than to provide a visual guide, approvals, coordination and information. Cadastral boundaries, areas and dimensions within Concept Plans are approximate only. Figured dimensions shall take preference to scaled dimensions. No reliance should be placed on this plan for any financial dealings of the land.



CLIENT  
Retire Australia

PROJECT  
Lot 101 & 102 Villa Street,  
Park Road & Currawong

PROJECT NO.  
18-0765S

DRAWING NAME

## Contour and Detail Survey

Local Authority: Brisbane City

Description: Lot 1 on SP328496

Level Datum: Supplied


Origin: Supplied

Co-ord System: GDA94 Plane

### REVISION TABLE

REV	DESCRIPTION	DRAWN	APPROVED	DATE
A	Original Issue	JC	TD	27-06-2025
B	Updated & New Survey Data	JC	TD	11-07-2025

DRAWING NO.  
18-0765S/RA-01  
SHEET NO.  
1 of 1  
REVISION  
B





## **Appendix B – BCC Floodwise Property Report**



# FloodWise Property Report

70 PARK RD, YERONGA 4104  
Lot 1 on SP328496



Dedicated to a better Brisbane


## THE PURPOSE OF THIS REPORT IS FOR BUILDING AND DEVELOPMENT

Brisbane City Council's FloodWise Property Report provides technical flood planning information including estimated flood levels, habitable floor level requirements and more. This report uses the adopted flood planning information in Brisbane City Plan 2014, that guides how land in Brisbane is used and developed for the future. Find out more about [planning and building](#). To understand how to be resilient and prepare for floods, visit Council's [Be Prepared](#) web page. Find more information about [how to read a FloodWise Property Report](#).

### This property has no flood levels

Brisbane City Council has not assigned flood level information for this property however it may be affected by one or more flood or property development flags. Please refer to the Flood Planning and Development Information below for details. The property may have 0.2% AEP flood level which will appear on the Flood Planning Information table if applicable. For professional advice or detailed assessment of a property contact a Registered Professional Engineer of Queensland.

Visit the [Be Prepared](#) page to find more information on how to prepare your home or business for potential flooding.

 **Combined** 1% AEP for river, creek and storm tide flood extent (if applicable) from the adopted Brisbane City Plan 2014. Read more about [Brisbane City Plan 2014](#).



## Are you resilient and ready for flood?

- Sign up to the Brisbane Severe Weather Alert at [brisbane.qld.gov.au/beprepared](https://brisbane.qld.gov.au/beprepared)
- Visit [bom.gov.au](https://bom.gov.au) for the latest weather updates.
- Have an evacuation plan, emergency kit and important phone numbers ready.
- Observe where water flows from and to during heavy rain.
- Consider how flood-resilient building techniques will have you home faster and with less damage.

Life threatening emergencies  
**000** Police/fire/ambulance  
(mobiles **000** and **112**)

State Emergency Service (SES) **132 500**  
Energex **13 19 62**  
Brisbane City Council **3403 8888**

### Technical Summary

This section of the FloodWise Property Report contains more detailed flood information for this property so **surveyors, builders, certifiers, architects, and engineers can plan and build** in accordance with Council's planning scheme.

Find more information about [planning and building](#) in Brisbane or talk to a Development Services Planning Information Officer via Council's Contact Centre on (07) 3403 8888.

Flood Planning and Development Information

This section of the FloodWise Property Report contains information about Council's planning scheme overlays. Overlays identify areas within the planning scheme that reflect distinct themes that may include constrained land and/or areas sensitive to the effects of development.

Flood overlay code

The Flood overlay code of Council's planning scheme uses the following information to provide guidelines when developing properties. The table below summarises the flood planning areas (FPAs) that apply to this property. Development guidelines for the FPAs are explained in [Council's planning scheme](#).

Flood planning areas (FPA)		
River	Creek / waterway	Overland flow
		Not Applicable

To find more information about Council's flood planning areas (FPAs) for Brisbane River and Creek/waterway flooding to guide future building and development in flood prone areas, please review [Council's Flood Planning Provisions](#).

Coastal hazard overlay code

The Coastal hazard overlay code of Council's planning scheme uses the following information to provide guidelines when conducting new developments. The table below summarises the coastal hazard categories that apply to this property. Development guidelines for the following Coastal hazard overlay sub-categories are explained in Council's [planning scheme](#).

Coastal hazard overlay sub-categories
There are currently no Coastal hazard overlay sub-categories that apply to this property.

Note: Where land is identified within one for more flood planning areas on the Flood overlay or is identified within one of the Storm tide inundation area sub-categories on the Coastal hazard overlay, the assessment criteria that provides the highest level of protection from any source of flooding applies.

#### Property development flags

**Large allotment** - This property is either a Large Allotment of over 1000 square metres or is located within a Large Allotment. Flood levels may vary significantly across allotments of this size. Further investigations may be warranted in determining the variation in flood levels and the minimum habitable floor level across the site.

For more information or advice, please consult a Registered Professional Engineer of Queensland (RPEQ).

## Useful Flood Information Definitions

**Australian Height Datum (AHD)** - The reference level for defining ground levels in Australia. The level of 0.0m AHD is approximately mean sea level.

**Annual Exceedance Probability (AEP)** - The probability of a flood event of a given size occurring in any one year, usually expressed as a percentage annual chance.

- **0.2% AEP** - A flood event of this size is considered rare but may still occur. A flood of size or larger has a 1 in 500 chance or a 0.2% probability of occurring in any year.
- **1% AEP** - A flood of this size or larger has a 1 in 100 chance or a 1% probability of occurring in any year.
- **2% AEP** - A flood of this size or larger has a 1 in 50 chance or a 2% probability of occurring in any year.
- **5% AEP** - A flood of this size or larger has a 1 in 20 chance or a 5% probability of occurring in any year.
- **20% AEP** - A flood of this size or larger has a 1 in 5 chance or a 20% probability of occurring in any year.

### Data quality

- **Data Quality Code A** - Level data based on recent surveyor report or approved as-constructed drawings.
- **Data Quality Code B** - Level data based on ground-based mobile survey or similar.
- **Data Quality Code C** - Level data derived from Airborne Laser Scanning or LiDAR information.

**Defined Flood Level (DFL)** - The DFL is used for commercial and industrial development. The Defined flood level (DFL) for Brisbane River flooding is a level of 3.7m AHD at the Brisbane City Gauge based on a flow of 6,800 m/s. DFL is only applicable for non-residential uses affected by Brisbane River flooding.

**Flood planning area (FPA)** - Council has developed five Flood planning areas (FPAs) as part of Brisbane City Plan 2014 Flood overlay mapping for Brisbane River, Creek/waterway flooding and Overland flow to guide future building and development in flood prone areas. Storm tide flooding is mapped separately. The FPAs are designed to recognise the flood hazard for different flooding types. Flood hazard is a combination of frequency of flooding, the flood depth, and the speed at which the water is travelling. [Find more information here.](#)

**Maximum and minimum ground level** - Highest and lowest ground levels on the property based on available ground level information. A Registered Surveyor can confirm exact ground levels.

**Minimum habitable floor level (dwelling house)** - The minimum level in metres AHD at which habitable areas of development (generally including bedrooms, living rooms, kitchen, study, family, and rumpus rooms) must be constructed as required by the Brisbane City Plan 2014.

**Indicative existing floor level** - The approximate level in metres AHD of the lowest habitable floor in the existing building (excluding apartments). The data is sourced from a range of sources with varying accuracy levels.

**Property** - A property will contain 1 or more lots. The multiple lot warning is shown if you have selected a property that contains multiple lots.

**Residential flood level (RFL)** - This flood level for the Brisbane River equates to the 1% annual exceedance probability (AEP) flood level.

To learn more, visit [Brisbane City Council's Flood Information Hub](#)



## Brisbane City Council's Online Flood Tools

Council provides several online flood tools:

- to guide planning and development
- to help residents and businesses understand their flood risk and prepare for flooding.

Council's online flood tools for planning and development purposes include:

- **FloodWise Property Report**
- **Flood Overlay Code**

For more information on Council's planning scheme and online flood tools for planning and development:

- phone (07) 3403 8888 and ask to talk to a Development Services Planning Information Officer

- visit [brisbane.qld.gov.au/planning-building](https://brisbane.qld.gov.au/planning-building)

Council's Planning Scheme - The Brisbane City Plan 2014 (planning scheme) has been prepared in accordance with the Sustainable Planning Act as a framework for managing development in a way that advances the purpose of the Act. In seeking to achieve this purpose, the planning scheme sets out the Council's intention for future development in the planning scheme area, over the next 20 years.

### Disclaimer

1. Defined flood levels and residential flood levels, minimum habitable floor levels and indicative existing floor levels are determined from the best available information to Council at the date of issue. These levels, for a particular property, may change if more detailed information becomes available or changes are made in the method of calculating levels.
2. Council makes no warranty or representation regarding the accuracy or completeness of a FloodWise Property Report. Council disdaims any responsibility or liability in relation to the use or reliance by any person on a FloodWise Property Report.



### Planning to build or renovate?

For information, guidelines, tools and resources to help you track, plan or apply for your development visit [brisbane.qld.gov.au/planning-building](https://brisbane.qld.gov.au/planning-building)

You can also find the Brisbane City Plan 2014 and Neighbourhood Plans as well as other information and training videos to help, with your building and development plans.

## **Appendix C – Erosion Hazard Assessment Form**





# Erosion Hazard Assessment - June 2014

Brisbane City Council (BCC), *Erosion Hazard Assessment* form must be read in conjunction with the *Erosion Hazard Assessment- Supporting Technical Notes* (June 2014 or later version) for explanatory terms and Certification information.

## What is an Erosion Hazard Assessment?

Soil erosion and sediment from urban development, particularly during construction activities, is a significant source of sediment pollution in Brisbane's waterways. The Erosion Hazard Assessment determines whether the risk of soil erosion and sediment pollution to the environment is 'low', 'medium' or 'high'.

## When is the EHA required?

An *Erosion Hazard Assessment* form must be completed and lodged with BCC for any Development Application (ie MCU or ROL) that will result in soil disturbance OR Operational Works or Compliance Assessment Application for 'Filling' or Excavation.

**Failure to submit this form during lodgement of an application may result in assessment delays or refusal of the application.**

## Privacy Statement

The personal information collected on this form will be used by Brisbane City Council for the purposes of fulfilling your request and undertaking associated Council functions and services. Your personal information will not be disclosed to any third party without your consent, unless this is required or permitted by law.

## Assessment Details

1 Please turn over and complete the erosion hazard assessment.

2 Based on the erosion hazard assessment overleaf, is the site:

☐ **A 'low' risk site**

*Best practice erosion and sediment control (ESC) must be implemented but no erosion and sediment control plans need to be submitted with the development application. Factsheets outlining best practice ESC can be found at <http://www.waterbydesign.com.au/factsheets>*

☐ **A 'medium' risk site**

*If the development is approved, the applicant will need to engage a Registered Professional Engineer (RPEQ) or Certified Professional in Erosion and Sediment Control (CPESC) to prepare an ESC Program and Plan and supporting documentation — in accordance with the requirements of the Infrastructure Design Planning Scheme Policy.*

☐ **A 'high' risk site**

*If the development is approved, the applicant will need to engage a RPEQ and CPESC to prepare an ESC Program and Plan and supporting documentation — in accordance with the requirements of the Infrastructure Design Planning Scheme Policy. The plans and program will need to be certified by a CPESC.*

## 3 Site Information and Certification

Application number (if known)

N/A

Site address

70 PARK ROAD, YERONGA

Postcode 4104

I certify that:

- ☐ I have made all relevant enquiries and am satisfied no matters of significance have been withheld from the assessment manager.
- ☐ I am a person with suitable qualifications and/or experience in erosion and sediment control.
- ☐ The Erosion Hazard Assessment was completed in accordance with the Erosion Hazard Assessment Supporting Technical Notes and the BCC Infrastructure Design Planning Scheme Policy.
- ☐ The Erosion Hazard Assessment accurately reflects the site's overall risk of soil erosion and sediment pollution to the environment.
- ☐ I acknowledge and accept that the BCC, as assessment manager, relies, in good faith, on this certification as part of its development assessment process and the provision of false or misleading information to the BCC constitutes an offence for which BCC may take punitive steps/ action against me/ enforcement action against me.

Certified by *Print name*

Katherine Leggett

Certifier's signature

*K Leggett*

Date

15 / 07 / 2025

**Table 1: Low Risk Test**

		<b>Yes</b>	<b>No</b>
<b>1.1</b>	is the area of land disturbance > 1000 m <sup>2</sup>	<input type="checkbox"/>	<input type="checkbox"/>
<b>1.2</b>	does any land disturbance occur in a BCC mapped waterway corridor	<input type="checkbox"/>	<input type="checkbox"/>
<b>1.3</b>	is there any slope on site (longer than three metres in length) before, during or after construction that is steeper than 5%	<input type="checkbox"/>	<input type="checkbox"/>
<b>1.4</b>	does any land disturbance occur below 5 m AHD	<input type="checkbox"/>	<input type="checkbox"/>
<b>1.5</b>	does development involve endorsement of a staging plan	<input type="checkbox"/>	<input type="checkbox"/>
<b>1.6</b>	is there an upstream catchment passing through the site > 1 hectare	<input type="checkbox"/>	<input type="checkbox"/>

Have you answered 'yes' to any of the questions in Table 1?

<b>Yes</b>	<b>No</b>
<input type="checkbox"/>	<input type="checkbox"/>

If '**No**' then site is **low risk** with respect to erosion and sediment control

If '**Yes**' then proceed to Table 2

**Table 2: Medium Risk Test**

		<b>Yes</b>	<b>No</b>
<b>2.1</b>	is the area of land disturbance > 1 hectare	<input type="checkbox"/>	<input type="checkbox"/>

If '**No**' then site is **medium risk** with respect to erosion and sediment control

If '**Yes**' then proceed to Table 3

**Table 3: High Risk Test**

<b>3.1</b>	is there an upstream catchment passing through the site > 1 hectare	<input type="checkbox"/>	<input type="checkbox"/>
<b>3.2</b>	does any land disturbance occurs in a BCC mapped waterway corridor	<input type="checkbox"/>	<input type="checkbox"/>
<b>3.3</b>	is there any slope on site (longer than three metres in length) before, during or after construction that is steeper than 15%	<input type="checkbox"/>	<input type="checkbox"/>

Have you answered 'yes' to any of the questions in Table 3?

<b>Yes</b>	<b>No</b>
<input type="checkbox"/>	<input type="checkbox"/>

If '**No**' then site is **medium risk** with respect to erosion and sediment control

If '**Yes**' then site is **high risk** with respect to erosion and sediment control

## **Appendix D – Proposed Engineering Development Plans**







RETIRE AUSTRALIA



LOT 101 PARKSIDE  
YERONGA

CIVIL SERVICES

70 PARK ROAD, YERONGA, QLD 4104

FOR DEVELOPMENT APPROVAL  
2025.07.22

Stantec Project Number: 301051102

THIS CIVIL WORKS DESIGN AND DOCUMENTATION HAS BEEN BASED UPON:  
• MARCHASE PARTNERS ARCHITECTURAL DRAWINGS RECEIVED 11/07/2025.  
• THEREFOR GROUP'S DETAIL SURVEY DATED 27/06/2025.

DRAWING LIST	
NO.	DRAWING NAME
CI-DA-000-GE-P01	COVER SHEET, LOCALITY PLAN & DRAWING INDEX
CI-DA-080-CS-P01	COMBINED SERVICES LAYOUT PLAN
CI-DA-100-EW-P01	BULK EARTHWORKS SHADING PLAN
CI-DA-106-EW-D01	EARTHWORKS SECTIONS (SHEET 1 OF 2)
CI-DA-106-EW-D02	EARTHWORKS SECTIONS (SHEET 2 OF 2)

- GENERAL NOTES
- DRAWINGS ARE CONCEPTUAL ONLY AND HAVE BEEN PREPARED AS AN ILLUSTRATION OF THE CONCEPTS DISCUSSED WITHIN THIS REPORT AND ARE INTENDED FOR DEVELOPMENT APPROVAL PURPOSES ONLY.
  - WHERE LEVELS OR SIZES OF ANY WORKS ARE SHOWN, THESE ARE INDICATIVE ONLY TO DEMONSTRATE THE CAPABILITY OF THE SERVICING OPTION PROPOSED AND ARE SUBJECT TO DETAILED DESIGN (OPERATIONAL WORKS DESIGN). THIS IS TO BE UNDERTAKEN IN ACCORDANCE WITH THE LATEST VERSIONS OF THE AUTHORITY STANDARDS, AUSTRALIAN STANDARDS AND OTHER INDUSTRY REFERENCE DOCUMENTS AT TIME OF DESIGN.
  - DRAWINGS ARE NOT INTENDED TO BE USED FOR TENDER, ESTIMATING OR CONSTRUCTION.

LEGEND

—


EXISTING PROPERTY BOUNDARY

—

PROPOSED PROPERTY BOUNDARY


---

SITE BOUNDARY




SITE LOCALITY PLAN  
Source: Nearmap  
N.T.S






- SERVICES NOTES**
- DRAWINGS ARE CONCEPTUAL ONLY AND HAVE BEEN PREPARED AS AN ILLUSTRATION OF THE CONCEPTS DISCUSSED WITHIN THIS REPORT AND ARE INTENDED FOR DEVELOPMENT APPROVAL PURPOSES ONLY.
  - WHERE LEVELS OR SIZES OF ANY WORKS ARE SHOWN, THESE ARE INDICATIVE ONLY TO DEMONSTRATE THE CAPABILITY OF THE SERVICING OPTION PROPOSED AND ARE SUBJECT TO DETAILED DESIGN (OPERATIONAL WORKS DESIGN). THIS IS TO BE UNDERTAKEN IN ACCORDANCE WITH THE LATEST VERSIONS OF THE AUTHORITY STANDARDS, AUSTRALIAN STANDARDS AND OTHER INDUSTRY REFERENCE DOCUMENTS AT TIME OF DESIGN.
  - DRAWINGS ARE NOT INTENDED TO BE USED FOR TENDER, ESTIMATING OR CONSTRUCTION.
  - ALL LOTS SHALL BE PROVIDED WITH CONNECTION TO SEWER, WATER, ELECTRICITY, TELECOMMUNICATIONS AND A LAWFUL POINT OF STORMWATER DISCHARGE.
  - WHERE EXISTING DWELLINGS ARE BEING RETAINED AS PART OF THE PROPOSAL, THE EXISTING DWELLING IS TO BE RECONNECTED TO ALL SERVICES UPON COMPLETION OF THE WORKS INCLUDING DECOMMISSIONING OF THE EXISTING SEPTIC TANK IF APPLICABLE.

- LEGEND**
- SITE BOUNDARY
  - EXISTING PROPERTY BOUNDARY
  - PROPOSED PROPERTY BOUNDARY
  - EXISTING CONTOURS & LABEL (0.25m INTERVAL)
  - PROPOSED MAJOR CONTOURS & LABEL (0.5m INTERVAL)
  - PROPOSED MINOR CONTOURS & LABEL (0.25m INTERVAL)
  - PROPOSED BASEMENT OUTLINE
  - EXISTING ROAD CENTRE-LINE
  - EXISTING BUILDING OUTLINE
  - EXISTING RETAINING WALL
  - EXISTING KERB & CHANNEL
  - EXISTING CONCRETE (FOOTPATHS, DRIVEWAYS)
  - EXISTING HANDRAIL
  - EXISTING FENCE
  - EXISTING FENCE GATE
  - EXISTING ROAD SIGNAGE
  - EXISTING LIGHT POLE
  - EXISTING TRAFFIC SIGNAL
  - EXISTING TRAFFIC PIT
  - EXISTING FIRE HYDRANT / WATER VALVE / WATER METER
  - EXISTING LINEMARKING
  - EXISTING PEDESTRIAN LINEMARKING
  - EXISTING YELLOW LINEMARKING
  - EXISTING YELLOW LINEMARKING
  - PROPOSED TYPE 'D' MOUNTABLE K&C
  - PROPOSED INVERT KERB
  - PROPOSED NEW CONCRETE FOOTPATH
  - PROPOSED NEW CONCRETE PAVEMENT
  - EXISTING CONCRETE TO BE REMOVED
  - EXISTING COMMS (FROM RECORD) TO BE REMOVED
  - EXISTING COMMS LINE (FROM RECORD) & PIT
  - EXISTING OVERHEAD POWER LINE & POWER POLE
  - EXISTING UNDERGROUND POWER LINE
  - EXISTING SEWER LINE (FROM RECORD) & STRUCTURE
  - EXISTING WATER LINE (FROM RECORD)
  - EXISTING GAS LINE (FROM RECORD)
- (X) DENOTES QUALITY LEVEL OF THE UNDERGROUND UTILITY IN REFERENCE TO ASS488-2019



<p>Notes</p> <p>Authorised <i>K. Leggett</i></p> <p>K LEGGETT RPEQ No. 27100</p> <p>DDJ JT KJL 2025.07.22</p> <p>Dwn. Dsgn. Chkd. YYYY.MM.DD</p>	<p>Issue Status</p> <p><b>FOR APPROVAL</b></p> <p>NOT FOR CONSTRUCTION</p> <p>This document is suitable only for the purpose noted above. Use of this document for any other purpose is not permitted.</p> <p>B DA SET FOR REVIEW BY EDQ URBAN PLANNING</p> <p>A FOR REVIEW</p> <p>Issued/Revision</p> <p>DDJ/JT KJL 2025.07.22</p> <p>DDJ/JT KJL 2025.07.15</p> <p>By Appd YYYY.MM.DD</p>	<p>Colour Disclaimer</p> <p>This drawing has been documented in colour. This drawing is required to be printed in colour. Failure to do so may result in loss of information. Black and white printing may be used if specific black and white documents have been obtained from Stantec.</p> <p>Notes</p>	<p>Client/Project Logo</p> <p><b>Stantec</b></p> <p>Stantec Australia Pty. Ltd.</p> <p>Level 3</p> <p>52 Merivale Street</p> <p>South Brisbane, QLD 4101</p> <p>Tel: +61 7 3029 5000</p> <p>Copyright Reserved</p> <p>The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden. The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.</p>	<p>Client/Project Logo</p> <p><b>retireaustralia</b></p>	<p>Client/Project</p> <p>RETIRE AUSTRALIA</p> <p>PARKSIDE YERONGA</p> <p>70 PARK ROAD, YERONGA</p> <p>File Name:</p> <p>DDJ JT KJL 2025.07.22</p> <p>Dwn. Dsgn. Chkd. YYYY.MM.DD</p>	<p>Title</p> <p>COMBINED SERVICES LAYOUT PLAN</p> <p>Project No. 301051102</p> <p>Scale 1:150 (A1)</p> <p>Revision B</p> <p>Drawing No. CI-DA-080-CS-P01</p>
--	--	--	---	--	--	--





- ### EARTHWORKS NOTES
- DRAWINGS ARE CONCEPTUAL ONLY AND HAVE BEEN PREPARED AS AN ILLUSTRATION OF THE CONCEPTS DISCUSSED WITHIN THIS REPORT AND ARE INTENDED FOR DEVELOPMENT APPROVAL PURPOSES ONLY.
  - WHERE LEVELS OR SIZES OF ANY WORKS ARE SHOWN, THESE ARE INDICATIVE ONLY TO DEMONSTRATE THE CAPABILITY OF THE SERVICING OPTION PROPOSED AND ARE SUBJECT TO DETAILED DESIGN (OPERATIONAL WORKS DESIGN). THIS IS TO BE UNDERTAKEN IN ACCORDANCE WITH THE LATEST VERSIONS OF THE AUTHORITY STANDARDS, AUSTRALIAN STANDARDS AND OTHER INDUSTRY REFERENCE DOCUMENTS AT TIME OF DESIGN.
  - DRAWINGS ARE NOT INTENDED TO BE USED FOR TENDER, ESTIMATING OR CONSTRUCTION.
  - ANY RETAINING WALL LEVELS AND WALL TYPE SHOWN ON THESE PLANS ARE INDICATIVE ONLY AND ARE SUBJECT TO DETAILED DESIGN.
  - ALL RETAINING WALLS PROPOSED ARE TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE BCA AND THE LOCAL AUTHORITY.
  - ALL PROPOSED EARTHWORKS SHALL BE DESIGNED AND CONSTRUCTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE RELEVANT AUTHORITY SPECIFICATIONS FOR FILLING AND EXCAVATION.

EARTHWORKS VOLUMES	
TOTAL CUT	10907m³
TOTAL FILL	61m³
TOTAL BALANCE	10846m³ CUT
INDICATIVE VOLUME ONLY:	
• ASSUME FINISH FLOOR LEVELS AS SHOWN, UNLESS NOTED OTHERWISE.	
• FROM DESIGN SURFACE LEVEL TO EXISTING SURFACE LEVEL WITH NO ALLOWANCE FOR PAVEMENT BOX, PIPE TRENCHING, BULKING OR COMPACTION FACTORS, SERVICES, BUILDING FOUNDATION SYSTEMS, FOOTPATHS, LANDSCAPE PAVEMENTS, GARDEN AREAS OR TOPSOIL.	
• ALLOWED FOR 150mm THICK BASEMENT SLAB & 50mm SAND BASE.	

- ### LEGEND
- SITE BOUNDARY
  - EXISTING PROPERTY BOUNDARY
  - PROPOSED PROPERTY BOUNDARY
  - EXISTING CONTOURS & LABEL (0.25m INTERVAL)
  - PROPOSED MAJOR CONTOURS & LABEL (0.5m INTERVAL)
  - PROPOSED MINOR CONTOURS & LABEL (0.25m INTERVAL)
  - PROPOSED BASEMENT OUTLINE
  - EXISTING ROAD CENTRE-LINE
  - EXISTING BUILDING OUTLINE
  - EXISTING RETAINING WALL
  - EXISTING KERB & CHANNEL
  - EXISTING CONCRETE (FOOTPATHS, DRIVEWAYS)
  - EXISTING HANDRAIL
  - EXISTING FENCE
  - EXISTING FENCE GATE
  - EXISTING LINEMARKING
  - EXISTING PEDESTRIAN LINEMARKING
  - EXISTING YELLOW LINEMARKING
  - EXISTING YELLOW LINEMARKING
  - PROPOSED TYPE 'D' MOUNTABLE K&C
  - PROPOSED INVERT KERB
  - EXISTING CONCRETE TO BE REMOVED
  - EXISTING FENCE TO BE REMOVED
  - EXISTING FENCE GATE TO BE REMOVED
  - EXISTING TREES TO BE RETAINED (REFER TO ARBORIST)

- ### CUT/FILL LEGEND
- AREA OF CUT DEPTH >5.0m
  - AREA OF CUT DEPTH 4.0m - 5.0m
  - AREA OF CUT DEPTH 3.0m - 4.0m
  - AREA OF CUT DEPTH 2.0m - 3.0m
  - AREA OF CUT DEPTH 1.0m - 2.0m
  - AREA OF CUT DEPTH 0.1m - 1.0m
  - AREA OF CUT & FILL DEPTH 0.0m - 0.1m
  - AREA OF FILL DEPTH 0.1m - 1.0m
  - AREA OF FILL DEPTH 1.0m - 2.0m
  - AREA OF FILL DEPTH 2.0m - 3.0m
  - AREA OF FILL DEPTH 3.0m - 4.0m
  - AREA OF FILL DEPTH 4.0m - 5.0m
  - AREA OF FILL DEPTH >5.0m

1:150 3 2 1 0 3 6 A1  
1:300 A3

Notes  K.Leggett Authorised K.LEGGETT RPEQ No. 27100	DDJ JT KJL 2025.07.22 Dwn. Dsgn. Chkd. YYYY.MM.DD	B DA SET FOR REVIEW BY EDQ URBAN PLANNING A FOR REVIEW Issued/Revision	DDJ/JT DDJ/JT KJL KJL 2025.07.22 2025.07.15 By Appd YYYY.MM.DD	Issue Status  <b>FOR APPROVAL</b> <b>NOT FOR CONSTRUCTION</b>  This document is suitable only for the purpose noted above. Use of this document for any other purpose is not permitted.	Colour Disclaimer This drawing has been documented in colour. This drawing is required to be printed in colour. Failure to do so may result in loss of information. Black and white printing may be used if specific black and white documents have been obtained from Stantec. Notes	Stantec Stantec Australia Pty. Ltd. Level 3 52 Merivale Street South Brisbane, QLD 4101 Tel: +61 7 3029 5000 Copyright Reserved The Copyright in all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden. The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing - any errors or omissions shall be reported to Stantec without delay.	Client/Project Logo  retireaustralia	Client/Project RETIRE AUSTRALIA  PARKSIDE YERONGA  70 PARK ROAD, YERONGA File Name:	DDJ JT KJL 2025.07.22 Dwn. Dsgn. Chkd. YYYY.MM.DD	Title BULK EARTHWORKS SHADING PLAN  Project No. 301051102 Scale 1:150 (A1) Revision B Drawing No. CI-DA-100-EW-P01







## **Appendix E – Proposed Architectural Plans**









**IMPORTANT NOTES**  
Do not scale from drawings. All dimensions to be checked on site before commencement of work. All discrepancies to be brought to the attention of the Architect. Larger scale drawings and written dimensions take preference. This drawing must not be used without the express authority of MARCHESE PARTNERS INTERNATIONAL PTY. LTD. Apartment areas measured to INSIDE face of all external party and corridor walls inclusive of structure and services risers within the I.A. Common service risers are EXCLUDED. External walls when adjacent to balcony or terrace are measured to CENTERLINE of wall. Balcony and terrace measured to INSIDE face of hob or planter wall.

REV	DATE	DESCRIPTION	BY
A	11/07/2025	DA DRAFT	ZJ
B	23/07/2025	DA SET FOR REVIEW BY EDO URBAN PLANNING	ZJ



**PRINCIPAL**

**D+C CONTRACTOR**

**CONSULTANT**


Marchese Partners International Brisbane Pty Ltd  
Level 14, 46 Edward Street, Brisbane, QLD 4000, Australia  
P +61 7 3211 2020 E info@marchesepartners.com W www.marchesepartners.com  
Sydney · Brisbane · Melbourne · Adelaide · Kuala Lumpur · Christchurch · London · Madrid

**PROJECT**  
**ARCADIA - BUILDING D**  
**70 PARK ROAD**  
**YERONGA QLD 4104**

DRAWING TITLE			
SITE PLAN			
SCALE 1: 150 @A1	DATE 23/07/2025	DRAWN ZJ	CHECKED SO
JOB 24015	DRAWING MP-AR-DWG-A2.00	REVISION B	




CAR PARKING (MINIMUM STATUTORY REQUIREMENT)		
MINIMUM REQUIRED SPACES = 59		
(A) 0.7 SPACES PER DWELLING FOR RESIDENTS		
(B) 0.3 SPACES PER DWELLING FOR VISITORS		
LEVEL	CAR PARK TYPE	PROPOSED SPACES
BASEMENT 3	RESIDENT	32
BASEMENT 2	RESIDENT	21
BASEMENT 1	RESIDENT	8
		61
BASEMENT 3	RESIDENT TANDEM	3
		3
BASEMENT 1	VISITOR	17
		17
TOTAL		81



DATE STAMP: 22/07/2025 3:05:04 PM	<div>IMPORTANT NOTES Do not scale from drawings. All dimensions to be checked on site before commencement of work. All discrepancies to be brought to the attention of the Architect. Larger scale drawings and written dimensions take preference. This drawing must not be used without the express authority of MARCHESE PARTNERS INTERNATIONAL PTY. LTD. Apartment areas measured to INSIDE face of all external, party and corridor walls inclusive of structure and services risers within the L.A. Common service risers are EXCLUDED. External walls when adjacent to balcony or terrace are measured to CENTERLINE of wall. Balcony and terrace measured to INSIDE face of hob or planter wall.</div>	<table><tr><th>REV</th><th>DATE</th><th>DESCRIPTION</th><th>BY</th></tr><tr><td>A</td><td>04/06/2025</td><td>ISSUE FOR INFORMATION</td><td>ZJ</td></tr><tr><td>B</td><td>10/06/2025</td><td>ISSUE FOR PRE-LODGE</td><td>ZJ</td></tr><tr><td>C</td><td>27/06/2025</td><td>ISSUE FOR INFORMATION</td><td>ZJ</td></tr><tr><td>D</td><td>08/07/2025</td><td>ISSUE FOR PRE-LODGE</td><td>ZJ</td></tr><tr><td>E</td><td>11/07/2025</td><td>DA DRAFT</td><td>ZJ</td></tr><tr><td>F</td><td>23/07/2025</td><td>DA SET FOR REVIEW BY EDQ URBAN PLANNING</td><td>ZJ</td></tr></table>	REV	DATE	DESCRIPTION	BY	A	04/06/2025	ISSUE FOR INFORMATION	ZJ	B	10/06/2025	ISSUE FOR PRE-LODGE	ZJ	C	27/06/2025	ISSUE FOR INFORMATION	ZJ	D	08/07/2025	ISSUE FOR PRE-LODGE	ZJ	E	11/07/2025	DA DRAFT	ZJ	F	23/07/2025	DA SET FOR REVIEW BY EDQ URBAN PLANNING	ZJ	<div><div><div></div><div>TRUE NORTH</div></div><div><div></div><div>PROJECT NORTH</div></div><div><div>0</div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div>&lt;/</div></div></div>
			REV	DATE	DESCRIPTION	BY																									
A	04/06/2025	ISSUE FOR INFORMATION	ZJ																												
B	10/06/2025	ISSUE FOR PRE-LODGE	ZJ																												
C	27/06/2025	ISSUE FOR INFORMATION	ZJ																												
D	08/07/2025	ISSUE FOR PRE-LODGE	ZJ																												
E	11/07/2025	DA DRAFT	ZJ																												
F	23/07/2025	DA SET FOR REVIEW BY EDQ URBAN PLANNING	ZJ																												




CAR PARKING (MINIMUM STATUTORY REQUIREMENT)		
MINIMUM REQUIRED SPACES = 59		
(A) 0.7 SPACES PER DWELLING FOR RESIDENTS		
(B) 0.3 SPACES PER DWELLING FOR VISITORS		
LEVEL	CAR PARK TYPE	PROPOSED SPACES
BASEMENT 3	RESIDENT	32
BASEMENT 2	RESIDENT	21
BASEMENT 1	RESIDENT	8
		61
BASEMENT 3	RESIDENT TANDEM	3
		3
BASEMENT 1	VISITOR	17
		17
TOTAL		81









DATE STAMP: 22/07/2025 3:05:05 PM	<div>IMPORTANT NOTES</div> <div>Do not scale from drawings. All dimensions to be checked on site before commencement of work. All discrepancies to be brought to the attention of the Architect. Larger scale drawings and written dimensions take preference. This drawing must not be used without the express authority of MARCHESE PARTNERS INTERNATIONAL PTY. LTD. Apartment areas measured to INSIDE face of all external, party and corridor walls inclusive of structure and services risers within the L.A. Common service risers are EXCLUDED.</div> <div>External walls when adjacent to balcony or terrace are measured to CENTERLINE of wall.</div> <div>Balcony and terrace measured to INSIDE face of hob or planter wall.</div>	<table><tr><th>REV</th><th>DATE</th><th>DESCRIPTION</th><th>BY</th></tr><tr><td>A</td><td>04/06/2025</td><td>ISSUE FOR INFORMATION</td><td>ZJ</td></tr><tr><td>B</td><td>10/06/2025</td><td>ISSUE FOR PRE-LODGE</td><td>ZJ</td></tr><tr><td>C</td><td>27/06/2025</td><td>ISSUE FOR INFORMATION</td><td>ZJ</td></tr><tr><td>D</td><td>08/07/2025</td><td>ISSUE FOR PRE-LODGE</td><td>ZJ</td></tr><tr><td>E</td><td>11/07/2025</td><td>DA DRAFT</td><td>ZJ</td></tr><tr><td>F</td><td>23/07/2025</td><td>DA SET FOR REVIEW BY EDQ URBAN PLANNING</td><td>ZJ</td></tr></table>	REV	DATE	DESCRIPTION	BY	A	04/06/2025	ISSUE FOR INFORMATION	ZJ	B	10/06/2025	ISSUE FOR PRE-LODGE	ZJ	C	27/06/2025	ISSUE FOR INFORMATION	ZJ	D	08/07/2025	ISSUE FOR PRE-LODGE	ZJ	E	11/07/2025	DA DRAFT	ZJ	F	23/07/2025	DA SET FOR REVIEW BY EDQ URBAN PLANNING	ZJ	<div><div><div></div><div>TRUE NORTH</div></div><div><div></div><div>PROJECT NORTH</div></div></div> <div><div>0</div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div></div><div>&lt;/</div></div>
		REV	DATE	DESCRIPTION	BY																										
		A	04/06/2025	ISSUE FOR INFORMATION	ZJ																										
B	10/06/2025	ISSUE FOR PRE-LODGE	ZJ																												
C	27/06/2025	ISSUE FOR INFORMATION	ZJ																												
D	08/07/2025	ISSUE FOR PRE-LODGE	ZJ																												
E	11/07/2025	DA DRAFT	ZJ																												
F	23/07/2025	DA SET FOR REVIEW BY EDQ URBAN PLANNING	ZJ																												




CAR PARKING (MINIMUM STATUTORY REQUIREMENT)		
MINIMUM REQUIRED SPACES = 59		
(A) 0.7 SPACES PER DWELLING FOR RESIDENTS		
(B) 0.3 SPACES PER DWELLING FOR VISITORS		
LEVEL	CAR PARK TYPE	PROPOSED SPACES
BASEMENT 3	RESIDENT	32
BASEMENT 2	RESIDENT	21
BASEMENT 1	RESIDENT	8
		61
BASEMENT 3	RESIDENT TANDEM	3
		3
BASEMENT 1	VISITOR	17
TOTAL		81



<b>IMPORTANT NOTES</b> Do not scale from drawings. All dimensions to be checked on site before commencement of work. All discrepancies to be brought to the attention of the Architect. Larger scale drawings and written dimensions take preference. This drawing must not be used without the express authority of MARCHESE PARTNERS INTERNATIONAL PTY. LTD. Apartment areas measured to INSIDE face of all external, party and corridor walls inclusive of structure and services risers within the L.A. Common service risers are EXCLUDED. External walls when adjacent to balcony or terrace are measured to CENTERLINE of wall. Balcony and terrace measured to INSIDE face of hob or planter wall.	<b>REV</b> A B C D E F	<b>DATE</b> 04/06/2025 10/06/2025 27/06/2025 08/07/2025 11/07/2025 23/07/2025	<b>DESCRIPTION</b> ISSUE FOR INFORMATION ISSUE FOR PRE-LODGE ISSUE FOR INFORMATION ISSUE FOR PRE-LODGE DA DRAFT DA SET FOR REVIEW BY EDQ URBAN PLANNING	<b>BY</b> ZJ ZJ ZJ ZJ ZJ ZJ	 TRUE NORTH   PROJECT NORTH  	<b>PRINCIPAL</b> 	<b>CONSULTANT</b>   Marchese Partners International Brisbane Pty Ltd Level 14, 46 Edward Street, Brisbane, QLD 4000 Australia P +61 7 2470 2600 E info@marchesepartners.com W www.marchesepartners.com Sydney Brisbane Melbourne Adelaide Kuala Lumpur Christchurch London Madrid	<b>DRAWING TITLE</b> <b>BASEMENT 1</b>			
	<b>D+C CONTRACTOR</b>		<b>PROJECT</b> <b>ARCADIA - BUILDING D</b> <b>70 PARK ROAD</b> <b>YERONGA QLD 4104</b>		<b>SCALE</b> 1 : 100 @A1	<b>DATE</b> 23/07/2025	<b>DRAWN</b> ZJ	<b>CHECKED</b> SO	<b>JOB</b> 24015	<b>DRAWING</b> MP-AR-DWG-A2.03	<b>REVISION</b> F





IMPORTANT NOTES

Do not scale from drawings. All dimensions to be checked on site before commencement of work. All discrepancies to be brought to the attention of the Architect. Larger scale drawings and written dimensions take preference. This drawing must not be used without the express authority of MARCHESE PARTNERS INTERNATIONAL PTY. LTD. Apartment areas measured to INSIDE face of all external, party and corridor walls inclusive of structure and services risers within the I.A. Common service risers are EXCLUDED. External walls when adjacent to balcony or terrace are measured to CENTERLINE of wall. Balcony and terrace measured to INSIDE face of hob or planter wall.

DATE STAMP: 22/07/2025 3:06:11 PM

REV	DATE	DESCRIPTION	BY
A	04/06/2025	ISSUE FOR INFORMATION	ZJ
B	10/06/2025	ISSUE FOR PRE-LODGE	ZJ
C	12/06/2025	ISSUE FOR PRE-LODGE	ZJ
D	27/06/2025	ISSUE FOR INFORMATION	ZJ
E	08/07/2025	ISSUE FOR PRE-LODGE	ZJ
F	11/07/2025	DA DRAFT	ZJ
G	23/07/2025	DA SET FOR REVIEW BY EDQ URBAN PLANNING	ZJ

TRUE NORTH

PROJECT NORTH

0

5

PRINCIPAL

D+C CONTRACTOR

CONSULTANT

marchesepartners

Life<sup>3A</sup>

Marchese Partners International Brisbane Pty Ltd  
Level 14, 46 Edward Street, Brisbane, QLD 4000, Australia  
P +61 7 3211 2030 E info@marchesepartners.com W www.marchesepartners.com  
Sydney Brisbane Melbourne Adelaide Kuala Lumpur Christchurch London Madrid

PROJECT

ARCADIA - BUILDING D  
70 PARK ROAD  
YERONGA QLD 4104

DRAWING TITLE

LOWER GROUND LEVEL

SCALE

1: 100 @A1

DATE

23/07/2025

DRAWN

ZJ

CHECKED

SO

JOB

24015


DRAWING

MP-AR-DWG-A2.04

REVISION

G





DATE STAMP: 22/07/2025 3:06:14 PM	<b>IMPORTANT NOTES</b> Do not scale from drawings. All dimensions to be checked on site before commencement of work. All discrepancies to be brought to the attention of the Architect. Larger scale drawings and written dimensions take preference. This drawing must not be used without the express authority of MARCHESE PARTNERS INTERNATIONAL PTY. LTD. Apartment areas measured to INSIDE face of all external, party and corridor walls inclusive of structure and services risers within the E.A. Common service risers are EXCLUDED. External walls when adjacent to balcony or terrace are measured to CENTERLINE of wall. Balcony and terrace measured to INSIDE face of hob or planter wall.			
	REV	DATE	DESCRIPTION	BY
	A	04/06/2025	ISSUE FOR INFORMATION	ZJ
	B	10/06/2025	ISSUE FOR PRE-LODGE	ZJ
	C	12/06/2025	ISSUE FOR PRE-LODGE	ZJ
	D	27/06/2025	ISSUE FOR INFORMATION	ZJ
	E	08/07/2025	ISSUE FOR PRE-LODGE	ZJ
	F	11/07/2025	DA DRAFT	ZJ
	G	23/07/2025	DA SET FOR REVIEW BY EDO URBAN PLANNING	ZJ
<div><div><div><div><div></div><div>TRUE NORTH</div></div><div><div></div><div>PROJECT NORTH</div></div></div><div><div></div><div>0 5</div></div></div></div>				
PRINCIPAL		retireaustralia		
D+C CONTRACTOR		CONSULTANT		
		marchesepartners   Life <sup>3A</sup>		
		<small>Marchese Partners International Brisbane Pty Ltd Level 14, 46 Edward Street, Brisbane, QLD 4000, Australia P +61 7 3211 2020 E info@marchesepartners.com W www.marchesepartners.com Sydney Brisbane Melbourne Adelaide Kuala Lumpur Christchurch London Madrid</small>		
		PROJECT		
		ARCADIA - BUILDING D		
		70 PARK ROAD		
		YERONGA QLD 4104		
		DRAWING TITLE		
		UPPER GROUND LEVEL		
		SCALE	DATE	DRAWN
		1:100 @A1	23/07/2025	ZJ
		JOB	DRAWING	CHECKED
		24015	MP-AR-DWG-A2.05	SO
				REVISION
				G




## **Appendix F – Parkside Yeronga subdivision documentation**




## **Appendix G – Before You Dig Records**









Scale 1: 700

Map Sources: Esri, Garmin, HERE, FAO, NOAA, USGS,  
© OpenStreetMap contributors, and the GIS User Community



Enquiry Area

Map Key Area



## Legend

Pipe	Pipe code and material	Object
Low pressure	C* (for example, C2) Cast iron	Valve
Medium pressure	CU Copper	Buried valve
High pressure	N2 Nylon	Regulator
Transmission pressure	P* Polyethylene (PE)	Gas supplied = yes
Critical main (behind pipe)	P3 Polyvinyl chloride (PVC)	CP rectifier terminal
Proposed (pressure by colour)	P6, P7, P9–P12 Medium density PE	CP test station
LPG (pressure by colour)	P2, P4, P8 High density PE	CP anode
Hydrogen blended (pressure by colour)	S* Steel	CP bond wire
Abandoned	W2 Wrought galv iron	Syphon
Idle/inactive	W3 PE coat wrought galv iron	Trace wire point
Sleeve		
Casing (behind pipe)		
Area	Abbreviation	
BYDA area of interest	BoK Back of kerb	FoK Front of kerb
	C Depth of cover	Galv Galvanized
	CP Cathodic protection	NTI Not tied in
Example		
<b>Pipe</b>	<b>Pipe code</b>	
40P6 in 80C2	40 mm high pressure medium density poly in an 80 mm cast iron casing	Pipe diameter in millimetres is shown before pipe code. 40P6 = 40 mm nominal diameter
63S8	63 mm medium pressure steel	

*This map was created in colour and should be printed in colour*





-RE  
6HT  
3URYLGHU %ULVEDQH &LW\ &RXQFLO  
7HOHSKRQH



/HJHQQ  
%<'\$(QTXLU)  
6WRUPZDWHU 1HWZR  
— 6WRUPZDWHU 'UDLQ  
— 6WRUPZDWHU \*XOO\  
5RRIZDWHU &RQQHFW  
1 6WRUPZDWHU 0DLQWH  
+ROH  
O 6WRUPZDWHU \*XOO\  
! 6WRUPZDWHU )LHOG  
%&& &DEOH 1HWZR  
— 7UDIILF 6LJQDO 'XFW

'LVFODLPHU  
%ULVEDQH &LW\ &RXQFLO > @  
,Q FRQVLGHUWLRQ RI &RXQFLO  
RZQHUV OLVWHG EHORZ SHUPLWWLQJ  
,RX DFNQRZOHGJH DQG DJUHH WKDW  
FRS\ULJKW RZQHUV JLYH QR ZDUUD  
GDWD LQFOXGLQJ DFFXUD\ UHOLD  
FXUUHQF\ RU VXLWDEOLW\ DQG  
'LQFOXGLQJ ZLWKRXW OLPLWDWLRQ  
IRU DQ ORVV GDPDJH RU FRV  
FRQVHTXHQWLDO GDPDJH UHODWLQ  
GDWD  
'DWD PXVW QRW EH XVHG IRU GLUH  
XVHG LQ EUDF RI WKH SULYDF\ OD  
&RS\ULJKW RI GDWD LV DV IROORZV  
&DGDVWUH DQG 6WUHHW 1DPHV %  
4XHHQVODQG 'HSDUWPHQW RI 1DW  
0LQHV DQG (QUJ\

&DXWLRQ 7KL V PDS PD\ FRQWDLQ  
DEDQGRQH XQGHUJURXQG DVEHVW  
JLYHV QR ZDUUDQW\ WR WKH FRPS  
RI WKHVH UHFRUGV \$SSURSULDWH  
WDNHQ LQ DOO FDVHV



OVERVIEW

CAUTION - HIGH  
VOLTAGE

- Substation
- Cable Marker
- Pit
- Pole
- Pillar
- LV Cable (up to 1kV)
- HV Cable (1kV - <33kV)
- HV Cable (33kV and over)
- Pit Boundary
- Planned Work Area

\$6" & DWHJRU\ 3" 3"

PH  
W  
WK  
Q  
O  
LV  
KH  
R  
IR  
FH



CAUTION - HIGH VOLTAGE

Substation

Cable Marker

Pit

Pole

Pillar

LV Cable (up to 1kV)

HV Cable (1kV - <33kV)

HV Cable (33kV and over)

Pit Boundary


Planned Work Area

\$ 6 " " " & D W H J R U \ 3 " " 3 0

P H  
W  
W K  
Q  
Q  
L V  
K H  
R  
I R  
F H



)RU (PHUJHQF\ 6LWXDWLRQV  
3OHDVH &DOO



\$6~'~&DWHJRU\ 3' 30


PH  
W  
WK  
Q  
Q  
LV  
KH  
R  
IR  
FH



## LEGEND



	Parcel and the location
	Pit with size "5"
	Power Pit with size "2E". Valid PIT Size: e.g. 2E, 5E, 6E, 8E, 9E, E, null.
	Manhole
	Pillar
	Cable count of trench is 2. One "Other size" PVC conduit (PO) owned by Telstra (-T-), between pits of sizes, "5" and "9" are 25.0m apart. One 40mm PVC conduit (P40) owned by NBN, between pits of sizes, "5" and "9" are 20.0m apart.
	2 Direct buried cables between pits of sizes, "5" and "9" are 10.0m apart.
	Trench containing any <b>INSERVICE/CONSTRUCTED</b> (Copper/RF/Fibre) cables.
	Trench containing only <b>DESIGNED/PLANNED</b> (Copper/RF/Fibre/Power) cables.
	Trench containing any <b>INSERVICE/CONSTRUCTED</b> (Power) cables.
	Road and the street name "Broadway ST"
Scale	0 20 40 60 Meters 1:2000  1 cm equals 20 m




# Emergency Contacts

You must immediately report any damage to the **nbn™** network that you are/become aware of. Notification may be by telephone - 1800 626 329.



## Urban Utilities - Water, Recycled Water and Sewer Infrastructure



Map Scale  
1:1000

## Before You Dig Australia- Urban Utilities Water, Recycled Water and Sewer Infrastructure

**BYDA Reference No: 256280020**

Date BYDA Ref Received: 10/06/2025

Date BYDA Job to Commence: 13/06/2025

Date BYDA Map Produced: 10/06/2025


This Map is valid for 30 days

Produced By: Urban Utilities

## Sewer

- ◆ Infrastructure
- ◆ Major Infrastructure
- Network Pipelines
- Network Structures

## Water

- Infrastructure
- ◆ Major Infrastructure
- Network Pipelines
-  Network Structures
- - - Water Service (Indicative only)

## Recycled Water

- Infrastructure
- ◆ Major Infrastructure
- Network Pipelines
- ▨ Network Structures

While reasonable measures have been taken to ensure the accuracy of the information contained in this plan response, neither Urban Utilities nor PelicanCorp shall have any liability whatsoever in relation to any loss, damage, cost or expense arising from the use of this plan response or the information contained in it or the completeness or accuracy of such information. Use of such information is subject to and constitutes acceptance of these terms.

The plans are indicative and approximate only and provided without warranties of any kind, express or implied including in relation to accuracy, completeness, correctness, currency or fitness for purpose.

Urban Utilities takes no responsibility and accepts no liability for any loss, damage, costs or liability that may be incurred by any person acting in reliance on the information provided on the plans.

This plan should be used as guide only. Any dimensions should be confirmed on site by the relevant authority.


Based on or contains data provided by the State of Queensland (Department of Natural Resources and Mines) [2020]. In consideration of the State permitting the use of this data you acknowledge and agree that the State gives no warranty in relation to the data (including accuracy, liability in negligence) for any loss, damage or costs (including consequential damage) relating to any use of the data. Data must not be used for direct marketing or be used in breach of the privacy laws. © State of Queensland Department of Natural Resources and Mines [2020]


For further information, please call Urban Utilities on 13 26 57 (8am-6pm weekdays). Faults and emergencies 13 23 64 (24/7).

[www.urbanutilities.com.au](http://www.urbanutilities.com.au)

ABN 86 673 835 011






	<p>Report Damage: <a href="https://service.telstra.com.au/customer/general/forms/report-damage-to-telstra">https://service.telstra.com.au/customer/general/forms/report-damage-to-telstra</a> Ph - 13 22 03 Email - Telstra.Plans@team.telstra.com Planned Services - ph 1800 653 935 (AEST bus hrs only) General Enquiries</p>	<p>Sequence Number: 256280019</p> <p><b>CAUTION: Fibre optic and/ or major network present in plot area. Please read the Duty of Care and contact Telstra Plan Services should you require any assistance.</b></p>
<p>TELSTRA LIMITED A.C.N. 086 174 781</p> <p>Generated On 10/06/2025 15:47:46</p>		

The above plan must be viewed in conjunction with the Mains Cable Plan on the following page

**WARNING**  
Telstra plans and location information conform to Quality Level "D" of the Australian Standard AS 5488-Classification of Subsurface Utility Information. As such, Telstra supplied location information is indicative only. Spatial accuracy is not applicable to Quality Level D. Refer to AS 5488 for further details. The exact position of Telstra assets can only be validated by physically exposing it. Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy. Further on site investigation is required to validate the exact location of Telstra plant prior to commencing construction work. A Certified Locating Organisation is an essential part of the process to validate the exact location of Telstra assets and to ensure the asset is protected during construction works.

See the Steps- Telstra Duty of Care that was provided in the email response.



Sequence Number: 256280019

**CAUTION:** Fibre optic and/ or major network present in plot area. Please read the Duty of Care and contact Telstra Plan Services should you require any assistance.


The above plan must be viewed in conjunction with the Mains Cable Plan on the following page

Telstra plans and location information conform to Quality Level "D" of the Australian Standard AS 5488-Classification of Subsurface Utility Information. As such, Telstra supplied location information is indicative only. Spatial accuracy is not applicable to Quality Level D. Refer to AS 5488 for further details. The exact position of Telstra assets can only be validated by physically exposing it. Telstra does not warrant or hold out that its plans are accurate and accepts no responsibility for any inaccuracy. Further on site investigation is required to validate the exact location of Telstra plant prior to commencing construction work. A Certified Locating Organisation is an essential part of the process to validate the exact location of Telstra assets and to ensure the asset is protected during construction works.


See the Steps- Telstra Duty of Care that was provided in the email response.



## LEGEND



### Some Examples of how to read Telstra Plans



One 50mm PVC conduit (P50) containing a 50-pair and a 10-pair cable between two 6-pits, approximately 20.0m apart, with a direct buried 30-pair cable along the same route

Two separate conduit runs between two footway access chambers (manholes) approximately 245m apart A nest of four 100mm PVC conduits (P100) containing assorted cables in three ducts (one being empty) and one empty 100mm concrete duct (C100) along

## Protect our Network:

by maintaining the following distances from our assets:

- 1.0m Mechanical Excavators, Farm Ploughing, Tree Removal
- 500mm Vibrating Plate or Wacker Packer Compactor
- 600mm Heavy Vehicle Traffic (over 3 tonnes) not to be driven across Telstra ducts or plant.
- 1.0m Jackhammers/Pneumatic Breakers
- 2.0m Boring Equipment (in-line, horizontal and vertical)

For more info contact a [CERTLOC Certified Locating Organisation \(CLO\)](#) or Telstra Location Intelligence Team 1800 653 935


- Use suitably qualified and supervised professionals, particularly if you are working near assets that contain electricity cables or gas pipes.
- Ensure the below minimum clearance distances between the construction activities and the actual location of our assets are met. If you need clearance distances for our above ground assets, or if the below distances cannot be met, call **1800 786 306** to discuss.

**Minimum assets clearance distances.**


- 300mm when laying asset inline, horizontal or vertical.
  - 1000mm when operating vibrating equipment. Eg: vibrating plates. No vibrating equipment on top of asset.
  - 1000mm when operating mechanical excavators or jackhammers/pneumatic breakers.
  - 2000mm when performing directional bore in-line, horizontal and vertical.
  - No heavy vehicle over 3 tonnes to be driven over asset with less than 600mm of cover.
- Reinstate exposed TPG network infrastructure back to original state.

**PRIVACY & CONFIDENTIALITY**

- Privacy Notice – Your information has been provided to us by Before You Dig Australia to respond to your Before You Dig Australia enquiry. We will keep your personal information in accordance with TPG’s privacy policy, see [www.tpg.com.au/about/privacy](http://www.tpg.com.au/about/privacy).
- Confidentiality – The information we have provided to you is confidential and is to be used only for planning and designing purposes in connection with your Before You Dig Australia enquiry. Please dispose of the information by shredding or other secure disposal method after use. We retain all intellectual property rights (including copyrights) in all our documents and plans.



TPG Telecom Limited



**Enquiry Number:** 256280016

**Map Sheet:** 1

**Scale:** 1: 750

0 0.008km

**LEGEND**

BYDA Work Area

AAPT/PowerTel Pit		TransACT Pit	
AAPT/PowerTel Duct		TransACT Duct	
DDA Pit		SOUL Pattinson Telecoms Pit	
DDA Duct		SOUL Pattinson Telecoms Duct	
Agile/Adam Pit		PIPE Networks Pit	
Agile/Adam Duct		PIPE Networks Duct	

**DISCLAIMER:** No responsibility/liability is taken by TPG Telecom Limited for any inaccuracy, error, omission or action based on the information supplied in this correspondence. © 2022 TPG Telecom Limited.



## **Appendix H – Geotech Report**





# **Douglas Partners**

*Geotechnics | Environment | Groundwater*

Report on  
Geotechnical Investigation

Yeronga Priority Development Area  
Park Road, Yeronga

Prepared for  
Economic Development Queensland

Project 200443.01  
February 2022

Integrated Practical Solutions



## Document History

### Document details

Project No.	200443.01	Document No.	R.001.Rev0
Document title	Report on Geotechnical Investigation Yeronga Priority Development Area		
Site address	Park Road, Yeronga		
Report prepared for	Economic Development Queensland		
File name	200443.00.R.001.Rev0		


### Document status and review

Status	Prepared by	Reviewed by	Date issued
DRAFT	Marc Salcor	David Qualischefski	7 April 2021
Revision 0	Marc Salcor	David Qualischefski	7 February 2022

### Distribution of copies

Status	Electronic	Paper	Issued to
DRAFT	1	0	John Marshall, Economic Development Queensland
Revision 0	1	0	John Marshall, Economic Development Queensland

The undersigned, on behalf of Douglas Partners Pty Ltd, confirm that this document and all attached drawings, logs and test results have been checked and reviewed for errors, omissions and inaccuracies.

	Signature	Date
Author		7 February 2022
Reviewer	<i>D. Qualischefski</i>	7 February 2022



Douglas Partners Pty Ltd  
 ABN 75 053 980 117  
[www.douglaspartners.com.au](http://www.douglaspartners.com.au)  
 439 Montague Road  
 West End QLD 4101  
 Phone (07) 3237 8900



## Table of Contents

	Page
1. Introduction .....	1
2. Site Description .....	2
3. Regional Geology .....	4
4. Field Work Methods .....	4
5. Field Work Results .....	5
6. Laboratory Testing .....	6
7. Dispersive/Erosion Assessment Criteria .....	7
8. Proposed Development.....	9
9. Appreciation of Ground Conditions .....	9
10. Comments.....	10
10.1 Groundwater Control.....	10
10.2 Basement Design and Construction.....	10
10.2.1 General.....	10
10.2.2 Excavatability .....	11
10.2.3 Temporary Slope Batters.....	11
10.2.4 'Hit and Miss' Panel Construction.....	12
10.2.5 Positive Support .....	12
10.3 Basement Preparation and Localised Fill Placement.....	14
10.4 Trench Construction.....	15
10.4.1 Batter Slopes.....	15
10.4.2 Shoring Design.....	16
10.4.3 Trench Backfill and Compaction.....	17
10.4.4 Trenchless Construction.....	17
10.5 Re-Use of Excavated Materials.....	18
10.6 Treatment of Existing Fill.....	18
10.7 Site Preparation and Filling Placement .....	19
10.8 Foundations .....	20
10.8.1 General.....	20
10.8.2 Allowable Thrust Block Bearing Pressures.....	21
10.8.3 High Level Footings.....	22
10.8.4 Pile Foundations.....	22
10.9 Presumptive Pavement and Slab-on-Ground Parameters .....	23
10.10 Site Classification.....	24
10.11 Site Earthquake Sub- Soil Class .....	25

10.12 Site Erosion Potential.....	26
11. Limitations.....	26
12. References.....	27
Appendix A:	About this Report
	Sampling Method
	Soil Descriptions
	Rock Descriptions
	Symbols & Abbreviations
Appendix B:	Drawing 1 - Site and Test Location Plan
Appendix C:	Field Work Results
Appendix D:	Laboratory Results



## **Report on Geotechnical Investigation**

### **Yeronga Priority Development Area**

### **Park Road, Yeronga**

---

## **1. Introduction**

This report presents the results of a geotechnical investigation undertaken for a Yeronga at Park Road, Yeronga. The investigation was commissioned in an email dated 1 March 2021 by Mr John Marshall of Economic Development Queensland, and was undertaken in accordance with Douglas Partners Pty Ltd (DP) proposal BNE200443 dated 25 February 2020 and proposal BNE200443.01 dated 6 October 2021.

It is understood that the proposed development includes residential, commercial and community buildings, roads and associated services. It is further understood that the scope of this investigation includes:

- trench alignments, both within the development and on adjacent roads;
- bulk earthworks across the allotments;
- community centre building (Lot 11), single storey with undercroft; and
- commercial centre building (Lot 1), six storeys with two basement levels.

The aim of the investigation was to assess the subsurface soil and groundwater conditions across the site to provide comments on:

- subsurface conditions including groundwater;
- site classification in accordance with AS2870-2011;
- excavation conditions;
- suitable temporary and permanent batter slopes;
- suitable foundation types (high level, raft or piles), bearing pressures and estimated settlements;
- site preparation and earthworks, including compaction and reuse of excavated materials;
- trenching and trenchless construction methods for in-ground services;
- lateral bearing pressure and thrust block design parameters;
- suitable basement retention options and basement type;
- suitable geotechnical retaining/basement wall design parameters;
- slab-on-ground subgrade design parameters (California bearing ratio (CBR) and modulus of subgrade reaction) for pavement design by others;
- site sub-soil class in accordance with AS1170.4-2007; and
- dispersion potential of near surface soils.

The investigation included the drilling of twenty-four boreholes, followed by laboratory testing, engineering analysis and reporting. The details of the field work and laboratory testing are presented in this report, together with comments and recommendations on the items listed above.

This report must be read in conjunction with the notes entitled 'About This Report' in Appendix A and other explanatory notes, and should be kept in its entirety without separation of individual pages or sections.

## 2. Site Description

The site is located on the eastern side of Park Road, Yeronga (refer to Drawing 1 in Appendix B), and is bounded by Park Road to the west, Villa Street to the south, the Ferny Grove and Beenleigh railway lines to the north and Yeronga State High School to the east. At the time of the investigation, the site was vacant with all previous buildings/developments having been demolished.

The ground surface at the site was sparsely covered by poorly-maintained grass with the remaining areas exposed fill subgrade and small to large sized trees were observed scattered along the northern, western and eastern boundaries. Furthermore, localised rock outcrops were also observed in various areas of the site. The topography within the majority of the site was relatively flat, however, generally sloped gently down from the southern and south-western boundary towards the north, north-eastern boundary. With reference to recorded bore levels and Brisbane City Council Interactive Mapping, the site levels are approximately RL 20 mAHD near the southern boundary, and approximately between RL10 mAHD and RL7 mAHD near the northern boundary of the site. Photographs of the site are indicated in Figures 1 to 3.



**Figure 1: Looking east towards the rig set up on Bore 2.**





**Figure 2: Looking north-west towards the rig set up on Bore 2.**



**Figure 3: Looking west towards the rig set up on Bore 24.**

### 3. Regional Geology

The Geological Survey of Queensland's 1:100,000 digital geological series 'South East Queensland' map, indicates that the site is underlain by three geological formations. Majority of the site is underlain by Triassic aged Arenite Rudite of the Aspley formation, typically comprising "Sandstone, conglomerate, minor shale." Two localised areas along the northern boundary are underlain by Quaternary aged Alluvium, typically comprising "Clay, silt, sand, gravel; flood plain alluvium" and by Holocene aged Anthropogenic deposits, typically comprising "land fill, mine tailings and rubble".

The subsurface conditions encountered during the field work comprised localised fill overlying residual soils then weathered sandstone to their termination depth. The residual soil is generally consistent with the weathering of sandstone from the Aspley Formation.

### 4. Field Work Methods

The field work was undertaken on 10 and 11 March 2021, 24 November 2021 and 13 December 2021 and comprised the drilling of 24 boreholes (designated Bores 1 to 8, 10, 12 to 26) to between 0.60 m and 10.05 m depth, at accessible locations across the site (refer Drawing 1 in Appendix B).

Boreholes 1 to 6 were drilled using a truck mounted drilling rig (Scout 3) and Boreholes 23 and 24 were drilled using a track rig (Hanjin 8D) and were commenced using 110 mm diameter solid flight augers and continued using rotary washbore techniques, whilst Boreholes 23 and 24 were further advanced using NMLC rock coring techniques. The remaining boreholes were drilled using a utility mounted drilling rig with 110 mm diameter solid flight augers. Standard penetration tests (SPTs), 'undisturbed' ( $U_{50}$ ) tube samples, and disturbed samples were undertaken at regular depth intervals within the bores for visual identification and laboratory testing. Dynamic cone penetrometer (DCP) testing was carried out adjacent to Boreholes 1 to 20 and 25 and 26 only to a maximum of 1 m depth (or prior refusal) with reference to test method AS 1289.6.3.2 (1997). The purpose of the DCP is to provide additional information on the strength consistency and relative density of the subsurface profile.

On completion of sampling and after checking for groundwater, the boreholes were backfilled with drilling spoil.

The test locations were set out by a geotechnical engineer and the UTM coordinates and ground surface levels at the test locations were recorded using a differential GPS accurate to approximately up to 5 m and are presented on Drawing 1 in Appendix B. Bores 1 to 6 were completed by an experienced engineer who logged the bores, collected samples for laboratory testing. The remaining bores were then completed by a geotechnician who prepared field logs of the subsurface conditions, collected samples for visual and tactile assessment, and laboratory testing. Upon receipt of the samples at DP's laboratory, the samples and field logs were checked by a geotechnical engineer.



## 5. Field Work Results

The subsurface conditions encountered in the bores are described in detail on the borehole logs in Appendix C. Notes defining the classification methods and descriptive terms used in their preparation are given in Appendix A.

In summary, the subsurface conditions encountered generally comprised **fill** overlying **residual soil** then **weathered sandstone / siltstone** to the limit of the investigation. The subsurface conditions are further described below:

- **Fill:** generally medium dense to dense granular fill was encountered in Bores 5 to 7, 10, 12 to 15, 19 and 21 from surface to between 0.1 m and 1.2 m depth. Generally stiff to hard clayey fill with some localised firm zones was encountered in all bores except Bores 8, 13, 14, 21, 23 to 26 from surface and beneath the granular fill and continued between 0.2 m and 2.7 m depth. The fill had some localised brick rubble, cobbles and boulders in Bores 4, 6, 15 to 18, 21 and 22 from surface up to 2.4 m depth. It should be noted that fill was not encountered in Bore 8 only.

In the absence of documentation to confirm the fill was placed and compacted in a controlled manner under engineering supervision and testing, it should be considered as 'uncontrolled'.

- **Residual Soil:** was encountered from the surface in Bore 8 and beneath the fill in Bores 1 to 5, and 19 to 26 down to 0.3 m and 6.8 m depth. The residual soils were also encountered in Bores 6, 10, 12 to 17 and 22 down between 1 m and 4 m depth where these boreholes were terminated. The residual soils were generally stiff to very stiff locally grading to hard with depth with some localised firm zones in Bores 5, 6 and 12, grey mottled orange and red and orange and yellow-brown and dark grey, low to high plasticity, residual gravelly sandy / sandy / silty / clay with some localised relict rock structure bands and fine to coarse sands and gravel. A localised layer of loose to medium dense, fine to medium grained, residual silty / clayey sand was encountered in Bores 5, 6 and 12 between 1.3 m and 2 m depth.
- **Sandstone / Siltstone:** very low strength, highly weathered, pale grey and orange-brown and red-brown and yellow-brown, sandstone was encountered locally in Bores 1 to 5, 7 and 8, 18 to 21, 23, 24 and 26 beneath the fill and residual soil and continued to the borehole termination depths of between 0.6 m and 10.05 m. The sandstone locally graded to medium strength, moderately weathered, highly to slightly fractured below 7 m in Bore 23 and below 5.5 m in Bore 24. A localised layer of very low strength, highly weathered, highly fractured siltstone was also encountered interbedded in weathered sandstone in Bore 24 between 6.12 m and 7.05 m depth and beneath the residual soils in Bore 25 and continued to bore termination depth of 2.4 m. Bores 7, 8, 18 to 21, 25 and 26 were terminated on auger refusal which is indicative of possible very low to medium strength (or stronger) rock.

Free groundwater seepage was not encountered during the auger drilling of the bores, however, was measured at 2.96 m depth in Bore 1 on the 6 April 2021 after the standpipe was purged on the 11 March 2021. Standpipes installed in Bores 12 and 22 were measured at 1.53 m and 0.46 m depth respectively on the 6 April 2021. It should be noted that the standpipes were measured after some recent heavy rainfall. It should be noted, however, that groundwater depths are affected by climatic conditions and soil permeability and will therefore vary with time.

## 6. Laboratory Testing

Successful collection of “undisturbed” samples intended for two shrink-swell tests was not possible due to the types and strengths of the materials encountered. Consequently, an Atterberg limits and linear shrinkage test was adopted for the laboratory testing.

Geotechnical laboratory testing comprised:

- two Atterberg limits, linear shrinkage and natural moisture content tests;
- two shrink-swell tests;
- ten Emerson class tests; and
- four dispersiveness suite which included pH, electrical conductivity (EC), cation-exchange capacity (CEC) exchangeable sodium percentage (ESP) (soil sodicity) and calcium (Ca) to exchangeable magnesium (Mg) ratio.

The laboratory test results are summarised in Tables 1 to 3, and detailed test report sheets are given in Appendix D.

**Table 1: Results of Moisture Content, Linear Shrinkage & Plasticity Tests**

Bore	Depth (m)	Material	M (%)	W <sub>L</sub> (%)	W <sub>P</sub> (%)	PI (%)	LS (%)
3	1.00 – 1.45	Silty Clay	14.7	39	23	16	9.0
13	0.70	Silty Clay	21.2	62	22	40	14.0

Legend: M – moisture content; W<sub>L</sub> – liquid limit; W<sub>P</sub> – plastic limit; PI – plasticity index; LS – linear shrinkage;

**Table 2: Results of Shrink-Swell Index (I<sub>ss</sub>) Testing**

Bore	Depth (m)	Material	Shrinkage (%)	Swell (%)	I <sub>ss</sub> (% per ΔpF)
14	0.50 – 0.80	Clay	4.7	0.5	2.8
17	1.20 – 1.70	Silty Clay	2.6	-0.0	1.4



**Table 3: Summary of Laboratory Test Results – Dispersiveness Assessment**

Bore	Depth (m)	Material	Emerson Class No.	pH	EC (µS/cm)	CEC (meq/100)	ESP (%)	Ca:Mg Ratio
2	0.50	Gravelly Sandy Clay Fill	1	Not Applicable				
7	0.50 – 0.95	Sandy Gravel Fill	1					
14	0.50 – 0.80	Clay	6					
16	0.50 – 0.95	Gravelly Clay Fill	3					
19	0.50	Sandy Clay Fill	3					
21	0.50 – 0.95	Silty Clay	6					
23	0.50	Silty Clay	2	3.9	272	6.4	46.7	<0.2
24	0.50	Silty Clay	3	3.7	701	3.2	42.4	<0.2
25	0.50	Sandy Clay Fill	6	6.1	698	16.3	20.5	2.6
26	0.50	Clay	2	3.8	158	6.7	33.1	0.8
Note:		Non-sodic and/or low potential for erosion		Marginally sodic to sodic and/or medium potential for erosion and dispersion		Strongly sodic and/or high potential for erosion and dispersion		Very high potential for erosion and dispersion

Note: Potential for erosion is detailed in Brisbane City Council's Erosion Hazard Assessment Technical Notes (2006)

## 7. Dispersive/Erosion Assessment Criteria

Assessment of the dispersive/erosive nature of the soils is based on the following references and tables.

Soil sodicity ratings from Amec Foster Wheeler (2014) – Section 3 are presented in Table 4.

**Table 4: Sodicty and Exchangeable Sodium Percentage (ESP)**

ESP (%)	Sodicty Rating
0 - 6	Non-sodic
6 - 15	Marginally sodic to sodic
> 15	Strongly sodic

Interpretation of Emerson Class test results based on BCC (2006) are presented in Table 5.

**Table 5: Emerson Class Interpretation from BCC**

Emerson Class	Erosion Potential
1 or 2	Very high potential for erosion
3	High potential for erosion
4	Medium potential for erosion
5	
6	
7 or 8	Low potential for erosion by dispersion process

The Ca:Mg ratio rating from Amec Foster Wheeler (2014) – Section 3 are presented in Table 6.

**Table 6: Ca:Mg Ratio**

Ca:Mg Ratio	Ratio Rating
<0.1	Very low
0.1 - 1	Low
1 - 2	Medium
>2	High

Calcium (Ca) to exchangeable magnesium (Mg) ratios of less than 0.1 (i.e. very low ratio rating) are often associated with highly dispersive soils.

Review of Best Practice Erosion and Sediment Control by International Erosion Control Association (IECA 2008) found that soils with an electrical conductivity (EC) greater than 0.5 mS/cm (500 µS/cm) are considered saline and may have a reduced risk of dispersion.



## 8. Proposed Development

It is understood that the proposed development includes residential, commercial community buildings, roads and associated services. It is further understood that the scope of this investigation includes:

- trench alignments, both within the development and on adjacent roads;
- bulk earthworks across the allotments;
- community centre building (Lot 11), single storey with undercroft; and
- commercial centre building (Lot 1), six storeys with two basement levels.

The nature of building construction was not known at the time of reporting, however, it is envisaged that the buildings will probably be of reinforced masonry block and / or concrete construction with a slab on ground and steel roof probably supported on either a raft slab or high level footings. Basement retention will probably be supported by piled walls.

Structural working loads and bulk earthworks levels were not provided prior to the preparation of this report, however, based on the client drawings, it is anticipated that column working loads of up to 5,000 kN and approximately up to 7 m depth of excavation would be required for the development.

## 9. Appreciation of Ground Conditions

The subsurface conditions encountered during the field work generally comprised fill up to 2.7 m depth, underlain generally by stiff to very stiff grading to hard (with some localised firm zones) residual gravelly sandy / sandy / silty clays to borehole termination depths of 1 m and 6.8 m with a localised layer of loose grading to medium dense residual silty / clayey sand between 1.3 m and 2 m depth. The fill and residual soils were locally underlain by very low grading to medium strength, highly weathered grading to moderately weathered sandstone / siltstone to borehole termination depths of between 0.6 m and the 10.05 m. Groundwater seepage was not encountered during the augering of the bores.

Historically imagery from QImagery mapping services indicate the site was natural bushland until early 1967 where the site was stripped for proposed TAFE development. The fill encountered in the bores suggests that the site was filled to construct a levelled building pad which may have potentially been won during the stripping and bulk excavation works for the proposed development.

The stiff (or stronger) residual clayey soils and weathered sandstone / siltstone encountered at shallow depths would generally be suitable for lightly loaded, settlement tolerant structures founded on high level footings, otherwise the alternative is by supporting the structure on pile foundations. It is also recommended that all structures be founded into similar strength strata to reduce the potential for differential settlement.

The 'uncontrolled' fill and loose / firm natural soils encountered in Bores 6 and 12 and 23 to 26 is assessed as unsuitable to support the structural loads for the development due to potentially large total and differential settlements which can damage movement sensitive structures. High level spread footings founding in controlled fill may only be suitable if the existing 'uncontrolled' fill is removed, screened, and replaced under controlled conditions.

Transferring the building loads below the fill and loose sandy / firm clayey soils via deep footings which are founded in the stiff (or stronger) residual clayey soils or via piles founded into the weathered sandstone / siltstone is probably a more economical solution.

Due to the subsurface conditions encountered and the need to excavate relatively close to the western and southern boundaries of the site and within the site, there will be implications for the design and construction of the basement, structure and installation of the underground pipelines, as follows:

- excavatability;
- stability of adjoining buildings, footpaths, roadways and in-ground services during construction;
- stability of excavated faces during construction; and
- potential groundwater seepage (if any) at basement and trench level.

It would be prudent to commission a dilapidation survey of nearby structures and in-ground services prior to construction.

Further comments on design and construction practice are given in the following sections of this report.

## 10. Comments

### 10.1 Groundwater Control

Groundwater was not encountered during the auger drilling of the bores, however, was measured at 2.96 m depth in the standpipe in Bore 1, 1.53 m depth in Bore 12 and 0.46 m depth in Bore 22. Given the ground conditions encountered which mainly comprise residual clays and weathered sandstone / siltstone, and proposed basement excavation depth of up to 7 m and some anticipated seepage inflow into the excavation, it is recommended that an allowance for sumps and pumping methods should be used during construction with localised temporary lowering of the groundwater table.

A 'drained' basement should generally be suitable and would require full height drainage to be installed behind all basement walls and beneath the basement floor slabs. All drainage would then need to be connected to sumps with pumps to remove water as required. The design of extraction pumps would require a detailed groundwater investigation to determine inflow rates. DP can assist with such an investigation. The alternate to a drained basement is a 'tanked' basement which requires design for full hydrostatic uplift and lateral pressures.

### 10.2 Basement Design and Construction

#### 10.2.1 General

Excavations of up to 7 m depth will generally be required to achieve the basement excavation level (BEL) in the south-western corner of the site for the proposed commercial building. Partial and / or full height benching and/or battering of the excavation face may be possible on the north and eastern boundaries where there is space, and the risk of collapse can be accepted and where the cut batter excavations are limited to maximum of 3 m vertical height. If a temporary cut batter is being considered for the 7 m deep cut, then specific stability assessment should be undertaken. Where the line of the



excavation extends close to the site boundaries such as the southern and western boundary, ground retention will be required. The extent of retention will depend upon the depth of excavation which is anticipated to decrease towards the north in line with falling ground levels.

The close proximity of the basement walls on the southern and western site boundary effectively negates the option of battering to maintain short term stability of excavation faces. Battering or benching may be possible for internal central excavations at the basement level, such as for spread footings, service trenches and lift pit overruns etc.

The excavation faces will require the use of a stiff retention system, such as cantilevered and/or anchored or propped pile wall, to minimise lateral and vertical ground movements behind the basement walls.

### 10.2.2 Excavatability

Based on the conditions encountered in the bores, the material cut from excavations to approximately 7m depth will generally comprise topsoil, fill, residual clays / sands and weathered sandstone / siltstone. Excavations in the soils and very low strength sandstone / siltstone should be achievable using conventional medium sized earthmoving plant (i.e. 30 tonne hydraulic excavator or larger) with rock teeth fitted buckets assisted with a ripping tyne. Confined excavations and excavation in very low to low strength (or stronger) sandstone / siltstone will require the use of a ripping tyne and a rock breaker. Any concrete if encountered would require the use of a rock breaker.

It should be recognised that the excavatability estimates are based on materials encountered at the test locations only and that conditions may prove more difficult (or easier) for excavatability beyond these test locations.

### 10.2.3 Temporary Slope Batters

For excavations up to 7 m in depth, full or partial height battering and / or benching of excavation faces may only be suitable provided they are excavated to a maximum of 3 m high stages with a minimum 3 m wide bench between each stage and a specific stability assessment is undertaken. This would only be suitable along the northern and eastern boundary where there is adequate space available during construction, and the potential risk of any collapse can be accepted.

Unsurcharged batter slopes cut up to 3 m vertical height into the 'uncontrolled' fill, residual soils and weathered sandstone / siltstone encountered during the field work may be preliminarily designed for temporary conditions as presented in Table 7.

**Table 7: Cut Batter Slopes (up to 3 m in height)**

Material	Safe Batter Slope (H:V)
	Short Term
Existing 'uncontrolled' fill and /or loose to medium dense residual sands	2:1
Stiff residual clays	1.5:1
Very stiff (or stronger) residual clays	1:1
Very low strength (or stronger) sandstone / siltstone	0.75:1 <sup>(1)</sup>

**Notes:**

- <sup>(1)</sup> Subject to geotechnical inspection during construction to confirm the absence of adverse joints.

The above temporary batter slopes are suggested with respect to slope stability only and do not allow for lateral stress relaxation which may result in movement of nearby in-ground services or shallow footings. If such services or footings are settlement-sensitive and are located such that a linear spread at 1H:1V outwards, down and away from the base of the service or footing, intersects the cut face, then the excavation may have to be positively supported.

### **10.2.4 'Hit and Miss' Panel Construction**

For lower height cut slopes up to 2.5m the use of a 'hit and miss' panel sequence could be considered for excavations along parts of the eastern and northern boundaries, with an 'a,b,c, a,b,c' sequence adopted with panel widths of 3 m to 3.5 m. Panel widths might be able to be increased where ground conditions are favourable and the risks associated with a slump can be accepted and controlled. It is recommended that this methodology be limited to slopes of maximum height of 2.5 m vertical comprising stiff (or stronger) residual clays and weathered sandstone / siltstone.

A typical construction sequence would involve excavating the 'hit' panels (ie. 'a') whilst leaving the next two 'miss' panels (ie. 'b,c') temporarily battered. Installation and backfilling of the concrete tilt panels or cast insitu wall to full height of the excavation (ie. up to 2.5 m maximum) at the 'hit' panel locations would occur prior to excavation of the next series of 'hit' panels (either 'b' or 'c'), and the same process followed. If required, the wall panels could be temporarily propped back to temporary footings or to the basement floor slab prior to installation of the first suspended floor.

If fissures are encountered during excavation, then it is recommended that 'hit and miss' panels not be used due to the risk of potential failure and risk of damage to adjoining structures, public roads and in-ground services. Prior to considering 'hit and miss' panel construction, it is recommended that trial excavations/trenches be undertaken to confirm the presence or otherwise of fissures.

### **10.2.5 Positive Support**

If the options above are not suitable in order to achieve the proposed basement dimensions, the installation of positive ground support prior to excavation will be necessary along parts of the site boundaries. The ground retention system selected will need to minimise ground movements behind the excavation faces to ensure adjacent structures, pavements, and in-ground services are not affected as a result of basement construction.

Cantilevered soldier piles with shotcrete infill panels are commonly used to support the faces in basement excavations. The advantage of a piled wall is that it could be incorporated into the final basement structure.

Where significant loads surcharge the excavation faces, the piled wall can be made stiffer by decreasing the pile spacing to form a contiguous pile wall or incorporating anchors or props for support.

Driven sheet piles would not be practical due to the presence of rock at close to the basement level.



#### 10.2.5.1 Pile Walls

Based on previous experience with similar subsurface conditions, it is envisaged that a soldier pile wall with shotcrete infill panels would be suitable. Soldier piles are typically spaced at up to approximately three pile diameters around the basement excavation with mesh and shotcrete infill panels. It is envisaged that uncased bored piles would be a suitable construction method. Provision for temporary steel liners and a cleaning bucket should also be allowed.

If anchors are required, they could be designed using the following working bond stresses:

- 50 kPa in very stiff (or stronger) residual clay; and
- 100 kPa in the very low strength (or stronger) sandstone / siltstone.

Anchor bond stresses are largely reliant upon drilling and cleaning techniques, and hence the amount of smear around the sides of the hole. It would be appropriate for checks of bond stress to be made by the contractor installing anchors at the time of construction, by way of pull out testing and proof load testing. It is possible that adopted bond stresses could be 50% higher than the above very low strength rock value if appropriate drilling and cleaning techniques are used, in conjunction with regular and favourable load testing.

Anchors need only be of temporary construction since it is assumed that long term earth loads will be supported by the permanent basement structure and ground level slab. After installation, all temporary anchors should be check stressed to 130% of the nominal working load then locked off at 100% of the working load. Checks should also be made at regular intervals to ensure that load is maintained in anchors and not lost due to creep effects.

The conditions indicated by the investigation suggest that the preparation of temporary anchors at the site should also include:

- a free length equal to their height above the base of the excavation;
- a minimum bond length of 3 m; and
- a maximum bond length of 10 m (unless specialist single bore multi-anchored systems are adopted).

Internal bracing systems are an alternative to anchored support, however, braces can restrict access which must be maintained during building construction. Approval from neighbours and *Council* will be required prior to construction of temporary/permanent anchors.

Determination of pile or wall depths, anchor spacing and lengths is a matter for detailed design. DP could assist in this design if required.

#### 10.2.5.2 Basement Wall Design Pressures

The design of flexible or rigid retaining walls either cantilevered with a single row of anchors or props could be designed by a triangular pressure distribution and the earth pressure coefficients in Table 8 can be adopted.

**Table 8: Earth Pressure Coefficients (non-sloping crest backfill)**

<b>Material</b>	<b>Unit Weight (kN/m<sup>3</sup>)</b>	<b>K<sub>o</sub> (braced structure)</b>	<b>K<sub>a</sub> (cantilever structure)</b>	<b>K<sub>p</sub> (passive)</b>
Existing 'uncontrolled' fill	18	0.70	0.55	1.8
'Controlled' fill <sup>(1)</sup> and /or stiff residual clays and / or loose to medium dense (or denser) residual sands	20	0.60	0.44	2.2
Very stiff (or stronger) residual clays	20	0.55	0.40	2.5
Very low strength (or stronger) sandstone / siltstone	22	0.35	0.25	(300 kPa)

Notes:

<sup>(1)</sup> Assuming controlled fill is undertaken in accordance with the recommendations of this report.

It is recommended that all permanent basement walls be drained for full height in order to minimise hydrostatic pressure build-up behind the walls. Tanked basements would need to be designed for full height hydrostatic pressure.

For design of basement and retaining walls:

- Due allowance should be made for surcharge loadings (over and above the lateral earth pressure coefficients presented above) where the finished ground level above retaining walls is above horizontal and where additional loading is likely to be applied from existing or future upslope structures, or from traffic. The effects of surcharge can be estimated by multiplying the vertical pressure by the appropriate lateral earth pressure coefficient presented above.
- An allowance of 10 kPa should be made for lateral stress induced by compaction plant operating behind any walls (if appropriate).
- Drainage material should be installed for the full height of the wall, for a width of at least 0.3 m. The material must be free draining and granular and have a perforated or slotted drainage pipe at the heel of the wall to rapidly remove the water into the stormwater system.
- Where not fully drained, the walls will need to be designed for full hydrostatic pressure.

It is recommended that a factor of safety of 2 be adopted for overturning and sliding stability, and 1.5 for global stability of all basement and retaining wall designs.

For limit state design methods, the ultimate parameters provided above in Table 8 will need to be factored in accordance with AS 4678 (2002). Guidance on the selection of material strength partial factors is provided in Section 5.2 of AS 4678 and is dependent upon the nature and state of the natural insitu soil.

### 10.3 Basement Preparation and Localised Fill Placement

Following excavation to BEL, the exposed subgrade is anticipated to comprise very low strength (or stronger) sandstone / siltstone. Where the exposed subgrade is subjected to increases in moisture



content from rainfall and/or overland flow, there is potential for the weathered sandstone / siltstone to soften.

A working platform will probably be required to prevent softening of the subgrade and may be required for the support of a piling rig if pile foundations are adopted. Temporary piling platform design can only be definitively carried out once the size and loading of the piling rig(s) are known. However, at this stage a nominal construction trafficking platform in the order of (say) 0.3 m thick well graded crushed rock may be required to support the anticipated large piling rigs given the presence of very low strength sandstone / siltstone and potential for softening following increases in moisture content from rainfall and/or overland flow.

It is important that suitable grades be maintained to allow drainage and to minimise the potential for ponding of surface water, which can be collected in screened sumps and pumped from the excavation.

Trafficability across the weathered sandstone subgrade at BEL, if water softened, will be relatively poor. Placement of the abovementioned construction trafficking platform would also assist trafficability of rubber tired vehicles.

Any new fill required up to 0.5 m depth to achieve design levels beneath on-ground basement slabs should be undertaken under 'Level 2' sampling and testing as detailed in AS 3798 (2007). Greater fill depths would require 'Level 1' inspection and testing where the fill is required for structural support. Any new fill required beneath floor slabs should also be compacted to a minimum dry density ratio of 98% relative to standard dry density at  $\pm 2\%$  OMC.

The above procedures will require geotechnical inspection and testing services to be employed during construction. DP is suitably qualified to conduct earthworks testing and supervision services, as well as engineering inspections of batters, footings and piled foundations, as may be required during the development.

## **10.4 Trench Construction**

### **10.4.1 Batter Slopes**

Where space is available, battering or benching of the trench side walls is recommended.

Based on the encountered natural strata profiles encountered, temporary excavations up to 1 m depth below existing ground level in stiff (or stronger) clays or medium dense (or denser) clayey sands or very low strength (or stronger) sandstone / siltstone may remain near vertical for short periods of time, provided that any loose or water-bearing granular soils are battered back from the crest, dry moisture conditions prevail at the time of construction and there are no loads, services, structures or traffic located within a distance from the crest of the batter equal to the slope height. It is recommended that geotechnical inspection of near vertical cuts be undertaken prior to personnel working in excavations to ensure conditions are as assumed in design.

All excavations greater than 1 m depth will need to be shored, benched or battered for stability prior to personnel entering the excavation. Unsurcharged batter slopes cut up to 3 m high into the various soil profiles encountered during the field work, may be designed for temporary and long term conditions as presented below in Table 9 below.

**Table 9: Cut Batter Slopes (up to 3 m high)**

Material	Safe Batter Slope (H:V)	
	Short Term	Long Term <sup>(2)</sup>
Existing 'uncontrolled' fill and /or loose to medium dense residual sands	2:1	Not Suitable
'Controlled' fill <sup>(1)</sup> and /or stiff residual clays	1.5:1	2:1
Very stiff (or stronger) residual clays	1:1	2:1
Very low strength (or stronger) sandstone / siltstone <sup>(3)</sup>	0.75:1	1:1

Notes:

- <sup>(1)</sup> Assuming controlled fill is undertaken in accordance with the recommendations of this report.
- <sup>(2)</sup> Long term slopes in engineered fill and residual clays would require surface protection to reduce the risk of erosion potential. Steeper values may be possible, subject to detailed stability analysis.
- <sup>(3)</sup> Subject to geotechnical inspection during construction to confirm the absence of adverse joints.

It should be noted that the above slopes assume dry conditions, if groundwater is encountered during excavation of granular i.e. sandy soils it may be accompanied by 'running sand' conditions and ensuing sidewall instability. In such instances, excavations will need to be battered considerably flatter than those given in Table 9 possibly flatter than 4H:1V and/or require dewatering for stability or require support measures such as shoring boxes with pumping from screened sumps.

It is recommended that crest and toe drainage and surface protection (such as vegetation or similar) be incorporated in all permanent batters to assist in the removal of surface water from the batters.

The above temporary batter slopes are suggested with respect to slope stability only, and do not allow for lateral stress relaxation which may result in movement of nearby inground services. If such services are settlement-sensitive and are located near the crest of the cut face, then the excavation may have to be positively supported.

#### 10.4.2 Shoring Design

Where space to batter or bench is not available in areas of open trench excavation, the temporary support of the excavations in soils could comprise shoring boxes. The design of cantilevered or single propped temporary excavation support could be undertaken using a triangular pressure distribution and the earth pressure parameters given in Table 8.

Flexible walls are those which are free to rotate or tilt (such as cantilevered walls) and should be designed using an active earth pressure coefficient ( $K_a$ ). For support systems with more than one prop, a constant earth pressure of 6H (where H is the depth of excavation) could be used for design. Any retention system will require detailed design.

Allowance should be made for hydrostatic pressure build-up behind the temporary shoring. Also, allowance for surcharge loads and sloping crest should be made as appropriate. The effect of surcharge should be included by multiplying the vertical surcharge pressure by the appropriate short term lateral earth pressure coefficient as given in Table 8 above in Section 10.2.5.2.



### 10.4.3 Trench Backfill and Compaction

It is anticipated that following placement of a bedding layer at the base of the trench, the service pipe will be installed, and the trench progressively backfilled using predominantly granular material to a predetermined height above the pipe invert. Trench depths, bedding layer thickness and cover requirements may vary and will be provided on the relevant construction drawings. Backfilling is then understood to comprise materials won from trench excavation, provided it is suitable.

Compaction of trench backfill material should be carried out in a manner to prevent damage to the installed service pipes. Appropriate purpose selected equipment may be required to achieve compaction requirements to prevent damage occurring.

Any trench backfill should be placed in layers not exceeding 200 mm loose thickness, with each layer compacted to a minimum dry density ratio of 98% relative to standard compaction (for cohesive material) or a minimum density index of 75% (for cohesionless soils), or as directed by Project guidelines. Hand-operated compaction equipment, or other approved methods as directed by Project guidelines, should be used to compact the first 600 mm of trench backfill above the pipe. Heavy compaction equipment may be used to compact the trench backfill provided a minimum of 1.2 m of backfill has been initially placed above the pipe. At any road crossings, the final 600 mm of the finished surface should be compacted to 100% Standard compaction (or a density index of 80%). Moisture contents should be within -2% to +2% of OMC.

Field density testing should be carried out to check the standard of compaction achieved during backfilling and the moisture content during placement. The frequency and extent of testing should be carried out in accordance with AS 3798 (2007) or as directed by Project guidelines. The above procedures will require geotechnical inspection and testing services to be employed during construction.

Where the pipeline is bedded and/or backfilled with free-draining pea gravel, sand or gravel, and where any utility trench slopes more than 5%, DP recommend that backfill “check dams” be constructed to prevent movement of groundwater through the bedding or backfill material. These check dams consist of relatively impermeable soil extending from the base of the trench, surrounding the pipe and extending to the surface to impede movement of groundwater along the trench backfill. Check dams are typically spaced 10 m to 30 m apart and should have minimum widths of 0.5 m. Steep utility trench grades (i.e. more than 8% to 10%) would probably require the minimum spacing.

### 10.4.4 Trenchless Construction

Trenchless installation methods are a possibility for this alignment; however, no locations have been indicated to DP at the time of this report. Depending on the method and locations, launch or receiver pits may be required at each end of proposed water pipelines. Sloped cuts or bracing/shoring could be used for the excavations, although this would depend on HDD transect depths and space requirements i.e. the excavation depth required which will be dependent upon the Contractor's equipment and operations.

The ground conditions along the alignment generally comprise existing fill over stiff (or stronger) residual clays overlying very low strength (or stronger) sandstone / siltstone from surface from between 1 m and 6.1 m depth. In terms of issues for construction:

- Given the shallow very low strength (or stronger) sandstone / siltstone, there may be potential difficulties in drilling and will require provision for measures to accommodate for this issue.
- The stiff (or stronger) residual clays and very low strength sandstone / siltstone should be relatively stable, but any residual sands may present some issues for hole stability and require provision for measures to accommodate this issue. If a high groundwater table is present at the time of construction (not anticipated), special measures would likely be required.
- The presence of residual sands and weathered sandstone suggests that ‘frac-out’ may potentially be a risk at the site and may require provision for measures to accommodate this issue.

Positive ground support such as shoring boxes should be used for excavations up to approximately 6 m depth (if required). If battered excavation is preferred for launch or receival pits (if required), it is recommended that the excavation sides be sloped or benched as per Table 9 in Section 10.4.1. For excavations deeper than 3 m in vertical height case specific stability analysis is recommended.

It is recommended that experienced trenchless pipeline contractors be contacted to discuss the suitability of the above installation methods with respect to the onsite conditions.

If this option is to be considered for specific portions of the proposed water alignment, then DP could provide more location specific information.

## 10.5 Re-Use of Excavated Materials

The results of the field work indicate the majority of materials ‘won’ from onsite excavation are likely to comprise existing fill, residual clays / sands and weathered sandstone / siltstone. The existing fill, residual clays / sands and weathered sandstone / siltstone will generally be suitable for re-use as fill (i.e. for platform subgrade construction). Such re-use is contingent upon acceptance of reactive surface movements, and on particle size distribution being controlled along with moisture content, and upon minimum placement and compaction requirements being met, all as indicated in Section 10.7 below. Re-use of any sand will require blending with clay to improve workability and reduce the potential for ‘slushy’ conditions when wet and unravelling when dry.

## 10.6 Treatment of Existing Fill

Where site fill has been placed (prior to this investigation) without any supporting documentation to confirm that the fill was placed under engineering supervision and testing in a ‘controlled’ manner, then there may be some risk of incurring unacceptably high differential settlement of the ‘uncontrolled’ filling under future upper-level footing loads and during any rainwater ingress. The results of the bores indicate that the existing moderately to well compacted ‘uncontrolled’ fill is between 0.1 m and 2.7 m thick. Accordingly, the following options are suggested to manage the risks associated with “uncontrolled” fill:

- **Pile Support the Buildings** – The option with lesser additional earthworks work is to leave the existing “uncontrolled” fill in place. With this option the future building loads would need to be supported on piles penetrating into competent natural material below the fill and the floor slabs fully suspended. Any new pavements to be constructed on the existing fill would need to be designed to accept the risk of settlements.



- **Excavate and Recompact the Filling** – The option with significant earthworks is to remove all “uncontrolled” fill and test roll the underlying natural ground for soft or loose conditions. The existing fill can then be screened to remove all coarse, oversize or deleterious material prior to replacement in layers of maximum 0.3 m ‘loose’ thickness. Each layer should be compacted under ‘Level 1’ inspection and testing in accordance with the recommendations presented in Section 10.7 below. Adopting this low level of risk will enable high level foundations for structures with light to moderate loads.

The above procedures will require geotechnical inspection and testing services to be employed during construction. It is further noted that the first option will have a risk of potential movement in pavement areas requiring on-going maintenance where this option is adopted.

## 10.7 Site Preparation and Filling Placement

Based on the depth of fill encountered in the proposed development area which ranges between 0.1 m to 2.7 m, and where an excavate and replace option is adopted as discussed above in Section 10.6, the following site preparation measures and subsequent use of a slab-on-ground footing system founding in engineered fill and/or pavements and/or structural components. The placement of controlled fill over natural soils is detailed below:

- Remove any ‘uncontrolled’ or deleterious, soft, wet or highly compressible material or topsoil material rich in organics or root matter which should be initially stockpiled for screening and to be potentially reused as fill.

Uncontrolled fill was encountered at the test locations to depths of between 0.2 m and 2.7 m.

- Reshape and grade the clay or sandy subgrade beneath proposed structures and pavements to drain towards the outside from a slightly domed centre. Any internal low spots should be prevented from developing as these may act as a drainage sink and subsequently lead to localised swelling and softening or unravelling.
- Assess moisture contents of the subgrade and adjust the moisture content (if required) to be within 2% of OMC, where OMC is the optimum moisture content at standard compaction.
- Roll the exposed surface with at least six passes of a minimum 8 tonne deadweight smooth drum roller, with a final test roll pass accompanied by careful visual inspection to ensure that any deleterious materials such as soft, wet or highly compressible soil and any organics are identified and removed;
- Compact the subgrade (including upper 0.5 m depth if in fill) to a minimum dry density ratio of 95% standard, but 100% standard for 1 m depth of a building platform subgrade where footings are to be founded in the fill. Clay fill should be limited to a maximum dry density ratio of 102% Standard to avoid over-compaction. Over-compacted clays (ie. minimum dry density ratio of >102%) which are dry of OMC, may swell significantly and lose strength if they are wetted after compaction, potentially changing the site classification and reducing subgrade strengths assumed in design, and therefore need to be avoided.
- Place fill in layers not exceeding 300 mm loose thickness, with each layer compacted to a minimum dry density ratio of 98% standard. It is recommended that the upper 1 m depth of fill for any fill which is required to support building footings and / or any pavements be compacted to a minimum dry density ratio of 100% standard. This higher dry density ratio should apply to all fill extending from a nominal horizontal distance of 2 m at the edge of each structural support footing with a

nominal zone of influence of 1H:1V down and away from the proposed engineered subgrade level. Where fill is clayey, moisture content within the fill should be maintained within 2% of OMC (where OMC is the optimum moisture content at standard compaction) during and after compaction.

- Seal or cover any compacted silty or sandy clay foundation soil at or close to footing formation level should be as soon as practicable, to reduce the opportunity for occurrence of desiccation and cracking. It is recommended that building platforms be overlaid with a working platform of nominal 200 mm thickness of well graded clayey granular fill of minimum CBR 20% with a minimum 15% fines (<75 µm) content to reduce moisture variation (and associated shrink-swell movements) in subgrade soils, and to improve trafficability for light vehicles. Where the surface is to be trafficked by heavy vehicles/machinery, then specific pavement thickness design should be undertaken.
- Undertake 'Level 1' inspection and testing as detailed in AS 3798 (2007) where any new fill is required to achieve design levels for support of any structural components including on-ground slabs and Level 2 for pavements.

The above procedures will require geotechnical inspection and testing services during construction.

Due to the high to low plasticity of the near surface clayey fill soils (if left in place) and residual clayey soils, it is expected that rubber tyred vehicles in particular will have trafficability problems during and after periods of rainfall or other increases in subgrade moisture content, and in some cases tracked plant will experience some difficulty. It will be essential to keep the site well drained during construction. As indicated previously, a granular working platform is recommended to reduce potential lost time during or following wet weather, and to reduce wetting or drying of the subgrade soils (with associated long-term movements).

Soils which become wet, 'slushy' and soft will need to be allowed to dry out or be replaced.

Where bulk fill is placed under controlled conditions, there is potential for 'creep' of the fill material as the fill settles over time under self-weight. Such settlement is expected to be in the order of approximately 0.5% to 1% of the fill thickness over a period of ten to twenty years for well compacted clay fill and less for granular fill.

The above procedures will require geotechnical inspection and testing services to be employed during construction.

## **10.8 Foundations**

### **10.8.1 General**

For proposed lightly loaded, settlement tolerant near surface structures, it is estimated that high level pad / strip footings founded into the stiff (or stronger) residual clays and / or medium dense (or denser) residual sands and / or very low strength (or stronger) sandstone / siltstone and /or where the existing 'uncontrolled' fill is removed, screened, and replaced under controlled conditions would be suitable. Given the anticipated column loads and the expected very low strength (or stronger) sandstone / siltstone at basement excavation level and potentially at pipe invert levels, it is estimated that pad footings and / or thrust blocks founded into the very low strength (or stronger) sandstone / siltstone would be suitable. Alternatively, the structures could be supported on the stronger underlying low strength (or stronger) sandstone / siltstone via piles.



It is also recommended that the proposed structures are be founded into similar strength strata to reduce the potential for differential settlement.

Where limit state methods are used to design the foundations, the ultimate geotechnical strength ( $R_{d,ug}$ ) can be calculated by multiplying the allowable parameters by the adopted safety factor of 2.5, and then multiplied by a suitable geotechnical strength reduction factor ( $\Phi_g$ ) to obtain the design geotechnical strength ( $R_{d,g}$ ). A nominal  $\Phi_g$  value of 0.5 is recommended for high level footings. The Piling Code AS 2159 (2009) requires a  $\Phi_g$  value of 0.45 to 0.65 where there is no testing of pile capacity, rising to 0.65 to 0.85 where a significant number of piles are tested after installation.

It is essential that foundation excavations be inspected by experienced geotechnical personnel to ensure the design parameters adopted are suitable for the ground conditions and to ensure that there is no soft or loose material remaining at the base of the excavations or smear on the side walls. Ground conditions can vary, and it is essential that adequate provision be made throughout the project to vary foundations to suit differing ground conditions.

### 10.8.2 Allowable Thrust Block Bearing Pressures

Table 10 below outlines the allowable bearing pressures for the materials encountered during the investigation for the design of thrust blocks.

**Table 10: Vertical and Horizontal Bearing Pressures**

<b>Material</b>	<b>Allowable Vertical Bearing Pressure (kPa)</b>	<b>Allowable Horizontal Bearing Pressure (kPa)<sup>(1)</sup></b>
Stiff residual clay	100	50
Very stiff residual clay	200	100
Hard residual clay	400	200
Medium dense residual sand	100	50
Dense residual sand	400	100
Very low strength (or stronger) sandstone / siltstone	500	250

Note: <sup>(1)</sup> - based upon values outlined in the Water Supply Code of Australia (2002)

The above bearing pressures are contingent upon the centre of the thrust block being a minimum of 1 m depth below the existing ground surface. Furthermore, any vertical pressures are contingent upon the founding material extending at least two times the footing width below the footing or higher strength/density material at depth.

It is recommended that all thrust block excavations be inspected by an experienced geotechnical engineer to confirm bearing pressure prior to casting of concrete.

These allowable values are based on a factor of safety of 2.5. Ground movement of up to 10 mm could be expected for properly designed and constructed thrust blocks sized using the allowable horizontal

bearing pressures given above. Vertical settlements of up to 1% of the footing width can be expected for footings constructed and loaded as outlined above.

### 10.8.3 High Level Footings

High level strip footings to a maximum width of 1 m and pad footings to a maximum width of 2 m, may be preliminary sized using allowable bearing pressures given in Table 11.

**Table 11: Allowable Bearing Pressures for Pad and Strip Footings**

<b>Material</b>	<b>Allowable Bearing Pressure (kPa)<sup>(1)</sup></b>
Existing 'Uncontrolled' fill and / or firm residual clays and /or loose residual sands	Not Suitable
Controlled fill <sup>(2)</sup> and / or stiff residual clays or medium dense (or denser) residual sands	100
Very stiff (or stronger) residual clays	200
Very low strength (or stronger) sandstone / siltstone	500 <sup>(3)</sup>

Notes: <sup>(1)</sup> Subject to confirmation through visual and tactile assessment of the material during inspection.

<sup>(2)</sup> Assuming engineered fill is undertaken in accordance with the recommendations of this report and AS3798.

<sup>(3)</sup> Provided no weaker foundation material exists within two footing widths below the base of the footing; else the value for very stiff (or stronger) residual clays should be adopted for design.

For upper level footings (loaded as above), it is considered that settlements under such applied loading will be less than 1% of footing width. Wider footings are possible but would be subject to specific settlement assessment in relation to footing size and founding depth.

The above allowable values are based on a factor of safety of 2.5 against bearing capacity failure.

### 10.8.4 Pile Foundations

Should the above maximum allowable bearing pressures prove too low for the development loads, then the structures will need to be supported on piles. Given the encountered ground conditions, auger bored piles would be suitable. Allowance should be made for the use of temporary steel liners and a cleaning bucket where water ingress is encountered and for base cleanliness

It is recommended that pile foundations be concreted promptly after excavation to reduce the potential for base softening caused by increases in moisture content and localised excavation relaxation.

Bored piles founded one pile diameter into sandstone/siltstone could be sized using the preliminary maximum allowable values given in Table 12.



**Table 12: Allowable Bored Pile Design Pressures**

<b>Material</b>	<b>Allowable Shaft Adhesion (kPa)</b>	<b>Allowable End Bearing (kPa)<sup>(1)</sup></b>
Existing 'Uncontrolled' fill and / or firm residual clays and /or loose residual sands	Not Suitable	Not Suitable
Controlled fill <sup>(2)</sup> and / or stiff residual clays or medium dense (or denser) residual sands	20	Not Suitable
Very stiff (or stronger) residual clays	25	Not Suitable
Very low strength (or stronger) sandstone / siltstone	60	750 <sup>(3)</sup>

Notes: <sup>(1)</sup> Subject to confirmation through visual and tactile assessment of the material during inspection.

<sup>(2)</sup> Assuming controlled filling is undertaken in accordance with the recommendations of this report.

<sup>(3)</sup> Provided no weaker foundation material exists within four pile diameters and below the base of the pile footing.

For bored pile foundations loaded as per the allowable bearing pressures in Table 12, it is considered that settlements under such applied loading will be less than 1% of the pile diameter. Bored piles should be socketed into similar strength strata to reduce the potential for differential settlement between adjacent piles.

It is recommended that the upper 0.9 m of soil be ignored or depth of fill (whichever is greater) in pile shaft adhesion calculations due to the effects of seasonal moisture variation and shaft load development effects.

## 10.9 Presumptive Pavement and Slab-on-Ground Parameters

If site preparation is carried out as detailed in Sections 10.3 and 10.7, the subgrade conditions are expected to comprise clay-bound engineered fill, residual clays / sands and / or weathered sandstone / siltstone.

Based on experience with similar subgrades and allowing for minor variations in subgrade type and strength, it is recommended that a

- presumptive CBR value of 3% (or a modulus of subgrade reaction (k) of 20 kPa/mm for rigid pavements) be adopted for clay-bound engineered fill and residual clay material;
- a presumptive CBR value of 4% (or a modulus of subgrade reaction (k) of 23 kPa/mm for rigid pavements) be adopted for residual sands; and
- a presumptive CBR value of 6% (or a modulus of subgrade reaction (k) of 30 kPa/mm for rigid pavements) be adopted for weathered sandstone / siltstone.

In the design of either flexible sealed, unsealed granular or rigid concrete pavements, subjected to highway type vehicular trafficking. These values are based on the assumption that the earthworks will be undertaken in accordance with the recommendations in Section 10.3 and 10.7 and additional onsite CBR tests should be carried out to confirm the above presumptive CBR values.

For controlled fill depths of less than 1 m, the Japan Road Association method of assessing weighted subgrade strength can be used:

$$CBR_W = (D_F \times CBR_F^{0.33} + (1-D_F) \times CBR_S^{0.33})^3$$

where:  $CBR_W$  = weighted subgrade CBR (%)  
 $D_F$  = depth of fill (m)  
 $CBR_F$  = CBR of fill material  
 $CBR_S$  = CBR of subgrade

For loaded areas of different proportion or different load intensity to standard highway type wheel loads, DP should be contacted for further advice.

The satisfactory on-going performance of pavements is dependent on the subgrade not being allowed to become 'over-wet'. To ensure the required subgrade performance, sufficient drainage should be installed in areas where there is potential for water to enter the subgrade (i.e. adjacent to garden beds, etc).

## 10.10 Site Classification

Site classification of foundation soil reactivity strictly only applies to residential buildings up to two-storeys and to other buildings of similar size, loading and flexibility as defined in accordance with AS 2870 (2011), and would not apply to this development. Such classification, as well as the results of the laboratory testing, provide an indication of the propensity of the ground surface to move with seasonal variation in moisture content, and has been used (along with general climatic zoning and general experience) to assess the potential depth of seasonal cracking and potential for softening under soaked conditions. The following is provided for information purposes.

Due to the presence of fill of unknown compaction history (which must be considered as 'uncontrolled' fill) up to 2.7 m depth, the site would strictly be given a "Class P" classification, in accordance with AS 2870 (2011), requiring design by engineering principles.

The shrink-swell index tests reported  $I_{ss}$  values of 1.4% and 2.8 % per  $\Delta pF$  for the residual silty clay samples tested.

To provide an indication of the reactive surface movements of the residual silty clay, the highest result of the Atterberg limits and linear shrinkage tests were compared with an in-house database of plasticity and shrink-swell index ( $I_{ss}$ ) values, to estimate a presumptive  $I_{ss}$  value of 3 % per  $\Delta pF$  for the residual silty clay sample tested. Therefore, we have adopted the higher  $I_{ss}$  value for this assessment.

The presumptive  $I_{ss}$  value was input into DP's in-house program *REACTIVE*, to calculate the characteristic surface movement ( $y_s$ ) values in general accordance with AS 2870 (2011) which provides recommended values of change in suction ( $\Delta u$ ) and depth of suction ( $H_s$ ) for major and regional centres throughout Australia. More detailed published data by Fox (2000) relating climatic conditions to suction was used for this report. A value of 1.2 pF was adopted for  $\Delta u$  and 1.8 m for  $H_s$  in the *REACTIVE* calculations. This is based on a "wet temperate" climatic zone. A cracking depth of 0.9 m was used in the analysis, based on  $0.5H_s$ .



The analysis indicates that the  $y_s$  values of a full depth soil profile tested in response to seasonal moisture variation, are in the order of up to 40 mm consistent with a “Class M” (moderately reactive) classification.

Where existing site soils (i.e. natural clay) of similar reactivity won from excavation are reused as controlled fill,  $y_s$  values of up to 60 mm consistent with a “Class H1” (highly reactive) classification would result. This is due to the need to consider uncracked conditions for a five-year period following fill placement and two years following excavation.

It should be noted that for the proposed commercial building with a basement level up to 7 m depth, this will be well below the depth of seasonal moisture change of 1.8 m depth. However the site classification will be of particular importance to high level footings for any at ground structures or inground services founded close to existing ground surface levels.

It should be noted that no assessment of the effect of soil moisture change by trees has been made in this site classification (either with respect to the removal of established trees prior to development of building pads, or the proximity of established or new trees to proposed buildings). Reference to the requirements in AS2870 (2011) should be made by the building designer in this regard. It should be further noted that the presence or removal of trees can result in additional surface movement, due to tree-induced suction changes and tree-induced centre heave. Such tree-induced movement is not included in the characteristic surface movement calculations used to classify the site.

If “abnormal” soil moisture conditions are experienced, the site would be classified as “Class P” (problem site) which would require more extensive foundation works to avoid adverse foundation performance. Abnormal soil moisture conditions are defined in AS 2870 (2011) (Clause 1.3.3) and, in summary, comprise:

- Recent removal of buildings or structures likely to have affected soil moisture conditions;
- Unusual moisture caused by drains, channels, ponds, dams or tanks;
- Recent removal of large trees;
- Growth of trees planted too close to a structure;
- Excessive or irregular watering of gardens adjacent to a structure;
- Lack of maintenance of site drainage; and
- Failure to repair plumbing leaks.

### 10.11 Site Earthquake Sub- Soil Class

Following excavation to basement level, the subgrade is anticipated to comprise weathered sandstone/siltstone. In accordance with AS1170.4 (2007), it is recommended that a site sub-soil classification of “Class B<sub>e</sub> – Rock” be adopted for parts of the structure founded in rock, in accordance with the definitions presented in *Section 4.2 – Class Definitions*. This is based on a sub-soil profile of no more than 3 m of soil underlain by rock with a compressive strength of between 1 MPa and 50 MPa over the top 30 m.

For components of the structure founded close to existing ground surface levels, a site sub-soil classification of “Class C<sub>e</sub> – Shallow Soil Site” is recommended.

## 10.12 Site Erosion Potential

Fine grained and granular soils are prevalent at the site, and the Emerson class tests (Class 1, 2, 3 and 6) indicate that the near surface granular / cohesive fill, residual clayey soils are moderately to very highly dispersive. Based on the assessment, a **dispersive management plan (DSMP)** will be required for the site.

Erosion control measures at the surface will require detailed design; however, it is expected that, as a minimum, measures will need to include silt fences, hay bales and measures to limit water runoff velocity (such as swales or benches) at the downslope boundaries of the site, and prompt installation of topsoiling and grassing or hydro mulching in completed areas. A sedimentation dam may also be required where bulk earthworks operations requiring large volumes of soil disturbance at the site.

It is recommended that adequate lined collector drainage be installed at the top/crest of all batters and that all clean drainage be discharged off-site via pipes or lined channels.

## 11. Limitations

Douglas Partners Pty Ltd (DP) has prepared this report for the proposed Yeronga Priority development at Park Road, Yeronga in accordance with DP's proposal BNE200443.P.002.Rev0 dated 25 February 2021 and proposal BNE200443.01.P.001.Rev0 dated 6 October 2021 in which acceptance was received from Mr John Marshall of Economic Development Queensland dated 3 March 2021 and 5 November 2021 respectively. The work was carried out under DP's Conditions of Engagement. This report is provided for the exclusive use of Economic Development Queensland for this project only and for the purposes as described in the report. It should not be used by or relied upon for other projects or purposes on the same or other site or by a third party. Any party so relying upon this report beyond its exclusive use and purpose as stated above, and without the express written consent of DP, does so entirely at its own risk and without recourse to DP for any loss or damage. In preparing this report DP has necessarily relied upon information provided by the client and/or their agents.

The results provided in the report are indicative of the sub-surface conditions on the site only at the specific sampling and/or testing locations, and then only to the depths investigated and at the time the work was carried out. Sub-surface conditions can change abruptly due to variable geological processes and also as a result of human influences. Such changes may occur after DP's field testing has been completed.

DP's advice is based upon the conditions encountered during this investigation. The accuracy of the advice provided by DP in this report may be affected by undetected variations in ground conditions across the site between and beyond the sampling and/or testing locations. The advice may also be limited by budget constraints imposed by others or by site accessibility.

The assessment of atypical safety hazards arising from this advice is restricted to the components set out in this report and based on known project conditions and stated design advice and assumptions. While some recommendations for safe controls may be provided, detailed 'safety in design' assessment is outside the current scope of this report and requires additional project data and assessment.



This report must be read in conjunction with all of the attached and should be kept in its entirety without separation of individual pages or sections. DP cannot be held responsible for interpretations or conclusions made by others unless they are supported by an expressed statement, interpretation, outcome or conclusion stated in this report.

This report, or sections from this report, should not be used as part of a specification for a project, without review and agreement by DP. This is because this report has been written as advice and opinion rather than instructions for construction.

The scope for work for this investigation/report did not include the assessment of surface or sub-surface materials or groundwater for contaminants, within or adjacent to the site. Should evidence of filling of unknown origin be noted in the report, and in particular the presence of building demolition materials, it should be recognised that there may be some risk that such filling may contain contaminants and hazardous building materials.

## 12. References

- AS 1170.4:2007, *Structural Design Actions, Part 4: Earthquake actions in Australia*, Standards Australia.
- AS 1289.6.3.2:1997, "Methods of testing soils for engineering purposes", Standards Australia.
- AS 2159:2009, 2009, "Piling – Design and installation", Sydney, NSW: Standards Australia.
- AS 2870:2011, "Residential slabs and footings"; Standards Australia.
- AS 3798:2007, "Guidelines on earthworks for commercial and residential developments", Sydney, NSW: Standards Australia.
- AS 4678:2002, 2002, "Earth-retaining structures", Sydney, NSW: Standards Australia.
- Fox E, 2000, "A Climate-Based Design Depth of Moisture Change Map of Queensland and the Use of Such Maps to Classify Sites Under AS 2870:1996", *Australian Geomechanics*, Vol 35, No 4.
- Water Services Association (WSAA) (2002), "Water Supply Code of Australia", Water Services Association

---

**Douglas Partners Pty Ltd**

---

## Appendix A

---

About This Report  
Soil Descriptions  
Rock Descriptions  
Sampling Methods  
Symbols and Abbreviations



# About this Report

# Douglas Partners



## Introduction

These notes have been provided to amplify DP's report in regard to classification methods, field procedures and the comments section. Not all are necessarily relevant to all reports.

DP's reports are based on information gained from limited subsurface excavations and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

## Copyright

This report is the property of Douglas Partners Pty Ltd. The report may only be used for the purpose for which it was commissioned and in accordance with the Conditions of Engagement for the commission supplied at the time of proposal. Unauthorised use of this report in any form whatsoever is prohibited.

## Borehole and Test Pit Logs

The borehole and test pit logs presented in this report are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling or excavation. Ideally, continuous undisturbed sampling or core drilling will provide the most reliable assessment, but this is not always practicable or possible to justify on economic grounds. In any case the boreholes and test pits represent only a very small sample of the total subsurface profile.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes or pits, the frequency of sampling, and the possibility of other than 'straight line' variations between the test locations.

## Groundwater

Where groundwater levels are measured in boreholes there are several potential problems, namely:

- In low permeability soils groundwater may enter the hole very slowly or perhaps not at all during the time the hole is left open;

- A localised, perched water table may lead to an erroneous indication of the true water table;
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report; and
- The use of water or mud as a drilling fluid will mask any groundwater inflow. Water has to be blown out of the hole and drilling mud must first be washed out of the hole if water measurements are to be made.

More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from a perched water table.

## Reports

The report has been prepared by qualified personnel, is based on the information obtained from field and laboratory testing, and has been undertaken to current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal, the information and interpretation may not be relevant if the design proposal is changed. If this happens, DP will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface conditions, discussion of geotechnical and environmental aspects, and recommendations or suggestions for design and construction. However, DP cannot always anticipate or assume responsibility for:

- Unexpected variations in ground conditions. The potential for this will depend partly on borehole or pit spacing and sampling frequency;
- Changes in policy or interpretations of policy by statutory authorities; or
- The actions of contractors responding to commercial pressures.

If these occur, DP will be pleased to assist with investigations or advice to resolve the matter.

# *About this Report*

## **Site Anomalies**

In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, DP requests that it be immediately notified. Most problems are much more readily resolved when conditions are exposed rather than at some later stage, well after the event.

## **Information for Contractual Purposes**

Where information obtained from this report is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a specially edited document. DP would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

## **Site Inspection**

The company will always be pleased to provide engineering inspection services for geotechnical and environmental aspects of work to which this report is related. This could range from a site visit to confirm that conditions exposed are as expected, to full time engineering presence on site.





### Sampling

Sampling is carried out during drilling or test pitting to allow engineering examination (and laboratory testing where required) of the soil or rock.

Disturbed samples taken during drilling provide information on colour, type, inclusions and, depending upon the degree of disturbance, some information on strength and structure.

Undisturbed samples are taken by pushing a thin-walled sample tube into the soil and withdrawing it to obtain a sample of the soil in a relatively undisturbed state. Such samples yield information on structure and strength, and are necessary for laboratory determination of shear strength and compressibility. Undisturbed sampling is generally effective only in cohesive soils.

### Test Pits

Test pits are usually excavated with a backhoe or an excavator, allowing close examination of the in-situ soil if it is safe to enter into the pit. The depth of excavation is limited to about 3 m for a backhoe and up to 6 m for a large excavator. A potential disadvantage of this investigation method is the larger area of disturbance to the site.

### Large Diameter Augers

Boreholes can be drilled using a rotating plate or short spiral auger, generally 300 mm or larger in diameter commonly mounted on a standard piling rig. The cuttings are returned to the surface at intervals (generally not more than 0.5 m) and are disturbed but usually unchanged in moisture content. Identification of soil strata is generally much more reliable than with continuous spiral flight augers, and is usually supplemented by occasional undisturbed tube samples.

### Continuous Spiral Flight Augers

The borehole is advanced using 90-115 mm diameter continuous spiral flight augers which are withdrawn at intervals to allow sampling or in-situ testing. This is a relatively economical means of drilling in clays and sands above the water table. Samples are returned to the surface, or may be collected after withdrawal of the auger flights, but they are disturbed and may be mixed with soils from the sides of the hole. Information from the drilling (as distinct from specific sampling by SPTs or undisturbed samples) is of relatively low

reliability, due to the remoulding, possible mixing or softening of samples by groundwater.

### Non-core Rotary Drilling

The borehole is advanced using a rotary bit, with water or drilling mud being pumped down the drill rods and returned up the annulus, carrying the drill cuttings. Only major changes in stratification can be determined from the cuttings, together with some information from the rate of penetration. Where drilling mud is used this can mask the cuttings and reliable identification is only possible from separate sampling such as SPTs.

### Continuous Core Drilling

A continuous core sample can be obtained using a diamond tipped core barrel, usually with a 50 mm internal diameter. Provided full core recovery is achieved (which is not always possible in weak rocks and granular soils), this technique provides a very reliable method of investigation.

### Standard Penetration Tests

Standard penetration tests (SPT) are used as a means of estimating the density or strength of soils and also of obtaining a relatively undisturbed sample. The test procedure is described in Australian Standard 1289, Methods of Testing Soils for Engineering Purposes - Test 6.3.1.

The test is carried out in a borehole by driving a 50 mm diameter split sample tube under the impact of a 63 kg hammer with a free fall of 760 mm. It is normal for the tube to be driven in three successive 150 mm increments and the 'N' value is taken as the number of blows for the last 300 mm. In dense sands, very hard clays or weak rock, the full 450 mm penetration may not be practicable and the test is discontinued.

The test results are reported in the following form.

- In the case where full penetration is obtained with successive blow counts for each 150 mm of, say, 4, 6 and 7 as:  
4,6,7  
N=13
- In the case where the test is discontinued before the full penetration depth, say after 15 blows for the first 150 mm and 30 blows for the next 40 mm as:  
15, 30/40 mm

# *Sampling Methods*

The results of the SPT tests can be related empirically to the engineering properties of the soils.

## **Dynamic Cone Penetrometer Tests / Perth Sand Penetrometer Tests**

Dynamic penetrometer tests (DCP or PSP) are carried out by driving a steel rod into the ground using a standard weight of hammer falling a specified distance. As the rod penetrates the soil the number of blows required to penetrate each successive 150 mm depth are recorded. Normally there is a depth limitation of 1.2 m, but this may be extended in certain conditions by the use of extension rods. Two types of penetrometer are commonly used.

- Perth sand penetrometer - a 16 mm diameter flat ended rod is driven using a 9 kg hammer dropping 600 mm (AS 1289, Test 6.3.3). This test was developed for testing the density of sands and is mainly used in granular soils and filling.
- Cone penetrometer - a 16 mm diameter rod with a 20 mm diameter cone end is driven using a 9 kg hammer dropping 510 mm (AS 1289, Test 6.3.2). This test was developed initially for pavement subgrade investigations, and correlations of the test results with California Bearing Ratio have been published by various road authorities.





## Description and Classification Methods

The methods of description and classification of soils and rocks used in this report are generally based on Australian Standard AS1726:2017, Geotechnical Site Investigations. In general, the descriptions include strength or density, colour, structure, soil or rock type and inclusions.

## Soil Types

Soil types are described according to the predominant particle size, qualified by the grading of other particles present:

Type	Particle size (mm)
Boulder	>200
Cobble	63 - 200
Gravel	2.36 - 63
Sand	0.075 - 2.36
Silt	0.002 - 0.075
Clay	<0.002

The sand and gravel sizes can be further subdivided as follows:

Type	Particle size (mm)
Coarse gravel	19 - 63
Medium gravel	6.7 - 19
Fine gravel	2.36 - 6.7
Coarse sand	0.6 - 2.36
Medium sand	0.21 - 0.6
Fine sand	0.075 - 0.21

Definitions of grading terms used are:

- Well graded - a good representation of all particle sizes
- Poorly graded - an excess or deficiency of particular sizes within the specified range
- Uniformly graded - an excess of a particular particle size
- Gap graded - a deficiency of a particular particle size with the range

The proportions of secondary constituents of soils are described as follows:

In fine grained soils (>35% fines)

Term	Proportion of sand or gravel	Example
And	Specify	Clay (60%) and Sand (40%)
Adjective	>30%	Sandy Clay
With	15 - 30%	Clay with sand
Trace	0 - 15%	Clay with trace sand

In coarse grained soils (>65% coarse)

- with clays or silts

Term	Proportion of fines	Example
And	Specify	Sand (70%) and Clay (30%)
Adjective	>12%	Clayey Sand
With	5 - 12%	Sand with clay
Trace	0 - 5%	Sand with trace clay

In coarse grained soils (>65% coarse)

- with coarser fraction

Term	Proportion of coarser fraction	Example
And	Specify	Sand (60%) and Gravel (40%)
Adjective	>30%	Gravelly Sand
With	15 - 30%	Sand with gravel
Trace	0 - 15%	Sand with trace gravel

The presence of cobbles and boulders shall be specifically noted by beginning the description with 'Mix of Soil and Cobbles/Boulders' with the word order indicating the dominant first and the proportion of cobbles and boulders described together.

# Soil Descriptions

## Cohesive Soils

Cohesive soils, such as clays, are classified on the basis of undrained shear strength. The strength may be measured by laboratory testing, or estimated by field tests or engineering examination. The strength terms are defined as follows:

Description	Abbreviation	Undrained shear strength (kPa)
Very soft	VS	<12
Soft	S	12 - 25
Firm	F	25 - 50
Stiff	St	50 - 100
Very stiff	VSt	100 - 200
Hard	H	>200
Friable	Fr	-

## Cohesionless Soils

Cohesionless soils, such as clean sands, are classified on the basis of relative density, generally from the results of standard penetration tests (SPT), cone penetration tests (CPT) or dynamic penetrometers (PSP). The relative density terms are given below:

Relative Density	Abbreviation	Density Index (%)
Very loose	VL	<15
Loose	L	15-35
Medium dense	MD	35-65
Dense	D	65-85
Very dense	VD	>85

## Soil Origin

It is often difficult to accurately determine the origin of a soil. Soils can generally be classified as:

- Residual soil - derived from in-situ weathering of the underlying rock;
- Extremely weathered material – formed from in-situ weathering of geological formations. Has soil strength but retains the structure or fabric of the parent rock;
- Alluvial soil – deposited by streams and rivers;

- Estuarine soil – deposited in coastal estuaries;
- Marine soil – deposited in a marine environment;
- Lacustrine soil – deposited in freshwater lakes;
- Aeolian soil – carried and deposited by wind;
- Colluvial soil – soil and rock debris transported down slopes by gravity;
- Topsoil – mantle of surface soil, often with high levels of organic material.
- Fill – any material which has been moved by man.

## Moisture Condition – Coarse Grained Soils

For coarse grained soils the moisture condition should be described by appearance and feel using the following terms:

- Dry (D) Non-cohesive and free-running.
- Moist (M) Soil feels cool, darkened in colour.  
Soil tends to stick together.  
Sand forms weak ball but breaks easily.
- Wet (W) Soil feels cool, darkened in colour.  
Soil tends to stick together, free water forms when handling.

## Moisture Condition – Fine Grained Soils

For fine grained soils the assessment of moisture content is relative to their plastic limit or liquid limit, as follows:

- 'Moist, dry of plastic limit' or 'w < PL' (i.e. hard and friable or powdery).
- 'Moist, near plastic limit' or 'w ≈ PL' (i.e. soil can be moulded at moisture content approximately equal to the plastic limit).
- 'Moist, wet of plastic limit' or 'w > PL' (i.e. soils usually weakened and free water forms on the hands when handling).
- 'Wet' or 'w ≈ LL' (i.e. near the liquid limit).
- 'Wet' or 'w > LL' (i.e. wet of the liquid limit).





## Rock Strength

Rock strength is defined by the Unconfined Compressive Strength and it refers to the strength of the rock substance and not the strength of the overall rock mass, which may be considerably weaker due to defects.

The Point Load Strength Index  $Is_{(50)}$  is commonly used to provide an estimate of the rock strength and site specific correlations should be developed to allow UCS values to be determined. The point load strength test procedure is described by Australian Standard AS4133.4.1-2007. The terms used to describe rock strength are as follows:

Strength Term	Abbreviation	Unconfined Compressive Strength MPa	Point Load Index * $Is_{(50)}$ MPa
Very low	VL	0.6 - 2	0.03 - 0.1
Low	L	2 - 6	0.1 - 0.3
Medium	M	6 - 20	0.3 - 1.0
High	H	20 - 60	1 - 3
Very high	VH	60 - 200	3 - 10
Extremely high	EH	>200	>10

\* Assumes a ratio of 20:1 for UCS to  $Is_{(50)}$ . It should be noted that the UCS to  $Is_{(50)}$  ratio varies significantly for different rock types and specific ratios should be determined for each site.

## Degree of Weathering

The degree of weathering of rock is classified as follows:

Term	Abbreviation	Description
Residual Soil	RS	Material is weathered to such an extent that it has soil properties. Mass structure and material texture and fabric of original rock are no longer visible, but the soil has not been significantly transported.
Extremely weathered	XW	Material is weathered to such an extent that it has soil properties. Mass structure and material texture and fabric of original rock are still visible
Highly weathered	HW	The whole of the rock material is discoloured, usually by iron staining or bleaching to the extent that the colour of the original rock is not recognisable. Rock strength is significantly changed by weathering. Some primary minerals have weathered to clay minerals. Porosity may be increased by leaching, or may be decreased due to deposition of weathering products in pores.
Moderately weathered	MW	The whole of the rock material is discoloured, usually by iron staining or bleaching to the extent that the colour of the original rock is not recognisable, but shows little or no change of strength from fresh rock.
Slightly weathered	SW	Rock is partially discoloured with staining or bleaching along joints but shows little or no change of strength from fresh rock.
Fresh	FR	No signs of decomposition or staining.
<i>Note: If HW and MW cannot be differentiated use DW (see below)</i>		
Distinctly weathered	DW	Rock strength usually changed by weathering. The rock may be highly discoloured, usually by iron staining. Porosity may be increased by leaching or may be decreased due to deposition of weathered products in pores.

# Rock Descriptions

## Degree of Fracturing

The following classification applies to the spacing of natural fractures in diamond drill cores. It includes bedding plane partings, joints and other defects, but excludes drilling breaks.

Term	Description
Fragmented	Fragments of <20 mm
Highly Fractured	Core lengths of 20-40 mm with occasional fragments
Fractured	Core lengths of 30-100 mm with occasional shorter and longer sections
Slightly Fractured	Core lengths of 300 mm or longer with occasional sections of 100-300 mm
Unbroken	Core contains very few fractures

## Rock Quality Designation

The quality of the cored rock can be measured using the Rock Quality Designation (RQD) index, defined as:

$$\text{RQD \%} = \frac{\text{cumulative length of 'sound' core sections} \geq 100 \text{ mm long}}{\text{total drilled length of section being assessed}}$$

where 'sound' rock is assessed to be rock of low strength or stronger. The RQD applies only to natural fractures. If the core is broken by drilling or handling (i.e. drilling breaks) then the broken pieces are fitted back together and are not included in the calculation of RQD.

## Stratification Spacing

For sedimentary rocks the following terms may be used to describe the spacing of bedding partings:

Term	Separation of Stratification Planes
Thinly laminated	< 6 mm
Laminated	6 mm to 20 mm
Very thinly bedded	20 mm to 60 mm
Thinly bedded	60 mm to 0.2 m
Medium bedded	0.2 m to 0.6 m
Thickly bedded	0.6 m to 2 m
Very thickly bedded	> 2 m



# Symbols & Abbreviations

## Douglas Partners



### Introduction

These notes summarise abbreviations commonly used on borehole logs and test pit reports.

### Drilling or Excavation Methods

C	Core drilling
R	Rotary drilling
SFA	Spiral flight augers
NMLC	Diamond core - 52 mm dia
NQ	Diamond core - 47 mm dia
HQ	Diamond core - 63 mm dia
PQ	Diamond core - 81 mm dia

### Water

▷	Water seep
▽	Water level

### Sampling and Testing

A	Auger sample
B	Bulk sample
D	Disturbed sample
E	Environmental sample
U <sub>50</sub>	Undisturbed tube sample (50mm)
W	Water sample
pp	Pocket penetrometer (kPa)
PID	Photo ionisation detector
PL	Point load strength Is(50) MPa
S	Standard Penetration Test
V	Shear vane (kPa)

### Description of Defects in Rock

The abbreviated descriptions of the defects should be in the following order: Depth, Type, Orientation, Coating, Shape, Roughness and Other. Drilling and handling breaks are not usually included on the logs.

### Defect Type

B	Bedding plane
Cs	Clay seam
Cv	Cleavage
Cz	Crushed zone
Ds	Decomposed seam
F	Fault
J	Joint
Lam	Lamination
Pt	Parting
Sz	Sheared Zone
V	Vein

### Orientation

The inclination of defects is always measured from the perpendicular to the core axis.

h	horizontal
v	vertical
sh	sub-horizontal
sv	sub-vertical

### Coating or Infilling Term

cln	clean
co	coating
he	healed
inf	infilled
stn	stained
ti	tight
vn	veneer

### Coating Descriptor

ca	calcite
cbs	carbonaceous
cly	clay
fe	iron oxide
mn	manganese
slt	silty

### Shape

cu	curved
ir	irregular
pl	planar
st	stepped
un	undulating

### Roughness

po	polished
ro	rough
sl	slickensided
sm	smooth
vr	very rough

### Other

fg	fragmented
bnd	band
qtz	quartz

# Symbols & Abbreviations

## Graphic Symbols for Soil and Rock


### General



Asphalt



Road base



Concrete



Filling


### Soils




Topsoil



Peat



Clay




Silty clay




Sandy clay




Gravelly clay




Shaly clay




Silt




Clayey silt




Sandy silt



Sand



Clayey sand



Silty sand



Gravel



Sandy gravel



Cobbles, boulders



Talus

### Sedimentary Rocks



Boulder conglomerate




Conglomerate




Conglomeratic sandstone




Sandstone



Siltstone




Laminite



Mudstone, claystone, shale




Coal




Limestone


### Metamorphic Rocks



Slate, phyllite, schist




Gneiss



Quartzite


### Igneous Rocks




Granite




Dolerite, basalt, andesite



Dacite, epidote



Tuff, breccia



Porphyry



---

## **Appendix B**


---

Drawing 1 - Site and Test Location Plan






Location Plan



**LEGEND:-**

 Borehole Location and Number


**NOTE:-**

1. Test locations are approximate only and are shown with reference to existing site features.
2. Image obtained from Metromap. Date of imagery 27-09-2020.







Location Plan



**LEGEND:-**

-  Borehole Location and Number
-  Approximate Site Boundary

**NOTE:-**

- Test locations are approximate only and are shown with reference to existing site features.
- Image obtained from Metromap. Date of imagery 24-09-2021.



---

## Appendix C

---

Field Work Results











# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 17.8 mAHD  
**EASTING:** 502043  
**NORTHING:** 6956295  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 1  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)
				Type	Depth	Sample	Results & Comments		
17.1	1	FILL Gravelly Sandy CLAY (Cl): medium plasticity, brown, fine to coarse sand, fine to medium gravel, w>PL, very stiff  - becoming hard		D	0.1				
				D	0.5		5,9,10 N = 19		
				S	0.95				
16.2	2	Sandy CLAY (Cl): medium plasticity, grey, fine to medium sand, w<PL, hard (Residual)  - becoming grey mottled orange-brown			2.0		15,17,17 N = 34		
				S	2.45				
					3.5		30/140mm		
14.4	4	SANDSTONE: fine to medium, grey with red and orange-brown, very low strength, highly weathered (Aspley Formation)		S	3.64				
					5.0		30/100mm		
				S	5.1				
12.5	6	Bore discontinued at 6.1m depth - Limit of investigation			6.0		30/50mm		
				S	6.05				

**RIG:** Hydrapower Scout 3

**DRILLER:** Ground Test

**LOGGED:** NS

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit. Well installed to 6m

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 19.1 mAH  
**EASTING:** 502050  
**NORTHING:** 6956267  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 2  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)
				Type	Depth	Sample	Results & Comments		
19.0		FILL Gravelly Sandy CLAY (CL): low plasticity, brown, fine to coarse sand, trace fine to medium gravel, w~PL, hard		D	0.1				
				D	0.5				
		- becoming very stiff to hard		S	0.9		6, 11, 30/100mm		
18.0	1								
17.0	2	Silty CLAY (CI): medium plasticity, pale grey mottled red and orange-brown, trace fine sand, w<PL, very stiff (Residual)		S	2.0		7, 10, 9 N = 19		
					2.45				
16.0	2.8	Sandy CLAY (CI): medium plasticity, pale grey with red and orange, fine to coarse sand, trace fine to medium gravel, w~PL, very stiff (Residual)							
				S	3.5		10, 15, 22 N = 37		
					3.95				
				S	5.0		15, 24, 30 N = 54		
		- becoming grey mottled red-brown, hard			5.45				
15.0	4								
14.0	5								
13.0	6								
12.0	6.8	SANDSTONE: fine to medium, grey with red and orange-brown, very low strength, highly weathered (Aspley Formation)		S	6.5		12, 20, 30/120mm		
					6.92				
				S	7.5		9, 30/110mm		
	7.8	Bore discontinued at 7.8m depth - Limit of investigation			7.76				
11.0	8								
10.0	9								
9.0	10								

**RIG:** Hydrapower Scout 3

**DRILLER:** Ground Test

**LOGGED:** NS

**CASING:** HQ to 2.5m

**TYPE OF BORING:** Auger to 2.5m, washbore to depth of termination

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)








# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 18.4 mAHD  
**EASTING:** 502021  
**NORTHING:** 6956279  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 3  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)
				Type	Depth	Sample	Results & Comments		
18 17 16 15 14 13 12 11 10 9 8	1.0	FILL Gravelly Sandy CLAY (CI): medium plasticity, fine to coarse sand, trace fine to medium gravel, w~PL, hard		D	0.1				5 10 15 20
				D	0.2				
	1.0	Silty CLAY (CI): medium plasticity, grey mottled red and orange-brown, w~PL, hard (Residual)		S	0.5				5 10 15 20
				S	1.0		12,21,20 N = 41		
				S	1.45				
				S	2.5		9,19,25 N = 44		
	4.7	Sandy CLAY (CL): low plasticity, grey mottled red-brown, fine to medium sand, w~PL, hard (Residual)		S	2.95				5 10 15 20
				S	4.0		14,20,28 N = 48		
				S	4.45				
				S	5.5		10,20,29 N = 49		
	6.5	SANDSTONE: fine to medium, grey with red and orange-brown, very low strength, highly weathered (Aspley Formation)		S	5.95				5 10 15 20
				S	7.0		30/55mm		
				S	7.06				
				S	8.5		30/80mm		
10	10.05	- very low to low strength Bore discontinued at 10.05m depth - Limit of investigation		S	8.58				5 10 15 20
				S	10.0		30/30mm		
				S	10.03				

**RIG:** Hydrapower Scout 3

**DRILLER:** Ground Test

**LOGGED:** NS

**CASING:**

**TYPE OF BORING:** Auger to 3m, washbore to depth of termination

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND











A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 18.4 mAHD  
**EASTING:** 501992  
**NORTHING:** 6956288  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 4  
**PROJECT No:** 200443.00  
**DATE:** 11/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)
				Type	Depth	Sample	Results & Comments		
18	0.0	FILL Sandy CLAY (CI-CH): medium to high plasticity, brown, fine to coarse sand, trace fine to medium gravel, w~PL, very stiff to hard  - trees, cobbles (possible old fill/foundation)		D	0.0				5
				D	0.2				
1	0.5	Silty CLAY (CI): medium plasticity, grey with orange and pale red-brown, w~PL, hard (Residual)  - becoming grey mottled pale red-brown		S	0.5		30/75mm		10
				S	0.58				
17	2.0	- hard		S	2.0		3, 30/148mm		2
				S	2.15				
16	2.3	Gravelly Sandy CLAY (CL): low plasticity, grey mottled red and orange-brown, fine to coarse sand, fine to medium gravel, w~PL, hard (Residual)  - becoming grey		S	2.3				3
				S	2.15				
15	3.5	SANDSTONE: fine to medium, grey with red and orange-brown, very low strength, highly weathered (Aspley Formation)  - becoming low strength		S	3.5		30/30mm		4
				S	3.58				
14	5.0			S	5.0		30/90mm		5
				S	5.09				
13	6.5			S	6.5		30/70mm		6
				S	6.57				
12	8.0			S	8.0		30/80mm		8
				S	8.06				
11	9.5			S	9.5		30/30mm		9
				S	9.53				
10	10.0	Bore discontinued at 10.0m depth - Limit of investigation							10

**RIG:** Hydrapower Scout 3

**DRILLER:** Ground Test

**LOGGED:** NS

**CASING:** HQ to 2.5m

**TYPE OF BORING:** Auger to 2.5m, washbore to depth of termination

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PLD	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 10.1 mAH  
**EASTING:** 502123  
**NORTHING:** 6956405  
**DIP/AZIMUTH:** 90°/--

**BORE No: 5**  
**PROJECT No: 200443.00**  
**DATE: 10/3/2021**  
**SHEET 1 OF 1**

[illegible]

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** Groundwater seepage observed at 1.2m

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test (s(50) (MPa)
		PL(D)	Point load diametral test (s(50) (MPa)
		pp	Pepp penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 9.6 mAHD  
**EASTING:** 502094  
**NORTHING:** 6956413  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 6  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)
				Type	Depth	Sample	Results & Comments		
	0.5	FILL Gravelly SAND (SM): fine to coarse, brown, fine to coarse gravel, trace cobbles, dry, medium dense to dense							
	0.5	FILL Gravelly CLAY (CL): low plasticity, brown with grey, fine to coarse gravel, with fine to coarse sand and gravels, with cobbles, w<PL, very stiff		S	0.5		8,9,15 N = 24		
	1.4	Silty SAND (SM): fine, dark grey, moist, estimated medium dense (Residual)							
	1.8	- grey, with clay, trace medium gravel							
	2.0	Clayey SAND (SC): fine, grey, trace medium gravel, moist, loose (Residual)		S	2.0		2,3,4 N = 7		
	2.45	Sandy CLAY (CH): high plasticity, pale grey mottled orange-brown, fine to medium sand, w>PL, firm (Residual)							
	3.5	- medium plasticity, pale grey with red and orange-brown, w~PL, stiff		S	3.5		5,8,13 N = 21		
	3.95	- very stiff							
	3.95	Bore discontinued at 3.95m depth - Limit of investigation			3.95				

**RIG:** Hydrapower Scout 3

**DRILLER:** Ground Test

**LOGGED:** NS

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)





# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 13.4 mAHD  
**EASTING:** 502050  
**NORTHING:** 6956365  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 7  
**PROJECT No:** 200443.00  
**DATE:** 11/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
13.0		FILL Sandy GRAVEL (GM): fine to coarse, brown-grey, fine to coarse sand, moist, dense to very dense										
		- medium dense		S	0.5		6,7,15 N = 22					
1.1				S	0.95							
1.3		SANDSTONE: fine to medium, grey with orange and red-brown, very low strength, highly weathered (Aspley Formation)		S	1.2		30/70mm					
		Bore discontinued at 1.3m depth - Refusal on very low strength or stronger sandstone			1.27							
2												
3												
4												
5												
6												
7												
8												
9												
10												

**RIG:** Christie

**DRILLER:** Geoserve

**LOGGED:** NS

**CASING:** Uncased

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 12.1 mAHD  
**EASTING:** 502019  
**NORTHING:** 6956408  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 8  
**PROJECT No:** 200443.00  
**DATE:** 11/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
12.1	0.0	Sandy CLAY (CL): low plasticity, brown mottled grey, fine to coarse sand, with relict rock structure, w>PL, hard (Residual)										
	0.8	SANDSTONE: fine to medium, grey and orange-brown, very low strength, highly weathered (Aspley Formation)		S	0.5		18, 28, 30/130mm					
	1.0				0.93							
	1.4	Bore discontinued at 1.4m depth - Refusal on very low strength or stronger sandstone		S	1.3		30/100mm					
	1.4				1.4							
	2.0											
	3.0											
	4.0											
	5.0											
	6.0											
	7.0											
	8.0											
	9.0											
	10.0											

**RIG:** Christie

**DRILLER:** Geoserve

**LOGGED:** NS

**CASING:** Uncased

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U <sub>s</sub>	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 18.3 mAHd  
**EASTING:** 502010  
**NORTHING:** 6956303  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 10  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET** 1 OF 1

[illegible]

**CASING:** Uncased

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 8.5 mAHD  
**EASTING:** 502098  
**NORTHING:** 6956427  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 12  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

[illegible]

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit. Well installed to 3m

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U <sub>s</sub>	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W <sub>s</sub>	Water seep
E	Environmental sample	W <sub>l</sub>	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)





# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 10.0 mAHD  
**EASTING:** 502083  
**NORTHING:** 6956398  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 13  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
10		FILL Sandy GRAVEL (GM): fine to coarse, brown, fine to coarse sand, dry, dense										
0.6												
0.8		Silty CLAY (CH): high plasticity, grey mottled orange-brown, with fine to coarse sand, w~PL, stiff (Residual)		D	0.7							
1				S	1.0		10, 30/50mm					
		Sandy CLAY (CL): low plasticity, orange with grey, fine to medium sand, w<PL, very stiff (Residual)			1.2							
		- grey mottled orange-brown, hard										
		- with some interbedded very low strength, highly weathered sandstone layers										
2												
		- very stiff			2.5		4,11,15 N = 26					
3				S	2.95							
		- hard										
		- becoming red-brown			3.5		22,25,23 N = 48					
4	4.0	Bore discontinued at 4.0m depth - Limit of investigation			3.95							
5												
6												
7												
8												
9												
10												

**RIG:** Christie

**DRILLER:** Geoserve

**LOGGED:** NS

**CASING:** Uncased

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND








A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 8.5 mAHD  
**EASTING:** 502077  
**NORTHING:** 6956432  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 14  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing			Water	Dynamic Penetrometer Test (blows per 100mm)
				Type	Depth	Sample		
	0.4	FILL Silty SAND (SM): fine, dark grey-brown, dry, dense - grey-brown		D	0.1			
		CLAY (CH): high plasticity, grey mottled orange-brown, trace fine to coarse sand, w~PL, stiff (Residual)		D	0.5		pp >350	
		- with trace fine gravel		U <sub>50</sub>	0.7			
					0.8			
					1.0			
	1.2	Sandy CLAY (Cl): medium plasticity, grey mottled orange-brown, fine to coarse sand, trace fine to medium gravel, w<PL, hard (Residual)		S			7,15,22 N = 37	
					1.45			
								
					2.5		14, 24, 30/30mm	
		- pale grey, with relict rock structure (extremely weathered sandstone)		S				
					2.83			
								
					3.5		12,17,25 N = 42	
				S				
					3.95			
	4.0	Bore discontinued at 4.0m depth - Limit of investigation						

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 13.7 mAH  
**EASTING:** 502079  
**NORTHING:** 6956321  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 15  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET** 1 OF 1

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)													
				Type	Depth	Sample	Results & Comments		5	10	15	20										
13.1	0.1	FILL Sandy GRAVEL (GM): fine to coarse, brown-grey, fine to coarse sand, moist, medium dense		S	0.5		3,7,8 N = 15															
12.1	1	FILL Sandy CLAY (CL): low plasticity, brown, fine to coarse sand, with fine to coarse gravel and cobbles, w>PL, stiff												0.95								
11.2	2	- with clay, firm												2.0								
11.1	2.4	Silty CLAY (CH): high plasticity, dark grey, w>PL, firm to soft (Residual)			2.45		2,3,3 N = 6															
10.3	3	- grey																				
10.3	3.3	- stiff		S	3.5		5,7,9 N = 16															
10.0	4	Sandy CLAY (CL): low plasticity, pale grey mottled orange-brown, fine to medium sand, w<PL, very stiff (Residual)																				
9.4	4.0	Bore discontinued at 4.0m depth - Limit of investigation			3.95																	
8.5	5																					
7.8	6																					
6.7	7																					
5.6	8																					
4.5	9																					
3.4	10																					

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U <sub>s</sub>	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W <sub>s</sub>	Water seep
E	Environmental sample	W <sub>l</sub>	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)





# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 16.4 mAHD  
**EASTING:** 502098  
**NORTHING:** 6956291  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 16  
**PROJECT No:** 200443.00  
**DATE:** 11/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
16		FILL Gravelly CLAY (CL): low plasticity, grey, fine to coarse gravel, with fine to coarse sand and cobbles, w<PL, hard			0.5		10,12,24 N = 36					
1				S	0.95							
1.3		FILL CLAY (CH): high plasticity, grey with brown-orange and red-brown, trace fine to coarse sand and gravel, w~PL, stiff			2.0		2,4,5 N = 9					
2				S	2.45							
2.7		Silty CLAY (CH): high plasticity, grey mottled orange-brown, w>PL, stiff (Residual)			3.5		3,6,5 N = 11					
3		- pale grey mottled orange-brown - stiff		S	3.95							
4	4.0	Bore discontinued at 4.0m depth - Limit of investigation										
5												
6												
7												
8												
9												
10												

**RIG:** Christie

**DRILLER:** Geoserve

**LOGGED:** NS

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 17.0 mAHd  
**EASTING:** 502071  
**NORTHING:** 6956268  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 17  
**PROJECT No:** 200443.00  
**DATE:** 11/3/2021  
**SHEET 1 OF 1**

[illegible]

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 9.3 mAHD  
**EASTING:** 502037  
**NORTHING:** 6956435  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 18  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

[illegible]

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U <sub>s</sub>	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W <sub>s</sub>	Water seep
E	Environmental sample	W <sub>l</sub>	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)










# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 11.8 mAHd  
**EASTING:** 502017  
**NORTHING:** 6956418  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 19  
**PROJECT No:** 200443.00  
**DATE:** 11/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing			Water	Dynamic Penetrometer Test (blows per 100mm)
				Type	Depth	Sample		
	0.2	FILL Gravelly SAND (SM): fine to coarse, brown, fine to coarse gravel, with cobbles, with clay, moist, medium dense						
11	0.7	FILL Sandy CLAY (CL): low plasticity, brown with grey, fine to coarse sand, with fine to coarse gravel, w>PL, stiff		S	0.5		3,13,22 N = 35	
1		Sandy CLAY (CL): low plasticity, pale grey mottled orange-brown, fine to medium sand, trace fine to medium gravel, w<PL, hard (Residual) - with interbedded very low strength, highly weathered sandstone			0.95			1
10					2.0		21, 18, 30/110mm	2
2	2.3	SANDSTONE: fine to medium, pale grey and orange-brown, very low strength, highly weathered (Aspley Formation)		S	2.41			
9	3.01	- very low to low strength		S	3.0		30/10mm	3
3		Bore discontinued at 3.01m depth - Refusal on very low to low strength or stronger sandstone			3.01			
8								4
4								5
7								6
6								7
5								8
4								9
8								10
9								
2								
10								

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test (s(50) (MPa)
		PL(D)	Point load diametral test (s(50) (MPa)
		pp	Pocket penetrometer (kPa)
		SP	Standard penetration test
		V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 14.0 mAH  
**EASTING:** 502027  
**NORTHING:** 6956375  
**DIP/AZIMUTH:** 90°/-

**BORE No:** 20  
**PROJECT No:** 200443.00  
**DATE:** 11/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
14.0	0.2	FILL Sandy CLAY (CL): low plasticity, brown with grey, fine to coarse sand, trace fine to coarse gravel, w<PL, very stiff		D	0.2							
	0.3			S	0.5		30/70mm					
	0.6	Sandy CLAY (CI): medium plasticity, pale grey mottled orange-brown, w<PL, Hard (Residual)			0.57							
	1.0	SANDSTONE: fine to medium grained, pale grey and orange-brown, very low strength, highly weathered (Aspley Formation)										
	1.5	Bore discontinued at 0.6m depth - Refusal on very low to low strength or stronger sandstone										
	2.0											
	3.0											
	4.0											
	5.0											
	6.0											
	7.0											
	8.0											
	9.0											
	10.0											

**RIG:** Christie

**DRILLER:** Geoserve

**LOGGED:** NS

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND





A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 17.1 mAH  
**EASTING:** 502006  
**NORTHING:** 6956336  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 21  
**PROJECT No:** 200443.00  
**DATE:** 11/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)				
				Type	Depth	Sample	Results & Comments		5	10	15	20	
17		FILL Silty SAND (SM): fine to coarse, brown, with fine to coarse gravel, trace cobble, building rubble, moist, dense		D	0.0 0.1								
	0.4	Silty CLAY (CH): high plasticity, grey mottled red-brown, with fine sand, w~PL, stiff (Residual)		D S	0.5		3,4,4 N = 8						
1	1.0	Sandy CLAY (CL): low plasticity, grey mottled orange-brown, fine to medium sand, w<PL, hard (Residual)			0.95				1				
	1.3	SANDSTONE: fine to medium, grey with orange-brown, very low strength, highly weathered (Aspley Formation)											
		- pale grey with red-brown, with relict rock structure (extremely weathered sandstone)			2.0		15, 30/120mm		2				
		- very low to low strength		S	2.27								
	3.14	Bore discontinued at 3.14m depth - Refusal on very low to low strength or stronger sandstone		S	3.1 3.14		30/40mm (hammer bounce)		3				
	4								4				
	5								5				
	6								6				
	7								7				
	8								8				
	9								9				
	10								10				

**RIG:** Christie

**DRILLER:** Geoserve

**LOGGED: NS**

**CASING:**

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit.

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)







# BOREHOLE LOG

**CLIENT:** Economic Development Queensland  
**PROJECT:** Yeronga Priority Development Area  
**LOCATION:** Park Road, Yeronga

**SURFACE LEVEL:** 12.1 mAHD  
**EASTING:** 502119  
**NORTHING:** 6956343  
**DIP/AZIMUTH:** 90°/--

**BORE No:** 22  
**PROJECT No:** 200443.00  
**DATE:** 10/3/2021  
**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																
				Type	Depth	Sample	Results & Comments		5	10	15	20																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
12		FILL Gravelly Sandy CLAY (Cl): medium plasticity, brown, fine to coarse sand, fine to coarse gravel, with cobbles and boulders, w~PL, stiff to hard - stiff		D	0.0		3,2,6 N = 8																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		</

**RIG:** Christie

**DRILLER:** Geoserve

**LOGGED:** NS

**CASING:** Uncased

**TYPE OF BORING:** Auger

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit. Well installed to 4m

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Block sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	W	Water seep
E	Environmental sample	W	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test Is(50) (MPa)
		PL(D)	Point load diametral test Is(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Turner & Townsend Pty Ltd

**PROJECT:** Proposed PDA Civil Works - Additional Investigation

**LOCATION:** 701 Park Road, Yeronga

**SURFACE LEVEL:** 18.5 mAH

**EASTING:** 501998.2

**NORTHING:** 6956277.3

**DIP/AZIMUTH:** 90°/-

**BORE No:** 23

**PROJECT No:** 200443.01

**DATE:** 13/12/2022

**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)				Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																		
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium		High	Very High	Ex High	0.01	0.05	0.10	0.50	1.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
	18	FILL CLAY (CH): high plasticity, pale grey, w~PL, estimated firm																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					

**RIG:** DRILLER: MK Drilling  
**TYPE OF BORING:** Auger to 7m depth, then NMLC to 10m depth

**LOGGED:** SP/JB

**CASING:** Uncased

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit

## SAMPLING & IN SITU TESTING LEGEND

A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)
B Bulk sample	P Piston sample	PL(A) Point load axial test (50) (MPa)
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test (50) (MPa)
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)
D Disturbed sample	W Water seep	S Standard penetration test
E Environmental sample	W Water level	V Shear vane (kPa)

# BOREHOLE LOG

**CLIENT:** Turner & Townsend Pty Ltd

**PROJECT:** Proposed PDA Civil Works - Additional Investigation

**LOCATION:** 701 Park Road, Yeronga

**SURFACE LEVEL: 18.5 mAHD**

**EASTING:** 501998.2

**NORTHING:** 6956277.3

**DIP/AZIMUTH:** 90°/--

**BORE No: 23**

**PROJECT No:** 200443.01

**DATE:** 13/12/2022

**SHEET 2 OF 2**

[illegible]

RIG: DRILLER: MK Drilling

**LOGGED:** SP/JB

**CASING:** Uncased

**TYPE OF BORING:** Auger to 7m depth, then NMLC to 10m depth

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit

SAMPLING & IN SITU TESTING LEGEND					
A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)





# BOREHOLE LOG

**CLIENT:** Turner & Townsend Pty Ltd

**PROJECT:** Proposed PDA Civil Works - Additional Investigation

**LOCATION:** 701 Park Road, Yeronga

**SURFACE LEVEL:** 18.3 mAH

**EASTING:** 502016.1

**NORTHING:** 6956287.3

**DIP/AZIMUTH:** 90°/-

**BORE No:** 24

**PROJECT No:** 200443.01

**DATE:** 13/12/2022

**SHEET** 1 OF 2

RL	Depth (m)	Description of Strata	Degree of Weathering					Graphic Log	Rock Strength					Water	Fracture Spacing (m)				Discontinuities		Sampling & In Situ Testing																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																													
			EW	HW	MW	SW	FS		FR	Ex Low	Very Low	Low	Medium		High	Very High	Ex High	0.01	0.05	0.10	0.50	1.00	B - Bedding S - Shear	J - Joint F - Fault	Type	Core Rec. %	RQD %	Test Results & Comments																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
18.3	0.6	FILL Sandy CLAY (CL): low plasticity, pale grey, fine to medium sand, w<PL. estimated firm																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																

Bore discontinued at 10.0m depth -  
Limit of investigation

**RIG:** DRILLER: MK Drilling

**LOGGED:** SP/JB

**CASING:** Uncased

**TYPE OF BORING:** Auger to 5.5m depth, then NMLC to 10m depth

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit

## SAMPLING & IN SITU TESTING LEGEND

A Auger sample	G Gas sample	PID Photo ionisation detector (ppm)
B Bulk sample	P Piston sample	PL(A) Point load axial test (50) (MPa)
BLK Block sample	U Tube sample (x mm dia.)	PL(D) Point load diametral test (50) (MPa)
C Core drilling	W Water sample	pp Pocket penetrometer (kPa)
D Disturbed sample	W Water seep	S Standard penetration test
E Environmental sample	W Water level	V Shear vane (kPa)



**Douglas Partners**  
Geotechnics | Environment | Groundwater

# BOREHOLE LOG

**CLIENT:** Turner & Townsend Pty Ltd

**PROJECT:** Proposed PDA Civil Works - Additional Investigation

**LOCATION:** 701 Park Road, Yeronga

**SURFACE LEVEL:** 18.3 mAHD

EASTING: 502016.1

**NORTHING:** 6956287.3

**DIP/AZIMUTH:** 90°/--

**BORE No: 24**

**PROJECT No:** 200443.01

**DATE:** 13/12/2022

**SHEET 2 OF 2**

[illegible]

**RIG:** **DRILLER:** MK Drilling

**LOGGED: SP/JB**

**CASING:** Uncased

**TYPE OF BORING:** Auger to 5.5m depth, then NMLC to 10m depth

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit

## SAMPLING & IN SITU TESTING LEGEND

SAMPLING & IN SITU TESTING LEGEND			
A	Auger sample	G	Gas sample
B	Bulk sample	P	Piston sample
BLK	Blank sample	U	Tube sample (x mm dia.)
C	Core drilling	W	Water sample
D	Disturbed sample	≡	Water seep
E	Environmental sample	≡	Water level
		PID	Photo ionisation detector (ppm)
		PL(A)	Point load axial test ts(50) (MPa)
		PL(D)	Point load diametral test ts(50) (MPa)
		pp	Pocket penetrometer (kPa)
		S	Standard penetration test
		V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Turner & Townsend Pty Ltd

**PROJECT:** Proposed PDA Civil Works - Additional Investigation

**LOCATION:** 701 Park Road, Yeronga

**SURFACE LEVEL:** 18.3 mAHD

**EASTING:** 501997

**NORTHING:** 6956293.8






**DIP/AZIMUTH:** 90°/--

**BORE No:** 25

**PROJECT No:** 200443.01

**DATE:** 24/11/2021

**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)
				Type	Depth	Sample	Results & Comments		
18.3	0.6	FILL Sandy CLAY (Cl): medium plasticity, pale brown with orange-brown, fine to medium sand, trace fine to medium gravel, w<PL, stiff - very stiff		D	0.5				
17.7	1.0	Silty CLAY (Cl): medium plasticity, grey mottled orange-brown, trace fine sand, w<PL, very stiff (Residual) - very stiff		D	0.6				
17.0	1.9	- hard		S	1.0		6,11,16 N = 27		
16.1	2.4	SILTSTONE: fine grained, pale brown and orange-brown, very low strength, highly weathered, with interbedded relict rock structure (Aspley Formation) - very low to low strength		S	1.45				
15.7	2.4	Bore discontinued at 2.4m depth - Refusal on probable low to medium strength siltstone		S	2.4		30/30mm		
15.3					2.43				
14.9									
14.5									
14.1									
13.7									
13.3									
12.9									
12.5									
12.1									
11.7									
11.3									
10.9									
10.5									
10.1									
9.7									
9.3									
8.9									
8.5									
8.1									
7.7									
7.3									
6.9									
6.5									
6.1									
5.7									
5.3									
4.9									
4.5									
4.1									
3.7									
3.3									
2.9									
2.5									
2.1									
1.7									
1.3									
0.9									
0.5									
0.1									

**RIG:** **DRILLER:** Geoserve

**LOGGED:** Geoserve/SP

**CASING:** Uncased

**TYPE OF BORING:** Auger to 2.4m depth

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	W	Water level	V	Shear vane (kPa)



# BOREHOLE LOG

**CLIENT:** Turner & Townsend Pty Ltd

**PROJECT:** Proposed PDA Civil Works - Additional Investigation

**LOCATION:** 701 Park Road, Yeronga

**SURFACE LEVEL:** 18.8 mAHD

**EASTING:** 502012.6

**NORTHING:** 6956274.9

**DIP/AZIMUTH:** 90°/-

**BORE No:** 26

**PROJECT No:** 200443.01

**DATE:** 24/11/2021

**SHEET 1 OF 1**

RL	Depth (m)	Description of Strata	Graphic Log	Sampling & In Situ Testing				Water	Dynamic Penetrometer Test (blows per 100mm)			
				Type	Depth	Sample	Results & Comments		5	10	15	20
	0.2	TOPSOIL FILL Sandy CLAY (CL): low plasticity, dark brown and grey, fine to medium sand, trace fine to coarse gravel, with some organics, w>PL, soft		D	0.2							
	0.5	FILL Gravelly CLAY (CI): medium plasticity, light grey with orange-brown, fine to coarse gravel, with fine to coarse sand, w>PL, hard		D	0.5							
	1.0	Silty CLAY (CL): low plasticity, pale grey mottled red-brown, trace fine sand, with relict rock structure, w<PL, hard (Residual)		S	1.0		14,20,25 N = 45					
	1.45	- hard			1.45							
	2.5			S	2.5		5, 30/140mm					
	2.79				2.79							
	4.0	- grey mottled orange-brown		S	4.0		22, 30/120mm					
	4.15	SANDSTONE: fine to medium grained, red-brown and orange-brown, very low strength, highly weathered, with interbedded relict rock structure (Aspley Formation)			4.27							
	5.5			S	5.5		8, 30/120mm					
	5.77	- very low to low strength			5.77							
	6.4			S	6.4		30/70mm					
	6.48	Bore discontinued at 6.48m depth - Refusal on probable low to medium strength sandstone			6.48							

**RIG:** **DRILLER:** Geoserve

**LOGGED:** Geoserve/SP

**CASING:** Uncased

**TYPE OF BORING:** Auger to 6.4m depth

**WATER OBSERVATIONS:** No free groundwater observed

**REMARKS:** w = moisture content, PL = plastic limit

☐ Sand Penetrometer AS1289.6.3.3  
☒ Cone Penetrometer AS1289.6.3.2

## SAMPLING & IN SITU TESTING LEGEND

A	Auger sample	G	Gas sample	PID	Photo ionisation detector (ppm)
B	Bulk sample	P	Piston sample	PL(A)	Point load axial test Is(50) (MPa)
BLK	Block sample	U	Tube sample (x mm dia.)	PL(D)	Point load diametral test Is(50) (MPa)
C	Core drilling	W	Water sample	pp	Pocket penetrometer (kPa)
D	Disturbed sample	W	Water seep	S	Standard penetration test
E	Environmental sample	WL	Water level	V	Shear vane (kPa)

---

## Appendix D

---

Laboratory Results

# Material Test Report

**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-10260A  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 17/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 16, Depth: 0.50 - 0.95 m  
**Material:** Fill /Gravelly CLAY



Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	3		
Soil Description	As per material description		
Nature of Water	De-ionized		
Temperature of Water (°C)	22.6		



# Material Test Report

**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-10260B  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 17/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 7, Depth: 0.50 - 0.95 m  
**Material:** Fill/ Sandy GRAVEL



Accredited for compliance with ISO/IEC 17025 - Testing

Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	1		
Soil Description	As per material description		
Nature of Water	De-ionized		
Temperature of Water (°C)	22.6		

# Material Test Report

**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-10260C  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 17/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 2, Depth: 0.50 m  
**Material:** Fill/ Gravelly Sandy CLAY



Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	1		
Soil Description	As per material description		
Nature of Water	De-ionized		
Temperature of Water (°C)	22.6		

# Material Test Report

**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-10260D  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 17/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 19, Depth: 0.50 m  
**Material:** Fill/ Sandy CLAY



Accredited for compliance with ISO/IEC 17025 - Testing

Approved Signatory: Aimee Cartwright  
Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	3		
Soil Description	As per material description		
Nature of Water	De-ionized		
Temperature of Water (°C)	22.6		



# Material Test Report

**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-10260E  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 17/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 21, Depth: 0.50 - 0.95 m  
**Material:** Silty CLAY



Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	6		
Soil Description	As per material description		
Nature of Water	De-ionized		
Temperature of Water (°C)	22.6		

# Material Test Report



Accredited for compliance with ISO/IEC 17025 - Testing

Approved Signatory: Aimee Cartwright


Laboratory Technician

Laboratory Accreditation Number: 828

**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-10260F  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 17/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 14, Depth: 0.50 - 0.80 m  
**Material:** CLAY

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	6		
Soil Description	As per material description		
Nature of Water	De-ionized		
Temperature of Water (°C)	22.6		
Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)			
Iss (%)	2.8		
Visual Description	Silty CLAY		
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.			
Core Shrinkage Test			
Shrinkage Strain - Oven Dried (%)	4.7		
Estimated % by volume of significant inert inclusions	10		
Cracking	Slightly Cracked		
Crumbling	No		
Moisture Content (%)	21.0		
Swell Test			
Initial Pocket Penetrometer (kPa)	460		
Final Pocket Penetrometer (kPa)	320		
Initial Moisture Content (%)	24.2		
Final Moisture Content (%)	24.6		
Swell (%)	0.5		
* NATA Accreditation does not cover the performance of pocket penetrometer readings.			

Shrink Swell



# Material Test Report



Accredited for compliance with ISO/IEC 17025 - Testing

Approved Signatory: Aimee Cartwright  
Laboratory Technician

Laboratory Accreditation Number: 828


**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-10260G  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 15/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 17, Depth: 1.20 - 1.70 m  
**Material:** Silty CLAY

Shrink Swell Index (AS 1289 7.1.1 & 2.1.1)	
Iss (%)	1.4
Visual Description	Silty CLAY
* Shrink Swell Index (Iss) reported as the percentage vertical strain per pF change in suction.	

Core Shrinkage Test	
Shrinkage Strain - Oven Dried (%)	2.6
Estimated % by volume of significant inert inclusions	20
Cracking	Slightly Cracked
Crumbling	No
Moisture Content (%)	18.8

Swell Test	
Initial Pocket Penetrometer (kPa)	200
Final Pocket Penetrometer (kPa)	240
Initial Moisture Content (%)	31.0
Final Moisture Content (%)	33.4
Swell (%)	-0.0

\* NATA Accreditation does not cover the performance of pocket penetrometer readings.





# Material Test Report

**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-10260H  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 17/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 13, Depth: 0.70 m  
**Material:** Silty CLAY



Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	62		
Plastic Limit (%)	22		
<b>Plasticity Index (%)</b>	<b>40</b>		
Weighted Plasticity Index (%)	2676		
Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	14.0		
Cracking Crumbling Curling	Curling		
Moisture Content (AS 1289 2.1.1)			
Moisture Content (%)		21.2	

# Material Test Report

**Report Number:** 200443.00-1  
**Issue Number:** 1  
**Date Issued:** 23/03/2021  
**Client:** Economic Development Queensland  
 GPO Box 2202, Brisbane QLD 4001  
**Contact:** John Marshall  
**Project Number:** 200443.00  
**Project Name:** Yeronga Priority Development Area  
**Project Location:** Park Road, Yeronga  
**Work Request:** 10260  
**Sample Number:** BN-102601  
**Date Sampled:** 10/03/2021  
**Dates Tested:** 15/03/2021 - 17/03/2021  
**Sampling Method:** Sampled by Others  
*The results apply to the sample as received*  
**Sample Location:** Bore 3, Depth: 1.00 - 1.45 m  
**Material:** Silty CLAY



Accredited for compliance with ISO/IEC 17025 - Testing

Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Atterberg Limit (AS1289 3.1.2 & 3.2.1 & 3.3.1)		Min	Max
Sample History	Oven Dried		
Preparation Method	Dry Sieve		
Liquid Limit (%)	39		
Plastic Limit (%)	23		
<b>Plasticity Index (%)</b>	<b>16</b>		
Weighted Plasticity Index (%)	1269		

Linear Shrinkage (AS1289 3.4.1)		Min	Max
Moisture Condition Determined By	AS 1289.3.1.2		
Linear Shrinkage (%)	9.0		
Cracking Crumbling Curling	None		

Moisture Content (AS 1289 2.1.1)	
Moisture Content (%)	14.7

# Material Test Report

**Report Number:** 200443.01-2  
**Issue Number:** 1  
**Date Issued:** 16/12/2021  
**Client:** Turner & Townsend Pty Ltd  
GPO Box 627, BRISBANE QLD 4001Q  
**Contact:** Lachlan Rigney  
**Project Number:** 200443.01  
**Project Name:** Proposed PDA Civil Works - Additional Investigation  
**Project Location:** 701 Park Road, Yeronga QLD  
**Work Request:** 12115  
**Sample Number:** BN-12115A  
**Date Sampled:** 13/12/2021  
**Dates Tested:** 14/12/2021 - 16/12/2021  
**Sampling Method:** Sampled by DP Brisbane Engineering Department  
*The results apply to the sample as received*  
**Sample Location:** BH 23 , Depth: 0.50m  
**Material:** Fill CLAY



Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	2		
Soil Description	As per material description		
Nature of Water	Distilled		
Temperature of Water (°C)	23		

pH Value of Soil (AS 1289 4.3.1)	
Depth	0.50 m
pH	3.9
Electrical Conductivity (µS/cm)	



# Material Test Report

**Report Number:** 200443.01-2  
**Issue Number:** 1  
**Date Issued:** 16/12/2021  
**Client:** Turner & Townsend Pty Ltd  
GPO Box 627, BRISBANE QLD 4001Q  
**Contact:** Lachlan Rigney  
**Project Number:** 200443.01  
**Project Name:** Proposed PDA Civil Works - Additional Investigation  
**Project Location:** 701 Park Road, Yeronga QLD  
**Work Request:** 12115  
**Sample Number:** BN-12115B  
**Date Sampled:** 13/12/2021  
**Dates Tested:** 14/12/2021 - 16/12/2021  
**Sampling Method:** Sampled by DP Brisbane Engineering Department  
*The results apply to the sample as received*  
**Sample Location:** BH 24 , Depth: 0.50m  
**Material:** Fill Sandy CLAY



Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	3		
Soil Description	As per material description		
Nature of Water	Distilled		
Temperature of Water (°C)	23		
pH Value of Soil (AS 1289 4.3.1)			
Depth		0.50 m	
pH		3.7	
Electrical Conductivity (µS/cm)			

# Material Test Report

**Report Number:** 200443.01-1  
**Issue Number:** 1  
**Date Issued:** 07/12/2021  
**Client:** Turner & Townsend Pty Ltd  
GPO Box 627, BRISBANE QLD 4001Q  
**Contact:** Lachlan Rigney  
**Project Number:** 200443.01  
**Project Name:** Proposed PDA Civil Works - Additional Investigation  
**Project Location:** 701 Park Road, Yeronga QLD  
**Work Request:** 12043  
**Sample Number:** BN-12043A  
**Date Sampled:** 24/11/2021  
**Dates Tested:** 01/12/2021 - 06/12/2021  
**Sampling Method:** Sampled by DP Brisbane Engineering Department  
*The results apply to the sample as received*  
**Sample Location:** BH 25 , Depth: 0.20 - 0.50 m  
**Material:** Fill Sandy CLAY



Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	6		
Soil Description	As per material description		
Nature of Water	Distilled		
Temperature of Water (°C)	23		
pH Value of Soil (AS 1289 4.3.1)			
Depth		0.20-0.50m	
pH		6.1	
Electrical Conductivity (µS/cm)			

# Material Test Report

**Report Number:** 200443.01-1  
**Issue Number:** 1  
**Date Issued:** 07/12/2021  
**Client:** Turner & Townsend Pty Ltd  
GPO Box 627, BRISBANE QLD 4001Q  
**Contact:** Lachlan Rigney  
**Project Number:** 200443.01  
**Project Name:** Proposed PDA Civil Works - Additional Investigation  
**Project Location:** 701 Park Road, Yeronga QLD  
**Work Request:** 12043  
**Sample Number:** BN-12043B  
**Date Sampled:** 24/11/2021  
**Dates Tested:** 01/12/2021 - 06/12/2021  
**Sampling Method:** Sampled by DP Brisbane Engineering Department  
*The results apply to the sample as received*  
**Sample Location:** BH 26 , Depth: 0.50 m  
**Material:** Silty CLAY



Accredited for compliance with ISO/IEC 17025 - Testing



Approved Signatory: Aimee Cartwright

Laboratory Technician

Laboratory Accreditation Number: 828

Emerson Class Number of a Soil (AS 1289 3.8.1)		Min	Max
Emerson Class	2		
Soil Description	As per material description		
Nature of Water	Distilled		
Temperature of Water (°C)	23		

pH Value of Soil (AS 1289 4.3.1)	
Depth	0.50m
pH	3.8
Electrical Conductivity (µS/cm)	



## CERTIFICATE OF ANALYSIS

**Work Order** : **EB2136417**  
**Client** : **DOUGLAS PARTNERS PTY LTD**  
**Contact** : MR MARC SALCOR  
**Address** : 439 MONTAGUE ROAD  
                   WEST END QLD, AUSTRALIA 4101  
**Telephone** : +61 07 3237 8900  
**Project** : Proposed Heart Commercial Building  
**Order number** : 200443.01  
**C-O-C number** : ----  
**Sampler** : Shebin  
**Site** : ----  
**Quote number** : EN/222  
**No. of samples received** : 4  
**No. of samples analysed** : 4

**Page** : 1 of 3  
**Laboratory** : Environmental Division Brisbane  
**Contact** : John Pickering  
**Address** : 2 Byth Street Stafford QLD Australia 4053  
  
**Telephone** : +61 7 3552 8634  
**Date Samples Received** : 14-Dec-2021 11:57  
**Date Analysis Commenced** : 17-Dec-2021  
**Issue Date** : 24-Dec-2021 12:26



This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted, unless the sampling was conducted by ALS. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

**Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QA/QC Compliance Assessment to assist with Quality Review and Sample Receipt Notification.**

### Signatories

This document has been electronically signed by the authorized signatories below. Electronic signing is carried out in compliance with procedures specified in 21 CFR Part 11.

<i>Signatories</i>	<i>Position</i>	<i>Accreditation Category</i>
Ben Felgendrejeris	Senior Acid Sulfate Soil Chemist	Brisbane Acid Sulphate Soils, Stafford, QLD
Mark Hallas	Senior Inorganic Chemist	Brisbane Acid Sulphate Soils, Stafford, QLD



## General Comments

The analytical procedures used by ALS have been developed from established internationally recognised procedures such as those published by the USEPA, APHA, AS and NEPM. In house developed procedures are fully validated and are often at the client request.

Where moisture determination has been performed, results are reported on a dry weight basis.

Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

When sampling time information is not provided by the client, sampling dates are shown without a time component. In these instances, the time component has been assumed by the laboratory for processing purposes.

Where a result is required to meet compliance limits the associated uncertainty must be considered. Refer to the ALS Contact for details.

Key : CAS Number = CAS registry number from database maintained by Chemical Abstracts Services. The Chemical Abstracts Service is a division of the American Chemical Society.  
 LOR = Limit of reporting  
 ^ = This result is computed from individual analyte detections at or above the level of reporting  
 Ø = ALS is not NATA accredited for these tests.  
 ~ = Indicates an estimated value.

- ALS is not NATA accredited for the analysis of Exchangeable Aluminium and Exchange Acidity in soils when performed under ALS Method ED005.
- ALS is not NATA accredited for the analysis of Exchangeable Cations on Alkaline Soils when performed under ALS Method ED006.
- ED006 (Exchangeable Cations on Alkaline Soils): Unable to calculate Magnesium/Potassium Ratio result as required Exchangeable Potassium results are less than the limit of reporting.
- ED007 and ED008: When Exchangeable Al is reported from these methods, it should be noted that Rayment & Lyons (2011) suggests Exchange Acidity by 1M KCl - Method 15G1 (ED005) is a more suitable method for the determination of exchange acidity (H<sup>+</sup> + Al<sup>3+</sup>).

## Analytical Results

Sub-Matrix: SOIL  
 (Matrix: SOIL)

Sample ID

				BH23-0.5	BH24-0.5	BH25-0.5	BH26-0.5	----
Sampling date / time				13-Dec-2021 00:00	13-Dec-2021 00:00	13-Dec-2021 00:00	13-Dec-2021 00:00	----
Compound	CAS Number	LOR	Unit	EB2136417-001	EB2136417-002	EB2136417-003	EB2136417-004	-----
				Result	Result	Result	Result	----
<b>EA002: pH 1:5 (Soils)</b>								
pH Value	----	0.1	pH Unit	9.2	9.3	9.3	8.6	----
<b>EA010: Conductivity (1:5)</b>								
Electrical Conductivity @ 25°C	----	1	µS/cm	272	701	698	158	----
<b>ED006: Exchangeable Cations on Alkaline Soils</b>								
Ø Exchangeable Calcium	----	0.2	meq/100g	0.3	<0.2	9.2	1.9	----
Ø Exchangeable Magnesium	----	0.2	meq/100g	2.9	1.8	3.6	2.4	----
Ø Exchangeable Potassium	----	0.2	meq/100g	<0.2	<0.2	<0.2	0.2	----
Ø Exchangeable Sodium	----	0.2	meq/100g	3.0	1.4	3.3	2.2	----
Ø Cation Exchange Capacity	----	0.2	meq/100g	6.4	3.2	16.3	6.7	----
Ø Exchangeable Sodium Percent	----	0.2	%	46.7	42.4	20.5	33.1	----
Ø Calcium/Magnesium Ratio	----	0.2	-	<0.2	<0.2	2.6	0.8	----
Ø Magnesium/Potassium Ratio	----	0.2	-	----	----	----	9.8	----





**With every community, we redefine what's possible.**

Stantec is a global leader in sustainable engineering, architecture, and environmental consulting. The diverse perspectives of our partners and interested parties drive us to think beyond what's previously been done on critical issues like climate change, digital transformation, and future-proofing our cities and infrastructure. We innovate at the intersection of community, creativity, and client relationships to advance communities everywhere, so that together we can redefine what's possible.



**Stantec Australia Pty Ltd**  
Level 3, 52 Merivale Street  
South Brisbane QLD 4101  
AUSTRALIA  
ABN 17 007 820 322  
[stantec.com](http://stantec.com)