

PROPOSED RESIDENTIAL DEVELOPMENT

HOMESTEAD DRIVE, MONARCH GLEN



TRUNK SEWER (PACKAGE 2)

TRUNK SEWER MAIN

24-0750-1600	TRUNK SEWER COVER PLAN
24-0750-1601	TRUNK SEWER GENERAL NOTES
24-0750-1602	TRUNK SEWER MAIN MH CONSTRUCTION NOTES SHEET 1 OF 2
24-0750-1603	TRUNK SEWER MAIN MH CONSTRUCTION NOTES SHEET 2 OF 2
24-0750-1605	TRUNK SEWER KEY PLAN
24-0750-1610	TRUNK SEWER MAIN LAYOUT PLAN SHEET 1 OF 3
24-0750-1611	TRUNK SEWER MAIN LAYOUT PLAN SHEET 2 OF 3
24-0750-1612	TRUNK SEWER MAIN LAYOUT PLAN SHEET 3 OF 3
24-0750-1614	TRUNK SEWER LONGITUDINAL SECTIONS SHEET 1 OF 3
24-0750-1615	TRUNK SEWER LONGITUDINAL SECTIONS SHEET 2 OF 3
24-0750-1616	TRUNK SEWER LONGITUDINAL SECTIONS SHEET 3 OF 3

REFERENCE DRAWINGS

LW-SEW-DWG-0020 (B)	GENERAL NOTES SHEET 1 OF 4
LW-SEW-DWG-0021 (B)	GENERAL NOTES SHEET 2 OF 4
LW-SEW-DWG-0022 (B)	GENERAL NOTES SHEET 3 OF 4
LW-SEW-DWG-0023 (B)	GENERAL NOTES SHEET 4 OF 4
LW-SEW-DWG-0024 (B)	GENERAL STRUCTURAL NOTES SHEET 1 OF 2
LW-SEW-DWG-0025 (B)	GENERAL STRUCTURAL NOTES SHEET 2 OF 2
LW-SEW-DWG-2000 (B)	COVER SHEET AND DRAWING LIST
LW-SEW-DWG-2050 (A)	TYPICAL INTERNALLY LINED MAINTENANCE HOLE DETAILS SHEET 1 OF 3
LW-SEW-DWG-2051 (A)	TYPICAL INTERNALLY LINED MAINTENANCE HOLE DETAILS SHEET 2 OF 3
LW-SEW-DWG-2052 (A)	TYPICAL INTERNALLY LINED MAINTENANCE HOLE DETAILS SHEET 3 OF 3
LW-SEW-DWG-2053 (A)	TYPICAL TYPE 'D' MAINTENANCE HOLE MODIFIED P3 MAINTENANCE HOLE
LW-SEW-DWG-2100 (A)	TYPICAL MAINTENANCE STRUCTURE DETAILS ON EXISTING GRAVITY SEWER
LW-SEW-DWG-2101 (A)	MISCELLANEOUS CONNECTION DETAILS
LW-SEW-DWG-2102 (A)	PE TO PVC CONNECTION DETAILS
LW-SEW-DWG-2103 (A)	TYPICAL DIAMETER SEWER CONNECTION TO EXISTING
LW-SEW-DWG-2120 (A)	MAINTENANCE HOLE TYPICAL PVC INTERNAL DROP DETAILS



LOCALITY PLAN
SCALE 1:5000 (A1)
SCALE 1:10000 (A3)

PROJECT INFORMATION SUMMARY:

RP DESCRIPTION LOT 1 ON SP35125
DATUM LEVEL AND LOCATION P.S.M. 61261 RL 52.921 AHD LOCATED LOCAL
LOCAL AUTHORITY: LOGAN CITY COUNCIL
LOGAN WATER REFERENCE NUMBER: TBC

REFERENCE DOCS:

- LOT CALCS - REV G - VERIS RECEIVED 16/06/25
- DTM SURVEY - REV B - VERIS RECEIVED 16/06/25
- DESIGN BASED ON FS94 COORDINATE SYSTEM.
- ROL4 BEW PACKAGE - COLLIERS (SEPERATE PACKAGE)



PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL
Approval no: DEV2025/1683
Date: 27 October 2025



REV	DATE	DESIGN	DRAWN	REVISION DETAILS	DRAWN	STATUS	SCALE	CLIENT	PROJECT NAME	DRAWING TITLE
A	17.03.25	BR	BR	ORIGINAL ISSUE	BR	NOT FOR CONSTRUCTION	1:2500 50 0 50 100 A1 1:5000		MONARCH GLEN No. 1 PTY LTD	TRUNK SEWER COVER PLAN
B	02.04.25	BR	BR	CLIENT UPDATES	BR	APPROVED DANIEL COLLINS RPEQ 18631 DATE 22.08.25			TRUNK SEWER MAIN - PACKAGE 2 HOMESTEAD DRIVE MONARCH GLEN	PROJECT No. 24-0750
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE	BR	FOR AND ON BEHALF OF COLLIERS INTERNATIONAL ENGINEERING & DESIGN PTY LTD				DRAWING No. 1600
D	22.08.25	BR	BR	RFI RESPONSE	BR					REVISION D

1. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH CURRENT SOUTH EAST QUEENSLAND WATER AND SEWERAGE BOARD SPECIFICATIONS AND STANDARDS (SEQCODE).
2. UNLESS SPECIFIED OTHERWISE ALL MATERIALS AND WORK SHALL COMPLY WITH THE RELEVANT AUSTRALIAN STANDARDS.
3. THE CONSTRUCTION OF THE WORK SHOWN ON THIS DRAWING SHALL BE SUPERVISED BY AN ENGINEER WHO HAS RPEQ REGISTRATION. WORKS NOT COMPLYING WITH THIS REQUIREMENT WILL NOT BE PERMITTED TO CONNECT INTO THE SEQ SERVICE PROVIDER.
4. ALL DESIGN AND CONSTRUCTION ACTIVITIES UNDERTAKEN SHALL COMPLY WITH CURRENT WORKPLACE HEALTH AND SAFETY REQUIREMENTS AND LEGISLATION/
5. ALL PIPES AND MATERIALS SHALL COMPLY WITH THE REQUIREMENTS OF THE "ACCEPTED PRODUCTS AND MATERIALS" LIST.
6. WHERE PIPES ARE LAID IN FILL, THE FILLING SHALL BE TESTED BY A NATA CERTIFIED TEST LABORATORY IN ACCORDANCE WITH THE SEQ CODE. IN ALL SUCH CASES APPROVAL OF CONSTRUCTED WORKS WILL NOT BE ISSUED BY THE SEQ SERVICE PROVIDER UNLESS CERTIFICATES ARE PRODUCED CERTIFYING THAT THE REQUIRED COMPACTION HAS BEEN ACHIEVED.
7. WHERE PIPES HAVE A GRADE OF 1 IN 20 OR STEEPER, BULKHEADS OR TRENCHSTOPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH SEQ-SEW-1206-1.
8. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DEPTH OF EXISTING SERVICES WITH RELEVANT AUTHORITIES BEFORE COMMENCING WORKS.
9. EXISTING MAINS SHALL BE DISUSED /ABANDONED IN ACCORDANCE WITH PROCEDURES SET OUT IN THE SEQ CODE.
10. HOLD POINT: ONCE THE BASE OF MANHOLES HAVE BEEN POURED, CONSTRUCTION SHALL ONLY RE-COMMENCE ONCE THE SUPERINTENDENT AND/OR ENGINEER HAVE INSPECTED THE WORKS
11. BENCH MARK AND LEVELS TO AHD.
12. THE CONTRACTOR SHALL SUPPLY ALL LABOR, MATERIALS, PLANT AND EQUIPMENT TO CONSTRUCT THE WORKS AS DOCUMENTED AND STRICTLY IN ACCORDANCE WITH THE RELEVANT AUTHORITY STANDARDS, SPECIFICATIONS AND REQUIREMENTS.
13. EXISTING SERVICES RELEVANT TO THE PROJECT HAVE BEEN CONSIDERED THROUGHOUT DESIGN AND IS BASED ON SURVEY INFORMATION PROVIDED BY THE SURVEYOR AND THE CONTRACTOR. THE RPEQ WHO CERTIFIED THE DESIGN OR THE PRINCIPAL'S CONSTRUCTION RPEQ HAVE RELIED UPON THIS INFORMATION TO INFORM THE DESIGN. THE CONTRACTOR SHALL VERIFY THE POSITION OF ANY UNDERGROUND SERVICES WITHIN THE AREAS OF WORKS AND SHALL BE RESPONSIBLE FOR MAKING GOOD ANY DAMAGE THERETO. ANY ALTERATION WORKS TO SERVICES WILL BE CARRIED OUT ONLY BY THE SERVICE OWNER AUTHORITY UNLESS APPROVED OTHERWISE.
14. PRIOR TO COMMENCING WORK, THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL RELEVANT LOCAL AUTHORITY PERMITS.
15. THE CONTRACTOR SHALL NOT COMMENCE THE DEMOLITION OF ANY EXISTING BUILDINGS AND/OR STRUCTURES WITHOUT APPROVAL FROM THE SUPERINTENDENT.
16. THE CONTRACTOR SHALL APPLY INDUSTRY BEST PRACTICE SO WORKS SHALL NOT DISTURB OR AFFECT NEARBY RESIDENTS EITHER BY DUST, NOISE, FLOODING OR DISCONNECTION OF SERVICES. CONTRACTOR TO ENSURE THAT ACCESS AND SERVICES TO EXISTING PROPERTIES ARE AVAILABLE AT ALL TIMES.
17. THE CERTIFICATION OF THIS DESIGN IS BASED ON SURVEY AND POTHOLE INFORMATION PROVIDED BY THE SURVEYOR AND/OR CONTRACTOR AT THE TIME OF DESIGN. PRIOR TO COMMENCEMENT OF WORKS, THE CONTRACTOR SHALL VERIFY LEVELS OF EXISTING SERVICE CROSSINGS AND CONNECTION POINTS AND NOTIFY THE RPEQ WHO CERTIFIED THE DESIGN OR THE PRINCIPAL'S CONSTRUCTION RPEQ OF ANY DISCREPANCIES BETWEEN ACTUAL AND PROPOSED DESIGN LEVELS. THE CERTIFICATION OF THIS DESIGN IS BASED ON SURVEY AND POTHOLE INFORMATION PROVIDED BY THE SURVEYOR AND CONTRACTOR AT THE TIME OF DESIGN.
18. THESE ENGINEERING DRAWINGS ARE TO BE READ IN CONJUNCTION WITH THE APPROVED VEGETATION MANAGEMENT PLAN, WHERE APPLICABLE. WHEN IN DOUBT, ALL EXISTING TREES ARE TO REMAIN UNLESS DIRECTED OTHERWISE.
19. THE CONTRACTOR SHALL NOTE DURING THE COURSE OF THE WORKS WHEN JOINT INSPECTIONS WITH THE AUTHORITY AND THE SUPERINTENDENT ARE REQUIRED. THESE INCLUDE PRE-STARTS, SUBGRADES, PRE-SEALS, CLEARING, AND OTHER SUCH INSPECTIONS AS NOMINATED DURING THE PRE-START, IN THE APPROVAL AND THE SPECIFICATIONS. THE CONTRACTOR SHALL ENSURE NO WORKS PROCEED PAST THE INSPECTION POINT UNTIL THE JOINT INSPECTION HAS BEEN SUCCESSFULLY COMPLETED.
20. ALL EXISTING ROADS THAT ARE DISTURBED DURING THE WORKS ARE TO BE REINSTATED

1. ALL WORK ASSOCIATED WITH LIVE SEWERS OR MAINTENANCE HOLES SHALL BE CARRIED OUT BY THE SEQ SERVICE PROVIDER AT THE DEVELOPER'S COST.
2. SEWERS SHALL BE DISUSED/ABANDONED IN ACCORDANCE WITH PROCEDURE SET OUT IN THE GRAVITY SEWER CODE.
3. DETECTABLE MARKER TAPE SHALL BE USED FOR ALL SEWER PIPES (EXCEPT FOR PIPE IN A STEEL ENVELOPER PIPE) IN ACCORDANCE WITH SEQ STANDARD DRAWING SEQ-SEW-1200 SERIES AND SEQ CODE STANDARDS.
4. CONCRETE FOR MH CONSTRUCTION SHALL BE SPECIAL CLASS TO WSA PS-358 WITH REQUIREMENT OF CALCAREOUS AGGREGATES.
5. CONSTRUCTION OF PAVEMENT IN UNSEALED ROAD SHOULDERS SHALL BE IN ACCORDANCE WITH SEQ STANDARD DRAWING SEQ-SEW-1205-1.
6. FOR CAST-IN-SITU MAINTENANCE HOLES, COPING AND ANCHOR BRACKETS TO BE AS PER SEQ-SEW-1301-1, WITH AMENDMENTS AS SHOWN ON DETAIL DRAWING FOR PE LINED MANHOLES NECKS
 - TOP SLAB REINFORCEMENT TO BE AS PER SEQ-SEW-1301-26-A
7. FOR POLYETHYLENE LINER (PE LINER) MAINTENANCE HOLES REFER TO SEQ-SEW-1101-6 A FOR INSTALLATION REQUIREMENTS



3. WHERE CONNECTING TO EXISTING PIPEWORK, THE LEVEL AND DIAMETER OF THE EXISTING PIPEWORK, SHALL BE CONFIRMED BY THE CONTRACTOR, PRIOR TO CONNECTION.
9. ALL FLANGES SHALL BE IN ACCORDANCE WITH AS 4087, CLASS 14 FOR CAST IRON AND, CLASS 16 FOR DUCTILE IRON AND STEEL, UNO.
10. ALL BACKING PLATES, NUTS, BOLTS AND WASHERS TO BE A MINIMUM GRADE 316 STAINLESS STEEL. COAT THE THREADED SECTIONS OF ALL STAINLESS STEEL BOLTS WITH AN ANTI-SEIZE LUBRICANT
11. INSTALL VALVE IDENTIFICATION CAP ON ALL SPINDLES.
12. GASKET MATERIAL TO COMPLY WITH AS4087 AND IN ACCORDANCE WITH WSA 109.
13. ALL FLANGE BOLT HOLE ORIENTATIONS SHALL BE OFF-CENTRE UNO.
14. ALL FLANGE BOLT SETS SHALL BE GRADE 316 STAINLESS STEEL. REFER AS 4087 - TABLE C1 FOR CLASS.
15. FLANGE GASKET MATERIAL AND THICKNESS SHALL BE IN ACCORDANCE WITH AS 4087 - TABLE C1.
16. THRUST AND PUDDLE FLANGES SHALL BE CAST CENTRALLY WITHIN WALLS UNLESS SHOWN OTHERWISE.
17. ALL SPIGOT AND SOCKET DCL PIPEWORK SHALL BE CLASS PN35.
18. ALL GATE AND REFLUX VALVES SHALL BE INTERNALLY AND EXTERNALLY COATED WITH A POLYMERIC COATING. ALL GATE VALVES SHALL BE RESILIENT SEATED. ALL REFLUX VALVES SHALL BE RESILIENT SEATED SWING FLEX CHECK VALVE OR SIMILAR APPROVED TOP OPENING VALVE.
19. DUCTILE IRON FITTINGS MAY BE USED WITH DI & PVC PIPE. FITTINGS SHALL BE FBE COATED AND LINED. CEMENT LINED WITH A BITUMINOUS EXTERNAL COATING MAY BE USED WITH APPROVAL. DO NOT USE PVC FITTINGS.
20. PE SLEEVING, COLOURED FOR THE PRODUCT IS REQUIRED ON ALL DI PIPE AND FITTINGS APPLIED IN ACCORDANCE WITH AS 3681. TWO THICKNESS REQUIRED BETWEEN FITTINGS AND THRUST BLOCK. REINSTATE ANY DAMAGED SLEEVING AS PER MANUFACTURER'S SPECIFICATIONS.
21. DI SPIGOTS SHALL NOT BE FITTED INTO PVC SOCKETS.

1. PVC PIPE SHALL NOT BE IN CONTACT WITH THRUST BLOCK CONCRETE.
2. MAXIMUM SIZE OF DRILLED HOLES FOR SERVICE CONNECTIONS IN PVC PIPE TO BE 30% OF DN OR 50 (LOWER VALUE TO BE USED).
3. PVC PIPE SHALL NOT BE BENT OR CURVED

1. PLACEMENT OF EMBEDMENT, TRENCHFILL & COMPACTION TO MEET THE REQUIREMENTS OF THE SEQ CODE AND DESIGN DRAWINGS.
2. EXCAVATE OR COMPACT TRENCH FLOOR TO PROVIDE A FLAT FIRM BASE TO SUPPORT BEDDING MATERIAL AND MINIMISE PIPELINE SETTLEMENT. WHEN EXCAVATED, REPLACE WITH GRANULAR MATERIAL AS SPECIFIED FOR BEDDING OR ADOPT SUPPORT AS REQUIRED.
3. WHERE ADDITIONAL SUPPORT IS REQUIRED THIS SHALL BE REFERRED TO GEO-TECHNICAL ENGINEER FOR REVIEW. SUPPORT SHALL BE INSTALLED AT A MINIMUM DEPTH OF 300 WITH A 20mm NOMINAL SIZE CRUSHED ROCK COMPLYING WITH TABLE G2 OR G3 OF AS2566.2. ADDITIONAL BEDDING SHALL BE WRAPPED WITH GEOTEXTILE TO FORM A SEPARATE GEOTECHNICAL PILLOW FOUNDATION FOR PIPE EMBEDMENT.
4. ENSURE BEDDING IS DEEP ENOUGH THAT PIPE JOINT PROJECTIONS (SOCKETS, FLANGES) DO NOT TOUCH TRENCH FLOOR.
5. GEOTEXTILE BIDIM A24 OR APPROVED EQUIVALENT TO BE USED WHERE TRENCH FILL IS A MIGRATORY NATIVE SOIL OR SAND OR FINE CLAY MATERIAL, AND WHERE SPECIFIED IN THE DESIGN.
6. LAY GEOTEXTILE FILTER FABRIC AGAINST TRENCH FLOOR AND WALLS SUCH THAT IT FULLY ENCASES THE EMBEDMENT AND SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS REQUIREMENTS.
 - PRESS FABRIC INTO THE VOIDS BEFORE INSTALLING EMBEDMENT TO PREVENT FABRIC TEARING.
 - PROVIDE A MINIMUM OF 250 OVERLAP AT ALL FABRIC JOINTS.
7. PURCHASE SPECIFICATIONS FOR EMBEDMENT MATERIAL ARE DETAILED IN THE SEQ CODE ACCEPTED PRODUCTS AND MATERIALS LIST. TRENCH FILL SHALL COMPLY WITH SEQ-SEW-1200-2. 10. DETECTABLE MARKER TAPE SHALL BE PROVIDED EITHER ABOVE THE EMBEDMENT ZONE OR 1000 BELOW THE F.S.L, WHICHEVER IS CLOSEST TO F.S.L
8. MARKER TAPE SHALL BE DETECTABLE TYPE IN ACCORDANCE WITH IPAM LIST, COLOUR CREAM FOR NON-PRESSURE AND PRESSURE SEWERAGE. THE TAPE SHALL BE MARKED "CAUTION SEWER BURIED BELOW"
9. TEMPORARY OR SHORT TERM BATTERS (UP TO 4 WEEKS) CAN BE CONSTRUCTED TO THE GRADIENTS PRESENTED IN TABLE 7 OF REPORT 8043 – 24-231.
10. USE TYPE 4 EMBEDMENT WITH GEOFABRIC WRAPPING IN ALL DISPERSIVE/FILL AREAS.
11. WRAPPING MUST FULLY ENCAPSULATE BEDDING WITH 250mm OVERLAP AT JOINS.
12. TRENCH BASE TO ACHIEVE MINIMUM BEARING PRESSURE OF 100kPa UNLESS OTHERWISE SPECIFIED.
13. BACKFILL COMPACTED TO 98% STANDARD COMPACTION PER AS3798 AND VERIFIED TO LCC REQUIREMENTS.
14. THRUST BLOCKS TO HAVE A MINIMUM HORIZONTAL BEARING PRESSURE ALLOWANCE OF 50kPa.
15. TRENCH BACKFILL FOR DEEP TRENCHES (>5m) MUST ACHIEVE A DENSITY RATIO OF AT LEAST 98% STANDARD AT MOISTURE CONTENTS RANGING BETWEEN +/- 2% OMC AND TESTED AT FREQUENCIES REQUIRED BY LOGAN WATER.

[illegible]

1. TREES LOCATED ALONG THE FOOTPATH SHALL BE TRANSPLANTED PRIOR TO CONSTRUCTION, OR REPLACED IF DESTROYED.
2. WHEN WORKING WITHIN 4 m OF TREES, RUBBER OR HARDWOOD GIRDLES SHALL BE CONSTRUCTED WITH 1.8 m BATTENS CLOSELY SPACED AND ARRANGED VERTICALLY FROM GROUND LEVEL. GIRDLES SHALL BE STRAPPED TO TREES PRIOR TO CONSTRUCTION AND REMAIN UNTIL COMPLETION.
3. TREE ROOTS SHALL BE TUNNELED UNDER, RATHER THAN SEVERED. IF ROOTS ARE SEVERED THE DAMAGED AREA SHALL BE TREATED WITH A SUITABLE FUNGICIDE. CONTACT RELEVANT COUNCIL ARBORIST FOR FURTHER ADVICE.
4. ANY TREE LOPPING REQUIRED SHOULD BE UNDERTAKEN BY AN APPROVED ARBORIST.
5. ALL ENVIRONMENTAL PROTECTION MEASURES SHALL BE IMPLEMENTED PRIOR TO ANY CONSTRUCTION WORK COMMENCING, INCLUDING CLEARING

1. TOPSOIL AND SUBSOIL SHALL BE STOCKPILED SEPARATELY.
2. CARE SHALL BE TAKEN TO PREVENT SEDIMENT FROM ENTERING THE STORMWATER SYSTEM. THIS MAY INVOLVE PLACING APPROPRIATE SEDIMENT CONTROLS AROUND STOCKPILES.
3. THE CONTRACTOR SHALL HAVE READ THE GEOTECHNICAL REPORT.
4. THE CONTRACTOR SHALL HAVE READ THE DISPERSIVE SOILS MANAGEMENT PLAN.

1. SILTATION CONTROL MEASURES SHALL BE PLACED DOWNSTREAM OF ANY EXCAVATION WORK.
2. APPROPRIATE SEDIMENT CONTROLS SHALL BE USED TO PREVENT SEDIMENT FROM ENTERING THE CREEK.
3. NO SOIL SHALL BE STOCKPILED WITHIN 5 m OF THE CREEK OR WATER WAY.

1. PREDISTURBANCE SOIL PROFILES AND COMPACTION LEVELS SHALL BE REINSTATED.
2. PREDISTURBANCE VEGETATION PATTERNS SHALL BE RESTORED.

1. THE DESIGN AND CONSTRUCTION OF THE WORKS SHALL COMPLY WITH ALL QUEENSLAND LEGISLATION.
2. THE SAFETY IN DESIGN, DESIGN AND RISK MITIGATION MEASURES FOR THESE DRAWINGS DO NOT NECESSARILY ACCOUNT FOR ALL DESIGN, CONSTRUCTION, OPERATION, MAINTENANCE AND DEMOLITION ASSESSMENTS. IT DOES NOT REDUCE OR LIMIT THE OBLIGATIONS OF THE CONSTRUCTOR, USER, OPERATOR, MAINTAINER AND DEMOLISHER TO PERFORM THEIR OWN SAFETY IN DESIGN RISK ASSESSMENT.
3. DEVELOP CONSTRUCTION AND INSTALLATION SAFE WORK METHOD STATEMENTS TO ELIMINATE AND MINIMISE INSTALLATION RISKS. THE SAFE METHOD STATEMENT SHALL BE REVIEWED AND APPROVED BY A SUITABLY QUALIFIED STRUCTURAL ENGINEER

1. ALL DIMENSIONS IN MILLIMETERS.
2. BEDDING MATERIAL SHALL BE A SINGLE SIZED 5mm OR 7mm NOMINAL SIZE CRUSHED ROCK COMPLYING WITH TABLE G2 OF AS2566.2.
3. IMPORTED BACKFILL MATERIAL SHALL HAVE A SOAKED CBR VALUE OF NOT LESS THAN 15% AND A MAXIMUM PARTICLE SIZE OF 75mm.
4. FLOWABLE FILL OR LEAN MIX CONCRETE SHALL BE THOROUGHLY MIXED PRIOR TO PLACEMENT WITH A CEMENT CONTENT OF 5%. SHALL CONSIST OF A GRADED SAND AND GRAVEL AGGREGATE OF 40mm MAXIMUM SIZE AND SUFFICIENT WATER TO ENSURE SLUMP OF LESS THAN 12mm.

1. FOR EACH BEDDING ZONE, BEDDING MATERIAL SHALL BE PLACED IN THE TRENCH TO THE DEPTH SHOWN ON THE DRAWINGS AND COMPACTED IN 150mm LAYERS FOR THE FULL WIDTH OF THE TRENCH BY TWO PASSES OF A VIBRATING PLATE.
2. TRENCH BACKFILL ABOVE BEDDING ZONE SHALL BE IN ACCORDANCE WITH THE GEOTECH REPORT AT 98% STANDARD COMPACTION AT MOISTURE CONTENTS RANGING BETWEEN +/- 2% OMC.
3. SINGLE SIZE COARSE AGGREGATES OF SIZES 7 & 10 mm ARE DEEMED "SELF COMPACTING" AND DO NOT REQUIRE COMPACTION TESTING WHEN USED AS EMBEDMENT U.N.O.
4. THE INSTALLED MAIN AND STRUCTURES SHALL CONFORM WITH THE CONSTRUCTION TOLERANCES NOMINATED WITHIN SEQ-CODE.

NOMINAL DIAMETER (DN)	MINIMUM CLEARANCE "Lc" TO AS/NZ 2566.1
≤300	150
>300 - ≤450	200
>450 - ≤900	300



REV	DATE	DESIGN	DRAWN	REVISION DETAILS		DRAWN	STATUS		SCALE		CLIENT	PROJECT NAME	DRAWING TITLE		
A	17.03.25	BR	BR	ORIGINAL ISSUE		BR	NOT FOR CONSTRUCTION								
B	02.04.25	BR	BR	CLIENT UPDATES											
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE											
D	15.08.25	BR	BR	REVISED ISSUE											
E	22.08.25	BR	BR	RFI RESPONSE											
						DESIGN	APPROVED DANIEL COLLINS  RPEQ 18631 DATE 22.08.25	 <th rowspan="6">SCALE</th> <th rowspan="6"></th> <th rowspan="6">CLIENT</th> <th rowspan="6">PROJECT NAME</th> <th colspan="3">DRAWING TITLE</th>	SCALE		CLIENT	PROJECT NAME	DRAWING TITLE		
						BR	FOR AND ON BEHALF OF COLLIER'S INTERNATIONAL ENGINEERING & DESIGN PTY LTD								
													PROJECT No.	DRAWING No.	REVISION
													24-0750	1601	E

MAINTENANCE HOLES – DESIGN REQUIREMENT

- DESIGN AND CONSTRUCTION OF ALL SEWERAGE INFRASTRUCTURE SHALL BE RPEQ CERTIFIED.
- TOP SLABS HAVE BEEN DESIGNED FOR THE FOLLOWING LIVE LOADS AND LOCATIONS

LOCATION	LIVE LOAD	ACCESS COVER TO AS 3996
RESERVES, RESIDENTIAL ALLOTMENTS, FOOTPATHS AND VERGES	25 kN	CLASS RATING B
ROADWAYS AND DRIVEWAYS, COMMERCIAL, INDUSTRIAL AND NON-RESIDENTIAL ALLOTMENTS	80 kN	CLASS RATING D

- DESIGN LIFE 100 YEARS
 - DEAD LOAD AS DETERMINED FROM SEQ SEWER CODE STANDARD DRAWINGS.
 - LIVE LOADS TO AS 1170.1 AND AS 5100.2
- DURABILITY CLASSIFICATION

STRUCTURE	COVER LOCATION	EXPOSURE CLASSIFICATION AS3600, AS3735	REINFORCEMENT COVER (mm)
SLABS	TOP	B2 TO AS3600-	40
	BOTTOM	B2 TO AS3735	50 INCLUDING PE LINER THICKNESS

- SEQ CODE SEWER MH STANDARD DRAWINGS THAT ARE APPLICABLE TO LOGAN WATER HAVE ASSUMED THAT A MINIMUM SOIL BEARING PRESSURE OF 50 KPA CAN BE ACHIEVED. RESPONSIBILITY FOR ALL ASPECTS OF THE DESIGN AND CONSTRUCTION OF SEWER INFRASTRUCTURE RESTS SOLELY WITH THE CERTIFYING RPEQ.
- SEQ CODE SEWER MH STANDARD DRAWINGS THAT ARE APPLICABLE TO LOGAN WATER HAVE ASSUMED THAT A MINIMUM SOIL BEARING PRESSURE OF 50 KPA CAN BE ACHIEVED. RESPONSIBILITY FOR ALL ASPECTS OF THE DESIGN AND CONSTRUCTION OF SEWER INFRASTRUCTURE RESTS SOLELY WITH THE CERTIFYING RPEQ.

MAINTENANCE HOLES - GENERAL

- THESE NOTES RELATE TO ALL TOP SLABS AND CAST-INSITU MAINTENANCE HOLES FOR LOGAN WATER.
- MAINTENANCE HOLE TOP SLABS SHALL BE PRECAST ELEMENTS.
- DIMENSIONS IN MILLIMETRES U.N.O.
- DIMENSIONS NOT TO BE SCALED FROM DRAWINGS.
- VERIFY ALL DIMENSIONS ON SITE PRIOR TO COMMENCING WORK ON SITE.
- MATERIALS AND WORKMANSHIP TO COMPLY WITH THE CURRENT STANDARDS AUSTRALIA CODES, BUILDING CODE OF AUSTRALIA, SEW CODE, WSAA PRODUCT SPECIFICATIONS, BY-LAWS AND ORDNANCES OF RELEVANT BUILDING AUTHORITIES.
- EXISTING STRUCTURES TO BE MAINTAINED IN A STABLE CONDITION AND NO PART TO BE OVER-STRESSED DURING CONSTRUCTION.
- ADDITIONAL SITE EXAVATION SHALL OCCUR UNTIL SUITABLE FOUNDATION MATERIAL IS LOCATED. ALL OVEREXCAVATION SHALL BE REPLACED WITH A LEAN MIX CONCRETE OR C.I.S.M.

MAINTENANCE HOLES

- MAINTENANCE HOLES SHALL BE LOCATED CENTRALLY OVER SEWERS UNLESS SPECIFIED OTHERWISE. REFER DRAWINGS SEQ-SEW-1304-1 AND SEQ-SEW-1305-1
- OBVERT LEVEL OF THE UPSTREAM SEWER PIPE SHALL ALWAYS BE ABOVE THE OBVERT LEVEL OF THE DOWNSTREAM SEWER PIPE UNLESS APPROVED OTHERWISE.
- ALL CONSTRUCTION JOINTS SHALL INCLUDE HYDROPHILIC SEALS INSTALLED TO MANUFACTURER'S SPECIFICATIONS.
- MAINTENANCE HOLE CONNECTORS, INCLUDING HYDROPHILIC SEALS AND PUDDLE FLANGES SHALL BE THE PRE-FABRICATED TYPE UNLESS APPROVED OTHERWISE.
- ENDS OF SEWER PIPES SHALL FINISH FLUSH WITH THE INSIDE FACE OF MAINTENANCE HOLE WALL.
- FINISHED BENCHING SHALL PROVIDE A SMOOTH NON-TURBULENT FLOW.
- SAFETY CHAINS AND ALL CONNECTIONS SHALL BE STAINLESS STEEL GRADE 316.
- PROPERTY CONNECTION JUNCTIONS SHALL NOT BE CONSTRUCTED ON SHORT PIPES AT MAINTENANCE HOLES OR BULKHEADS.

MAINTENANCE HOLE CIRCULAR ACCESS COVERS

- CIRCULAR ACCESS COVERS AND FRAMES SHALL BE RATED TO CLASS RATING B OR CLASS RATING D TO AS 3996.
- PRODUCT CERTIFICATION TO AS 3996 SHALL BE SUPPLIED FOR EACH COVER ASSEMBLY.
- COVERS, FRAMES AND RISER RINGS, WHERE REQUIRED, SHALL BE SUPPLIED ASSEMBLED.
- COVERS SHALL BE SOLID TOP. IN LOGAN WATER AREAS ONLY, CLASS B CONCRETE INFILL COVERS MAY BE USED.
- COVERS SHALL HAVE IDENTIFICATION TAGS DETAILING, SEWER / VACUUM SEWER / CLASS RATING B, D / SEALED / COVER PATTERN DETAIL / SEQ-SP NAME / WEIGHT.
- BOLT DOWN COVERS SHALL BE PROVIDED IN FLOOD PRONE AREAS, STORM SURGE AREAS, SURCHARGING SEWERS AND WHERE SPECIFIED IN THE DESIGN.
- BOLT DOWN COVER FRAMES TO BE FIXED TO THE TOP SLAB WITH 4 M16 STAINLESS STEEL CHEMICAL ANCHORS. EMBEDMENT LENGTH SHALL BE MINIMUM 110 mm UNLESS APPROVED OTHERWISE.

CONCRETE

- CONCRETE WORKMANSHIP AND MATERIALS TO COMPLY WITH AS 3600 AND AS 3610
- CONCRETE TO COMPLY WITH AS 1379, AS 1478.1, AS 1478.2, AS 3582.1, AS 3582.2, AS 3582.3 AND AS 3972.
- SLUMP TO BE AS REQUIRED FOR PLACEMENT, COMPACTION AND FINISHING. A SAMPLE OF FRESH CONCRETE SHALL BE TESTED FOR SLUMP AND STRENGTH UPON ARRIVAL ON SITE.
- WATER NOT TO BE ADDED TO CONCRETE AFTER TRUCK HAS LEFT BATCHING PLANT UNLESS APPROVED OTHERWISE.
- TEST SLUMP OF EACH BATCH OF CONCRETE DELIVERED.
- DESIGN, CERTIFICATION, CONSTRUCTION AND PERFORMANCE OF FORMWORK BY CONTRACTOR.
- CONCRETE CONSTRUCTION TOLERANCES TO AS 3610.
- CONCRETE SIZES DO NOT INCLUDE FINISHES. SIZES NOT TO BE REDUCED OR PENETRATIONS ADDED.
- CONDUITS, PIPES, ETC. NOT TO BE PLACED IN CONCRETE COVER TO THE REINFORCEMENT.
- EXPOSED EDGES AND RE-ENTRANT CORNERS TO HAVE 25 MM CHAMFERS OR FILLETS UNLESS NOTED OTHERWISE.
- CONSTRUCTION JOINTS AS DETAILED AND LOCATED ON DESIGN DRAWINGS.
- CONCRETE SURFACE FINISHES TO AS 3610. FORMED EXPOSED SURFACES - CLASS 2
- CONCRETE TEMPERATURE NOT TO EXCEED TEMPERATURES STATED BELOW.

CONCRETE STRUCTURE	CONCRETE STRENGTH	TEMPERATURE LIMIT
CONCRETE SECTIONS LESS THAN 600mm THICK	EQUAL TO OR MORE THAN 40MPa	35°C
CONCRETE SECTIONS EQUAL TO OR GREATER THAN 600mm THICK	EQUAL TO OR MORE THAN 40 MPa	27°C

- CONCRETE CURING TO AS3600 AS SOON AS POSSIBLE AFTER PLACING AND FINISHING.
- CONCRETE GRADE S40.

TYPE OF AGGREGATE	CALCAREOUS
COMPRESSIVE STRENGTH AT 28 DAYS	40 MPa
MIN. CEMENT CONTENT	380 kg/m ³
MAX. CEMENTITIOUS MATERIAL	25%
MAX W/C RATIO	0.5
NOMINAL SLUMB	80 mm±15
DRYING SHRINKAGE AT 21 DAYS	500 x 10 ⁻⁶
MAXIMUM AGGREGATE SIZE	20 mm
MINIMUM AGGREGATE SIZE	10 mm

- CONCRETE SHALL BE SPECIAL CLASS TO WSA-PS 358 WITH CALCAREOUS AGGREGATE.
- BENCHING FINISH SHALL CONSIST OF EQUAL PARTS OF CEMENT AND SAND.
- HOLD POINT: ONCE THE BASE OF MANHOLES HAVE BEEN POURED, CONSTRUCTION SHALL ONLY RE-COMMENCE ONCE THE SUPERINTENDENT AND/OR ENGINEER HAVE INSPECTED THE WORKS


REINFORCEMENT

- REINFORCEMENT FOR THE TOP SLABS SHALL BE A PREFABRICATED ELEMENT.
- REINFORCEMENT TO COMPLY WITH AS4671.
- SYMBOLS ON DRAWINGS FOR GRADE AND TYPE OF REINFORCEMENT ARE:
 - R - STRUCTURAL GRADE 250 PLAIN ROUND BARS
 - N - HOT ROLLED GRADE 500 DEFORMED BAR, DUCTILITY CLASS N
 - L - HOT ROLLED GRADE 500 DEFORMED BAR, DUCTILITY CLASS L
 - SL - HARD DRAWN WIRE GRADE 500 MESH, DUCTILITY CLASS L
 - RL - HARD DRAWN WIRE GRADE 500 MESH, DUCTILITY CLASS L
 - W - STEEL REINFORCING WIRE GRADE 500
- REINFORCEMENT DESIGNATION AS FOLLOWS (e.g. 14/N16-250 EF)
 - 14 - NUMBER OF BARS
 - N - BAR GRADE AND DUCTILITY CLASS
 - 16 - BAR DIAMETER IN mm
 - 250 - SPACING OF BARS IN mm
 - EF - LOCATION
- ABBREVIATIONS TO REINFORCEMENT LOCATION:
 - EW - EACH WAY
 - EF - EACH FACE
 - B - BOTTOM
 - T - TOP
 - CP - CENTRALLY PLACED
- REINFORCEMENT IS SHOWN DIAGRAMMATICALLY ONLY AND NOT NECESSARILY IN TRUE PROJECTION.
- REINFORCEMENT TO BE FIXED SECURELY AND SUPPORTED ON PROPRIETY CONCRETE, METAL OR PLASTIC SUPPORTS.
- REINFORCEMENT TO BE SPICED AS SHOWN ON PROJECT DRAWINGS. LAP LENGTHS TO COMPLY WITH AS 3600 AND TABLE BELOW U.N.O.

BAR SIZE	LAP LENGTH (mm)
N12	350
N16	500
N20	600
N24	700
N28	850
N32	950

- REINFORCEMENT NOT TO BE WELDED UNLESS SHOWN ON PROJECT DRAWINGS OR APPROVED OTHERWISE.
- REINFORCEMENT NOT TO BE BENT, CUT OR HEATED ON SITE UNLESS APPROVED OTHERWISE.
- REINFORCEMENT TO BE CLEAN, FREE OF MILL SCALE, RUST, OIL, GREASE ETC.
- DOWEL LOCATION TOLERANCE SHALL BE +/- HALF THE DIAMETER OF THE DOWEL. THE ALIGNMENT TOLERANCE SHALL BE 2 mm IN 300 mm.

PLOT - Z: Aug 2025 04:21 PM LOCATION - H:20.25-0408 Uncluttered (Jazwin) | Page: 0001 | Design: 040801 Trunk Sewer | 24-0750-1602 | TRUNK SEWER COVER.dwg

REV	DATE	DESIGN	DRAWN	REVISION DETAILS			DRAWN	STATUS		SCALE		CLIENT	PROJECT NAME	DRAWING TITLE						
A	17.03.25	BR	BR	ORIGINAL ISSUE			BR	NOT FOR CONSTRUCTION						TRUNK SEWER MAIN MH						
B	02.04.25	BR	BR	CLIENT UPDATES										CONSTRUCTION NOTES						
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE										SHEET 1 OF 2						
							DESIGN	APPROVED				DATE								
							BR	DANIEL COLLINS			RPEQ 18631	22.08.25								
																				
								FOR AND ON BEHALF OF COLLIERS INTERNATIONAL ENGINEERING & DESIGN PTY LTD												
								ASSOCIATED CONSULTANT												
											TRUNK SEWER MAIN - PACKAGE 2									
											HOMESTEAD DRIVE									
											MONARCH GLEN									
											PROJECT No.	DRAWING No.	REVISION							
											24-0750	1602	C							

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2025/1683
Date: 27 October 2025



PLOT - ZI Aug 2025 04:21 PM LOCATION - H:20.25-0408 Unsubstation (Jazwin) Flagpanel Design/Kasiti Trunk Sewer/24-0750-1603-TRUNK SEWER COVER.dwg

PRECAST CONCRETE - TOP SLABS ONLY

1. PRECAST CONCRETE MEMBERS TO COMPLY WITH AS 3850.1 AND AS 3850.2
2. PRECAST MEMBERS ARE DESIGNED FOR THE FINAL INSTALLED CONDITIONS ONLY. PRECAST MANUFACTURER TO DESIGN THE PRECAST MEMBERS INCLUDING CONNECTIONS, FIXING DETAILS, JOINTS, FIRE RESISTANCE, ETC. FOR STABILITY, SERVICEABILITY AND STRENGTH REQUIREMENTS REQUIRED DURING MANUFACTURE, TRANSPORT, LIFTING, ERECTION AND INSTALLATION.
3. PRECAST MANUFACTURER TO PROVIDE THEIR SHOP DRAWINGS AND RPEQ CERTIFICATION FOR CONSTRUCTION OF THE PRECAST SLAB TO THE DESIGNS PROVIDED IN MAINTENANCE HOLE DRAWINGS INCLUDING DESIGN AND CONSTRUCTION CERTIFICATION FOR CONNECTIONS AND FIXING REQUIRED FOR MANUFACTURE, TRANSPORT, ERECTION AND INSTALLATION. (FORM 16)
4. PRECAST CONCRETE MEMBERS TO BE SUPPLIED AND CONSTRUCTED BY A PRECAST CONCRETE CONSTRUCTOR.
5. ADEQUATELY DESIGNED TEMPORARY BRACING, AS REQUIRED, TO BE PROVIDED DURING ERECTION AND INSTALLATION.
6. MINIMUM CHARACTERISTIC COMPRESSIVE STRENGTH OF CONCRETE AT REMOVAL FROM MOULDS SHALL BE 15MPa.
7. ALL INSERTS IN PRECAST CONCRETE MEMBERS TO BE STAINLESS STEEL.
8. ALL STRUCTURAL STEELWORK CONNECTIONS TO PRECAST CONCRETE MEMBERS TO BE HOT DIP GALVANISED TO AS 4680 SYSTEM DESIGNATION HDG600.
9. PROVIDE 15 MM CHAMFERS OR FILLETS AT EDGES AND CORNERS OF PRECAST MEMBERS EXCEPT AT UNDERSIDE OF MH SLAB ACCESS OPENING UNLESS APPROVED OTHERWISE.
10. PRECAST CONCRETE MEMBERS NOT TO BE ERECTED ON REINFORCED CONCRETE STRUCTURES UNTIL THE REINFORCED CONCRETE STRUCTURES HAVE BEEN CURED TO ACHIEVE 28 DAYS STRENGTH.
11. WEIGHT OF TOP SLAB TO BE STAMPED ON THE SLAB.
12. CONCRETE TO BE SPECIAL CLASS TO WSA PS-358 WITH CALCAREOUS AGGREGATE.
13. APPROVED LIFTING PLAN IS TO BE AVAILABLE ON REQUEST.

FORMWORK

1. DESIGN, CERTIFICATION, CONSTRUCTION, INSPECTION AND PERFORMANCE OF THE FORMWORK AND FALSE WORK SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, EXCEPT TO THE EXTENT THAT FORMWORK DESIGN IS SHOWN ON THE STRUCTURAL DRAWINGS.
2. FORMWORK SHALL NOT BE DESIGNED TO RELY ON RESTRAINT OR SUPPORT FROM THE PERMANENT STRUCTURE WITHOUT PRIOR APPROVAL FROM THE STRUCTURAL ENGINEER.
3. INFORMATION FOR THE FOUNDATIONS UNDER THE FORMWORK SHALL BE DETERMINED FROM THE CONDITIONS EXISTING ON SITE AT THE TIME OF CONSTRUCTION.
4. CONSTRUCTION TOLERANCES AND STRIPPING TIMES SHALL COMPLY WITH AS3610 AND AS3600 FOR THE APPROPRIATE FINISH CLASS UNLESS OTHERWISE APPROVED BY THE STRUCTURAL ENGINEER.
5. CONSTRUCTION, NO MATERIALS ARE TO BE STACKED ON THE VALVE PIT UNTIL THE NOMINATED 28 DAY STRENGTH HAS BEEN ATTAINED, THESE LOADS SHALL NOT EXCEED THE DESIGN SUPERIMPOSED LOADS OF 10 kPa.
6. PERMANENT LOADS ON THE CONCRETE STRUCTURE SHALL NOT BE APPLIED UNTIL AFTER FORMWORK AND FALSEWORK IS REMOVED.
7. APPLY A RELEASE AGENT TO THE FACE OF THE FORMWORK COMPATIBLE WITH THE REQUIRED SURFACE FINISH WHEN PLACING REINFORCEMENT IN THE FORMWORK..
8. RE-ENTRANT ANGLES AND FILLET AT CORNERS BY 25mm UNO.
9. PRIOR TO PLACING CONCRETE, REMOVE ALL WATER, DUST, AND DEBRIS FROM THE FORMWORK.
10. WHERE HOLES ARE LEFT BY FORM TIE BOLTS THESE SHALL BE FILLED WITH MORTAR MATCHING THE SURFACE COLOUR OF THE FINISHED SURFACE.

STAINLESS STEEL

1. STAINLESS STEEL TO COMPLY TO ASTM A240/A240M AND ASTM A480/ A480M.
2. FABRICATION BY MANUFACTURERS ASSDA ACCREDITED OR APPROVED EQUIVALENT.
3. STAINLESS STEEL TO BE GRADE 316 OR 316L U.N.O.
4. STORAGE, FABRICATION AND WELDING TO BE IN APPROVED DEDICATED AREAS.
5. WELDING, CLEANING, PICKLING AND PASSIVATION TO COMPLY TO AS 1554.6 AND WTIA TECHNICAL NOTE 16 WELDING OR STAINLESS STEEL.
6. SURFACE FINISH TO BE 2B OR BETTER TO ASTM A480.
7. MEMBERS TO BE ACID PASSIVATED AFTER FABRICATION.
8. ANTI GALLING COMPOUND "DURALAC" OR SEQ-SP APPROVED EQUIVALENT REQUIRED ON ALL FASTENERS UNLESS APPROVED OTHERWISE.

POLYETHYLENE LINER (PE LINER)

1. THE PE LINER SHALL FORM A COMPLETELY SEALED AND WELDED ROBUST CONTINUOUS MEMBRANE SYSTEM. THE PE LINER SHALL BE BUILT TO THE MH CONSTRUCTION TOLERANCES WITHOUT ANY DEFECTS SUCH AS BULGING, WARPING, PINCHING, OVERLAPPING.
2. THE PE SHEETS SHALL:
 - HAVE A MINIMUM THICKNESS OF 2.5 mm.
 - ACHIEVE A MECHANICAL BOND BETWEEN THE CONCRETE AND LINER.
 - BE INSTALLED BY AN ACCREDITED APPLICATOR APPROVED BY THE MANUFACTURER.
 - BE TENSIONED OVER THE FORMWORK WITHIN THE YIELD ELONGATION LIMIT PRIOR TO SECURING TO THE FORMWORK.
3. PREPARATION, APPLICATION AND INSTALLATION TO COMPLY WITH THE MANUFACTURER'S SPECIFICATION.
4. POURED CONCRETE TO BE AT A COOLER AMBIENT TEMPERATURE THAN THE TEMPERATURE WHEN THE PE SHEETS WERE ATTACHED TO THE FORMWORK.
5. EXTRUSION WELDING AND WELD TESTING AT SEAMS TO BE UNDERTAKEN BY THE APPROVED APPLICATOR TO THE MANUFACTURER'S SPECIFICATION.
6. ENCAPSULATION OF ANCHORS TO BE CHECKED BY TAPPING THE SURFACE TO DETECT HOLLOW

- SOUNDS THAT INDICATE VOIDS. VOIDS TO BE FILLED BY INJECTION GROUT AND PE SHEET REPAIRED BY EXTRUSION WELDING OVER THE INJECTION HOLE.
7. REFER TO SEQ CODE CIVIL IPAM LIST FOR APPROVED PE LINER PRODUCTS. PREPARATION, APPLICATION AND INSTALLATION OF LINER TO COMPLY WITH MANUFACTURER'S SPECIFICATIONS AND BE READ IN CONJUNCTION WITH WSA 201 MANUAL FOR SELECTION AND APPLICATION OF PROTECTIVE COATINGS AND SEQ-SEW-1101-6.

PE LINING TO EXTEND TO BASE OF MANHOLE PRIOR TO BENCHING BEING POURED.

STRUCTURAL STEEL

1. STRUCTURAL STEEL WORKMANSHIP AND MATERIALS TO COMPLY WITH AS 4100.
2. STEEL TO COMPLY WITH:
 - AS 1163 GRADE C350 FOR RECTANGULAR AND HOLLOW SECTIONS.
 - AS 3678 FOR PLATES AND FLOOR PLATES.
 - AS 3679.1 GRADE 300 OR BHP GRADE 300 PLUS FOR PARALLEL FLANGE CHANNELS.
 - AS 3679.2 GRADE 300 FOR WELDED BEAMS AND COLUMNS.
 - OTHER SECTIONS TO COMPLY WITH AS 3678 OR AS 3679 GRADE 250.
3. WELDS TO AS 1554.
 - WELD CATEGORY SP.
 - BUTT WELDS TO BE FULL PENETRATION WELDS.
 - WELDS TO BE 6 MM CONTINUOUS FILLET WELDS ALL ROUND INTERFACES.
 - ELECTRODES TO AS 1554 CLASSIFICATION E48XX.
4. BOLTS TO AS 1275. COMMERCIAL GRADE 4.6/S TO AS 1111 AND AS 1112. HIGH STRENGTH STRUCTURAL BOLTS TO AS 1252.
 - BOLTS, NUTS AND WASHERS M16 AND LARGER TO GRADE 8.8/S. M12 TO BE GRADE 4.6/S
 - STRUCTURAL CONNECTIONS TO BE 2 M16 8.8/S WITH 10 mm THICK CLEAT PLATE U.N.O.
 - INSTALL WASHERS UNDER BOLT HEAD AND NUT. INSTALL TAPERED WASHERS AS REQUIRED.
 - BOLT PROJECTION BEYOND NUT TO BE MINIMUM TWO THREADS AND MAXIMUM 10 mm
5. HOLD DOWN BOLTS TO BE GRADE 4.6/S U.N.O. HOLD DOWN BOLTS GROUPS TO BE RIGIDLY
6. TIED FOR CORRECT SET-OUT AND LOCATION.
7. SEAL WELD HOLLOW SECTIONS WITH 3 MM THICK CAP PLATE UNLESS NOTED OTHERWISE.
8. GROUT BASE PLATES WITH HIGH STRENGTH NON-SHRINK PRE-MIXED GROUT BEFORE COLUMNS ARE LOADED.

STEEL WORK PROTECTIVE COATING


1. STEELWORK TO BE HOT DIP GALVANISED TO AS 4680 SYSTEM DESIGNATION HDG600 AND THREADED FASTENERS TO AS 1214.
2. DAMAGED GALVANISED COATING REPAIR:
POWER CLEAN TO AS 1627.2
SOLVENT CLEAN/ DEGREASE TO AS 1627.1
APPLY TIN/ZINC TO PRE-HEATED STEEL OVERLAPPING THE GALVANISING COATING.

REPAIR OF EXPOSED REINFORCEMENT AND CONCRETE AROUND NEW PIPE PENETRATION IN EXISTING CONCRETE

1. EXPOSED REINFORCEMENT AND CONCRETE REPAIRED AS FOLLOWS:
 - CORE HOLES ON EACH CORNER OF AREA TO BE CUT.
 - SAW CUT CONCRETE, PERPENDICULAR TO CONCRETE SURFACE, 15 mm DEEP AROUND PERIMETER OF THE OPENING.
 - BREAKOUT REMAINING CONCRETE AROUND THE OPENING WITHOUT DAMAGING REINFORCEMENT.
 - CUT EXPOSED REINFORCEMENT SO THAT IS 30 mm CLEAR OF THE PIPE.
 - CLEAN CONCRETE SURFACE AND REMOVE ALL LOOSE MATERIAL.
 - ABRASIVE BLAST CLEAN EXPOSED REINFORCEMENT. IF IT IS CORRODED AND APPLY "NITOPRIME" ZINC RICH PRIMER UNLESS APPROVED OTHERWISE.
 - THOROUGHLY SOAK SUBSTRATE WITH CLEAN WATER FOR A MINIMUM OF TWO HOURS.
 - PLACE N12 CIRCULAR TRIMMER ON BOTH SIDES OF THE PIPE FLANGE.
 - INSTALL HYDROTITE CJ-07-25 SEAL ON PIPE 50 mm FROM CONCRETE SURFACE UNLESS APPROVED OTHERWISE.
 - APPLY "NITOBOND HAR" PRIMER TO CONCRETE SURFACE UNLESS APPROVED OTHERWISE.
 - POUR CONCRETE/GROUT UNDER PRESSURE TO FILL OPENING.
 - FILL CONCRETE/GROUT TO SUPPLIER REQUIREMENTS.

REPAIR OF EXPOSED REINFORCEMENT AND ANCHOR AT CONCRETE SURFACE

1. ALL EXPOSED REINFORCEMENT AND MILD STEEL ANCHORED TO BE REPAIRED AS FOLLOWS:
 - SAW CUT OR CHISEL CUT CONCRETE, PERPENDICULAR TO CONCRETE SURFACE, 15 mm DEEP AROUND REINFORCEMENT/ANCHOR.
 - BREAKOUT CONCRETE AROUND REINFORCEMENT/ANCHOR TO A DEPTH OF 60 mm.
 - CUT EXPOSED REINFORCEMENT/ANCHOR AT A MINIMUM DEPTH OF 50 mm FROM CONCRETE SURFACE.
 - CLEAN CONCRETE SURFACE AND REMOVE ALL LOOSE MATERIAL.
 - ABRASIVE BLAST CLEAN EXPOSED REINFORCEMENT/ANCHOR.
 - APPLY "NITOPRIME" ZINC RICH PRIMER TO REINFORCEMENT/ANCHOR UNLESS APPROVED OTHERWISE.
 - THOROUGHLY SOAK SUBSTRATE WITH CLEAN WATER.
 - APPLY "NITOBOND HAR" PRIMER TO CONCRETE UNLESS APPROVED OTHERWISE.
 - APPLY "RENDEROC HB40" TO FILL OPENING UNLESS APPROVED OTHERWISE.

REV	DATE	DESIGN	DRAWN	REVISION DETAILS		DRAWN	STATUS			SCALE		CLIENT	PROJECT NAME	DRAWING TITLE				
A	17.03.25	BR	BR	ORIGINAL ISSUE		BR	NOT FOR CONSTRUCTION											
B	02.04.25	BR	BR	CLIENT UPDATES														
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE														
						DESIGN	APPROVED	DATE										
						BR	DANIEL COLLINS	RPEQ 18631	22.08.25									
																		
							FOR AND ON BEHALF OF COLLIERS INTERNATIONAL ENGINEERING & DESIGN PTY LTD											


LEGEND

- ST PROPOSED TRUNK SEWER MAIN
- PROPOSED PACKAGE 1
- PROPOSED PACKAGE 2
- PROPOSED PACKAGE 3

This approval relates to package 2 only.
Package 1 and 3 are not approved as part of this application.

AMENDED IN RED

By: Ali Rizayee
Date: 22 October 2025



PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL
Approval no: DEV2025/1683
Date: 27 October 2025



PLOT: 22 Aug 2025 04:21 PM LOCATION: H:\2025\0408 Unpublished (Jazwin)\Flagstone\Design\Kadit Trunk Sewer\24-0750-1605-TRUNK SEWER KEY PLAN.dwg

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
A	17.03.25	BR	BR	ORIGINAL ISSUE
B	02.04.25	BR	BR	CLIENT UPDATES
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE

DRAWN	STATUS
BR	NOT FOR CONSTRUCTION
DESIGN	APPROVED
BR	DANIEL COLLINS RPEQ 18631 DATE 20.08.25
FOR AND ON BEHALF OF COLLIERS INTERNATIONAL ENGINEERING & DESIGN PTY LTD	




SCALE
1:2500 50 0 50 100 A1 1:5000

CLIENT
ASSOCIATED CONSULTANT

PROJECT NAME
MONARCH GLEN No. 1 PTY LTD
TRUNK SEWER MAIN - PACKAGE 2 HOMESTEAD DRIVE MONARCH GLEN

DRAWING TITLE		
TRUNK SEWER KEY PLAN		
PROJECT No.	DRAWING No.	REVISION
24-0750	1605	C



- ## LEGEND
- | | |
|--|-----------------------------------|
| | PROPOSED AREA OF WORKS |
| | PROPOSED TRUNK SEWER MAIN |
| | PROPOSED SEWER MAIN |
| | EXISTING TRUNK SEWER MAIN |
| | PROPOSED EASEMENT |
| | FINISHED SURFACE CONTOURS |
| | PROPOSED STORMWATER DRAINAGE PIPE |
| | PROPOSED WATER MAIN |
| | PROPOSED WATER MAIN |

PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

Approval no: DEV2025/1683
Date: 27 October 2025

Queensland
Government

LEGEND

- PROPOSED AREA OF WORKS
- PROPOSED TRUNK SEWER MAIN
- PROPOSED SEWER MAIN
- EXISTING TRUNK SEWER MAIN
- PROPOSED EASEMENT
- FINISHED SURFACE CONTOURS
- PROPOSED STORMWATER DRAINAGE PIPE
- PROPOSED WATER MAIN
- PROPOSED WATER MAIN

KEYPLAN
SCALE: 1:8000 (A1)
SCALE: 1:16000 (A3)

NOTE - SETOUT:
REFER TO THE LONGITUDINAL SECTIONS
FOR EASTING AND NORTHING SETOUT OF
SEWER STRUCTURES AND ENDS.

WARNING! - EXISTING SERVICES
EXTREME CARE SHOULD BE TAKEN WHEN EXCAVATING
IN THIS AREA. THE FOLLOWING EXISTING SERVICES ARE
LIKELY TO BE PRESENT IN THE VICINITY OF THE SITE:

- ELECTRICAL CABLES
- TELECOMMUNICATIONS CABLES
- GAS MAINS
- WATER MAINS
- SEWER MAINS

THE CONTRACTOR SHOULD CONTACT THE SERVICE
PROVIDER FOR FURTHER INFORMATION AND SATISFY
THEMSELVES OF ANY SPECIFIC TREATMENT OR
REQUIREMENTS.

NOTE - SETOUT:
REFER TO THE LONGITUDINAL SECTIONS
FOR EASTING AND NORTHING SETOUT OF
SEWER STRUCTURES AND ENDS.

WARNING! - EXISTING SERVICES

EXTREME CARE SHOULD BE TAKEN WHEN EXCAVATING IN THIS AREA. THE FOLLOWING EXISTING SERVICES ARE LIKELY TO BE PRESENT IN THE VICINITY OF THE SITE:

- ELECTRICAL CABLES
- TELECOMMUNICATIONS CABLES
- GAS MAINS
- WATER MAINS
- SEWER MAINS

THE CONTRACTOR SHOULD CONTACT THE SERVICE PROVIDER FOR FURTHER INFORMATION AND SATISFY THEMSELVES OF ANY SPECIFIC TREATMENT OR REQUIREMENTS.

REV	DATE	DESIGN	DRAWN	REVISION DETAILS		DRAWN	STATUS			SCALE		CLIENT		PROJECT NAME			DRAWING TITLE		
A	17.03.25	BR	BR	ORIGINAL ISSUE		BR	NOT FOR CONSTRUCTION					MONARCH GLEN No. 1 PTY LTD		TRUNK SEWER MAIN - PACKAGE 2 HOMESTEAD DRIVE MONARCH GLEN			TRUNK SEWER MAIN LAYOUT PLAN SHEET 1 OF 3		
B	02.04.25	BR	BR	CLIENT UPDATES															
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE															
						DESIGN	APPROVED	DATE			ASSOCIATED CONSULTANT	TRUNK SEWER MAIN - PACKAGE 2 HOMESTEAD DRIVE MONARCH GLEN			PROJECT No.	DRAWING No.	REVISION		
						BR	DANIEL COLLINS  RPEQ 18631 22.08.25								24-0750	1610	C		
						FOR AND ON BEHALF OF COLLIERS INTERNATIONAL ENGINEERING & DESIGN PTY LTD													

PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

Approval no: DEV2025/1683
Date: 27 October 2025


Queensland
Government

WARNING! - EXISTING SERVICES

EXTREME CARE SHOULD BE TAKEN WHEN EXCAVATING
IN THIS AREA. THE FOLLOWING EXISTING SERVICES ARE
LIKELY TO BE PRESENT IN THE VICINITY OF THE SITE:

- ELECTRICAL CABLES
- TELECOMMUNICATIONS CABLES
- GAS MAINS
- WATER MAINS
- SEWER MAINS

THE CONTRACTOR SHOULD CONTACT THE SERVICE
PROVIDER FOR FURTHER INFORMATION AND SATISFY
THEMSELVES OF ANY SPECIFIC TREATMENT OR
REQUIREMENTS.

NOTE - SETOUT:


REFER TO THE LONGITUDINAL SECTIONS
FOR EASTING AND NORTHING SETOUT OF
SEWER STRUCTURES AND ENDS.




KEYPLAN

SCALE: 1:8000 (A1)
SCALE: 1:16000 (A3)

REFER SHEET 3 FOR CONTINUATION






PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

Approval no. DEV2025/1683
Date: 27 October 2025



REFER SHEET 3 FOR CONTINUATION



This approval relates to package 2 only.

Package 3 is not approved as part of this application.

WARNING! - EXISTING SERVICES


EXTREME CARE SHOULD BE TAKEN WHEN EXCAVATING
IN THIS AREA. THE FOLLOWING EXISTING SERVICES ARE
LIKELY TO BE PRESENT IN THE VICINITY OF THE SITE:

- ELECTRICAL CABLES
- TELECOMMUNICATIONS CABLES
- GAS MAINS
- WATER MAINS
- SEWER MAINS

THE CONTRACTOR SHOULD CONTACT THE SERVICE
PROVIDER FOR FURTHER INFORMATION AND SATISFY
THEMSELVES OF ANY SPECIFIC TREATMENT OR
REQUIREMENTS.

NOTE - SETOUT:

REFER TO THE LONGITUDINAL SECTIONS
FOR EASTING AND NORTHING SETOUT OF
SEWER STRUCTURES AND ENDS.



KEYPLAN

SCALE: 1:8000 (A1)
SCALE: 1:16000 (A3)

AMENDED IN RED


By: Ali Rizayee
Date: 22 October 2025



PLOT: 22 Aug 2025 04:22 PM LOCATION: H:\2025\0408\Uncluttered\Drawings\Flagplan\Design\CardTrunk Sewer\24-0750-16-10-TRUNK SEWER LAYOUT.dwg

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
A	17.03.25	BR	BR	ORIGINAL ISSUE
B	02.04.25	BR	BR	CLIENT UPDATES
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE

DRAWN	STATUS
BR	NOT FOR CONSTRUCTION
DESIGN	APPROVED
BR	DANIEL COLLINS RPEQ 18631 DATE 22.08.25
FOR AND ON BEHALF OF COLLIERS INTERNATIONAL ENGINEERING & DESIGN PTY LTD	



PROJECT NAME
MONARCH GLEN No. 1 PTY LTD
TRUNK SEWER MAIN - PACKAGE 2 HOMESTEAD DRIVE MONARCH GLEN

DRAWING TITLE		
TRUNK SEWER MAIN LAYOUT PLAN SHEET 3 OF 3		
PROJECT No. 24-0750	DRAWING No. 1612	REVISION C

REFER SHEET 1 FOR CONTINUATION

STRUCTURE NAME	1/1	2/1	3/1	4/1	5/1	6/1	7/1	8/1	9/1	10/1	11/1	12/1	13/1	14/1	15/1	16/1	17/1
STRUCTURE TYPE & DROP	C3 V	C3	V PE LINED	C3	V PE LINED	C3	V PE LINED	C3	V PE LINED	C3	V PE LINED	C3	V PE LINED	C3	V PE LINED	C3	V PE LINED
STRUCTURE LID TYPE	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D	D
BRANCH LINE No.	-9°	-90°	4°		1°			61°		1°	32°	-90°	10°	21°	-79°	6°	-8°
BRANCH DROP TYPES												V 2		Z 3			Z 4

STRUCTURE TYPES
C1 = CAST-IN-SITU 1.050Ø
C2 = CAST-IN-SITU 1.200Ø
C3 = CAST-IN-SITU 1.500Ø
C4 = CAST-IN-SITU 1.800Ø
C5 = CAST-IN-SITU 2.000Ø
C6 = CAST-IN-SITU 2.400Ø

FOR DEEP STRUCTURES - REFER TO LOGAN WATER STANDARD DRAWING LW-SEW-DWG-2052

MH DROP TYPES:
AS PER LW-SEW-DWG-2120

DROP TYPES:
V = DROP THROUGH BASE
Z = >750mm INTERNAL DROP

LID TYPES
B = NON-TRAFFICABLE
D = TRAFFICABLE
D(BD) = TRAFFICABLE WITH BOLT DOWN

NOTE: PE LINING OF MANHOLES:
PE LINING REQUIREMENTS AS PER SEWER SEQ CODE CLAUSE 7.6.2.

EMBEDMENT NOTE:
REFER TO DWG. No. 1601 FOR PIPE EMBEDMENT & TRENCHFILL DETAIL.

IF MATERIAL CHANGES FROM ROCK TO OTHER MATERIAL, GEOTECH TO CONFIRM IF TYPE 4 BEDDING IS REQUIRED.

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2025/1683

Date: 27 October 2025


Queensland Government

DATUM RL(m)	34.0																
LAND USE	ROAD RES.				ROAD RESERVE (NEW BEITH ROAD)			NEW BEITH ROAD	OPEN SPACE						ROAD RESERVE		
PIPE DIA & TYPE							DN375 SewerMAX+ SN20								DN375 SewerMAX+ SN20		
PIPE GRADE (1 in x)	1 IN 300	1 IN 300	1 IN 41.127	1 IN 300	1 IN 300	1 IN 300	1 IN 300	1 IN 300	1 IN 200	1 IN 300	1 IN 300	1 IN 300	1 IN 200	1 IN 300	1 IN 300	1 IN 300	1 IN 300
EMBEDMENT					TYPE '3' (REFER EMBEDMENT NOTE)				MICROTUNNEL	TYPE '3' (REFER EMBEDMENT NOTE)				TYPE '3' (REFER EMBEDMENT NOTE)			
JUNCTION INVERT LEVEL																	
DEPTH TO INVERT	1.905	1.905	1.952	1.922													
SEWER INVERT LEVEL	43.210	43.210	43.225	43.255													
DESIGN SURFACE LEVEL																	
EXISTING SURFACE LEVEL																	
SETOUT	E33773.363	N73669.192	E33770.033	N73872.438	E33748.867	N73887.261	E33681.869	N73791.395		E33609.633	N73700.972	E33536.450	N73610.888	E33463.259	N73520.893	E33388.634	N73429.136
RUNNING CHAINAGE	0.000	4.650	4.650	25.840	30.491	116.794	147.284	115.969		263.253	115.987	379.240	116.000	405.240	118.271	613.511	32.726

LINE NUMBER

LINE 1

REV	DATE	DESIGN	DRAWN	REVISION DETAILS	DRAWN	STATUS
A	17.03.25	BR	BR	ORIGINAL ISSUE	BR	NOT FOR CONSTRUCTION
B	02.04.25	BR	BR	CLIENT UPDATES		
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE		
D	22.08.25	BR	BR	RFI RESPONSE		
E	27.08.25	BR	BR	UPDATE PIPE TYPE		

Colliers

FOR AND ON BEHALF OF COLLIERIES INTERNATIONAL ENGINEERING & DESIGN PTY LTD

SCALE

1:2000 20 0 20 40 60 80 100 A1

1:4000 HORIZONTAL A3

1:200 2 0 2 4 6 8 10 A1

1:400 VERTICAL A3

CLIENT



ASSOCIATED CONSULTANT

PROJECT NAME

MONARCH GLEN No. 1 PTY LTD

TRUNK SEWER MAIN - PACKAGE 2

HOMESTEAD DRIVE

MONARCH GLEN

DRAWING TITLE

TRUNK SEWER LONGITUDINAL SECTIONS SHEET 1 OF 3

PROJECT No. 24-0750

DRAWING No. 1614

REVISION E

PLOT: 27 Aug 2025 09:30 AM LOCATION: H:\2025\0408_Undrline (Jzwm)\Figural\Design\Card\Trunk Sewer\24-0750-1614-TRUNK SEWER LONGITUDINAL.dwg

STRUCTURE TYPES
C1 = CAST-IN-SITU 1.050Ø
C2 = CAST-IN-SITU 1.200Ø
C3 = CAST-IN-SITU 1.500Ø
C4 = CAST-IN-SITU 1.800Ø
C5 = CAST-IN-SITU 2.000Ø
C6 = CAST-IN-SITU 2.400Ø

FOR DEEP STRUCTURES - REFER TO LOGAN WATER STANDARD DRAWING LW-SEW-DWG-2052

MH DROP TYPES:
AS PER LW-SEW-DWG-2120


DROP TYPES:
V = DROP THROUGH BASE
Z = >750mm INTERNAL DROP

LID TYPES
B = NON-TRAFFICABLE
D = TRAFFICABLE
D(BD) = TRAFFICABLE WITH BOLT DOWN

**NOTE: PE LINING OF MANHOLES:
PE LINING REQUIREMENTS AS PER SEWER SEQ CODE CLAUSE 7.6.2.**


EMBEDMENT NOTE:
REFER TO DWG. No. 1601 FOR PIPE EMBEDMENT & TRENCHFILL DETAIL.

IF MATERIAL CHANGES FROM ROCK TO OTHER MATERIAL, GEOTECH TO CONFIRM IF TYPE 4 BEDDING IS REQUIRED.

[illegible]

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL Approval no: DEV2025/1683 Date: 27 October 2025	 Queensland Government
--	---

REV	DATE	DESIGN	DRAWN	REVISION DETAILS	DRAWN	STATUS
A	17.03.25	BR	BR	ORIGINAL ISSUE	BR	NOT FOR CONSTRUCTION
B	02.04.25	BR	BR	CLIENT UPDATES		
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE		
D	22.08.25	BR	BR	RFI RESPONSE		
E	27.08.25	BR	BR	UPDATE PIPE TYPE		
					DESIGN	APPROVED DANIEL COLLINS  RREQ 18631 DATE 27.08.25
					BR	FOR AND ON BEHALF OF COLLIER INTERNATIONAL ENGINEERING & DESIGN PTY LTD



CLIENT

 **mircvac**

ASSOCIATED CONSULTANT

PROJECT NAME

MONARCH GLEN No. 1 PTY LTD

TRUNK SEWER MAIN - PACKAGE 2
HOMESTEAD DRIVE
MONARCH GLEN

DRAWING TITLE		
TRUNK SEWER LONGITUDINAL SECTIONS SHEET 2 OF 3		
PROJECT No.	DRAWING No.	REVISION
24-0750	1615	E

STRUCTURE NAME

12/1 (STUB/2) 1/2

STRUCTURE TYPE & DROP	C3	Z	PE LINED	END		C1	V
STRUCTURE LID TYPE	D					D	V
BRANCH LINE No.	1						
BRANCH DROP TYPES	V						

STRUCTURE TYPES
C1 = CAST-IN-SITU 1.0500
C2 = CAST-IN-SITU 1.2000
C3 = CAST-IN-SITU 1.5000
C4 = CAST-IN-SITU 1.8000
C5 = CAST-IN-SITU 2.0000
C6 = CAST-IN-SITU 2.4000

FOR DEEP STRUCTURES - REFER TO LOGAN WATER STANDARD DRAWING LW-SEW-DWG-2052
MH DROP TYPES:
AS PER LW-SEW-DWG-2120
DROP TYPES:
V = DROP THROUGH BASE
Z = >750mm INTERNAL DROP
LID TYPES
B = NON-TRAFFICABLE
D = TRAFFICABLE
D(BD) = TRAFFICABLE WITH BOLT DOWN

NOTE: PE LINING OF MANHOLES:
PE LINING REQUIREMENTS AS PER SEWER SEQ CODE CLAUSE 7.6.2.

EMBEDMENT NOTE:
REFER TO DWG. No. 1601 FOR PIPE EMBEDMENT & TRENCHFILL DETAIL.

IF MATERIAL CHANGES FROM ROCK TO OTHER MATERIAL, GEOTECH TO CONFIRM IF TYPE 4 BEDDING IS REQUIRED.


NOTE: ALL STUBS TO BE END CAPPED FOR FUTURE CONNECTION AS PART OF INTERNAL DEVELOPMENT

DATUM RL(m)	33.0						
LAND USE	ROAD RES.	ROAD					
PIPE DIA & TYPE	DN150 uPVC SN8	DN150 uPVC SN8					
PIPE GRADE (1 in x)	1 IN 180	1 IN 180					
EMBEDMENT	TYPE 3	TYPE 3					
JUNCTION INVERT LEVEL	49.559						
DEPTH TO INVERT	6.282	6.057	5.924	5.924	4.795		
SEWER INVERT LEVEL	49.334	49.559	49.569	49.569	49.648		
DESIGN SURFACE LEVEL	55.615		55.493				
EXISTING SURFACE LEVEL	52.958		52.936				
SETOUT	E33113.230	N73511.094	E33114.449	N73512.419	E33124.157		
RUNNING CHAINAGE	0.000	1.800	1.800	14.349	16.149		

LINE 2

14/1 (STUB/3) 1/3

STRUCTURE TYPE & DROP	C3	Z	PE LINED	END		C1	V
STRUCTURE LID TYPE	D					D	V
BRANCH LINE No.	1						
BRANCH DROP TYPES	V						




DATUM RL(m)	35.0						
LAND USE	ROAD RES.	ROAD					
PIPE DIA & TYPE	DN150 uPVC SN8	DN150 uPVC SN8					
PIPE GRADE (1 in x)	1 IN 180	1 IN 180					
EMBEDMENT	TYPE 3	TYPE 3					
JUNCTION INVERT LEVEL	50.359	53.734					
DEPTH TO INVERT	6.248	3.248	3.173	3.173	3.273		
SEWER INVERT LEVEL	53.734	53.744	53.744	53.794	53.794		
DESIGN SURFACE LEVEL	56.983	56.917					
EXISTING SURFACE LEVEL	57.514	57.651					
SETOUT	E32972.312	N73370.411	E32973.123	N73388.804	E32977.150		
RUNNING CHAINAGE	0.000	1.800	1.800	8.939	10.739		

LINE 3

17/1 (STUB/4) 1/4

STRUCTURE TYPE & DROP	C3	Z	PE LINED	END		C1	V
STRUCTURE LID TYPE	D					D	V
BRANCH LINE No.	1						
BRANCH DROP TYPES	V						




DATUM RL(m)	34.0						
LAND USE	ROAD RES.	ROAD					
PIPE DIA & TYPE	DN150 uPVC SN8	DN150 uPVC SN8					
PIPE GRADE (1 in x)	1 IN 180	1 IN 180					
EMBEDMENT	TYPE 3	TYPE 3					
JUNCTION INVERT LEVEL	51.168	53.232					
DEPTH TO INVERT	3.248	3.175	3.175	3.274			
SEWER INVERT LEVEL	53.232	53.242	53.242	53.291	53.291		
DESIGN SURFACE LEVEL	56.480	56.417					
EXISTING SURFACE LEVEL	53.457	53.500					
SETOUT	E32763.005	N73319.324	E32763.613	N73317.630	E32766.619		
RUNNING CHAINAGE	0.000	1.800	1.800	8.904	10.704		

LINE 4

20/1 (STUB/5) 1/5

STRUCTURE TYPE & DROP	C3	Z	PE LINED	END		C1	V
STRUCTURE LID TYPE	D					D	V
BRANCH LINE No.	1						
BRANCH DROP TYPES	V						




DATUM RL(m)	35.0						
LAND USE	ROAD RES.	ROAD					
PIPE DIA & TYPE	DN150 uPVC SN8	DN150 uPVC SN8					
PIPE GRADE (1 in x)	1 IN 180	1 IN 180					
EMBEDMENT	TYPE 3	TYPE 3					
JUNCTION INVERT LEVEL	51.940	53.305					
DEPTH TO INVERT	3.132	3.194	3.194	3.170			
SEWER INVERT LEVEL	53.305	53.315	53.315	53.368	53.368		
DESIGN SURFACE LEVEL	56.438	56.509					
EXISTING SURFACE LEVEL	55.739	55.720					
SETOUT	E32610.641	N73184.460	E32611.781	N73183.067	E32617.760		
RUNNING CHAINAGE	0.000	1.800	1.800	9.440	11.240		

LINE 5

22/1 (STUB/6) 1/6

STRUCTURE TYPE & DROP	C3	Z	PE LINED	END		C1	V
STRUCTURE LID TYPE	D					D	V
BRANCH LINE No.	1						
BRANCH DROP TYPES	V						




DATUM RL(m)	36.0						
LAND USE	ROAD RES.	ROAD					
PIPE DIA & TYPE	DN150 uPVC SN8	DN150 uPVC SN8					
PIPE GRADE (1 in x)	1 IN 180	1 IN 180					
EMBEDMENT	TYPE 3	TYPE 3					
JUNCTION INVERT LEVEL	52.295	53.324					
DEPTH TO INVERT	3.248	3.175	3.175	3.274			
SEWER INVERT LEVEL	53.324	53.334	53.334	53.383	53.383		
DESIGN SURFACE LEVEL	56.572	56.509					
EXISTING SURFACE LEVEL	58.707	58.749					
SETOUT	E32526.663	N73161.259	E32526.539	N73159.463	E32525.924		
RUNNING CHAINAGE	0.000	1.800	1.800	8.900	10.700		

LINE 6

PLOT: 27 Aug 2025 09:30 AM LOCATION: H:\2025\24-0750\Unlabeled\Drawings\Trunk Sewer\24-0750-16-10-TRUNK SEWER LONGITUDINAL.dwg

REV	DATE	DESIGN	DRAWN	REVISION DETAILS
A	17.03.25	BR	BR	ORIGINAL ISSUE
B	02.04.25	BR	BR	CLIENT UPDATES
C	20.06.25	BR	BR	SEWER ALIGNMENT UPDATE
D	22.08.25	BR	BR	RFI RESPONSE
E	27.08.25	BR	BR	UPDATE PIPE TYPE

DRAWN	STATUS
BR	NOT FOR CONSTRUCTION
DESIGN	APPROVED
BR	DANIEL COLLINS RPEQ 18631 DATE 27.08.25
FOR AND ON BEHALF OF COLLIER'S INTERNATIONAL ENGINEERING & DESIGN PTY LTD	



PROJECT NAME

MONARCH GLEN No. 1 PTY LTD

TRUNK SEWER MAIN - PACKAGE 2
HOMESTEAD DRIVE
MONARCH GLEN

PLANS AND DOCUMENTS referred to in the PDA DEVELOPMENT APPROVAL

Approval no: DEV2025/1683

Date: 27 October 2025

DRAWING TITLE		
TRUNK SEWER LONGITUDINAL SECTIONS SHEET 3 OF 3		
PROJECT No.	DRAWING No.	REVISION
24-0750	1616	E