



GEOTECHNICAL INVESTIGATION

PROJECT NO. 1-12516

JANUARY, 2016

825 STANLEY PTY LTD

APARTMENT BUILDINGS

825 STANLEY STREET, WOOLLOONGABBA

Soil Surveys Engineering Pty Limited

A.B.N. 70 054 043 631

www.soilsurveys.com.au

Brisbane
Level 2, 19 Finchley Street, Milton, QLD, 4064, Australia
PO Box 317, Paddington, QLD, 4064, Australia
Ph +617 3369 6000
Fax +617 3369 6660
brisbane@soilsurveys.com.au

Gold Coast
Unit 8, 140 Millaroo Drive, Helensvale, QLD, Australia
PO Box 3429, Helensvale, QLD, 4212, Australia
Ph +617 5500 0465
Fax +617 5500 0462
goldcoast@soilsurveys.com.au

Document Information

Project Number	1-12516
Document Title	Geotechnical Investigation Apartment Buildings
Site Address	825 Stanley Street, Woolloongabba
Client	825 Stanley Pty Ltd
File ref	1-12516, 2016-02-01, BR VER 1
Author	Murray Geale

Review

Ver No.	Document Type	Reviewed by	Approved for Issue	
			Name	Date
1	Final	Jim Dixon		

Distribution List

Ver No.	Organisation	Contact	Email	Date Sent
1	825 Stanley Pty Ltd	Bill McClanachan	bill.mcclanachan@sarazin.com.au	5/02/16
1	Nettleton Tribe	George Fatseas Rebecca Elsdon	georgefatseas@nettletontribe.com.au rebeccaelsdon@nettletontribe.com.au	5/02/16
1	Martin Cosgrove and Associates	Martin Cosgrove	Martin.cosgrove@mcaeng.com.au	05/02/16

TABLE OF CONTENTS

1.0	INTRODUCTION.....	1
2.0	SCOPE OF GEOTECHNICAL SERVICES.....	3
3.0	SITE DESCRIPTION	3
4.0	GEOTECHNICAL INVESTIGATION.....	8
4.1	Field Investigation.....	8
4.2	Laboratory Testing.....	8
5.0	INVESTIGATION FINDINGS.....	9
5.1	Regional Geology.....	9
5.2	Subsurface Profile.....	10
5.3	Groundwater	11
6.0	ENGINEERING ASSESSMENT.....	13
6.1	Trafficability	13
6.1.1	Stage 1.....	13
6.1.2	Stages 2 and 3.....	15
6.2	Earthworks	15
6.3	Excavatability.....	16
6.4	Dewatering - Construction	17
6.5	Excavation/Boundary Retention	17
6.5.1	General.....	17
6.5.2	Detailed Design.....	18
6.5.3	Cantilever Sheet Pile.....	18
6.5.4	Secant Pile Wall	18
6.5.5	Anchor Design.....	19
6.5.6	Anchored Mesh/Shotcrete Wall	20
6.5.7	Retaining Walls	22
6.5.8	Design Comments.....	22
6.6	Dilapidation Survey.....	23
6.7	Building Foundations	23
6.7.1	General	23
6.7.2	Bored Piers – Stage 1.....	24
6.7.3	Pad Footings – Stages 2 and 3	25
6.7.4	Detention Basin Slab.....	25
6.7.5	Basement Slab – Stages 2 and 3	25
7.0	LIMITATIONS.....	26

Appendices

Appendix A

Notes Relating to this report

Appendix B

Borehole Record Sheet

Appendix C

Laboratory Test Certificates

Appendix D

Drawings

1.0 INTRODUCTION

This report presents the results of the geotechnical investigation carried out by Soil Surveys Engineering Pty Limited for the proposed Apartment Buildings development at 825 Stanley Street, Woolloongabba.

It is understood that the proposed development will comprise:-

- Three, twenty level towers, constructed in three stages.
- Buildings 2 and 3 will incorporate three levels of basement carparking. Earthworks will comprise excavations of up to 9.5m to form the lower basement level of RL - 4.5m.
- No basement is proposed for Building 1. However, excavation to RL 3.0m is proposed at Building 1 location to create a lined detention basin (concrete base and walls) beneath ground floor; the detention basin will be located to the east of the brick drain.

Refer Figures 1, 2 and 3.



FIGURE 1 – STANLEY STREET PERSPECTIVE




FIGURE 2 – GROUND FLOOR




FIGURE 3 – SECTION

2.0 SCOPE OF GEOTECHNICAL SERVICES

The scope of geotechnical services provided by Soil Surveys Engineering Pty Limited was directed towards evaluating the following items as detailed in our proposal 1-12516 dated 20th November, 2015:-

- Investigation of the subsurface profile by drilling, sampling and insitu testing with ten boreholes.
- Laboratory testing on selected samples to assess engineering properties of the subsurface material.
- Engineering analysis of site investigation and laboratory test results to evaluate:-
 - Trafficability
 - Excavatability
 - Construction Dewatering
 - Excavation Retention System Options
 - Retaining Wall Design Parameters
 - Building Foundations
 - Basement Slab Construction

3.0 SITE DESCRIPTION

The site of the proposed development is located at 825 Stanley Street, Woolloongabba – refer Figure 4.




FIGURE 4 – SITE LOCATION

The site is occupied by a series of single and two level structures, along with a large open carpark area.

Ground surface levels fall north to south and west to east, with ground surface levels typically between RL 5.0m and RL 4.5m.

Drainage conditions are considered to be poor.

Numerous underground services exist on site.

Of particular note is the presence of the “brick drain” located to the east of the site within Stage 1 – refer detailed survey, Appendix D. Provided survey indicates that this brick drain runs north south, is approximately 2.8m wide, has an invert level of RL 1.07m, with top of drain recorded at levels between RL 3.83m and RL 3.38m. The brick drain will be retained as part of the proposed development.

Boundary conditions comprise:-

- Northern Boundary – Stanley Street
- Eastern Boundary – residential tower, currently under construction (refer Photographs 1 and 4).

- Southern Boundary – Trafalgar Street.
- Western Boundary – Jurgen Street, with a single storey brick veneer “BCC Building” (refer Photograph 3) located adjacent the north western corner of the development site.

Photographs 1 to 4 indicate typical site conditions. Please also refer Detailed Survey prepared by Jensen Bowers (Appendix D).



PHOTOGRAPH 1



PHOTOGRAPH 2



PHOTOGRAPH 3



PHOTOGRAPH 4

4.0 GEOTECHNICAL INVESTIGATION

4.1 Field Investigation

Subsurface conditions at the site were investigated by drilling and sampling ten boreholes to depths up to 26.77m; all boreholes extended to rock. Boreholes were drilled using both a 4WD mounted small drilling rig (EVH1750) along with a truck mounted large drilling rigs (Scout rigs), i.e.:-

- Boreholes 1 to 4 and 8 to 10 – Scout drilling rigs
- Boreholes 5 to 7 – EVH1750 drilling rig.

The soil classification descriptions, field and laboratory testing were carried out in general accordance with the following Australian Standards:-

- AS.1726-1993 “Geotechnical Site Investigations”
- AS.1289 “Methods of Testing Soils for Engineering Purposes”

A description of the investigation method, borehole records and a site plan showing investigation locations are included in the Appendices. Borehole coordinates were recorded using a hand held GPS device, with accuracy consistent with such devices.

4.2 Laboratory Testing

Laboratory testing was carried out on selected samples retrieved from the site investigation program and was directed towards assessing the strength of the rock.

The laboratory testing certificate is contained in Appendix C.

5.0 INVESTIGATION FINDINGS

5.1 Regional Geology

Reference to the Department of Mines 1:100,000 Brisbane Geological Map (Sheet 9543), 1986 (Refer Figure 5), indicates that the site is underlain by undifferentiated alluvial soils (Qa), above a basement geology comprising rocks of the Middle Triassic Period (~240 Mya), which in this area are made up of the Brisbane Tuff (Rii). This unit is understood to outcrop in a broad band from Annerley in the south through Woolloongabba and Kangaroo point to Bowen Hills in the north.

It is expected that the majority of the soil directly underlying the site is most likely to be from the older of the alluvial deposits (sand, silt, clay and gravel) and/or residual soils derived from the weathering of the underlying rock.

The typical lithologies of the Brisbane Tuff can include ignimbrite, stratified and massive rhyolitic tuff, conglomerate, sandstone and scree breccia. Structurally, the rocks commonly show clearly defined orthogonal joint sets (linear rock defects), creating a blocky rock mass.

It is understood that these volcanic rocks were formed as the product of explosive eruptions of rhyolitic magma, onto an erosional surface. The older bedrock consisted of Bunya Phyllite (DCb) which also outcrops nearby. Associated with the Tuff are sedimentary rocks (sandstones, conglomerate, shale, coal, etc.) of the Aspley Formation (Rip) which were laid down in and adjacent to rivers and lakes also during this period.

Because the volcanic and sedimentary rocks were laid down at a similar time, there is generally not a clear boundary between the units; rather they tend to be inter-bedded, particularly towards the outer edges of the Tuff flows.




FIGURE 5 – SECTION OF REGIONAL GEOLOGY MAP ON GOOGLE EARTH

5.2 Subsurface Profile

Subsurface conditions encountered are consistent with conditions described on geological maps; subsurface conditions can be broadly grouped into three material types:-

- Fill Material
- Natural Soils
- Tuff Rock

Fill Material

Fill material was encountered at all boreholes to depths between 0.2m (BH5) and 2.6m (BH8); maximum depth of fill is expected to be encountered directly adjacent the brick drain, with fill depth approximating the drain invert level. The fill material is variable in terms of nature and type and comprised:-

- Bitumen and pavement gravels
- Ash
- Clayey Gravel – medium dense
- Clayey/Gravelly Sand – loose/very loose
- Clayey Sand – loose
- Gravelly Sand – medium dense
- Gravelly/Sandy Clay – stiff
- Clay – stiff

The fill stratum is considered to be generally poor quality, weak and uncontrolled.

Natural Soils

Natural soils were encountered at levels between RL 4.86m (BH1) and RL 2.4m (BH8). Please note that depth to natural soils is expected to be greater along the brick drain alignment, with level to top of natural approximately the same as the brick drain invert level (approximately RL 1.0m).

Natural soils encountered were variable in nature and type, and comprised:-

- Gravelly Clayey Sand – very loose/loose/medium dense
- Silty Clayey Sand/Clayey Sand – very loose/loose/medium dense
- Silty Clay/Clay – firm/stiff/very stiff
- Sandy Clay – firm/stiff/very stiff/hard
- Gravelly Sandy Clay – stiff/very stiff/hard

Tuff Rock

Tuff rock was encountered at levels between RL 4.4m (BH5) and RL -1.8m (BH7). As borehole records indicate, the level to tuff rock is variable, with significant differences in levels to rock observed at adjacent boreholes.

The tuff rock was described as initially being very weak/weak, however, rock strength increased with depth, with medium strong/strong/very strong tuff encountered (refer Boreholes 8, 9 and 10).

* * *

A summary of the subsurface profile is presented in Table 1.

TABLE 1 SUBSURFACE PROFILE

Location	Surface Level RL (m)	Fill Material (m)	Natural Soils (m)	Tuff Rock (m)	Termination Depth (m)
BH 1	5.5	0.00-0.80	0.80-5.30	5.30-6.00	6.00
BH 2	5.0	0.00-0.25	0.25-4.00	4.00-4.50	4.50
BH 3	5.0	0.00-1.60	1.60-5.20	5.20-6.00	6.00
BH 4	4.0	0.00-1.20	1.20-2.60	2.60-3.00	3.00
BH 5	5.0	0.00-0.20	0.20-0.60	0.60-1.20	1.20 ⁽⁴⁾
BH 6	4.5	0.00-0.80	0.80-2.70	2.70-3.20	3.20 ⁽⁴⁾
BH 7	5.0	0.00-0.14	0.14-6.80	6.80-7.00	7.00 ⁽⁴⁾
BH 8	5.0	0.00-2.60	2.60-4.80	4.80-26.77	26.77
BH 9	4.2	0.00-1.60	1.60-5.50	5.50-20.20	20.20
BH10	5.0	0.70-4.30	0.70-4.30	4.30-20.66	20.66

Notes:-

1. NE – Not Encountered.
2. All depths below existing ground surface level as of date of investigation.
3. Surface levels inferred from Client supplied survey.
4. Borehole terminated at drill rig refusal ('TC' bit refusal).

5.3 Groundwater

Groundwater was encountered at most borehole locations as seepage at the time of the investigation during augering; Table 2 refers.

TABLE 2 GROUNDWATER

Location	Surface Level RL (m)	Groundwater Noted RL (m)
BH1	5.5	4.9
BH2	5.0	4.1
BH3	5.0	2.7
BH4	4.0	NE
BH5	5.0	NE
BH6	4.5	3.7
BH7	5.0	0.5
BH8	5.0	2.4
BH9	4.2	2.2
BH10	5.0	NE

Note:- Groundwater noted indicates depth at which groundwater was observed during open hole augering.

As Table 2 indicates, seepage (where encountered) was encountered at or near (within 0.4m) of the fill/natural interface at Boreholes 1, 2, 6, 8 and 9, with seepage encountered within natural soils at Boreholes 3 and 7.

Groundwater monitoring wells were installed at Boreholes 3, 9 and 10, with steady groundwater levels recorded at RL 0.7m, RL 0.3m and RL -0.8m respectively (refer borehole records).

Groundwater wells at Boreholes 9 and 10 were also checked on 3rd February, 2016, with groundwater levels recorded at RL 0.4m and RL -1.3m respectively.

Seepage is expected to be encountered, particularly within the fill material/natural soils, and at the fill/natural and soil/rock interfaces at all boreholes locations. It should also be noted that groundwater conditions can vary both seasonally and with prevailing weather conditions. If construction is to be undertaken at a “significant” time following this investigation, or following ‘wet’ weather, then it would be prudent to confirm groundwater levels prior to construction.

6.0 ENGINEERING ASSESSMENT

This section of the report includes evaluation of the following:-

- Trafficability
- Excavatability
- Construction Dewatering
- Excavation Retention System Options
- Retaining Wall Design Parameters
- Building Foundations
- Basement Slab Construction

*

*

*

An Acid Sulfate Soil (ASS) Study was carried out by Soil Surveys Engineering for this site. It should be ensured that all works are carried out in accordance with recommendations contained within the ASS management plan.

6.1 Trafficability

Trafficability conditions at the time of the geotechnical study were considered to be fair due to the paved surface. However, some problems may be anticipated following removal of pavement/building slabs.

The soils underlying the pavements (fill and natural) are sensitive to repetitive vehicle loading and water (ie. they will lose strength through repetitive vehicle loading or if they become overly moist or wet). Further, seepage may also result in a subsequent loss of strength. This may limit trafficability for light weight construction vehicles and create difficulties during construction. This situation would be more pronounced if rainfall followed demolition, clearing, excavation, etc.

Problems may also arise from disturbance of the soil fabric with removal of existing structures, services, etc. Depressions could be formed resulting in water traps and potential softening of adjacent and underlying soils. Extreme care should be exercised during the demolition/clearing phase to ensure that excessive subgrade disturbance is not caused during removal of existing structures, services, etc.

6.1.1 Stage 1

Stage 1 works will include foundation construction using large truck mounted foundation rigs and cranes, and excavation to RL 3.0m, to the east of the brick drain, to create a lined detention basin (concrete base and walls).

Borehole records indicate that subgrade conditions at RL 3.0m may comprise:-

- Uncontrolled fill material, eg. Boreholes 4A, 8 and 9.
- Natural stiff sandy clay and loose gravelly clayey sand, eg. Borehole 3A.
- Tuff rock, eg. Borehole 5.

Trafficability conditions are expected to be poor in areas where uncontrolled fill material and natural soils form the subgrade.

Considering the above, it is recommended that foundation works for Stage 1 be carried out prior to removal of the existing pavement or concrete floor slab (associated with the building to the south east of the site), i.e. **place the working platform (to support construction plant) on top of the existing pavement**. Please note that the scope of Soil Surveys Engineering's study **DOES NOT** include the design of a working platform for heavy construction vehicles or heavy tracked plant. Detailed design of a working platform should be carried out considering the operation of actual machinery proposed to be used. This is particularly important when considering the use of **heavy** foundation rigs and **heavy** cranes - the piling/crane contractor should be consulted regarding their requirements.

Following foundation works, working platform material, along with select "good quality" existing fill material, should be excavated and stockpiled for later reuse (refer next paragraph and Section 6.2).

Following excavation to RL 3.0m for the detention basin, in areas where soils form the subgrade, it is recommended that a working layer (bridging layer), possibly in conjunction with a geotextile, be placed to support personnel and light weight construction equipment (as required). Working platform material and select "good quality" existing fill material is envisaged to be suitable (and reused) for this working layer. Some over excavation (below RL 3.0m) will be required. The working layer thickness is subject to subgrade conditions at time of construction, proposed works, machinery type/weight proposed to be operated at the base of the detention basin, etc. However, planning should consider the advantages associated with limiting the use of any machinery operating at the base of the detention basin.

Brick Drain

Whilst Soil Surveys Engineering do not have any knowledge as to the condition of the brick drain, and the ability of the brick drain to accommodate construction plant/vehicle loads, a cautious approach is recommended. It is recommended that plant/vehicles do not travel over the brick drain, i.e. construct a temporary bridge, and that construction works be carried out in a manner where the brick drain is not adversely affected.

It is recommended that dilapidation survey of this brick drain be carried out prior to construction.

6.1.2 Stages 2 and 3

Stages 2 and 3 works will comprise excavation to RL -4.5m to form basement levels. Subgrade conditions at RL -4.5m will comprise tuff rock.

Trafficability conditions are expected to be good in areas where tuff rock forms the subgrade. However, during excavation works, trafficability will be poor where soils (uncontrolled fill material and natural soils) form the subgrade.

The Building Contractor should acknowledge the nature of the uncontrolled fill material and natural soils, and groundwater/seepage conditions, when planning excavation works for Stages 2 and 3.

6.2 Earthworks

Earthworks will comprise:-

- Stage 1 – excavation to RL 3.0m to create a detention basin. Further, subgrade treatment is expected to be required in areas where existing uncontrolled fill material/natural soils form the subgrade.
- Stages 2 and 3 – excavation to RL -4.5m for basement construction. Refer Section 6.3.

Earthwork procedures should be carried out in a responsible manner in accordance with AS.3798-2007 "Guidelines on Earthworks for Commercial and Residential Developments".

The following earthwork procedures are recommended for Stage 1.

Stage 1

Uncontrolled fill material was encountered across Stage 1, with natural soils recorded at levels between RL 2.4m and RL 4.8m. The fill material is of poor quality, weak, is considered to be uncontrolled and is very sensitive to water (ie. will lose strength if it becomes wet) and vehicle movement.

Further natural soils encountered beneath the uncontrolled fill were weak on occasions, eg. loose gravelly clayey sand as encountered at Borehole 3A and Borehole 4 at RL 2.9m and RL 3.5m respectively.

It is envisaged that the detention basin will be lined with a concrete base and walls – subgrade treatment will therefore be required.

The following subgrade treatment is recommended:-

- **Fill material encountered should be considered uncontrolled and requiring treatment ie. excavate to expose natural soils (subject to ongoing site inspections by Soil Surveys Engineering during excavation works).**

- In areas where soils form the subgrade, it is envisaged that a working layer (to support construction personnel and light weight construction equipment) will be required. The following is offered for consideration:-
 - Place a geotextile (say 'G' rating of 2400); the geotextile will act as a separator as well as providing some strength.
 - Place bridging layer (say rocky material, ie. crushed rock/concrete/brick and/or working platform material), lightly compact.

It is envisaged that the bridging layer may need to be at least 0.3m in thickness. However, the bridging layer thickness is subject to inspection by Soil Surveys Engineering during excavations, proposed works, machinery type/weight, movement, etc.

Engineering supervision of the earthworks operations by Soil Surveys Engineering Pty Limited is recommended.

6.3 Excavatability

Subsurface conditions are variable and comprise fill material, natural soils and weathered rock.

Considering the findings of the geotechnical investigation, the following comments can be made on excavation characteristics:-

- Soils – soils will be within the excavation limits of a medium sized backhoe.
- Rock - rock excavation will require the use of large excavators (say 30 tonne) with use of rock breakers, rock saws, etc.
- Bored Piers - the ability to drill piers in the rock is not only dependent on material characteristics but also the type (power and size) of the bored pier drilling rig, drilling teeth, size of pier, etc. **It is recommended that the drilling contractors be consulted on this matter.** However, we recommend that planning considers that the use of large tracked mounted bored pier machines (say 30 tonne machines) with rock coring capabilities will be required for piers extending into the tuff rock stratum.

Vibrations

The effect of vibrations on adjacent structures, services, brick drain, roads, etc. from excavation works, particularly use of rock breakers, must be carefully considered. Regardless, adequate vibration monitoring and control is recommended.

Inspection of Core

Soil Surveys Engineering hold rock core recovered from the site.

It is recommended that tender documents include a requirement to inspect retrieved core so that intending contractors can make their own assessment and judgement on the excavatability of the rock stratum.

6.4 Dewatering - Construction

The potential to encounter groundwater exists (refer Section 5.2).

For construction works a drainage system, comprising a gravel blanket, side drains etc., grading to a sump pump, could be considered.

6.5 Excavation/Boundary Retention

6.5.1 General

Considering the proposed development, excavation support will be required, i.e.:-

Stage 1

To retain soils associated with the detention basin excavation (approximately 2.0m in height), a cantilever sheet pile system (possibly with internal propping) is recommended. In areas where high level rock is encountered, eg. Borehole 5, alternative retention methods would need to be considered, eg. mesh/shotcrete wall with anchor/dowel.

Groundwater was recorded as seepage within fill material and natural soils. Steady groundwater levels were recorded at levels between RL 0.7m and RL -1.3m. Refer Section 5.3. The Designer of the retention system will need to consider groundwater conditions.

Stages 2 and 3

Excavation from approximately RL 5.0m to approximately RL -4.5m (i.e. 9.5m excavation) will be required for basement construction. The retention system will retain soils, both fill and natural soils, and tuff rock.

Groundwater was recorded as seepage within fill material and natural soils. Steady groundwater levels were recorded at levels between RL 0.7m and RL -0.8m. Refer Section 5.3. The Designer of the retention system will need to consider groundwater conditions.

Considering subsurface conditions encountered the following retention system is recommended:-

- In that zone from ground level to tuff rock, an anchored secant pile wall (interlocking piers) is recommended. Piers are to found into the tuff rock.
- In that zone retaining tuff, i.e. that zone below secant pile wall piers, an anchored mesh/shotcrete wall, is recommended.

*

*

*

Retention systems must be installed prior to excavation works.

6.5.2 Detailed Design

DETAILED RETENTION SYSTEM DESIGN (which is outside the scope of Soil Surveys Engineering's commission and study) IS REQUIRED; a detailed soil-structure analysis must be carried out to determine an effective retention support system.

The requirement to limit deflections to acceptable levels should be explicit in the brief to retention system designers.

The effect of potential vertical and horizontal movements (resulting from deflection of the retention system) on existing adjacent structures, services, brick drain, road etc. must be carefully considered. Services locations and adjacent building foundation systems must be established/considered by the retention system designer – this matter is the responsibility of the retention system designer.

The design of a support system should take into account overexcavation possibly associated with foundation construction, earthworks, services installation, etc.

UNSUPPORTED EXCAVATIONS ARE NOT RECOMMENDED.

Further, it is recommended that several monitoring stations be set up to check for movement during excavation. A regular monitoring program of these stations should be implemented e.g. twice daily during excavation and daily at any other time.

6.5.3 Cantilever Sheet Pile

Stage 1 excavations will extend to approximately RL 3.0m. The retention system will largely retain fill and natural soils – groundwater is expected to be encountered (refer Section 5.3).

A cantilever sheet pile system (possibly with internal propping), with sheets founding at a suitable level below proposed excavation level, is recommended.

In areas where high level rock is encountered, eg. Borehole 5, alternative retention methods would need to be considered, eg. mesh/shotcrete wall with anchor/dowel.

6.5.4 Secant Pile Wall

With this option, **interlocking piers** are drilled and then joined at the surface using a capping beam.


The following general construction procedure would be applicable:-

- Install secant piers with a suitable embedment into the tuff stratum.
- Excavate to allow installation of the first row of temporary ground anchors.

- Continue excavation/installation of temporary ground anchors in accordance with design requirements.

Please note that permission to install anchors into adjacent properties would be required.

It is recommended that a capping beam be incorporated into the design. Figure 6 refers.



A minimum pier diameter of 0.60m is recommended for anchored piers, however, pier diameter is dependent on the moment capacity of the pier section, lateral deflection requirement, boundary conditions, etc.

6.5.5 Anchor Design

Anchor design should consider the following:-

- Anchor free length should extend from the anchor head to $0.15H$ (H is total excavation height) behind the design failure plane drawn up at 60° from the base of the cut with a minimum length of 3m (temporary only).
- Anchor bond length will depend upon desired anchor capacity, drill hole size and material parameters of intersected material. An allowable bond stress of 250kPa for SW tuff rock or better could be adopted. It is recommended that pull out tests be carried out during excavation to assess allowable bond stress design values. It is possible that greater values could be used, subject to test results.

- Anchors are designed as temporary.

6.5.6 Anchored Mesh/Shotcrete Wall


An anchored mesh/shotcrete wall is considered appropriate for temporary support of the tuff rock stratum and below the secant pile system.


A maximum panel size of 2.0m wide by 2.0m high is recommended, subject to inspection during excavation works.

The method of construction for this wall type comprises excavation in stages/levels; at each level, excavate on a hit one/miss two basis leaving the buttress supporting the area to be retained, (Figures 7 and 8); please note that this requirement may be relaxed subject to inspection by Soil Surveys Engineering during bulk earthworks. The anchor hole is drilled, anchor placed and grouted, panel steel placed and sprayed.

Drainholes (in conjunction with strip drains) should be drilled during the process and a short piece of PVC placed in the neck of the hole during spraying to allow the hole to continue through the wall.

Once a panel has been completed the adjoining panels should then be excavated and the process repeated until all panels have been constructed.





6.5.7 Retaining Walls

Retaining walls should be designed in accordance with AS4678-2002 “Earth Retaining Structures”.

The following parameters (unfactored) may be adopted for basement wall design (Table 3).

TABLE 3 PARAMETERS FOR USE IN RETAINING WALL DESIGN

Material	Density (kN/m ³)	Earth Pressure Coefficient	Long Term Drained ϕ (degrees)
		Vertical Wall	
		Ko	
Rock	23	0.43	35
Natural Soils	19	0.53	28

6.5.8 Design Comments

As noted previously, **detailed retention system design is required (and is outside the scope of Soil Surveys Engineering’s commission and study)**; Soil Surveys Engineering would however be pleased to assist with the geotechnical engineering aspects of the design process, if requested.

However, please note that Soil Surveys Engineering do not produce engineering drawings; our geotechnical engineering retention design will be provided in a report which sets out sufficient detail to allow the drafting (by others) of engineering drawings for construction. These drawings should (at least) consist of an elevation showing anchor installation locations (if required) as well as typical sections and other design/construction parameters. Soil Surveys Engineering should provide geotechnical design review of the drawings.

It should be noted that as well as geotechnical design review of drawings, construction inspections (i.e. inspection of piers associated with retention system, inspections during earthworks, etc. - please contact Soil Surveys Engineering for advice) will also be required. **Soil Surveys Engineering is however not able to provide construction inspection services unless we have reviewed and approved any drawings prepared from our report PRIOR TO CONSTRUCTION COMMENCING.**

Further, vertical and lateral movement of soils will occur for any non-anchored system; movements occur as a result of stress release caused by the excavation.

The effect of potential vertical and horizontal movement on adjacent structures, brick drain, roads, services etc. must be carefully considered. The construction methods described may need to be modified following detailed design.

6.6 Dilapidation Survey

Adjacent buildings, brick drain, roads and underground services are located within and adjacent to proposed works.

It is recommended that a dilapidation survey of adjoining structures, brick drain, roads, etc. be carried out in order to establish their present condition prior to commencement of construction.

This survey should include the following:-

- The general condition of the property, ie. condition of all exposed walls, pavement condition, etc.
- The extent of existing damage (if any)
- Photographs/video

Actual locations of underground services and adjacent building foundation systems should be established prior to construction and during the design phase.

6.7 Building Foundations

6.7.1 General

Stage 1

The foundation system for Stage 1 should consider the following:-

- Detention basin beneath Stage 1 building.
- Structure loads – up to 15,000kN (working) loads have been advised.
- Presence of brick drain.
- Proposed Stage 2 works, i.e. basement to RL -4.5m.
- Subsurface conditions.

All considered, a deep foundation system, i.e. bored piers (in conjunction with liners), with piers founding in tuff rock, creating a fully suspended structure, is recommended. Piers will need to not only extend to levels below Stage 2 basement works, but extend to a sufficient level to accommodate structural loads.

Stages 2 and 3

For Stages 2 and 3, a high level pad footing system could be adopted with pads founding in fresh tuff rock at basement level.

6.7.2 Bored Piers – Stage 1

The pier foundation system should be designed in accordance with AS 2159-2009 'Piling - Design and Installation'. This code uses the limit state design method.

A bored pier foundation system (in conjunction with liners – liners to found into rock) is recommended.

The design of a single pier or a pier group must be such that both the design geotechnical strength $R_{d,g}$ and the structural strength $R_{d,s}$, are greater than or equal to the design action effect E_d , i.e.

$$R_{d,g} \geq E_d \text{ and } R_{d,s} \geq E_d$$

The design geotechnical strength ($R_{d,g}$) can be calculated as the ultimate design geotechnical strength ($R_{d,ug}$) multiplied by the geotechnical strength reduction factor ϕ_g . Ultimate design geotechnical strength ($R_{d,ug}$) parameters for the materials encountered on the site are outlined in Table 4.

TABLE 4 ULTIMATE GEOTECHNICAL STRENGTH ($R_{d,ug}$) PARAMETERS

Material	fb - Base Bearing (kPa)	fm,s - Skin Friction (kPa)
Fill Material	NR	NC
Natural Soils	NR	NC
Tuff Rock		
- Weak/Medium Strong	7500	150
- Strong to Very Strong	15000	500
Notes:		
<ol style="list-style-type: none"> NR - Not Recommended; NC - Not Considered in skin friction calculations. Ultimate geotechnical strength for compression can be determined from $R_{d,ug} = f_{m,s} A_s + f_{b} A_b$. For determination of geotechnical strength reduction factor (ϕ_g) refer Section 4.3.2 AS2159-2009. Considering limit state analysis (AS 2159-2009), the design geotechnical strength $R_{d,g}$ is calculated by multiplying the ultimate geotechnical strength $R_{d,ug}$ by the geotechnical strength reduction factor ϕ_g, i.e. $R_{d,g} = R_{d,ug} \times \phi_g$. Should a "working stress" approach be adopted, a minimum factor of safety of 3.0 on base and 2.0 on skin friction is recommended. The above parameters are for single piers. If piers are spaced at closer than three diameters, a reduction factor (Group Efficiency Ratio) may apply. Base bearing and skin friction parameters to be confirmed by inspection. 		

It should be ensured that all loose material is removed from the base of piers prior to pouring of concrete. The use of a 'clean-out' bucket or vacuum truck should be explicit in instructions to the drilling contractor. The practice of 'using water and spinning the augers' to remove loose material from the pier base is generally unacceptable.

Groundwater was encountered in boreholes (refer Section 5.3) at the time of the investigation.

An allowance for dewatering and the use of liners should be made.

Screw Piers

Screw piers (as an alternative to piers) could be considered for support of the detention basin perimeter wall. Screw piers should extend to found in tuff rock.

6.7.3 Pad Footings – Stages 2 and 3

It is envisaged that fresh tuff rock will be exposed at basement level (RL -4.5m) over Stages 2 and 3. In this case, a high level foundation system could be considered.

High level footings should found into the fresh tuff stratum. Footings founding in the fresh tuff stratum may be dimensioned for an allowable bearing capacity (subject to inspection by Soil Surveys Engineering) of 5,000kPa.

It should be ensured that the bases of all footings are cleaned of loose material.

6.7.4 Detention Basin Slab

The detention basin slab will need to be designed for groundwater/seepage. An under slab drainage system, in conjunction with hydrostatic valves, could be considered.

6.7.5 Basement Slab – Stages 2 and 3

For design purposes, it is recommended that the basement slab be designed adopting principles as contained in the Cement & Concrete Association of Australia, Industrial Floors & Pavements, Guidelines for Design, Construction & Specification.

It is envisaged that tuff rock will be exposed at basement level over the site. For design, a design CBR value of > 15% may be adopted where tuff rock forms the subgrade.

The basement slab will need to be designed for groundwater/seepage. A drained basement comprising an under slab drainage system with permanent pumps could be considered subject to water quality issues, long term maintenance of pumps, etc. A fully tanked basement, designed for hydrostatic uplift, could also be considered. Please note that significant uplift pressures may develop; permanent anchors/dowels may be required to resist uplift loads.

7.0 LIMITATIONS

We have prepared this report for the use of **825 Stanley Pty Ltd**, for design purposes in accordance with generally accepted geotechnical engineering practices. No other warranty, expressed or implied, is made as to the professional advice included in this report. This report has not been prepared for use by parties other than **825 Stanley Pty Ltd**; it may not contain sufficient information for purposes of other parties or for other uses. Please note that any third party relying on the information contained in this report for any purpose whatsoever does so entirely at its own risk, and any duty of care to that third party is excluded.

Any interpretation or recommendation given by Soil Surveys Engineering shall be understood to be based on judgement and experience and not on greater knowledge of the facts than the reported investigations would imply. The interpretation and recommendations are therefore opinions provided for our Client's sole use in accordance with the specific brief. As such they do not necessarily address all aspects of ground behaviour on the subject site. Information provided by others has been taken in good faith, but no liability can be accepted for information provided by others.

Your attention is drawn to 'Appendix A', 'Notes Relating to this Report'. Interpretation of factual data given in this report is based on judgement, not a greater knowledge of facts other than those reported.

Interpretation of the information shown on the logs, and its application to design and construction, should therefore take into account the spacing of boreholes, the method of drilling, the frequency of sampling and testing and the possibility of other than "straight line" variations between the boreholes. Subsurface conditions between boreholes may vary significantly from conditions encountered at the borehole locations.

In the event that conditions encountered on site during construction appear to vary from those expected from the information contained in the report, the Company requests that it immediately be notified. Most problems are more readily resolved when conditions are exposed than at some later stage, after the event.

Soil Surveys Engineering consider that a documentation review service (during the design phase and prior to construction) to verify that the intent of geotechnical recommendations is properly reflected in the design, along with construction inspections, forms a very important component of the geotechnical engineering design service/process.

The geotechnical review ensures geotechnical risks to our Client and their project are minimised at the design and tender stage of the project. Further, with Soil Surveys Engineering being commissioned to carry out geotechnical construction inspections, an opportunity at the time of construction to confirm any assumptions made in the preparation of the report and allow the effect of any normally occurring variation in ground conditions to be assessed with respect to construction becomes available.

The above statements are not intended to reduce the level of responsibility accepted by Soil Surveys Engineering in accordance with our commission, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in doing so and the risks they accept should they decline to have Soil Surveys Engineering carry out a geotechnical documentation review and geotechnical construction inspections.

It is highly recommended that the Client avail themselves of these review and inspection services; our standard rates will apply.



M. V. GEALE (RPEQ 3839)

PRINCIPAL ENGINEER

for and on behalf of

SOIL SURVEYS ENGINEERING PTY LIMITED

APPENDIX A

NOTES RELATING TO THIS REPORT

INTRODUCTION

These notes are provided by Soil Surveys Engineering Pty Limited (the Company) to complement the geotechnical report in regard to classification methods and field procedures. Not all notes are necessarily relevant to all reports.

The ground is a product of continuing natural and man-made processes and therefore exhibits a variety of characteristics and properties which vary from place to place and can change with time. Geotechnical engineering involves gathering and assimilating limited information about these characteristics and properties in order to understand or predict the behaviour of the ground on a particular site under certain conditions. This report may contain such information obtained by inspection, excavation, probing, sampling, testing or other means of investigation. If so, they are directly relevant only to the ground at the place where and at the time when the investigation was carried out.

DESCRIPTION AND CLASSIFICATION METHODS

Soils - The methods of description and classification of soils and rocks used in this report are based on Australian Standard 1726-1993 (Geotechnical Site Investigations), where appropriate. In general, descriptions cover the following properties - soil or rock type, colour, structure, strength or density, and inclusions. Identification and classification of soil and rock involves judgement and the Company infers accuracy only to the extent that is common in current geotechnical practice.

Soil types are described according to the dominant particle size and behaviour as set out in AS 1726-1993.

Cohesive soils are classified on the basis of strength (consistency) either by use of hand penetrometer, shear vane, laboratory testing or engineering examination. The strength terms are defined in AS1726-1993 Table A4.

Non-cohesive soils are classified on the basis of relative density usually based on insitu testing or engineering examination (see AS1726-1993 Table A5).

Rocks - Rock types are classified by their geological names (AS1726-1993 Table A6), together with

descriptive terms regarding weathering (AS1726-1993 Table A9), strength (refer Table 1 below), defects (AS1726-1993 Table A10), etc. Where strength testing (ie Point Loads) is carried out, AS1726-1993 Table A8 is used. Where relevant, further information regarding rock classification is attached.

Table 1 Estimated strength descriptions given to rock based on engineering examination

Strength Term	Approximate Qu (MPa)
Extremely Weak	< 1.0
Very Weak	1.0 - 5.0
Weak	5.0 - 25
Medium Strong	25 - 50
Strong	50 - 100
Very Strong	100 - 250
Extremely Strong	> 250

Ref ISRM "Suggested Methods for the Quantitative Description of Discontinuities in Rock Masses"

SAMPLING

Sampling is carried out during drilling or from other excavations to allow engineering examination (and laboratory testing where required) of the soil or rock.

Disturbed samples taken during drilling provide information on plasticity, grain size, colour, moisture content, minor constituents and, depending upon sample disturbance, (information on strength and structure).

Undisturbed samples are taken by pushing a thin walled sample tube, usually 50mm diameter (U50), into the soil and withdrawing it with a sample of the soil contained in a relatively undisturbed state. Such samples yield information on structure and strength, and are necessary for laboratory determination of shear strength, volume change potential and compressibility. Undisturbed sampling is generally effective only in cohesive soils.

Details of the type and method of sampling used are given on the attached logs.

TEST LOCATIONS

Test locations (e.g. boreholes, CPT's, test pits etc.) were based on available access at the time of testing (access may need to be provided "by others"). Test locations may have been shifted if access was not suitable.

Unless noted otherwise, accuracy of test locations are to the accuracy of hand held GPS equipment.

INVESTIGATION METHODS

The following is a brief summary of investigation methods currently adopted by the Company and some comments on their use and application.

Test Pits - These are normally excavated with a backhoe or a tracked excavator, allowing close examination of the insitu soils if it is safe to descend into the pit. The depth of penetration is limited to about 3m for a backhoe and up to 6m for an excavator. Limitations of test pits are the problems associated with disturbance and difficulty of reinstatement and the consequent effects on close-by structures. Care must be taken if construction is to be carried out near test pit locations to either properly recompact the backfill during construction or to design and construct the structure so as not to be adversely affected by poorly compacted backfill at the test pit location.

Hand Auger Drilling - A borehole of 50 to 100mm diameter is advanced by manually operated equipment. Refusal of the augers can occur on a variety of materials such as hard clay, gravel or rock fragments and does not necessarily indicate rock level.

Continuous Spiral Flight Augers - The borehole is advanced using 75 to 300 mm diameter continuous spiral flight augers, which are withdrawn at intervals to allow sampling or insitu testing. This is a relatively economical means of drilling in clays and in sands above the water table. Samples are returned to the surface by the flights or may be collected after withdrawal of the augers. Information from the drilling (as distinct from specific sampling) is of relatively lower reliability due to remoulding, inclusion of cuttings from above or softening of samples by groundwater, or uncertainties as to the original depth of the samples. Augering below the groundwater table has a lower reliability than augering above the water table. Various drill bits are attached to the base of the augers during

the drilling. The depth of refusal of the different bit types can provide information as to the strength of the material encountered. Generally two different bit types are used. The 'V' bit is a V shaped steel bit and the 'TC' bit is a tungsten carbide tipped screw type bit.

Wash Boring - The borehole is usually advanced by a rotary bit with water or fluid pumped down the hollow drill rods and returned up in the space between the rods and the soil or casing, carrying the drill cuttings. Only major changes in stratification can be determined from the cuttings, together with some information from "feel" and rate of penetration. More accurate information on soil strata is gained by regular testing and sampling using the Standard Penetration Test (SPT) and undisturbed thin walled tube samples (U50).

Mud Stabilized Drilling - Either Wash Boring or Continuous Core Drilling can use drilling mud as a circulating fluid to stabilize the borehole. The term "mud" encompasses a range of products ranging from bentonite to polymers such as Revert or Biogel. The mud tends to mask the cuttings and reliable identification is only possible from regular intact sampling (eg. from SPT and U50 samples) or from rock coring, etc.

Continuous Core Drilling - A continuous core sample is obtained using a diamond or tungsten carbide tipped core barrel. Provided full core recovery is achieved (which is not always possible in very weak rocks and granular soils), this technique provides a very reliable method of investigation. In rocks, NMLC coring (nominal 52 mm diameter) is usually used with water flush. The length of core recovered is compared to the length drilled and any length not recovered is shown as CORE LOSS. The location of losses is determined on site by the supervisor. If the location of the loss is uncertain, it is placed at the top end of the run, when the core is placed in a storage tray and recorded on the log.

Standard Penetration Tests - Standard Penetration Tests (SPT) are used mainly in non-cohesive soils, but can also be used in cohesive soils, as a means of indicating density or strength. The test procedure is described in Australian Standard 1289, "Methods of Testing Soils for Engineering Purposes" - Test 6.3.1.

exist between static cone and nearby borehole information.

Portable Dynamic Cone Penetrometers - Portable Dynamic Cone Penetrometer (DCP) tests are carried out by driving a rod into the ground with a falling weight hammer and measuring the blows for successive 100mm increments of penetration.

The DCP comprises a Cone of 20 mm diameter with 30 degree taper attached to steel rods of smaller section.

The cone end is driven with a 9 kg hammer falling 510 mm (AS. 1289 Test 6.3.2). The test was developed initially for pavement subgrade investigations, and empirical correlations of the test results with California Bearing Ratio have been published by various Road Authorities. The Company has developed their own correlations with Standard Penetration tests and Density Index tests in sands.

LOGS

The borehole or test pit logs presented herein are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on the frequency of sampling and the method of drilling or excavation. Ideally, continuous undisturbed sampling or core drilling will enable the most reliable assessment but is not always practicable or possible to justify on economic grounds. In any case, the boreholes or test pits represent only a very small sample of the total subsurface conditions.

The attached explanatory notes define the terms and symbols used in preparation of the logs.

Interpretation of the information shown on the logs, and its application to design and construction, should therefore take into account the spacing of boreholes or test pits, the method of drilling or excavation, the frequency of sampling and testing and the possibility of other than "straight line" variations between the boreholes or test pits. Subsurface conditions between boreholes or test pits may vary significantly from conditions encountered at the borehole or test pit locations.

GROUNDWATER

Where groundwater levels are measured in boreholes, there are several potential problems.

- Although groundwater may be present in lower permeability soils, it may enter the hole slowly or perhaps not at all during the time the hole is open.
- A localized perched water table may lead to an erroneous indication of the true water table.
- Water table levels will vary from time to time with seasons or recent weather changes and may not be the same at the time of construction.
- The use of water or mud as a drilling fluid will mask any groundwater inflow. Water has to be bailed out of the bore and mud must be washed out of the hole or "reverted" if water observations are to be made.

More reliable measurements can be made by use of standpipes which are read after stabilizing at periods ranging from several days to perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be advisable in low permeability soils or where there may be interference from perched water tables or surface water.

FILL

The presence of fill materials can often be determined only by the inclusion of foreign objects (eg. bricks, steel, etc.) or by distinctly unusual colour, texture or fabric. Identification of the extent of fill materials will also depend on investigation methods and frequency. Where natural soils similar to those at the site are used for fill, it may be difficult with limited testing and sampling to reliably determine the extent of the fill.

The presence of fill materials is usually regarded with caution as the possible variation in density, strength and material type is much greater than with natural soil deposits. Consequently, there is an increased risk of adverse engineering characteristics or behaviour. If the volume and quality of fill is important to a project, then frequent test pit excavations are preferable to boreholes.

LABORATORY TESTING

Laboratory testing is normally carried out in accordance with Australian Standard 1289 "Methods of Testing Soil for Engineering Purposes". Details of the test procedure used are given on the individual report forms and the attached explanatory notes summarize important aspects of the Laboratory Test Procedures adopted.

ENGINEERING REPORTS

Engineering reports are prepared by qualified personnel and are based on the information obtained and on current engineering standards of interpretation and analysis. The information provided in Soil Surveys Engineering reports is opinion and interpretation and not factual. The client/contractor increases their risk by not retaining the person who authored the geotechnical report, to carry out site inspection and review (overseeing role) during construction, to confirm opinion and interpretation expressed in the report is accurate. Where the report has been prepared for a specific design proposal the information and interpretation may not be relevant if the design proposal is changed. If this happens, the Company will be pleased to review the report and the sufficiency of the investigation work.

Every care is taken with the report as it relates to interpretation of subsurface conditions, discussion of geotechnical aspects and recommendations or suggestions for design and construction. Since the test sites in any exploration represent a very small proportion of the total site and since the exploration only identifies actual ground conditions at the test sites, even under the best circumstances actual conditions may vary from those inferred to exist. No responsibility is taken for:-

- Unexpected variations in ground and/or groundwater conditions.
- Changes in policy or interpretation of policy by statutory authorities.
- The actions of other persons.
- Any work where the company is not given the opportunity to supervise the construction using the Companies designs/recommendations.

If differences occur, the Company will be pleased to assist with investigation or advice to resolve any problems occurring.

SITE ANOMALIES

In the event that conditions encountered on site during construction appear to vary from those expected from the information contained in the report, the Company requests that it immediately be notified. Most problems are more readily resolved when conditions are exposed than at some later stage, well after the event.

Extreme events including but not limited to the results of climate change, eg. flood levels above previously identified levels, beach scour or erosion beyond normal expectations (as identified by local authorities) extreme rainfall events, war, espionage, sabotage may result in different conditions between time of investigation and time of construction.

REPRODUCTION OF INFORMATION FOR CONTRACTUAL PURPOSES

Attention is drawn to the document "Guidelines for the Provision of Geotechnical Information in Construction Contracts (1987)", published by the Institution of Engineers, Australia. Where information obtained from this investigation is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances, where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a specially edited document. The Company would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

REVIEW OF DESIGN

Where major civil or structural developments are proposed or where only a limited investigation has been completed or where the geotechnical conditions/constraints are quite complex, it is prudent to have a joint design review which involves a senior geotechnical engineer. We would be happy to assist in this regard as an extension of our investigation commission. Construction drawings should be reviewed by Soil Surveys Engineering, with sufficient time to allow changes if required, prior to inspections.

Otherwise Soil Surveys Engineering reserves the right to refuse to carry out inspections.

SITE INSPECTION

The Company will always be pleased to provide engineering inspection services for geotechnical aspects of work to which this report is related.

- i) Site visits during construction to confirm reported ground conditions
- ii) Site visits to assist the contractor or other site personnel in identifying various soil/rock types such as appropriate footing or pier founding depths, the stability of a filled or excavated slope; or
- iii) Full-time engineering presence on site.

In the vast majority of cases it is advantageous to the principal for the geotechnical engineer who wrote the investigation report to be involved in the construction stage of the project.

The geotechnical engineer cannot take responsibility for variations in encountered conditions, where he is not given the opportunity to review plans for the proposed development with sufficient time to allow review and make changes to the proposed development if required, and where he is not given the opportunity to inspect the site and oversee construction methods with regard to site conditions with sufficient time to observe all relevant site conditions and operations.

RESPONSIBLE USE OF GEOTECHNICAL INFORMATION

Recommendations in our report are for design purposes only and provided on the basis that inspections are carried out to allow finalisation of opinions and recommendations contained in our report.

The geotechnical investigation consisting of field and laboratory testing has been carried out to indicate typical conditions by indicating conditions and parameters at the specific locations of boreholes/test pits. Subsurface conditions are indicated at these locations only and the inference of conditions between or away from these locations (interpolation and extrapolation) involves a certain degree of risk. Persons inferring such conditions or carrying out such inferences should do so with a degree of caution and

conservatism which is commensurate with the consequences of the risk of error.

Estimates of volumes based on our findings require interpolation and extrapolation between test locations and as such may be significantly different from actual volumes.

APPENDIX B

BOREHOLE RECORD SHEET



Easting: 503740 Northing: 6959618 RL: 5.5 m
 Logger: DA Operator: DA Machine: Scout 2

Drilling Method				Depth	Graphic	Description	Samples and Remarks
TC	WB	RR	NM/LC				
				0.20		FILL Sandy GRAVEL (GP) Medium dense, fine to medium size, grey and yellow brown, fine to coarse grained sand, dry.	ASS
				0.60		FILL Clayey Gravelly SAND (SC) Loose, fine to coarse grained, dark grey and brown, fine to medium size gravel, high plasticity fines, dry.	ASS
				0.80		FILL Clayey Gravelly SAND (SC) Very loose, fine to coarse grained, dark grey, fine size gravel, high plasticity fines, wet.	ASS
				1.00		NATURAL Clayey SAND (SC) Very loose, fine to medium grained, grey brown, high plasticity fines, wet.	ASS
				1.60		CLAY (CH) Very stiff, high plasticity, red brown and grey mottled, moist.	ASS
				2.00			ASS
				2.80			ASS
				3.00		Sandy CLAY (CH) Very stiff to hard, high plasticity, grey and red brown mottled, fine grained sand, moist.	ASS
				3.40		CLAY (CH) Very stiff, high plasticity, grey red and yellow brown mottled, moist.	ASS
				4.00			ASS
				4.20			ASS
				4.50		CLAY (CH) Very stiff, high plasticity, grey, trace of fine grained sand, moist.	ASS
				4.80		CLAY (CH) Very stiff, high plasticity, yellow brown mottled, trace of fine grained sand, moist.	ASS
				5.00		Gravelly Sandy CLAY (CH) Hard, high plasticity, grey mottled, fine to coarse grained sand, fine size gravel, moist.	ASS
				5.30			ASS
				5.60		TUFF (DW) Very weak, light grey and light yellow brown.	ASS
				5.80			ASS
				6.00		TUFF (DW) Weak, light yellow brown.	ASS
				6.00		BOREHOLE BH 1A TERMINATED AT 6.00 m	
				7.00			
				8.00			
				9.00			
				10.00			

Comments:

1) Groundwater noted at 0.6m.

Water First Noted Water Steady Level

Weathering Grades
 RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh
Rock Strength
 VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples
 U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: JD
 Date: 4/02/2016

SOIL_SURVEYS_00_LIBRARY_2012-05.GLB Log SOIL_SURVEY AUGER LOG 110-12516 GINT BH1A-4A.GPJ - <<DrawingFile>> 05/02/2016 16:54 8.30.004 Developed by Dargel



Soil Surveys Engineering Pty. Limited

Specialist in Applied Geotechnics

Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au
 Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

BOREHOLE RECORD SHEET

Location Number: BH 2A

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 24/07/2010

Page: 1 OF 1

Easting: 503748 Northing: 6959568 RL: 5.0 m
 Logger: DA Operator: DA Machine: Scout 2

Drilling Method				Depth	Graphic	Description	Samples and Remarks
TC	WB	RR	NM/LC				
				0.25		FILL Sandy GRAVEL (GP) Medium dense, fine to medium size, yellow brown, fine to coarse grained sand, dry.	ASS
				0.50		NATURAL Clayey SAND (SC) Loose, fine to medium grained, dark grey and brown, high plasticity fines, moist.	ASS
				0.90		Clayey SAND (SC) Very loose, fine to coarse grained, brown, high plasticity fines, moist.	ASS
				1.10		Clayey SAND (SC) Very loose, fine to coarse grained, brown, high plasticity fines, wet.	ASS
				1.60		Gravelly Sandy CLAY (CH) Very stiff, high plasticity, grey and red brown, fine to coarse grained sand, fine to medium size gravel, moist.	ASS
				2.00		Sandy CLAY (CH) Very stiff, high plasticity, grey and red brown, fine to medium grained sand, moist.	ASS
				2.20		Sandy CLAY (CH) Very stiff, high plasticity, grey and red brown, with fine grained sand, moist.	ASS
				3.00			ASS
				3.70			ASS
				4.00		Gravelly Sandy CLAY (CH) Hard, high plasticity, grey red and yellow brown, fine to coarse grained sand, fine to medium size gravel, moist.	ASS
				4.50		TUFF (DW) Weak, yellow brown, dry.	ASS
				4.50		BOREHOLE BH 2A TERMINATED AT 4.50 m	ASS
				5.00			
				6.00			
				7.00			
				8.00			
				9.00			
				10.00			

Comments:
 1) Groundwater noted at 0.9m.

Water First Noted Water Steady Level

Weathering Grades
 RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh
Rock Strength
 VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples
 U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: JD
 Date: 4/02/2016

SOIL_SURVEYS_00_LIBRARY_2012-05.GLB Log_SOIL_SURVEY_AUGER_LOG_110-12516_GINT_BH1A-4A.GPJ <<DrawingFile>> 05/02/2016 16:54 8.30.004 Developed by Dargel



Easting: 503797 Northing: 6959609 RL: 5.0 m
 Logger: DA Operator: DA Machine: Scout 2

Drilling Method				Depth	Graphic	Description	Samples and Remarks
TC	WB	RR	NM/LC				
				0.90	[Cross-hatch]	Bitumen	ASS
				1.20	[Diagonal lines]	FILL Gravelly Clayey SAND (SC) Loose, fine to coarse grained, dark grey and brown, high plasticity fines, fine size gravel, dry.	ASS
				1.60	[Diagonal lines]	FILL Clayey SAND (SC) Loose, fine to coarse grained, dark grey, high plasticity fines, with charcoal, dry.	ASS
				2.10	[Vertical lines]	FILL Gravelly Sandy CLAY (CH) Stiff, high plasticity, yellow red brown and dark grey, fine to coarse grained sand, fine to medium size gravel, moist.	ASS
				2.60	[Vertical lines]	NATURAL Sandy CLAY (CH) Stiff, high plasticity, grey brown, fine to medium grained sand, moist.	ASS
				3.20	[Diagonal lines]	Gravelly Clayey SAND (SC) Loose, fine to coarse grained, orange and yellow brown, high plasticity fines, some fine size gravel.	ASS
				3.80	[Diagonal lines]	Clayey SAND (SC) Loose, fine to medium grained, grey and light yellow brown mottled, high plasticity fines, wet.	ASS
				4.70	[Vertical lines]	Sandy CLAY (CH) Hard, high plasticity, yellow brown and light grey, fine to medium grained sand, moist.	ASS
				5.20	[Vertical lines]	Clayey SAND (SC) Medium dense, fine to coarse grained, yellow brown and light grey, high plasticity fines, moist.	ASS
				6.00	[Cross-hatch]	Sandy CLAY (CH) Hard, high plasticity, yellow brown and light grey, fine to medium grained sand, moist.	ASS
				6.00	[Cross-hatch]	TUFF (DW) Weak, yellow brown and light grey.	ASS
BOREHOLE BH 3A TERMINATED AT 6.00 m							

Comments:
 1) Groundwater noted at 2.3m.
 2) Groundwater level noted at 4.3m.
 3) Groundwater monitoring well installed to 6.0m.

Water First Noted Water Steady Level

Weathering Grades RS - Residual Soil XW - Extremely weathered DW - Distinctly weathered SW - Slightly weathered FR - Fresh Rock Strength VW - Very weak W - Weak MS - Medium strong S - Strong VS - Very strong ES - Extremely strong	Samples U50 SPT Disturbed Sample Bulk Sample	Approved: JD Date: 4/02/2016
---	---	---------------------------------

SOIL_SURVEYS_00_LIBRARY_2012-05.GLB Log_SOIL_SURVEY_AUGER_LOG_110-12516 GINT BH1A-4A.GPJ <<DrawingFile>> 05/02/2016 16:54 8.30.004 Developed by Dargel



Easting: 503807 Northing: 6959567 RL: 4.0 m
 Logger: DA Operator: DA Machine: Scout 2

Drilling Method				Depth	Graphic	Description	Samples and Remarks
TC	WB	RR	NM/LC				
				0.25		Bitumen	ASS
				0.40		FILL Sandy GRAVEL (GP) Medium dense, fine to medium size, yellow brown, fine to coarse grained sand, dry.	ASS
				0.60		FILL Gravelly Clayey SAND (SC) Very loose, fine to coarse grained, dark grey, high plasticity fines, fine size gravel, moist.	ASS
				1.0		FILL Gravelly Sandy CLAY (CH) Stiff, high plasticity, grey brown, fine to coarse grained sand, fine size gravel, moist.	ASS
				1.20		FILL Gravelly Clayey SAND (SC) Loose, fine to coarse grained, brown, high plasticity fines, fine size gravel, moist.	ASS
				1.50		NATURAL Gravelly Sandy CLAY (CH) Stiff, high plasticity, yellow red brown, fine to coarse grained sand, fine size gravel, moist.	ASS
				2.0		Gravelly Clayey SAND (SC) Loose, fine to coarse grained, red yellow brown and grey mottled, high plasticity fines, some fine size gravel.	ASS
				2.00		Gravelly Clayey SAND (SC) Medium dense, fine to coarse grained, red yellow brown and grey mottled, high plasticity fines, some fine size gravel.	ASS
				2.60		TUFF (DW) Weak, yellow brown and light grey.	ASS
				3.0			ASS
				3.00		BOREHOLE BH 4A TERMINATED AT 3.00 m	SPT 30/120mm N=R
				4.0			
				5.0			
				6.0			
				7.0			
				8.0			
				9.0			
				10.0			

Comments:
 1) Groundwater not observed.

Weathering Grades
 RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh
Rock Strength
 VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples
 U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: JD
 Date: 4/02/2016

Water First Noted Water Steady Level



Soil Surveys Engineering Pty. Limited

Specialist in Applied Geotechnics

Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au
 Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

SOIL SURVEYS

BOREHOLE RECORD SHEET

Location Number: BH 05

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 14/01/2016

Page: 1 OF 1

Easting: 503824 Northing: 6959588 RL: 5.0 m
 Logger: RH Operator: RH Machine: EVH1750

Drilling Method					Depth	Graphic	Description	DCP Test (blows/100mm)					Samples and Remarks		
TC	WB	RR	NM/LC	Casing				0	6	12	18	24		30	
					0.10	X X X X	BITUMEN								
					0.20		FILL Gravelly CLAY (CH) Stiff, high plasticity, dark grey, fine to medium sized gravel, moist,								
					0.50										
					0.60	X X X X	NATURAL Silty CLAY (CH) Stiff, high plasticity, dark brown, trace of fine sized gravel, moist.								
					1.0	X X X X									
					1.10	X X X X	Silty CLAY (CH) Stiff, high plasticity, dark brown mottled orange-brown, trace of fine to medium sized gravel, moist.								
					1.20	X X X X	TUFF (DW) Very weak, light brown, moist.								
							TUFF (DW) Weak, light brown, moist.								
							BOREHOLE BH 05 TERMINATED AT 1.20 m								
					2.0										
					3.0										
					4.0										
					5.0										
					6.0										
					7.0										
					8.0										
					9.0										
					10.0										

Comments:
 1. Groundwater not encountered.
 2. DCP refusal at 0.62m.
 3. TC bit refusal at 1.20m.

Weathering Grades
 RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh
Rock Strength
 VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples
 U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: JD
 Date: 4/02/2016

SOIL SURVEYS 00: LIBRARY 2012:05:G.LB Log SOIL SURVEY AUGER LOG 110-12516 GINT 2015 BH05-10.GPJ <-DrawingFile-> 05/02/2016 16:49 8.30.004 Developed by Datrol

Water First Noted Water Steady Level



Easting: 503754 Northing: 6959591 RL: 5.0 m
 Logger: RH Operator: RH Machine: EVH1750

Drilling Method				Depth	Graphic	Description	DCP Test (blows/100mm)	Samples and Remarks
TC	WB	RR	NM/LC Casing					
				0.02	X	BITUMEN		
				0.14		FILL Sandy GRAVEL (GP) Dense, fine to medium sized, light brown, fine to coarse grained sand, trace of low plasticity fines, moist.		
				0.60		NATURAL Silty CLAY (CH) Firm, high plasticity, dark grey, with fine to coarse grained sand, trace of fine sized gravel, moist.		U50 PP = 140
				1.0		Silty CLAY (CH) Stiff, high plasticity, dark grey mottled red-brown, trace of fine sized gravel, moist.		U50 PP = 100
				2.0				
				2.30		Silty CLAY (CH) Very stiff, high plasticity, dark grey mottled red-brown, trace of fine sized gravel, moist.		
				3.0				
				3.40		Silty CLAY (CH) Very stiff, high plasticity, light grey mottled red-brown, trace of fine sized gravel, moist.		U50 PP = 230
				4.0				
				4.20		Silty CLAY (CH) Very stiff, high plasticity, dark grey mottled light brown, trace of fine sized gravel, moist.		
				5.0				
				6.0				
				6.20		Silty CLAY (CH) Very stiff, high plasticity, dark grey mottled light brown, trace of fine sized gravel, with some GRAVEL bands, moist.		U50 PP = 230
				6.80				
				7.0	X X X	TUFF (DW) Weak, light brown, moist.		
				7.00	X X X	BOREHOLE BH 07 TERMINATED AT 7.00 m		
				8.0				
				9.0				
				10.0				

SOIL SURVEYS 00:LIBRARY 2012:05:G.LB Log SOIL SURVEY AUGER LOG 110-12516 GINT 2015 BH05-10.GPJ <-DrawingFile>> 05/02/2016 16:50 8.30.004 Developed by Datcel

Comments:
 1. Groundwater encountered at 5.50m.
 2. DCP refusal at 4.09m.
 3. TC bit refusal at 7.00m.

Water First Noted Water Steady Level

Weathering Grades
 RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh
Rock Strength
 VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples
 U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: JD
 Date: 4/02/2016



Easting: 503817 Northing: 6959609 RL: 5.0 m
 Logger: DA/CB Operator: DA Machine: Scout

Drilling Method	Depth	Graphic	Description	Weathering	Strength Estimated RS WW MS S VS	Defect Spacing 20 60 200 600	Rec (%)	RQD	Samples and Remarks
	0.02		BITUMEN						
	0.60		FILL Sandy GRAVEL (GP) Medium dense, fine to medium sized, grey, fine to coarse grained sand, dry.						
	0.80		FILL ASH Very loose, dark grey/black.						
	1.10		FILL Gravelly Clayey SAND (SC) Loose, fine to coarse grained, brown mottled, high plasticity fines, fine sized gravel, moist.						SPT 2, 2, 4 N=6
	1.70		FILL Gravelly Sandy CLAY (CH) Stiff, high plasticity, brown, fine to coarse grained sand, fine sized gravel, moist.						U50
	2.0		FILL Gravelly Clayey SAND (SC) Loose, fine to coarse grained, yellow-brown, high plasticity fines, fine sized gravel, moist.						
	2.60		NATURAL Clayey SAND (SC) Very loose, fine to coarse grained, grey and brown, high plasticity fines, wet.						
	3.25		Sandy CLAY (CH) Firm, high plasticity, dark grey, fine to medium grained sand, moist.						SPT 1, 2, 2 N=4
	3.90		Clayey SAND (SC) Loose, fine to medium grained, brown, high plasticity fines, wet.						
	4.30		Sandy CLAY (CH) Very stiff, high plasticity, light grey and yellow brown, fine to medium grained sand, moist.						
	4.80		TUFF (DW) Weak, yellow brown and light grey.						U50 PP > 600
	5.60		TUFF (DW) Weak, orange/yellow-brown.						
	6.05		TUFF (DW) Weak, yellow-brown.						SPT
	6.10		TUFF fine to medium grained, light grey/light red, mottled orange, massive, with very closely spaced fractures, with some limonite staining and veins.	DW					6.14 m; J, 15°, P, R, O, L 6.26 m; J, 20°, S, R, O, W 6.32 m; J, 15°, P, R, O, L 6.45 m; J, 10°, S, R, O, W 6.52 m; J, 15°, S, R, O, L 6.76 m; J, 20°, S, R, O, W 7.16 m; Is50 = 0.16 MPa 7.08 m; J, 10°, S, R, O, L 7.10 m; J, 5°, P, R, O, L 7.25 m; J, 10°, P, R, O, L 7.34 m; J, 10°, P, R, O, L 7.41 m; J, 15°, P, R, O, L 7.84 m; J, 10°, P, R, O, L 8.20 m; J, 10°, S, V, O, L 8.33 m; J, 10°, S, R, O, L 8.40 m; J, 10°, S, R, O, L 8.70 m; J, 20°, P, R, O, L 8.9m, Is50 = 0.68 MPa 8.83 m; J, 15°, P, R, O, L 9.04 m; J, 10°, S, R, O, W 9.19 m; J, 10°, P, R, O, Z 9.24 m; J, 20°, P, R, O, L 9.35 m; V, 80°, R, C, L
	9.67		TUFF fine to coarse grained, light grey/light brown with closely spaced fractures.	DW					100 18 100 76
	10.00								

SOIL SURVEYS 00:LIBRARY 2012:05:GLB Log SOIL SURVEY BOREHOLE LOG 110-12516:GINT 2015:BH08:10.GPJ <-DrawingFile>> 05/02/2016 16:51 8.30.004 Developed by Dalgel

Comments:
 1. Groundwater encountered at 2.60m.
 2. Borehole bailed on completion of drilling.
 3. Steady water level measured post bailing at 4.75m on 15/1/16.
 Chainage : m Offset : m
 Water First Noted Water Steady Level

Defects - 1.54m : F,60° P,R,O,C

Depth (m)	Type	Dip (Deg)	Planarity	Roughness	Aperture	Infill
	B - Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay
	C - Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide
	F - Foliation		P - Planar	R - Rough	N - Clean	K - Calcite
	H - Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite
	J - Joint		T - Stepped	V - Very rough	S - Stain	Q - Quartz
	L - Cleavage		R - Fracture			S - Secondary mineral
	R - Fracture		S - Shear zone			U - Undifferentiated mineral
	T - Contact		T - Contact			W - Weathered rock
	V - Vein		Z - Decomposed Zone			X - Carbonaceous
	Z - Decomposed Zone		DI - Drilling induced break			Z - Clean

Weathering Grades

RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples

U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: JD
 Date: 4/02/2016



Soil Surveys Engineering Pty. Limited
 Specialist in Applied Geotechnics
 Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au
 Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

BOREHOLE RECORD SHEET

Location Number: BH 08

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 15/01/2016

Page: 2 OF 3

Easting: 503817 Northing: 6959609 RL: 5.0 m
 Logger: DA/CB Operator: DA Machine: Scout

Drilling Method				Depth	Graphic	Description	Weathering	Strength Estimated RSWVW MS S VS	Defect Spacing 20 60 200 600	Rec (%)	ROD	Samples and Remarks
TC	WB	RR	NMLC									
				11.0	XXXXXX	TUFF, fine to coarse grained, light grey/light green, mottled orange, massive with moderately widely spaced fractures and trace limonite staining.	DW - SW					10.07 m; J, 15°, P, R, O, L
				11.0	XXXXXX		SW			100	76	10.48 m; J, 10°, S, R, O, L 10.92m, Is50 = 0.22 MPa 10.88 m; J, 10°, P, V, O, L
				12.0	XXXXXX	TUFF, fine to coarse grained, speckled light grey, massive with widely spaced fractures with a limonite stained clay infilled joint at 12.65m, near vertical joint between 14.9m and 15.5m.	FR					11.54m, Is50 = 1.43 MPa 11.47 m; J, 12°, P, V, O, Z
				13.0	XXXXXX		SW - FR			100	84	12.65 m; J, 60°, P, R, O, L/C 13.20 m; J, 30°, P, R, O, Z 13.45 m; J, 20°, U, R, O, W
				14.0	XXXXXX							14.08 m; J, 50°, P, R, O, Z 14.18 m; J, 15°, S, V, O, Z
				15.0	XXXXXX							14.64 m; J, 10°, S, R, O, W 14.88m, Is50 = 0.75 MPa 15.05 m; J, 70°, U, R, O, W 15.20 m; J, 20°, S, R, O, Z
				16.0	XXXXXX	TUFF, fine to coarse grained, speckled grey to dark grey, massive, with widely to very widely spaced fractures, with some calcite lenses.	FR			100	79	15.9m, Is50 = 1.45 MPa 16.64 m; J, 10°, P, R, O, Z 17.28 m; J, 10°, S, V, O, Z 17.38 m; J, 10°, S, V, O, Z
				17.0	XXXXXX							17.89m, Is50 = 1.15 MPa
				18.0	XXXXXX							
				19.0	XXXXXX							
				20.0	XXXXXX							19.46 m; J, 40°, P, R, O, Z

SOIL SURVEYS 00: LIBRARY 2012:05:G.L.B. Log, SOIL SURVEY BOREHOLE LOG 110-12516.GINT 2015:B.H.6:10.GPJ <-DrawingFile>> 05/02/2016 16:51 8.30.004 Developed by Dalgel

Comments:
 1. Groundwater encountered at 2.60m.
 2. Borehole bailed on completion of drilling.
 3. Steady water level measured post bailing at 4.75m on 15/1/16.
 Chainage :m Offset : m
 Water First Noted Water Steady Level

Defects - 1.54m : F,60°,P,R,O,C

Depth (m)	Type	Dip (deg)	Planarity	Roughness	Aperture	Infill
	B - Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay
	C - Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide
	F - Foliation		P - Planar	R - Rough	N - Clean	K - Calcite
	H - Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite
	J - Joint		T - Stepped	V - Very rough	S - Stain	Q - Quartz
	L - Cleavage		R - Fracture			S - Secondary mineral
	R - Fracture		S - Shear zone			U - Undifferentiated mineral
	T - Contact		Z - Decomposed Zone			W - Weathered rock
	V - Vein		DI - Drilling induced break			X - Carbonaceous
	Z - Decomposed Zone					Z - Clean

Weathering Grades

RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh

Rock Strength

VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples

U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: JD
 Date: 4/02/2016



Soil Surveys Engineering Pty. Limited

Specialist in Applied Geotechnics

Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au
Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

BOREHOLE RECORD SHEET

Location Number: BH 08

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 15/01/2016

Page: 3 OF 3


Easting: 503817 Northing: 6959609 RL: 5.0 m
Logger: DA/CB Operator: DA Machine: Scout

Drilling Method					Depth	Graphic	Description	Weathering	Strength Estimated RSWVW MS S VS	Defect Spacing 20 60 200 600	Rec (%)	ROD	Samples and Remarks																																								
TC	WB	RR	NM/LC	Casing																																																	
					21.0		TUFF, fine to coarse grained, speckled grey to dark grey, massive, with widely to very widely spaced fractures, with some calcite lenses. (continued)	FR			100	100	20.85m, Is50 = 1.36 MPa 21.12m, Is50 = 1.28 MPa 21.19 m; J, 10°, S, R, O, Z																																								
					22.0											100	100	24.20 m; J, 15°, P, R, O, Z																																			
					23.0																100	100	24.9m, Is50 = 1.06 MPa 24.80 m; J, 10°, S, R, O, Z																														
					24.0																					100	100	26.55m, Is50 = 0.99 MPa																									
					25.0																										100	100	BOREHOLE BH 08 TERMINATED AT 26.77 m																				
					26.0																															100	100	BOREHOLE BH 08 TERMINATED AT 26.77 m															
					26.77																																				100	100	BOREHOLE BH 08 TERMINATED AT 26.77 m										
					27.0																																									100	100	BOREHOLE BH 08 TERMINATED AT 26.77 m					
					28.0																																														100	100	BOREHOLE BH 08 TERMINATED AT 26.77 m
					29.0																																																
					30.0			100	100	BOREHOLE BH 08 TERMINATED AT 26.77 m																																											

SOIL SURVEYS 00:LIBRARY 2012:05:G.LB Log SOIL SURVEY BOREHOLE LOG 110-12516 GINT 2015 BH08-10.GPJ <-DrawingFile>> 05/02/2016 16:51 8.30.004 Developed by Dalgel

<p>Comments:</p> <ol style="list-style-type: none"> Groundwater encountered at 2.60m Borehole bailed on completion of drilling. Steady water level measured post bailing at 4.75m on 15/1/16. <p>Chainage :m Offset : m</p> <p> Water First Noted Water Steady Level </p>	<p>Defects - 1.54m : F,60°,P,R,O,C</p> <table border="0"> <tr> <td>Depth (m)</td> <td>Type</td> <td>Dip (Deg)</td> <td>Planarity</td> <td>Roughness</td> <td>Aperture</td> <td>Infill</td> </tr> <tr> <td>B</td> <td>Bedding</td> <td></td> <td>C - Curvilinear</td> <td>L - Slickensides</td> <td>C - Closed</td> <td>C - Clay</td> </tr> <tr> <td>C</td> <td>Clay seam</td> <td></td> <td>D - Discontinuous</td> <td>P - Polished</td> <td>F - Filled</td> <td>F - Iron Oxide</td> </tr> <tr> <td>F</td> <td>Foliation</td> <td></td> <td>P - Planar</td> <td>R - Rough</td> <td>N - Clean</td> <td>K - Calcite</td> </tr> <tr> <td>H</td> <td>Schistosity</td> <td></td> <td>S - Subplanar</td> <td>S - Smooth</td> <td>O - Open</td> <td>L - Limonite</td> </tr> <tr> <td>J</td> <td>Joint</td> <td></td> <td>T - Stepped</td> <td>V - Very rough</td> <td>S - Stain</td> <td>Q - Quartz</td> </tr> <tr> <td>L</td> <td>Cleavage</td> <td></td> <td>U - Undulating</td> <td></td> <td></td> <td>S - Secondary mineral</td> </tr> <tr> <td>R</td> <td>Fracture</td> <td></td> <td></td> <td></td> <td></td> <td>U - Unidentified mineral</td> </tr> <tr> <td>S</td> <td>Shear zone</td> <td></td> <td></td> <td></td> <td></td> <td>W - Weathered rock</td> </tr> <tr> <td>T</td> <td>Contact</td> <td></td> <td></td> <td></td> <td></td> <td>X - Carbonaceous</td> </tr> <tr> <td>V</td> <td>Vein</td> <td></td> <td></td> <td></td> <td></td> <td>Z - Clean</td> </tr> <tr> <td>Z</td> <td>Decomposed Zone</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DI</td> <td>Drilling induced break</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>	Depth (m)	Type	Dip (Deg)	Planarity	Roughness	Aperture	Infill	B	Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay	C	Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide	F	Foliation		P - Planar	R - Rough	N - Clean	K - Calcite	H	Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite	J	Joint		T - Stepped	V - Very rough	S - Stain	Q - Quartz	L	Cleavage		U - Undulating			S - Secondary mineral	R	Fracture					U - Unidentified mineral	S	Shear zone					W - Weathered rock	T	Contact					X - Carbonaceous	V	Vein					Z - Clean	Z	Decomposed Zone						DI	Drilling induced break						<p>Weathering Grades</p> <p>RS - Residual Soil XW - Extremely weathered DW - Distinctly weathered SW - Slightly weathered FR - Fresh</p> <p>Rock Strength</p> <p>VW - Very weak W - Weak MS - Medium strong S - Strong VS - Very strong ES - Extremely strong</p>	<p>Samples</p> <p>U50 SPT Disturbed Sample Bulk Sample</p>
Depth (m)	Type	Dip (Deg)	Planarity	Roughness	Aperture	Infill																																																																																								
B	Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay																																																																																								
C	Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide																																																																																								
F	Foliation		P - Planar	R - Rough	N - Clean	K - Calcite																																																																																								
H	Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite																																																																																								
J	Joint		T - Stepped	V - Very rough	S - Stain	Q - Quartz																																																																																								
L	Cleavage		U - Undulating			S - Secondary mineral																																																																																								
R	Fracture					U - Unidentified mineral																																																																																								
S	Shear zone					W - Weathered rock																																																																																								
T	Contact					X - Carbonaceous																																																																																								
V	Vein					Z - Clean																																																																																								
Z	Decomposed Zone																																																																																													
DI	Drilling induced break																																																																																													

Approved: JD
Date: 4/02/2016



Client: 825 Stanley Street Pty Ltd
Project: Apartment Buildings
Location: 825 Stanley Street, Woolloongabba

SSE Borehole: 8
Depth: 6.10m - 12.00m
Box: 1 of 4

Project no: 110-12516



Client: 825 Stanley Street Pty Ltd
Project: Apartment Buildings
Location: 825 Stanley Street, Woolloongabba

SSE Borehole: 8
Depth: 12.00m - 18.00m
Box: 2 of 4


Project no: 110-12516

PointID : BH 08 Depth Range: 12.00 - 18.00 m



TITLE
 825 Stanley Pty Ltd
 825 Stanley Street, Woolloongabba
 Apartment Buildings
 Core Photo - BH 08

DRAWN	CB	DATE	18/01/2016
CHECKED	GB	DATE	18/01/2016
SCALE	Not To Scale		A4
PROJECT No	110-12516	FIGURE No	1/2



PointID : BH 08 Depth Range: 24.00 - 26.77 m

	TITLE 825 Stanley Pty Ltd 825 Stanley Street, Woolloongabba Apartment Buildings Core Photo - BH 08	DRAWN CB	DATE 18/01/2016	
		CHECKED GB	DATE 18/01/2016	
		SCALE Not To Scale		A4
		PROJECT No 110-12516	FIGURE No 2/2	



Soil Surveys Engineering Pty. Limited
 Specialist in Applied Geotechnics
 Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au
 Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

BOREHOLE RECORD SHEET

Location Number: BH 09

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 13/01/2016

Page: 1 OF 3

Easting: 503780 Northing: 6959568 RL: 4.2 m
 Logger: DA/CB Operator: DA Machine: Scout

Drilling Method		Depth	Graphic	Description	Weathering	Strength Estimated RSWVW MS S VS	Defect Spacing 20 60 200 600	Rec (%)	RQD	Samples and Remarks
TC	WB									
		0.20		BITUMEN						
		0.70		FILL Clayey SAND (SC) Loose, fine to coarse grained, dark grey, high plasticity fines, dry.						
		0.90		FILL Clayey SAND (SC) Loose, fine to coarse grained, dark grey, high plasticity fines, with ASH, dry.						SPT 3, 3, 1 N=4
		1.60		FILL CLAY (CH) Stiff, high plasticity, brown mottled, moist.						
		2.00		NATURAL Silty Clayey SAND (SC) Very loose, fine to medium grained, dark brown, high plasticity fines.						U50
		2.60		Clayey SAND (SC) Very loose, fine to coarse grained, grey, high plasticity fines, wet.						SPT 2, 1, 2 N=3
		3.0		Sandy CLAY (CH) Firm to stiff, high plasticity, grey, fine to medium grained sand, moist.						U50 PP = 100
		4.30		Gravelly Clayey SAND (SC) Very loose, fine to coarse grained, dark grey, high plasticity fines, fine sized gravel.						SPT 1, 0, 0 N=0
		5.70		TUFF (DW) Weak, yellow-brown and grey.						
		5.80		TUFF (SW) Medium strong, yellow-brown and grey.	SW					5.82 m; J, 35°, P, V, O, L 5.95m, Is50 = 1.51 MPa
		6.93		TUFF fine to medium grained, light grey mottled light brown, massive, with closely spaced fractures. Some orange stained weathered bands from 6.27m to 6.49m and 6.69m to 6.93m.	DW					6.08 m; J, 10°, P, V, O, W 6.21 m; J, 15°, P, V, O, W 6.27 m; J, 10°, P, R, O, W 6.33 m; J, 10°, S, R, O, W 6.36 m; J, 10°, P, R, O, W 6.41 m; J, 15°, P, R, O, L 6.48 m; J, 10°, P, R, O, L 6.71 m; J, 10°, P, R, O, L 6.79 m; J, 10°, P, R, O, L 6.86 m; J, 10°, S, R, O, L
		9.60		TUFF fine to medium grained, light grey, massive, with widely spaced fractures, possible shear zone at 9.60m.	FR					7.37 m; J, 10°, P, V, O, Z 7.85m, Is50 = 2.71 MPa
		8.94								8.94 m; J, 70°, P, R, O, C 9.05m, Is50 = 2.77 MPa
		9.22								9.22 m; J, 10°, P, V, O, Z
		9.42								9.42 m; J, 15°, P, R, O, Z
		9.61								9.61 m; J, 60°, P, R, O, W

Comments:

- Groundwater encountered at 2.00m
- Borehole bailed on completion of drilling and groundwater monitoring well installed at 9.20m (RL 5.0m)
- Steady water level measured at 3.90m on 15/1/16 and 3.8m 03/02/16

Chainage : m Offset : m

Water First Noted Water Steady Level

Defects - 1.54m : F,60° P,R,O,C

Depth (m)	Type	Dip (deg)	Planarity	Roughness	Aperture	Infill
	B - Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay
	C - Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide
	F - Foliation		P - Planar	R - Rough	N - Clean	K - Kaolinite
	H - Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite
	J - Joint		T - Stepped	V - Very rough	S - Stain	Q - Quartz
	L - Cleavage		U - Undulating			S - Secondary mineral
	R - Fracture					U - Undifferentiated mineral
	S - Shear zone					W - Weathered rock
	T - Contact					X - Carbonaceous
	V - Vein					Z - Clean
	Z - Decomposed Zone					
	DI - Drilling induced break					

Weathering Grades

- RS - Residual Soil
- XW - Extremely weathered
- DW - Distinctly weathered
- SW - Slightly weathered
- FR - Fresh
- W - Weak
- MS - Medium strong
- S - Strong
- VS - Very strong
- ES - Extremely strong

Samples

- U50
- SPT
- Disturbed Sample
- Bulk Sample

Approved: MG
 Date: 4/02/2016

SOIL SURVEYS 00:LIBRARY 2012-05.GLB Log_SOIL SURVEY BOREHOLE LOG 110-12516.GINT 2015 BH6-10.GPJ <-DrawingFiles> 05/02/2016 16:51 8.30.004 Developed by Dalgel



Soil Surveys Engineering Pty. Limited
 Specialist in Applied Geotechnics
 Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au
 Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

BOREHOLE RECORD SHEET

Location Number: BH 09

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 13/01/2016

Page: 2 OF 3

Easting: 503780 Northing: 6959568 RL: 4.2 m
 Logger: DA/CB Operator: DA Machine: Scout

Drilling Method		Depth	Graphic	Description	Weathering	Strength Estimated RSWV W MS S VS	Defect Spacing 20 60 200 600	Rec (%)	ROD	Samples and Remarks
TC	WB									
		11.0	XXXXXX	TUFF fine to medium grained, light grey mottled light red, massive, with widely spaced fractures, with a near vertical joint between 13.70m and 13.95m.	FR			100	100	10.61 m; J, 10°, P, R, O, Z 10.73 m; J, 10°, P, R, O, Z
		12.0	XXXXXX					100	94	11.32 m; J, 15°, S, R, O, Z
		13.0	XXXXXX					100	94	12.75m, Is50 = 2.51 MPa 12.66 m; J, 15°, P, V, O, Z 12.91 m; J, 20°, P, V, O, Z
		14.0	XXXXXX					100	94	13.80 m; J, 70°, U, R, O, U
		14.10	XXXXXX	TUFF fine to medium grained, light grey mottled light green, massive, with moderately widely spaced fractures.	SW - FR			98	89	14.33 m; J, 10°, P, R, O, Z 14.50 m; J, 10°, P, R, O, Z 14.57 m; J, 15°, P, V, O, Z 14.73 m; J, 10°, T, R, O, Z
		15.0	XXXXXX					98	89	15.86 m; J, 10°, P, V, O, Z 16.15 m; J, 70°, P, R, O, U 16.63 m; J, 70°, T, R, O, U 16.95m, Is50 = 3.38 MPa
		17.0	XXXXXX	TUFF fine to medium grained, light grey mottled light red, massive, with very widely spaced fractures.	FR			100	100	19.8m, Is50 = 5.59 MPa
		18.0	XXXXXX					100	100	
		19.0	XXXXXX					100	100	
		20.0	XXXXXX					100	100	

SOIL SURVEYS 00:LIBRARY 2012:05:G.LB Log SOIL SURVEY BOREHOLE LOG 110-12516 GINT 2015 BH6-10.GPJ <-DrawingFile>> 05/02/2016 16:51 8.30.004 Developed by Dalgel

Comments:
 1. Groundwater encountered at 2.00m
 2. Borehole bailed on completion of drilling and groundwater monitoring well installed to 9.20m (RL 5.0m) 3. Steady water level measured at 3.90m on 15/1/16 and 3.8m 03/02/16
 Chainage : m Offset : m
 Water First Noted Water Steady Level

Defects - 1.54m : F,60°,P,R,O,C

Depth (m)	Type	Dip (Deg)	Planarity	Roughness	Aperture	Int
	B - Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay
	C - Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide
	F - Fallation		P - Planar	R - Rough	N - Clean	K - Calcite
	H - Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite
	J - Joint		T - Stepped	V - Very rough	S - Stain	O - Quartz
	L - Cleavage		U - Undulating			S - Secondary mineral
	R - Fracture					U - Undifferentiated mineral
	S - Shear zone					W - Weathered rock
	T - Contact					X - Carbonaceous
	V - Vein					Z - Clean
	Z - Decomposed Zone					
	DI - Drilling induced break					

Weathering Grades

RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh

Rock Strength

VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples

U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: MG
 Date: 4/02/2016



Soil Surveys Engineering Pty. Limited

Specialist in Applied Geotechnics

Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au

Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

SOIL SURVEYS

BOREHOLE RECORD SHEET

Location Number: BH 09

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 13/01/2016

Page: 3 OF 3

Easting: 503780 Northing: 6959568 RL: 4.2 m
 Logger: DA/CB Operator: DA Machine: Scout

Drilling Method					Depth	Graphic	Description	Weathering	Strength Estimated RS WW MS S VS	Defect Spacing 20 60 200 600	Rec (%)	RQD	Samples and Remarks
TC	WB	RR	NM/LC	Casing									
					20.20	XXXX	BOREHOLE BH 09 TERMINATED AT 20.20 m	FR	XXXX	XXXX	100	100	20.15m, Is50 = 6.77 MPa
					21.0								
					22.0								
					23.0								
					24.0								
					25.0								
					26.0								
					27.0								
					28.0								
					29.0								
					30.0								

SOIL SURVEYS 00: LIBRARY 2012:05:G.L.B. Log SOIL SURVEY BOREHOLE LOG 110-12516.GINT 2015:B.H.6-10.GPJ <-DrawingFile>> 05/02/2016 16:51 8.30.004 Developed by Dalgel

Comments:
 1. Groundwater encountered at 2.00m
 2. Borehole bailed on completion of drilling and groundwater monitoring well installed to 9.20m (RL 5.0m) 3. Steady water level measured at 3.90m on 15/1/16 and 3.8m 03/02/16
 Chainage : m Offset : m
 Water First Noted Water Steady Level

Defects - 1.54m : F,60° P,R,O,C



Depth (m)	Type	Dip (Deg)	Planarity	Roughness	Aperture	Infill
	B - Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay
	F - Fallion		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide
	H - Schistosity		P - Planar	R - Rough	N - Clean	K - Calcite
	J - Joint		S - Subplanar	S - Smooth	O - Open	L - Limonite
	L - Cleavage		T - Stepped	V - Very rough	S - Stain	Q - Quartz
	R - Fracture		U - Undulating			S - Secondary mineral
	S - Shear zone					U - Unidentified mineral
	T - Contact					W - Weathered rock
	V - Vein					X - Carbonaceous
	Z - Decomposed Zone					Z - Clean
	DI - Drilling induced break					

Weathering Grades
 RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh


Rock Strength
 WW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples
 U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: MG
 Date: 4/02/2016



PointID : BH 09 Depth Range: 11.00 - 17.00 m

	TITLE 825 Stanley Pty Ltd 825 Stanley Street, Woolloongabba Apartment Buildings Core Photo - BH 09	DRAWN CB	DATE 18/01/2016	
		CHECKED GB	DATE 18/01/2016	
		SCALE Not To Scale		A4
		PROJECT No 110-12516	FIGURE No 1/2	



Client: 825 Stanley Street Pty Ltd
Project: Apartment Buildings
Location: 825 Stanley Street, Woolloongabba

SSE Borehole: 9
Depth: 17.00m - 20.20m
Box: 3 of 3

Project no: 110-12516



TITLE

825 Stanley Pty Ltd
 825 Stanley Street, Woolloongabba
 Apartment Buildings
 Core Photo - BH 09

DRAWN

CB

DATE

18/01/2016

CHECKED

GB

DATE

18/01/2016

SCALE

Not To Scale

A4

PROJECT No

110-12516

FIGURE No

2/2



Easting: 503768 Northing: 6959624 RL: 5.0 m
 Logger: DA/CB Operator: DA Machine: Scout

Drilling Method	Depth	Graphic	Description	Weathering	Strength Estimated RSW W MS S VS	Defect Spacing 20 60 200 600	Rec (%)	RQD	Samples and Remarks
	0.02		BITUMEN						
	0.08		FILL Gravelly SAND (SP) Medium dense, fine to coarse grained, brown, fine to medium sized gravel, dry.						
	0.70		FILL ASH Loose, fine to coarse grained, black, dry.						SPT 3, 1, 2 N=3
	1.10		FILL Clayey Gravelly SAND and ASH (SC) Very loose, fine to coarse grained, brown and dark grey/black, fine to medium sized gravel, moist.						U50 PP = 200
	1.60		NATURAL Sandy CLAY (CH) Firm, high plasticity, grey brown, fine grained sand, wet.						
	2.0		Sandy CLAY (CH) Stiff to very stiff, high plasticity, red-brown and grey mottled, fine to medium grained sand, moist.						
	2.40		Sandy CLAY (CH) Very stiff, high plasticity, grey and brown mottled, fine grained sand, moist.						
	3.0								U50 PP = 200-450
	3.40		Sandy CLAY (CH) Very stiff, high plasticity, light grey mottled, fine to coarse grained sand.						
	4.30		TUFF(DW) Very weak, light grey.						
	4.50		TUFF (SW) Strong, light yellow-brown and light grey.	DW - SW					SPT 38/66mm N-R
	4.60		TUFF fine to medium grained, light grey mottled orange with some limonite staining, massive, with widely spaced fractures with a dark brown mineral infill in some defects, some evidence of near vertical jointing.	DW - SW					4.92m, Is50 = 4.44 MPa
	5.0			SW			100	83	5.34 m; J, 70°, U, V, O, X
	6.0			DW					6.36 m; J, 15°, S, R, O, W
	6.46			SW					6.46 m; J, 20°, S, V, O, Z
	6.50								6.50 m; J, 15°, P, R, O, W
	6.54								6.54 m; J, 15°, P, R, O, W
	6.58								6.58 m; J, 15°, S, V, O, W
	6.9m								6.9m, Is50 = 3.5 MPa
	7.05m						100	55	7.05m, Is50 = 1.93 MPa
	7.43m			DW - SW					7.43 m; J, 70°, P, R, O, L
	7.70m								7.70 m; J, 80°, U, V, O, X
	8.10m								8.10 m; J, 80°, U, C, X
	8.23m								8.23 m; J, 10°, T, V, O, X
	8.39m								8.39 m; J, 15°, S, R, O, W
	8.51m								8.51 m; J, 10°, S, R, O, W
	8.80m								8.80 m; J, 75°, S, V, O, X
	9.00		TUFF fine to medium grained, light grey, massive with very widely spaced fractures.	FR			100	89	
	9.95m								9.95m, Is50 = MPa

Comments:

- Groundwater not encountered during augering.
- Borehole bailed on completion of drilling and groundwater monitoring well installed to 10.0m (RL-5.0m). Steady water level measured at 5.80m on 15/1/16 and 6.3m 03/02/16.

Water First Noted Water Steady Level

Defects - 1.54m : F,60° P,R,O,C

Depth (m)	Type	Dip (deg)	Planarity	Roughness	Aperture	Infill
	B - Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay
	C - Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide
	F - Faultion		P - Planar	R - Rough	N - Clean	K - Kaolite
	H - Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite
	J - Joint		T - Stepped	V - Very rough	S - Stain	Q - Quartz
	L - Cleavage					S - Secondary mineral
	R - Fracture					U - Undersized mineral
	S - Shear zone					W - Weathered rock
	T - Contact					X - Carbonaceous
	V - Vein					Z - Clean
	Z - Decomposed Zone					
	DI - Drilling induced break					

Weathering Grades

RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh
 Rock Strength
 VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples

U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: MG
 Date: 4/02/2016



Soil Surveys Engineering Pty. Limited
 Specialist in Applied Geotechnics
 Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au
 Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

BOREHOLE RECORD SHEET

Location Number: BH 10

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 14/01/2016

Page: 2 OF 3

Easting: 503768 Northing: 6959624 RL: 5.0 m
 Logger: DA/CB Operator: DA Machine: Scout

Drilling Method					Depth	Graphic	Description	Weathering	Strength Estimated RS WW MS S VS	Defect Spacing 20 60 200 600	Rec (%)	RQD	Samples and Remarks
TC	WB	RR	NM/LC	Casing									
					11.0	XXXX	TUFF fine to medium grained, light grey, massive with very widely spaced fractures. (continued)	FR			100	89	
					11.72	XXXX							11.53m, Is50 = 3.6 MPa
					12.0	XXXX	TUFF fine to medium grained, light grey, massive with moderlatly widely spaced fractures. With several Calcite infilled near vertical, irregular joints.	SW - FR					
					13.0	XXXX					100	83	12.48 m; V, 70°, C, K 12.70 m; J, 80°, P, R, O, K 13.1m, Is50 = 4.07 MPa
					14.0	XXXX							13.70 m; V, 80°, C, K
					15.0	XXXX							14.7m, Is50 = 2.12 MPa
					16.0	XXXX							15.20 m; V, 80°, C, K
					17.0	XXXX							15.80 m; J, 85°, S, R, O, K
					17.68	XXXX							16.51 m; V, 5°, C, K 16.80 m; V, 85°, C, K
					18.0	XXXX	TUFF fine to medium grained, light grey, massive with widely spaced fractures and trace calcite lenses/bands.	FR					17.9m, Is50 = 3.32 MPa
					19.0	XXXX							
					20.0	XXXX							19.11 m; J, 45°, P, R, O, K

SOIL SURVEYS 00: LIBRARY 2012:05:G.LB Log SOIL SURVEY BOREHOLE LOG 110-12516 GINT 2015 BH6-10.GPJ <-DrawingFile>> 05/02/2016 16:51 8.30.004 Developed by Dalgel

Comments:
 1. Groundwater not encountered during augering.
 2. Borehole bailed on completion of drilling and groundwater monitoring well installed to 10.0m (RL-5.0m).
 3. Steady water level measured at 5.80m on 15/1/16 and on 3m 03/02/16.
 Chainage .m Offset : m
 Water First Noted Water Steady Level

Defects - 1.54m : F,60°,P,R,O,C

Depth (m)	Type	Dip (Deg)	Planarity	Roughness	Aperture	Infill
	B - Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay
	C - Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide
	F - Fallation		P - Planar	R - Rough	N - Clean	K - Calcite
	H - Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite
	J - Joint		T - Stepped	V - Very rough	S - Stain	Q - Quartz
	L - Cleavage		U - Undulating			S - Secondary mineral
	R - Fracture					U - Unidentified mineral
	S - Shear zone					W - Weathered rock
	T - Contact					X - Carbonaceous
	V - Vein					Z - Clean
	Z - Decomposed Zone					
	DI - Drilling induced break					

Weathering Grades

RS - Residual Soil
 XW - Extremely weathered
 DW - Distinctly weathered
 SW - Slightly weathered
 FR - Fresh

Rock Strength

VW - Very weak
 W - Weak
 MS - Medium strong
 S - Strong
 VS - Very strong
 ES - Extremely strong

Samples

U50
 SPT
 Disturbed Sample
 Bulk Sample

Approved: MG
 Date: 4/02/2016



Soil Surveys Engineering Pty. Limited

Specialist in Applied Geotechnics

Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au

Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

BOREHOLE RECORD SHEET

Location Number: BH 10

Project Number: 110-12516

Project Name: Apartment Buildings

Location: 825 Stanley Street, Woolloongabba

Client: 825 Stanley Pty Ltd

Date: 14/01/2016

Page: 3 OF 3

Easting: 503768 Northing: 6959624 RL: 5.0 m
Logger: DA/CB Operator: DA Machine: Scout

Drilling Method					Depth	Graphic	Description	Weathering	Strength Estimated RSWVW MS S VS	Defect Spacing 20 60 200 600	Rec (%)	RQD	Samples and Remarks
TC	WB	RR	NM/LC	Casing									
					20.66	XXXXXX	TUFF fine to medium grained, light grey, massive with widely spaced fractures and trace calcite lenses/bands. (continued)	FR			100	100	20.38 m; V, 15°, C, K 20.6m, Is50 = 3.35 MPa
					21.0		BOREHOLE BH 10 TERMINATED AT 20.66 m						
					22.0								
					23.0								
					24.0								
					25.0								
					26.0								
					27.0								
					28.0								
					29.0								
					30.0								

SOIL SURVEYS 00:LIBRARY 2012:05:G.LB Log SOIL SURVEY BOREHOLE LOG 110-12516 GINT 2015 BH6-10.GPJ <-DrawingFile>> 05/02/2016 16:51 8.30.004 Developed by Dalgel

Comments:

- Groundwater not encountered during augering.
- Borehole bailed on completion of drilling and groundwater monitoring well installed to 10.0m (RL-5.0m). Steady water level measured at 5.80m on 15/1/16 and on 3m 03/02/16.

Chainage .m Offset : m

Water First Noted Water Steady Level

Defects - 1.54m : F,60° P,R,O,C

Depth (m)	Type	Dip (Deg)	Planarity	Roughness	Aperture	Infill
	B - Bedding		C - Curvilinear	L - Slickensides	C - Closed	C - Clay
	C - Clay seam		D - Discontinuous	P - Polished	F - Filled	F - Iron Oxide
	F - Fallation		P - Planar	R - Rough	N - Clean	K - Calcite
	H - Schistosity		S - Subplanar	S - Smooth	O - Open	L - Limonite
	J - Joint		T - Stepped	V - Very rough	S - Stain	Q - Quartz
	L - Cleavage		U - Undulating			S - Secondary mineral
	R - Fracture					U - Unidentified mineral
	S - Shear zone					W - Weathered rock
	T - Contact					X - Carbonaceous
	V - Vein					Z - Clean
	Z - Decomposed Zone					
	DI - Drilling induced break					

Weathering Grades

RS - Residual Soil
XW - Extremely weathered
DW - Distinctly weathered
SW - Slightly weathered
FR - Fresh


Rock Strength

VW - Very weak
W - Weak
MS - Medium strong
S - Strong
VS - Very strong
ES - Extremely strong

Samples

U50
SPT
Disturbed Sample
Bulk Sample

Approved: MG
Date: 4/02/2016



Client: 825 Stanley Street Pty Ltd
Project: Apartment Buildings
Location: 825 Stanley Street, Woolloongabba

SSE Borehole: 10
Depth: 4.60m - 10.00m
Box: 1 of 3

Project no: 110-12516



Client: 825 Stanley Street Pty Ltd
Project: Apartment Buildings
Location: 825 Stanley Street, Woolloongabba

SSE Borehole: 10
Depth: 10.00m - 16.00m
Box: 2 of 3

Project no: 110-12516

PointID : BH 10 Depth Range: 10.00 - 16.00 m



TITLE
 825 Stanley Pty Ltd
 825 Stanley Street, Woolloongabba
 Apartment Buildings
 Core Photo - BH 10

DRAWN	CB	DATE	18/01/2016
CHECKED	GB	DATE	18/01/2016
SCALE	Not To Scale		A4
PROJECT No	110-12516	FIGURE No	1/2



Client: 825 Stanley Street Pty Ltd
Project: Apartment Buildings
Location: 825 Stanley Street, Woolloongabba

SSE Borehole: 10
Depth: 16.00m - 20.66m
Box: 3 of 3

Project no: 110-12516



TITLE

825 Stanley Pty Ltd
 825 Stanley Street, Woolloongabba
 Apartment Buildings
 Core Photo - BH 10

DRAWN	CB	DATE	18/01/2016
CHECKED	GB	DATE	18/01/2016
SCALE	Not To Scale		A4
PROJECT No	110-12516	FIGURE No	2/2

APPENDIX C

LABORATORY TEST CERTIFICATES



Soil Surveys Engineering Pty. Limited
Specialist in Applied Geotechnics

Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au
Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

SOIL SURVEYS

POINT LOAD INDEX TEST REPORT

as per AS4133.4.1-2007




Project Number : 110-12516 **Project Name : Apartment Buildings**

Project Location : 825 Stanley Street, Woolloongabba

Project Client : 825 Stanley Pty Ltd

Sheet 1 of 2

Borehole	Depth	Rock Type	Weathering Grade	Moisture Condition	Test Method	Core Size (mm)	Date Drilled	Date Tested	Failure Type	Failure Load (kN)	Is (MPa)	Is50 (MPa)	AS1726 Classification	Operator
BH 08	7.16	TUFF	DW	Field	Diametral	52	15/01/2016	18/01/2016	Along joint	0.4	0.16	0.16	LOW	CB
BH 08	8.90	TUFF	DW-SW	Field	Axial	52	15/01/2016	18/01/2016	Through rock mass	2.2	0.63	0.68	MEDIUM	CB
BH 08	10.92	TUFF	SW	Field	Axial	52	15/01/2016	18/01/2016	Through rock mass	0.7	0.2	0.22	LOW	CB
BH 08	11.54	TUFF	FR	Field	Diametral	52	15/01/2016	18/01/2016	Through rock mass	3.8	1.41	1.43	HIGH	CB
BH 08	14.88	TUFF	SW-FR	Field	Axial	52	15/01/2016	18/01/2016	Through rock mass	2.4	0.7	0.75	MEDIUM	CB
BH 08	15.90	TUFF	FR	Field	Diametral	52	15/01/2016	18/01/2016	Through rock mass	3.9	1.42	1.45	HIGH	CB
BH 08	17.89	TUFF	FR	Field	Diametral	52	15/01/2016	18/01/2016	Through rock mass	3.1	1.13	1.15	HIGH	CB
BH 08	20.85	TUFF	FR	Field	Diametral	52	15/01/2016	18/01/2016	Through rock mass	3.6	1.33	1.36	HIGH	CB
BH 08	21.12	TUFF	FR	Field	Axial	52	15/01/2016	18/01/2016	Through rock mass	4.1	1.19	1.28	HIGH	CB
BH 08	24.90	TUFF	FR	Field	Axial	52	15/01/2016	18/01/2016	Through rock mass	3.4	0.98	1.06	HIGH	CB
BH 08	26.55	TUFF	FR	Field	Diametral	52	15/01/2016	18/01/2016	Through rock mass	2.6	0.97	0.99	MEDIUM	CB
BH 09	5.95	TUFF	SW	Field	Diametral	52	13/01/2016	18/01/2016	Through rock mass	4.0	1.48	1.51	HIGH	CB
BH 09	7.85	TUFF	FR	Field	Diametral	52	13/01/2016	18/01/2016	Through rock mass	7.2	2.67	2.71	HIGH	CB
BH 09	9.05	TUFF	FR	Field	Axial	52	13/01/2016	18/01/2016	Through rock mass	8.9	2.58	2.77	HIGH	CB
BH 09	12.75	TUFF	FR	Field	Diametral	52	13/01/2016	18/01/2016	Through rock mass	6.7	2.47	2.51	HIGH	CB
BH 09	16.95	TUFF	SW-FR	Field	Axial	52	13/01/2016	18/01/2016	Through rock mass	10.8	3.14	3.38	VERY HIGH	CB
BH 09	19.80	TUFF	FR	Field	Axial	52	13/01/2016	18/01/2016	Through rock mass	17.9	5.2	5.59	VERY HIGH	CB
BH 09	20.15	TUFF	FR	Field	Diametral	52	13/01/2016	18/01/2016	Through rock mass	18.0	6.65	6.77	VERY HIGH	CB
BH 10	4.92	TUFF	DW-SW	Field	Diametral	52	14/01/2016	18/01/2016	Through rock mass	11.8	4.36	4.44	VERY HIGH	CB
BH 10	6.90	TUFF	SW	Field	Axial	52	14/01/2016	18/01/2016	Through rock mass	11.2	3.26	3.5	VERY HIGH	CB
BH 10	7.05	TUFF	SW	Field	Diametral	52	14/01/2016	18/01/2016	Through rock mass	5.1	1.9	1.93	HIGH	CB
BH 10	9.95	TUFF	FR	Field	Axial	52	14/01/2016	18/01/2016	Exceeded Machine limit	>20.0	>7.4	>7.53		CB
BH 10	11.53	TUFF	FR	Field	Diametral	52	14/01/2016	18/01/2016	Through rock mass	9.6	3.54	3.6	VERY HIGH	CB
BH 10	13.10	TUFF	SW-FR	Field	Axial	52	14/01/2016	18/01/2016	Through rock mass	13.1	3.79	4.07	VERY HIGH	CB
BH 10	14.70	TUFF	SW-FR	Field	Diametral	52	14/01/2016	18/01/2016	Along joint	5.6	2.08	2.12	HIGH	CB





Soil Surveys Engineering Pty. Limited

Specialist in Applied Geotechnics

Milton: ph +61 7 3369 6000 brisbane@soilsurveys.com.au

Gold Coast: ph +61 7 5500 0465 goldcoast@soilsurveys.com.au

SOIL SURVEYS

POINT LOAD INDEX TEST REPORT

as per AS4133.4.1-2007




Project Number : 110-12516 Project Name : Apartment Buildings

Project Location : 825 Stanley Street, Woolloongabba


Project Client : 825 Stanley Pty Ltd

Sheet 2 of 2

Borehole	Depth	Rock Type	Weathering Grade	Moisture Condition	Test Method	Core Size (mm)	Date Drilled	Date Tested	Failure Type	Failure Load (kN)	Is (MPa)	Is50 (MPa)	AS1726 Classification	Operator
BH 10	17.90	TUFF	FR	Field	Axial	52	14/01/2016	18/01/2016	Through rock mass	10.7	3.09	3.32	VERY HIGH	CB
BH 10	20.60	TUFF	FR	Field	Diametral	52	14/01/2016	18/01/2016	Through rock mass	8.9	3.29	3.35	VERY HIGH	CB



APPENDIX D
DRAWINGS



Borehole Location Plan reproduced from plan ref. S-8483-001-A

SCALE			
REFERENCE			
V:\Milton\Milton 12001-13000\Milton 12401-12600\1-9819 Woolloongabba\Graphics\			
A3	DRW. NO	DATE	CHECKED
110-12516-02	13/01/2016	MG	

DRAWING TITLE

APARTMENT BUILDINGS

BOREHOLE LOCATION PLAN

CLIENT



825 STANLEY PTY LTD

LOCATION

825 STANLEY ST, WOOLLOONGABBA

Soil Surveys
SOIL SURVEYS ENGINEERING PTY.LIMITED
Specialists in Applied Geotechnics


KEY MAP



Stanley Street
Looking North toward The Gabba

Legend

- | | | | |
|---------|-----------------------------|----------|-----------------------|
| — CAG — | Comms Above Ground | ● BH | Bore Hole |
| □ COMK | Comms Marker | ● BOL | Bollard |
| ▣ COMP | Comms Pit | —//— | Edge Garden |
| — CUG — | Comms Under Ground | — — — | Fence |
| — SWD — | Drainage Swug | ● IO | Inspection Opening |
| — — — | Drainage Centre Line | ⊙ MH | Unidentified Manhole |
| ● SWMH | Stormwater MH | □ PO | Post |
| □ SWGT | Stormwater Gully Trap | ⊙ SI | Sign |
| □ SWFI | Field Inlet Pit | ⊙ TBM | Temporary Bench Mark |
| △ SWKA | Stormwater Kerb Adaptor | — T — | Telecom Line |
| — UE — | Power Line Under Ground | ▣ TEL | Telecom Pit |
| — — — | Power Line Above Ground | ▣ TELBOX | Telecom Telbox |
| ⊙ ELMK | Electrical Marker | ⊙ TEM | Telecom Marker |
| ▣ ELP | Electrical Pillar | ⊙ TP | Telecom Pole |
| ▣ ELPI | Electrical Pit | — — — | Bottom of Bank |
| ○ GW | Guy Wire Anchor | — — — | Top of Bank |
| ⊙ LAMP | Lamp Post | — — — | Change of Grade |
| ⊙ LP # | Light Pole | — — — | Water Line |
| ⊙ PPL | Power Pole | — — — | Edge of Vegetation |
| ⊙ PPLT | PP with Light & Transformer | — — — | Tree - 0.3m Dia Trunk |
| ⊙ PPT | Power Pole with Transformer | — — — | & 6m Canopy Spread |
| — G — | Gas Main | — W — | Water Main |
| ▣ GM | Gas Meter | HR | Fire Hose Reel |
| ▣ GV | Gas Valve | HY | Water Hydrant |
| — — — | Road Crown | SPR | Water Sprinkler |
| — — — | Edge of Bitumen | SV | Water Valve |
| — — — | Edge Track | TAP | Water Tap |
| ○ GP | Guide Post | WBE | Hydrant Booster |
| — — — | Guard Rail | WM | Water Meter |
| — — — | Road Kerb Invert | WMK | Water Marker |
| — S — | Sewer Main | — — — | Bitumen |
| ⊙ SMH | Sewer Manhole | — — — | Concrete |
| ⊙ SMK | Sewer Marker | — — — | Dirt |
| ⊙ SVE | Sewer Vent | — — — | Garden |
| — — — | Awning / Top of Gutter | — — — | Gravel / Rock |
| | | — — — | Pavers |
| | | — — — | Tiles |



SEE SHEET 2

JENSEN BOWERS
SURVEYORS
PLANNERS
DEVELOPMENT ADVISORS
jensenbowers.com.au

72 Costin Street, Fortitude Valley, Qld. 4006
PO Box 799, Spring Hill, Qld. 4004
T (07) 3852 1771 F (07) 3252 9818
T.H. Jensen & Bowers Pty. Ltd. (Consulting Surveyors)
ABN. 52 010 872 607
© Copyright reserved to Jensen Bowers Group Consultants Pty Ltd

Associated Consultants

Local Authority: Brisbane C.C.
Authority Ref. No:
RP Description: Lots 19-23 & 43-46 on RP11809,
Lot 1 on RP11810, Lots 3 & 4 on
RP59481, Lot 47 on RP110862
& Lots 2 & 42 on SP107611
Original Portion: 165
Parish/County: South Brisbane/Stanley
Date of Survey: 01/12/15
Level Datum: AHD
Origin: OPM36559 RL 9.354
Level Bk / Fid Bk:
Horizontal Datum: IS249973
Contour Interval: 0.5m

Scale
0 5 10 15m
1 : 500 @ A3 (Before Reduction)

Notes
The services shown hereon have been located where possible by field survey. Whilst due care and attention have been exercised, T.H. Jensen and Bowers Pty. Ltd. does not warrant that the services have been located in their entirety.
The boundaries shown hereon are for plotting purposes only and are subject to final survey.
The location of underground service lines are approximate only and have been plotted from field survey observations and/or service searches. Should their accurate location be critical to detail design we recommend further investigation.

Disclaimer
Any licence, expressed or implied, to use this document for any purpose whatsoever is restricted to the terms of the agreement or implied agreement between Jensen Bowers and the instructing party.

Drawn: ML	Date: 03/12/15
Surveyed: BR	Date: 01/12/15
Checked: DH	Date: 08/12/15



Issue	Description	Date	Appc
A	Original Issue	08/12/15	DH
B	Adjoining Substation Added	18/12/15	DNH

Client
825 Stanley Pty Ltd

825 Stanley Street
Woolloongabba

Detail Survey
Sheet 1 of 2


Drawing No. S-8483-001	Issue B	Original Size A3
---------------------------	------------	---------------------



72 Costin Street, Fortitude Valley, Qld. 4006
PO Box 799, Spring Hill, Qld. 4004
T (07) 3852 1771 F (07) 3252 9818
T.H. Jensen & Bowers Pty. Ltd. (Consulting Surveyors)
ABN. 52 010 872 607
© Copyright reserved to Jensen Bowers Group Consultants Pty Ltd

Associated Consultants

Local Authority: Brisbane C.C.
Authority Ref. No:
RP Description: Lots 19-23 & 43-46 on RP11809,
Lot 1 on RP11810, Lots 3 & 4 on
RP59481, Lot 47 on RP110862
& Lots 2 & 42 on SP107611
Original Portion: 165
Parish/County: South Brisbane/Stanley
Date of Survey: 01/12/15
Level Datum: AHD
Origin: OPM36559 RL 9.354
Level Bk / Fid Bk:
Horizontal Datum: IS249973
Contour Interval: 0.5m



Notes
The services shown hereon have been located where possible by field survey. Whilst due care and attention have been exercised, T.H. Jensen and Bowers Pty. Ltd. does not warrant that the services have been located in their entirety.
The boundaries shown hereon are for plotting purposes only and are subject to final survey.
The location of underground service lines are approximate only and have been plotted from field survey observations and/or service searches. Should their accurate location be critical to detail design we recommend further investigation.

Disclaimer
Any licence, expressed or implied, to use this document for any purpose whatsoever is restricted to the terms of the agreement or implied agreement between Jensen Bowers and the instructing party.

Drawn: ML	Date: 03/12/15
Surveyed: BR	Date: 01/12/15
Checked: DH	Date: 08/12/15

Issue	Description	Date	Appc
A	Original Issue	08/12/15	DH
B	Adjoining Substation Added	18/12/15	DNH

Client
825 Stanley Pty Ltd

**825 Stanley Street
Woolloongabba**

**Detail Survey
Sheet 2 of 2**

Drawing No. S-8483-001	Issue B	Original Size A3
---------------------------	------------	---------------------