

Site Based Stormwater Management Report

893-899 Stanley St & 10 Hampton St
East Brisbane

Prepared for DAKL Group Pty Ltd



PLANS AND DOCUMENTS
referred to in the PDA
DEVELOPMENT APPROVAL

Approval no: DEV-2026-WGB-4631
Date: 25-May-2026



Queensland
Government

AMENDED IN RED

By: Essen Joseph
Date: 25-May-2026



Queensland
Government

See amendments
in red to drawing
number C200,
contained in
Appendix C.



ABN 48 644 618 253
www.ensilon.com.au

BRISBANE
IPSWICH
GOLD COAST

CIVIL ENGINEERING
LAND DEVELOPMENT
TRANSPORT & TRAFFIC
HYDROLOGY & HYDRAULICS
PROJECT MANAGEMENT
FORENSIC & EXPERT SERVICES

ISSUE	DATE	ISSUE DETAILS	AUTHOR	CHECKED	APPROVED
1	19.03.2026	DA Issue	JCH	NM	JCH

COMMERCIAL IN CONFIDENCE

This document including any intellectual property is confidential and proprietary to Ensilon Pty Ltd and may not be disclosed in whole or in part to any third party nor used in any manner whatsoever other than for the purposes expressly consented to by Ensilon Pty Ltd in writing. Ensilon reserves all legal rights and remedies in relation to any infringement of its rights in respect of its confidential information.

- 1 Introduction
- 2 Scope
- 3 Criteria
- 4 Site Characteristics
- 5 Flooding
- 6 Stormwater Quantity Management
- 7 Stormwater Quality Management
- 8 Conclusion
- 9 Qualifications and Limitations

Appendices

Appendix A – Detailed Site Survey

Appendix B – Proposed Development Plans

Appendix C – Preliminary Stormwater Plans

Appendix D – Proprietary Information

1. Introduction

Ensilon Consulting has been commissioned by DAKL Group to prepare a Site Based Stormwater Management Plan for the proposed residential development at the corner of Stanley Street and Hampton Street, East Brisbane (known as 893-899 Stanley St & 10 Hampton St and described as Lot 61 on RP11567, Lot 62 on RP11567, Lot 63 on RP11567, Lot 1 on RP116092 and Lot 60 on RP11567) within the Brisbane City Council (BCC) local government area. The site is currently within the EDQ Woolloongabba Priority Development Area (PDA).

This report addresses issues relating to flooding, stormwater quantity and stormwater quality management for the overall development with details to demonstrate the specific requirements.

The objective of this report is to demonstrate that the proposed development can be supported by the existing and/or proposed stormwater infrastructure and is compliant with the EDQ Development Scheme and Brisbane City Council (BCC) Planning Scheme.

2. Scope

The following items will be addressed in this report;

- Lawful point of discharge for the development;
- Proposed concept stormwater quantity management plan for the site; and
- Proposed concept stormwater quality management plan for the site.

3. Criteria

This report has been compiled based on:

- Existing site survey prepared by Bplanned (Surveyor);
- Proposed site layout plan prepared by NMDS Architecture (Architect);
- Discussions with the Client and Architect; and
- Information obtained from Council's online resources and EDQ Prelodgement minutes.

4. Site Characteristics

4.1 Location and Description

The proposed development is located at 893-899 Stanley St & 10 Hampton St, East Brisbane. The site is located within the Brisbane City Council (BCC) local government area. The site is currently within the EDQ Woolloongabba Priority Development Area (PDA). The current site is a mixture and commercial and warehousing with multi access points off Stanley St & 10 Hampton St.

The existing total area of the site is 2621 m².



Figure 4.1 Site Locality Plan (Source: Nearmap 2025)

4.2 Watercourses and Topography

The site is generally located on uniformly undulating terrain that tends to drain toward the west and southwest. The footpath on the Stanley Street frontage appears to drain toward Stanley Street, whilst surface water and the majority of roofwater drains towards Hampton Street.

Surface levels within the development site vary between RL 11m AHD at the southwest corner to RL 13m AHD at the northeast corner. The site generally falls in a south-westerly direction from the rear boundary at approximately 1-2%. No distinct overland flow paths discharge into the site, although a small sub catchment does discharge surface flow onto the eastern site boundary.



Figure 2.3 Contour Map (Source: BCC 2025)

Stanley Street and Hampton Street have kerb and channel on both sides. Flow within Stanley Street is currently directed to the west, with no indication that excess carriageway surface flow spills either into the site or onto Hampton Street. Figure 2.3 presents the topography of the site and surrounds via a contour map. A Detailed Survey is attached to Appendix A which provides further details of the site topography.



Figure 4.4 Existing Roofwater line that exists within 905 Stanley Street (photo taken on the eastern site boundary in an eastern direction toward Lisburn Street. Note that the existing roofwater line is laid above the ground)

4.4 Lawful Point of Discharge

The lawful point of discharge test is described in Section 3.9.1 of the Queensland Urban Drainage Manual (QUDM) 4th Edition 2016 and has been considered with regard to the proposed discharge of stormwater from this site.

The criteria for determining the lawful point of discharge are:

- i. Will the proposed development alter the site's stormwater discharge characteristics in a manner that may substantially damage a third party property (see Section 3.6)?*
 - If not, then no further steps are required to obtain tenure for a lawful point of discharge (assuming any previous circumstances and changes were lawful).*
 - If there is a reasonable risk of such damage, then consider issue (ii) or (iii).*
- ii. Is the location of the discharge from the development site under the lawful control of the local government or other statutory authority from whom permission to discharge has been received? This will include a park, watercourse, drainage or road reserve, stormwater registered drainage easement, or land held by local government (including freehold land).*
 - If so, then no further steps are required to obtain tenure for a lawful point of discharge.*
 - If not, then consider issue (iii). A land owner or regulator may require that the developer obtain an authority to discharge as described in (iii) in order for the stormwater to ultimately flow to a location described in (ii).*
- iii. An authority to discharge over affected properties will be necessary. In descending order of certainty, an authority may be in the form of:*
 - Dedication of a drainage reserve or park*
 - A registered easement for stormwater discharge/works*
 - Written discharge approval*

Existing stormwater infrastructure in the form of kerb and channel and roofwater kerb adaptors, and the general direct of surface flow from the rear carpark onto Hampton Street, indicates that the existing lawful point of discharge for the site is the kerb and channel within Hampton Street.

It is proposed that this existing discharge point be maintained for the proposed development.

5. Flooding

5.1 Overview

The Brisbane City Council flood overlay mapping does not identify the site as being within a flood affected area from Brisbane River flooding (See Figure 5.1). The site is also not identified as being affected by creek/waterway or overland flow. (See Figure 5.2 and 5.3).




Figure 5.1 BCC Flood Overlay – Brisbane River Flooding (Source: BCC 2026)

As the lowest existing level of the site is RL 11.0m AHD and the maximum predicted flood level is 5.2m AHD during a 1% AEP storm event, the likelihood of the site being inundated due to Brisbane River backwater flooding is very low.




Figure 5.2 BCC Creek and River Flooding (Source: BCC 2026)




Figure 5.3 BCC Overland Flow Flooding (Source: BCC 2026)

6. Stormwater Quantity Management

6.1 Stormwater Quantity Analysis

The proposed development will not result in increased rates of stormwater runoff, and an on-site detention system will not be required. This is based on the observation that the current site has an existing (predeveloped) percentage of fraction impervious of 100% with appropriate lawful points of discharge. As the post-developed fraction impervious will not exceed the pre-developed fraction impervious and the predeveloped fraction impervious exceeds 60% (see Figure 6.1), in accordance with Clause 7.5.2 Chapter 7 of the SC6.16 Infrastructure design planning scheme policy, stormwater detention is not required.



Figure 5.2 Pre-developed Impervious Surface (Source: Nearmap 2026)

The post-developed fraction impervious is 91% and this surface is shown in Figure 6.2




Figure 6.2 Post-developed Impervious Surface (Source: NMDS Architecture 2026)

6.1.1 Pre-developed Site Discharge

The predeveloped site discharge rate was calculated by analysing the 63%, 50%, 20%, 10%, 5%, 2% and 1% AEP events using the Rational Method.

Table 6.1 Pre-developed Site Characteristics

Parameter	Value
Area	0.262 ha
Fraction Impervious	1.0
Time of Concentration (Paved)	10 min

The peak flow rates for each AEP are detailed in Table 6.2

Table 6.2 Calculated Pre-developed Peak Flow Rates

AEP %	Peak Discharge (m ³ /s)
63	0.046
50	0.062
20	0.089
10	0.106
5	0.128
2	0.160
1	0.179

6.1.2 Post-developed Site Discharge

The predeveloped site discharge rate was calculated by analysing the 63%, 50%, 20%, 10%, 5%, 2% and 1% AEP events. The post developed fraction impervious is 91%. The peak flow rates for each AEP are detailed in Table 6.3.

Table 6.3 Calculated Post-developed Peak Flow Rates

AEP %	Peak Discharge (m ³ /s)
63	0.045
50	0.062
20	0.088
10	0.105
5	0.127
2	0.160
1	0.179

The difference between pre-developed and post-developed site discharge is considered negligible.

6.2 Proposed Design and Analysis

Post-developed flows from the site will be discharged to existing stormwater infrastructure located within Hampton Street. Roofwater and surface water generated within the proposed development will be routed through multiple kerb adaptors located on the south-west corner of the site where it will be discharged into the street drainage system. No onsite detention will be provided. Refer to Appendix C for the concept stormwater layout sketch for the Site.

7. Stormwater Quality Management

7.1 Water Quality Objectives

7.1.1 Construction Phase

- Control measures to be put in place to protect downstream properties from nuisance flows.
- Maximum of 50mg/L of total suspended solids present in run-off discharged from the site during the construction stage, and a pH between 8 and 8.5.

7.1.2 Operational Phase

According to the BCC Planning Scheme the threshold for stormwater quality management for development for urban purposes is as follows:

- material change of use for an urban purpose which involves greater than 2,500m² of land that:
 - will result in an impervious area greater than 25% of the net developable area; or
 - will result in 6 or more dwellings.
- reconfiguring a lot for an urban purpose that involves greater than 2,500m² of land and will result in 6 or more lots.
- operational work for an urban purpose which involves disturbing greater than 2,500m² of land.

Consequently, the proposed site will require water quality improvement devices.

7.1.2.1 MUSIC Modelling Guidelines

Water quality parameters and the proposed limits applicable to this site were selected in accordance with Water by Design MUSIC Modelling Guidelines for South-East Queensland (2018).

7.1.2.2 Rainfall Data

MUSIC Modelling Guidelines provide advice on meteorological data for different climatic regions of South-East Queensland. Six minutes step rainfall data from City of Brisbane station from 1980 to 1989 were adopted for the site. Monthly evapotranspiration values were also obtained from the MUSIC Modelling Guidelines for the same Council/station. The below values were used in the MUSIC model.

7.1.2.3 Model Selection, Assumptions and Removal Effectiveness

In accordance with the Water by Design MUSIC Modelling Guidelines, split catchment methods were used for the source nodes utilising modified % impervious area. Rainfall threshold, soil properties & pollutant concentration input values were also sourced from the guideline. The MUSIC modelling inputs for the rainfall source nodes are summarised below.

Table 7.1 MUSIC Source Parameters (Source: MUSIC Modelling Guidelines 2018)

PARAMETER	URBAN RESIDENTIAL	COMMERCIAL AND INDUSTRIAL
RAINFALL THRESHOLD (MM)	1	1
SOIL STORAGE CAPACITY (MM)	500*	18
INITIAL STORAGE (% CAPACITY)	10	10
FIELD CAPACITY (MM)	200	80
INFILTRATION CAPACITY COEFFICIENT A	211	243
INFILTRATION CAPACITY COEFFICIENT B	5.0	0.6
INITIAL DEPTH (MM)	50	50
DAILY RECHARGE RATE (%)	28	0
DAILY BASEFLOW RATE (%)	27	31
DAILY DEEP SEEPAGE RATE (%)	0	0

Base flow and Storm flow parameters for TSS, TP and TN for roofs, roads and ground levels were sourced from Water by Design MUSIC Modelling Guidelines (2018). Refer below for a summary of the parameters used for the model.

Table 7.2 Source Node MUSIC Input Parameters (Source: MUSIC Modelling Guidelines 2018)

	FLOW TYPE	POLLUTANT SOURCE	TSS LOG ¹⁰ VALUES		TP LOG ¹⁰ VALUES		TN LOG ¹⁰ VALUES	
			MEAN	ST. DEV.	MEAN	ST. DEV.	MEAN	ST. DEV.
Lumped	Baseflow	Urban Lumped	1.00	0.34	-0.97	0.31	0.31	0.20
	Stormflow		2.18	0.39	-0.47	0.32	0.32	0.23
Split	Baseflow	Roof	N/A	N/A	N/A	N/A	N/A	N/A
		Roads	1.00	0.34	-0.97	0.31	0.20	0.20
		Ground Level	1.00	0.34	-0.97	0.31	0.20	0.20
	Stormflow	Roof	1.30	0.39	-0.89	0.31	0.26	0.23
		Roads	2.43	0.39	-0.30	0.31	0.26	0.23
		Ground Level	2.18	0.39	-0.47	0.31	0.26	0.23

7.2.1.4 Catchment Split

Total land use directed to the treatment devices and the catchment breakdown is shown in the table below.

Table 7.3 MUSIC Model Catchments

Catchment	Area (ha)	Comments
Site Capture (Roof)	0.201	Site catchment flows to the proposed treatment device prior to site discharge.
Fugitive Site Release – Driveway (Ground)	0.002	A small section of driveway and planting along the Hampton Street frontage with an assumed fraction impervious of 0.6
Pervious Deep Planting Zone 1 (along southern boundary) (Ground)	0.021	A small section of deep planting along the southern boundary bypasses the treatment device, is treated by a swale and flows directly into Hampton Street with an assumed fraction impervious of 0.1
Pervious Deep Planting along Hampton Street – Zone 2 (Ground)	0.004	A small section of deep planting along the southern boundary bypasses the treatment device, is treated by a swale and flows directly into Hampton Street with an assumed fraction impervious of 0.1
Pervious Deep Planting at corner of Hampton and Stanley Street (Ground)	0.022	A small section of deep planting along the southern boundary bypasses the treatment device, is treated by a swale and flows directly into Hampton Street with an assumed fraction impervious of 0.25
Total	0.262	

7.2.2 Proposed Treatment Train

A treatment train consisting of proprietary treatment devices from Humes is proposed for the Site. The figure below summarises the proposed treatment train for the development.




Figure 7.1 MUSIC Model Layout

Refer to Appendix C for the concept stormwater layout sketch.

7.2.2.1 Treatment devices


The following proprietary treatment devices from Humes are proposed for the site.

- 1 x Humefilter UPT 1800 (SQIDEP approved)
- 1 x Humefilter UPT 1200 (SQIDEP approved)
- 2 x Swales

Refer to Appendix D for the SQIDEP and proprietary information.

7.2.3 Treatment train effectiveness

The following tables summarise the effectiveness of the proposed treatment trains modelled in MUSIC.



	Sources	Residual Load	% Reduction
Flow (ML/yr)	2.87	2.87	0
Total Suspended Solids (kg/yr)	129	18.9	85.4
Total Phosphorus (kg/yr)	0.543	0.152	72.1
Total Nitrogen (kg/yr)	6.15	3.2	47.9
Gross Pollutants (kg/yr)	58.3	6.17	89.4

Figure 7.2 Overall Development Treatment Train Effectiveness Results

7.2 Construction Phase Stormwater Quality Management

7.2.1 Reference and Guidelines

Erosion and sediment control management for the development should be in accordance with the International Erosion Control Association (IECA) Best Management Practices (2008), the Institute of Engineers (QLD) 'Sediment and Erosion Control Guidelines' and Council requirements.

All erosion and sediment control devices used during and after construction are to be in line with current best management practices and all practical measures applicable to the site. Erosion and Sediment Control Measures should include, but not be limited to, details within the Erosion and Sediment Control Plan Drawings to be provided at detailed design stage.

As per the Environmental Protection Act (EPA) 1994 all personnel must comply with the general environmental controls under Sections 319 and 320, provided as follows:

- Section 319 of the EPA states that all persons involved in the project, from design to construction, are to act in accordance with the 'general environmental duty'. This requires all reasonable and practicable measures to be adopted to prevent or minimise environmental harm. Consequently, any erosion and sediment control devices proposed or implemented on site must represent current best management practices and all practical measures applicable to the site.

- In addition, Section 320 of the EPA, all personnel have a legally binding duty to notify their employer, their Local Regulatory Authority and the Environmental Protection Agency (QLD) should they become aware of a potential or actual incident of environmental harm. The Principal Contractor should therefore be aware of their responsibility to ensure all persons on site are aware of their environmental duties.

7.2.2 Responsibility

In addition to the above, it is the responsibility of the Contractor to put in place all the erosion and sediment control measures on site until all disturbed areas are reinstated including maintenance of such measures. The Contractor is, at all times, responsible for the erosion and sediment control measures to ensure minimal environmental harm and compliance with Council's standards.

7.3 Proposed Erosion & Sediment Control Measures

During the construction phase of the development, an Erosion and Sediment Control Program will be implemented to minimise water quality impacts.

This Program will be developed by the Contractor that is engaged to design and construct the development and hence, will not be available until closer to the start of construction.

Details of the required construction phase sediment and erosions control measures will be provided on the engineering drawings (detailed design phase) and shall be in accordance with the SPP.

The Contractor shall be ultimately responsible for the preparation and implementation of an Erosion and Sediment Control Program and meeting the required minimum construction phase water quality objectives.

The information below is provided to identify possible controls and procedures, that could be adopted to mitigate erosion and sediment impacts, including who is responsible for them, and is recommended to be incorporated into the Erosion and Sediment Control Program.

7.3.1 Pre-Construction

- Establish a single stabilised entry/exit point for each stage of construction. This point should also include a vehicle shakedown device to mitigate the transportation of dust and dirt.
- Sediment fences are to be placed along the low side of the site to slow flows, reduce scour and capture some sediment runoff. Soil testing needs to be undertaken (if required) to confirm the type of sediment fence most suitable for the site.

- Areas for plant and construction material storage are to be designated along with associated diversion drains and spillage holding ponds.
- Prepare a detailed erosion and sediment control plan suitable for the site and the proposed development layout prior to starting works.
- Incorporate measures to address potential acid sulfate soils.
- Site personnel must be inducted on to the sediment and erosion control measures implemented on site.

7.3.2 During Construction

- Progressive stabilization of exposed areas.
- Construction activities are to be confined to the necessary construction areas.
- Tracking the excavation and stockpiling of materials.
- Incorporate measures to address potential acid sulfate soils.
- The provision of a construction entry/exit point and shakedown area to prevent the tracking of debris from vehicles onto public roads. Only one construction exit should be nominated to limit the movement of construction equipment.
- Transport loads that are subject to loss through wind or spillage shall be covered or sealed to prevent entry of pollutants to the stormwater system.
- Regular inspection and maintenance of sediment fences, sediment basins and other erosion control measures. Following rainfall events greater than 50mm, inspection of erosion control measures and removal of collected material should be undertaken. Replacement of any damaged equipment should be performed immediately.

7.3.3 Post Construction

The Contractor/Developer will be responsible for the maintenance of erosion and sediment control devices from the possession of the site until ground surface stabilisation has occurred to the satisfaction of the Superintendent and the Principal. The Sediment and Erosion Control Management Plans should be provided to all people involved with the Project, including sub-contractors, private certifiers, body corporates and regulators. These guidelines have been formed in accordance with the Healthy Waterways Fact Sheet 'Erosion and Sediment Control Management Plans' and the 'Best Practice Erosion and Sediment Control'.

8. Conclusion

A stormwater management plan has been prepared to manage stormwater quantity and quality for the development. The following key points are as follows.

- No on-site pipe detention system is required for the site.
- Two (2) Humefilters and two (2) swales for water quality treatment devices have been proposed for the development.
- The site is not directly affected by 1% AEP backwater flooding according to Council's online mapping and Council's planning scheme.

The information presented in this report demonstrates that the proposed development may be serviced and constructed generally in accordance with the EDQ Development Scheme and Brisbane City Council (BCC) Planning Scheme.

Following our review of the proposed service requirements for the subject site and based on the enclosed information we advise there are no stormwater constraints that would make the subject site unsuitable for development.

Prepared by:

Jason Harley

Principal Engineer, Ensilon Consulting
BE(Hon), BSurv(Hon), MEngSc. RPEQ 05665

9. Qualifications and Limitations

This report must be read in its entirety along with all relevant references. Due regard should be given to the limitations and constraints involved in the derivation of SMPs and flood studies which must be considered by future users of the information to correctly interpret the outcomes and outputs from this study. The following points summarise the main limitations and uncertainties associated with this study:

- LiDAR inherently has issues with accuracy as it cannot penetrate dense vegetation or water. As part of this project, the LiDAR has been reviewed through critical locations in the model. However, locations may not be accurately represented in the LiDAR topography which may affect hydraulic results.
- There are errors in LiDAR accuracy which should be considered when using design flood levels and design planning levels.
- From time to time, there may be minor errors introduced into DEMs when LiDAR is reprojected between different GDA datums or when post-developed surfaces are retriangulated and merged back into surrounding LiDAR tiles.
- The hydraulic validation model assumes no blockage of hydraulic structures, other than that directly as a result of the structure itself (piers, deck, railing etc). During real flood events, blockage can occur at structures and within waterways which may increase peak flood levels in some locations and reduce flood levels in others.
- Uncertainties in hydraulic modelling parameters and model discretisation. While these have been minimised through adopting industry standard parameter values derived and fine-tuned through calibration and verification of the hydraulic model to observed flood behaviour, uncertainties will still remain.
- Whilst the hydraulic assessment is a highly comprehensive detailed investigation, the models represent a point in time and are based on available data. Triggers for revisiting or reworking the study will depend on the significance of change to the study outcomes which will need to be assessed accordingly. Such triggers could include major flood events, improvements to design rainfalls, increased certainty on the effects of climate change, significant advancements in modelling techniques and major civil works such as large dams or extensive levee work.
- Not all structures within the catchment have been reviewed or inspected during the site visits. There may be errors in the Council database or previous modelling which have been used to inform the structure sizes and representations at some locations.

- The earthworks model which this study relies on may change or be modified in the future; either as a result of changes enacted by the Developer in future development applications or by future asset owners and their respective agents.

In preparing this document, including all relevant calculations and modelling, Ensilon Consulting has exercised the degree of skill, care and diligence normally exercised by members of the engineering profession and has acted in accordance with accepted practices of engineering principles.

Ensilon Consulting has used reasonable endeavours to inform itself of the parameters and requirements of the project and has taken reasonable steps to ensure that the works and documents are as accurate and comprehensive as possible given the information upon which it has been based including information that may have been provided or obtained by any third party or external sources which has not been independently verified. In making technical directions, Council takes on the full liability for any issues associated with those directions.

Ensilon Consulting reserves the right to review and amend any aspect of the works performed including any opinions and recommendations from the works included or referred to in the works if:

- Additional sources of information not presently available (for whatever reason) are provided or become known to Ensilon Consulting; or
- Ensilon Consulting considers it prudent to revise any aspect of the works in light of any information which becomes known to it after the date of submission.

Ensilon Consulting does not give any warranty nor accept any liability in relation to the completeness or accuracy of the works, which may be inherently reliant upon the completeness and accuracy of the input data and the agreed scope of works. All limitations of liability shall apply for the benefit of the employees, agents and representatives of Ensilon Consulting to the same extent that they apply for the benefit of Ensilon Consulting.

This document is for the use of the party to whom it is addressed and for no other persons. No responsibility is accepted to any third party for the whole or part of the contents of this report.

If any claim or demand is made by any person against Ensilon Consulting on the basis of detriment sustained or alleged to have been sustained as a result of reliance upon the report or information therein, Ensilon will rely upon this provision as a defence to any such claim or demand.

This report does not provide legal advice or legal interpretation in any way whatsoever.










Appendix A - Detailed Site Survey



TELSTRA - WHITE - (T)	
ELECTRICAL - ORANGE - (E)	
WATER - BLUE - (W)	
GAS - YELLOW - (G)	
SEWER - CREAM - (S)	
RECYCLED WATER - PURPLE - (RM)	
STORMWATER - GREEN - (SW)	
FIRE MAINS - RED - (FM)	
UNIDENTIFIED SERVICES - PINK - (U)	
COMMUNICATIONS - WHITE - (C)	
OPTUS - WHITE - (OPT)	

NBN - WHITE - (NBN)	
REEF NETWORKS - WHITE - (RN)	
VOCUS - WHITE - (VOC)	
AAPT - WHITE - (APT)	
TPG - WHITE - (TPG)	
POWERTEL - WHITE - (PWT)	
AARNET - WHITE - (ARN)	
NEXTGEN - WHITE - (NXT)	
UECOMM - WHITE - (UE)	
PIPE NETWORKS - WHITE - (PN)	

DATE:	
COMPANY:	
CONTACT:	
ADDRESS:	
JOB #:	
PROJECT:	
SKETCH #:	
LOCATED BY:	
REPORT BY:	
SITE CONTACT:	

 NORTH FACING	 TELSTRA PILLAR	 ELECTRICAL MANHOLE	 RECYCLED WATER MANHOLE	 SEWER MANHOLE	 OPTUS PIT
 DEPTH BOX	 TELSTRA MANHOLE	 ELECTRICAL MANHOLE	 RECYCLED WATER VALVE	 SEWER MANHOLE	 UECOMM PIT
 POTHOLE LOCATION	 TELSTRA 9 PIT	 ELECTRICAL PIT	 RECYCLED WATER METER	 SEWER MANHOLE	 PIPE NETWORKS PIT
 GAS PIT	 TELSTRA 8 PIT	 ELECTRICAL PIT	 RECYCLED WATER TAP	 SEWER MANHOLE	 REEF NETWORKS PIT
 GAS VALVE	 TELSTRA 6 PIT	 ELECTRICAL PILLAR	 STORMWATER MANHOLE	 SEWER INSPECTION OPENING	 VOCUS PIT
 WATER MANHOLE	 TELSTRA 5 PIT	 ELECTRICAL TRANSFORMER	 STORMWATER MANHOLE	 SEWER VALVE	 AAPT PIT
 WATER VALVE	 TELSTRA 4 PIT	 STREET LIGHT	 STORM WATER GULLY PIT	 NBN PIT	 TPG PIT
 WATER HYDRANT	 TELSTRA 3 PIT	 POWER POLE	 STORM WATER GULLY PIT	 NBN NODE	 POWERTEL PIT
 WATER METER	 TELSTRA 2 PIT	 FIRE MAIN VALVE	 STORM WATER GULLY PIT	 COMMUNICATIONS PIT	 AARNET PIT
 WATER TAP	 TELSTRA BURIED PIT	 FIRE MAIN HYDRANT	 STORM WATER HEAD WALL	 COMMUNICATIONS PIT	 NEXTGEN PIT
 SCOPE OF WORKS	 WARNING CLOUD	 FIRE MAIN HYDRANT	 FIRE HOSE REEL	 COMMUNICATIONS PIT	

-- (a) -- (a) -- QUALITY LEVEL A

-- (b) -- (b) -- QUALITY LEVEL B

-- (c) -- (c) -- QUALITY LEVEL C

-- (d) -- (d) -- QUALITY LEVEL D

-- T -- T -- TELSTRA

-- E -- E -- ELECTRICAL

-- G -- G -- GAS

-- W -- W -- WATER

-- S/W -- S/W -- STORMWATER

-- FM -- FM -- FIRE MAINS

-- S -- S -- SEWER

-- R/W -- R/W -- RECYCLED WATER

-- U -- U -- UNIDENTIFIED

-- C -- C -- COMMUNICATIONS

-- OPT -- OPT -- OPTUS

-- NBN -- NBN -- NBN

-- UE -- UE -- UECOMM

-- PN -- PN -- PIPE NETWORKS

-- RN -- RN -- REEF NETWORKS

-- V -- V -- VOCUS

-- APT -- APT -- AAPT

-- TPG -- TPG -- TPG

-- PWT -- PWT -- POWERTEL

-- ARN -- ARN -- AARNET

-- NXT -- NXT -- NEXTGEN

ULS SERVICE LOCATION REPORT TERMS AND CONDITIONS

1. ULS advises that Electronic and GPR depths & alignments are indicative only. Customer must validate all known assets before commencing excavation via potholing of services either by Hydrovac Excavation or Hand Digging to achieve a Quality Level A as per AS 5488-2022.
2. The client acknowledges that the information contained in this document are only correct at the time of producing the document, changes in circumstances after the time of recording data may impact on the accuracy of this data eg. ground levels can change and other underground assets could be installed without our knowledge.
3. Utility Location Services Pty Ltd gives no warranty or assurance and makes no representation as to the accuracy of any information or advice contained, it is **NOT TO SCALE** and intended for visual purposes only.
4. Depth readings are for "general information" only and NOT accurate for Design and Construction. Depths if depicted, are from ground surface to somewhere on or within the service based on locating procedures and signal strength. All on site and documented depths are for potholing purposes only. Size of materials of services, if depicted are per the BYDA records or if the service is visually exposed to the locator. It may not however be applicable to the entire service.
5. All locations are done as per BYDA or GIS Documentation provided. Locations are made only for the services requested, Other services may remain unmarked if they were not part of the request.
6. Client is responsible for complying with the duty of care of the asset holders as well as following all relevant Workplace Health and Safety Legislation and Regulations.
7. It is the responsibility of the client to ensure that all necessary permits, permissions or authorisations are obtained for the work to be carried out on site.

DEFINITION OF QUALITY LEVEL CLASSIFICATIONS AS PER AS 5488-2022

This Standard provides a framework for the classification of subsurface utility location and attributes information in terms of specified quality levels. This Standard applies to subsurface utilities and associated surface features that facilitate the location and identification of subsurface utility infrastructure. These features may include access chambers, stop valves, terminal pads and other surface related facilities. This Standard does not apply to utility infrastructure that is above the surface, such as overhead wires. This Standard applies to all existing (including redundant) and under-construction subsurface utility infrastructure. A quality level describes the amount and accuracy of information that is collected or held on subsurface utility. There are four quality levels A, B, C & D

Quality Level A - (meets location accuracy standard for minimum risk when excavating)

QL-A is the highest Quality Level accuracy and consists of positive identification (Potholing) of the attribute of a subsurface utility at a point to an absolute spatial position in three dimensions. It is the only quality level that defines a subsurface utility as "Validated".

Quality Level B - (significant risk reduction)


QL-B provides relative subsurface feature in 3 dimensions. The minimum requirement for QL-B is relative spatial position, this can be achieved via an electromagnetic frequency locating device. An electronic location provided by a DBYD Certified Locator to QL-B standard would have a minimum horizontal tolerance of plus or minus 300mm and a maximum vertical tolerance of plus or minus 500mm.

Quality Level C - (low accuracy and a high risk of damage)

QL-C is described as a subsurface feature correlation or an interpretation of the approximate location and attribute of a subsurface utility asset using a combination of existing records and site survey of visible evidence - for example you can see the pit lids shown on the plan but the actual position of underground connection between pits is still assumed.

Quality Level D - (least accurate level and if used on its own has a high risk of damage)

QL-D information is generally obtained from existing records provided by utilise as a result of a Before You Dig enquiry being lodged. In many cases the asset depicted on the plan is in a schematic format only and intended to indicate its presence.




Appendix B - Proposed Development Plans



FINISHES LEGEND:	
FACADE	
BRK	FEATURE BRICK CLADDING TO PODIUM
BAT	INFILL ALUMINIUM BATTENS POWDERCOAT: MONUMENT.
CONC1	PRECAST CONCRETE PANEL COLOUR: WHITE.
CONC2	PRECAST CONCRETE PANEL COLOUR: MID-GREY.
CONC3	PRECAST CONCRETE PANEL COLOUR: DARK-GREY.
BAISTRADES	
BAL-1	CLEAR GLASS BALUSTRADE
BAL-2	METAL BALUSTRADE

NORTH
17.03.2026



Appendix C - Preliminary Stormwater Sketch


LEGEND

	EXISTING LOT BOUNDARY
	DESIGN SURFACE CONTOUR (0.1m INTERVALS)
	PROPOSED STORMWATER LINE
	PROPOSED STORMWATER STRUCTURE
	EARTHWORKS BATTER TOP
	EARTHWORKS BATTER BOTTOM
	PROPOSED BUILDING EXTENT
	PROPOSED WATER RETICULATION
	PROPOSED SEWER RETICULATION
	PROPOSED SWALE
	PROPOSED FLOW PATH
	PROPOSED RETAINING WALL (HEIGHT IN m)
	PROPOSED DRIVEWAY CROSSOVER - CONCRETE 180mm THICK
	LANDSCAPE PLANTING - REFER LANDSCAPE ARCHITECTS PLANS
	EXISTING KERB
	EXISTING STORMWATER
	EXISTING SEWER
	EXISTING WATER
	EXISTING ELECTRICAL
	EXISTING TELECOMMUNICATION
	EXISTING COMMS
	EXISTING GAS
	EXISTING U/G HIGH VOLTAGE ELECTRICAL
	EXISTING WATER REMOVED

Discharge arrangement subject to compliance assessment approval, as per condition 28.

NOTE:

FLOOR PLAN PROVIDED BY NMDS ARCHITECTURE, REV (A) DATED 18.03.26



REV	DESCRIPTION	BY	DES	DATE
A	FOR APPROVAL	NM	NM	26.02.26

2.5 0 2.5 5.0m
1 : 125 (FULL SIZE A1)

NAME: RPEQ:	DATE:
Approved by, for and on behalf of Ensilon	
This drawing has been produced for the exclusive use of the client (nominated on this document). No third party is to rely on this document without written permission from Ensilon. This drawing is not to be constructed from unless "Issued for construction" is displayed and only where signed by an RPEQ.	
© Copyright	

Ensilon Pty Ltd
ACN 644 618 253

<http://www.ensilon.com.au>
© Copyright



CLIENT	DAKL GROUP
TITLE	SITWORKS LAYOUT PLAN

PROJECT	UNIT DEVELOPMENT 893-899 STANLEY ST EAST + 10 HAMPTON ST, EAST BRISBANE										
STATUS	FOR APPROVAL				DESIGNED NM	DRAWN NM	APPROVED -	DATE 26.02.26	SCALE 1:125	SHEET 1 of	
					PROJECT No 26-001	DRAWING No C200				REV A	


Appendix D - Proprietary Information

UNIVERSAL POLLUTANT TRAP (UPT1200) PARTS TABLE				
ITEM No.	PART	MANUFT	SUPPLIED BY	APPROX MASS (t)
1	BASE UNIT	HUMES	HUMES	1
2	PLINTH	BY OTHERS	HUMES	1
3	FILTER MEDIUM CARTRIDGE	BY OTHERS	HUMES	1
4	TREATMENT CHAMBER SHAFT	HUMES	HUMES	1
5	TREATMENT CHAMBER INSERT	BY OTHERS	HUMES	1
6	TREATMENT CHAMBER SUPPORT FRAME	BY OTHERS	HUMES	1
7	TREATMENT CHAMBER SUPPORT FRAME BRACKET	BY OTHERS	HUMES	4
8	CONCRETE SURROUND RING	HUMES	HUMES	1
9	RUBBER RING	HUMES	HUMES	1
10	CONCRETE LID	HUMES	HUMES	1
	ANCON 1.3" UNILIFT CONE ANCHOR CLUTCHES	ANCON	CONTRACTOR	4
	ANCON 2.5" UNILIFT CONE ANCHOR CLUTCHES	ANCON	CONTRACTOR	4
	MEGAPOXY / EPOXY / MASTIC SEALANT	-	HUMES	-
	STAINLESS STEEL CLEVIS PIN / R-CLIP	WHITWORTHS	HUMES	4x EACH

PIPES CONNECTION TABLE			
UPT	SIZE / TYPE	CONNECTION	COMMENTS
UPT INLET	DN150 uPVC CLASS TBC CONSULTANT	EPOXY JOINT	uPVC SUPPLIED AND INSTALLED BY CONTRACTOR ON-SITE.
UPT OUTLET	DN150 uPVC CLASS TBC CONSULTANT	EPOXY JOINT	uPVC SUPPLIED AND INSTALLED BY CONTRACTOR ON-SITE.

- GENERAL NOTES:
- CONCRETE DESIGNED TO ASS600
 - EXPOSURE CLASSIFICATION B2 AS PER ASS600. SELF COMPACTING CONCRETE WITH RIGID FORMWORK
 - TRAFFIC LOADING SW1800 VEHICLE TO ASS100 AND LIVE LOAD FACTOR 1.5 WITH 1.25 DYNAMIC ALLOWANCE
 - MINIMUM COVER TO REINFORCEMENT = 25mm (NOMINAL COVER = 30mm ± 5 UNO)
 - FOUNDING MATERIAL TO BE A MINIMUM 150kPa (WORKING LOAD) AND 150mm THICK COMPACTED GRAVEL TO 95% MOD
 - SEALANT: PU MASTIC OR SIKAFLEX 11FC
 - ABBREVIATIONS:


O/A = OVERALL
I/D = INTERNAL DIAMETER
O/D = OUTSIDE DIAMETER
TC = TREATMENT CHAMBER
MU = MAKEUP (SHAFT)



HUMEFILTER UPT1200

PLAN - SITE ARRANGEMENT

SCALE 1: NTS



SECTION A AS INSTALLED

DESIGN IS A CONCEPT ONLY.
DRAWING MAY VARY
SUBJECT TO DETAIL DESIGN

										FOR INFORMATION ONLY										CLIENT		HUMES WATER SOLUTIONS							
																				STATUS		PROJECT NO.		PROJECT NAME					
																				DWG		TITLE 1		TITLE 2					
																				PROG		HUMEFILTER UPT1200		A2					
																				BY		CHK		APP					
																				SOL TUONS		KRB		NIA		GJH		CK	
																				QTY CA		ENG		CHK		APP			
																				CODE		ENG		CHK		APP			
																				DATE		02/02/22		02/02/22		02/02/22			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV		DETAILS OF A REVISION		DWG		DATE ISS.			
																				REV									



Stormwater Quality Improvement Device Evaluation Protocol (SQIDEP)

VERIFICATION CERTIFICATE

Applicant Information

Company Name	Holcim Australia
Company Address	18 Little Cribb St Milton QLD 4064
Website	www.humes.com.au
Contact Email	charles.kelly@holcim.com

Verified Technology

Product Title	HumeFilter UPT Family
SQIDEP Pathway	Local Field Trial Evaluation Pathway
Reviewed Documents	The following documents form the basis of this independent evaluation: • SQIDEP Detailed Performance Report 31/01/23 (Issue 1) (superseded) • SQIDEP Detailed Performance Report 22/03/23 (Issue 2) (current) • Appendix C – iAuditor Sample Collection Reports_Timelapse Videos • Appendix D - ALS Lab testing documentation • Appendix E – Hydrographs • Appendix F - Statutory Declarations • Appendix H - Lab Testing Reports The following files and documents were also provided: • Dirty Water Test.MP4 • Filter_S04pc_Q0100_view1_hiRes.avi • Filter_S04pc_Q0100_view3_hiRes.avi • Hume Filter_Animation.MP4 • Humes UPT.ppt • Stormwater Quality Lab Testing- Final Report • Manly hydraulic laboratory testing Additional information was requested after a meeting between the Evaluators and applicants, chaired by a senior representative from Stormwater Australia including: • Additional laboratory Quality Assurance information in the form of Sample Receipt Notices • Sizing spreadsheets supplied on a confidential basis for the purpose of this review • Additional information on maintenance procedures Further information was provided on 30th May 2023 related to the permeability of the pleated filter. This included: • Technical Data –Non-woven Filter • Cover letter from Matthew King of Filquip Pty Ltd regarding filter permeability

Conditions	The limitations of the acceptance of these claims include: The results are reliant on the maintenance of the device being consistent with the manufacturer's guidelines. The life expectancy of the media should be regularly monitored and replaced in accordance with the Manufacturer's Technical Guidelines/Maintenance Manual. The tested device was configured "offline" with flows exceeding the TFR externally bypassing the device. Alternative installations may result in different outcomes. While the device should be capable of capturing Gross Pollutants it has not been optimized for this function
-------------------	--

Independent Reviewers

Evaluator	Evaluator
Andrew Allan	Rod Wiese
 AFFLUX CONSULTING STORMWATER MANAGEMENT SOLUTIONS	

Issue of Verification Certificate

Acceptance by SQIDEP Governance Panel	24-Aug-2023
Acceptance by Stormwater Australia Board of Directors	25-Aug-2023
Verification Issued	31-Aug-2023
Stormwater Australia Verification Certificate Number Reference	SA-2023/07a-VC

Verified under SQIDEP Version 1.3

Field Evaluation Pathway

