

Central Village Phase 2

Flood Assessment

Project Number: J11078/R4/v2

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

26 JUN 2015

MEDQ

Prepared for
Metro Property Development Pty Ltd

21 November 2014

Cardno (Qld) Pty Ltd
ABN 57 051 074 992

Level 11 Green Square North Tower
515 St Paul's Terrace
Fortitude Valley Qld 4006
Locked Bag 4006 Fortitude Valley
Queensland 4006 Australia

Telephone: 07 3369 9822

Facsimile: 07 3369 9722

International: +61 7 3369 9822

cardno@cardno.com.au

www.cardno.com.au

Document Control:					
Version	Date	Author		Reviewer	
		Name	Initials	Name	Initials
1	23 October 2014	L. Allan	LA	M. Giles	MG
2	21 November 2014	L. Allan	LA	M. Giles	MG

"© 2014 Cardno All Rights Reserved. Copyright in the whole and every part of this document belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or in or on any media to any person without the prior written consent of Cardno."

TABLE OF CONTENTS

1	INTRODUCTION	1
1.1	Background.....	1
1.2	Stormwater Infrastructure	1
1.3	Report Purpose.....	2
2	SITE AND DEVELOPMENT DESCRIPTION	3
2.1	Existing Topography and Drainage	3
3	HYDROLOGIC ANALYSIS.....	5
3.1	Rational Method Calculations.....	5
3.1.1	Rainfall Intensities.....	5
3.1.2	Catchment Areas	5
3.1.3	Runoff Coefficient Values.....	5
3.1.4	Times of Concentration	6
3.1.5	Peak Flows.....	6
3.2	Hydrologic Modelling	7
4	HYDRAULIC ANALYSIS.....	8
4.1	Data Sources.....	8
4.2	Stormwater Infrastructure	8
4.3	Existing Pre-Developed TUFLOW Scenario Model Setup.....	9
4.3.1	Model Data	9
4.3.2	Roughness Values.....	9
4.3.3	Inflows.....	9
4.3.4	Tail water Conditions.....	10
4.3.5	Time Step.....	10
4.4	Post-Developed TUFLOW Scenario Model Setup.....	10
4.5	Results.....	10
4.6	Discussion	11
4.7	Minimum Development Levels.....	11
5	CONCLUSION.....	14

TABLES:

Table 1	Catchment Areas	5
Table 2	Runoff Coefficients.....	5
Table 3	Time of Concentration Calculations	6
Table 4	Rational Method Peak Flow – Existing Case	6
Table 5	RAFTS Model Validation – 100 Year ARI Event	7
Table 6	Roughness Values.....	9
Table 7	Peak Water Surface Levels (mAHD).....	10

FIGURES:

Figure 1	Site Location
Figure 2	RAFTS Water Street Catchment Delineation
Figure 3	Pre-Development Model Topography Map
Figure 4	Post-Development Model Topography Map

APPENDICES:

Appendix A	Pre-Developed TUFLOW Results
Appendix B	Post-Developed TUFLOW Results

1 INTRODUCTION

1.1 Background

The Central Village Phase 2 site is bounded by Water Street to the south, Brunswick Street to the west, the existing Cromwell Terrace Office Park to the north and the existing Central Village Phase 1 site to the east. The total area of the Central Village Phase 2 site is approximately 4,920 m² and is situated on Lot 1 RP10553, Lots 11 and 12 RP10552, Lots 5, 6 and 13 RP81335 and Lot 102 SP143465 in Fortitude Valley, Brisbane.

Located 2km north-north-east of the Brisbane CBD, the Central Village Phase 2 site is situated within the Water Street catchment which covers an area of approximately 87 hectares spanning from Boundary Street, Spring Hill through Fortitude Valley and Bowen Hills where it meets Breakfast Creek and ultimately the Brisbane River.

As part of the Central Village Phase 2 development it is proposed to demolish the existing structures on the site and build 2 residential towers with underground basement levels combined with several mixed use podium levels including retail areas along the ground floor frontages of Water Street and Brunswick Street. Additionally, the proposed building footprint has been set to allow the existing Water Street road reserve to be widened.

The impact of the development of Central Village Phase 2 was assessed relative to conditions prior to any development occurring on the Central Village Phase 2 site but also considers the adjacent Central Village Phase 1 site in its fully developed condition including the stormwater mitigation elements designed for the Central Village Phase 1 site. The Central Village Phase 1 works and associated flood assessment is detailed in Cardno's '*Central Village – Stage 2 Detailed Design – Flood Report*' dated 8th August 2013.

1.2 Stormwater Infrastructure

The Central Village Phase 2 development is located immediately upstream of the Central Village Phase 1 development, which is currently nearing completion. Phase 1 of the Central Village development included the construction of an underground detention tank with a volume of 380 m³ and an outlet to the existing stormwater drainage system. The purpose of the tank was to provide storage to offset the filling associated with development of the Central Village Phase 1 site. A series of vertical inlets were provided along the frontage of the Central Village Phase 1 development to provide for the capture of flow during those events sufficient to exceed the capacity of the existing underground stormwater drainage system and cause overland flow along Water Street.

These inlets capture the stormwater flow that would have previously entered the site prior to the Central Village Phase 1 development, draining to the underground tank allows for the temporary storage of runoff, thereby mimicking the storage afforded within the Central Village Phase 1 site prior to development. The tank drains via gravity to the existing stormwater drainage system in Water Street following the peak flow in the underground pipe system. The tank provided as part of Central Village Phase 1 was sized to provide sufficient storage to offset the development of the entire Central Village Phase 1 site. For this reason, the Central Village Phase 1 works were included in the pre-developed scenario for the Central Village Phase 2 flood assessment.

1.3 Report Purpose

The purpose of the report is to present the results of hydraulic modelling completed to assess flooding impacts associated with the development of the Central Village Phase 2 site in order to ensure that the development will not cause any adverse or actionable flood impacts on existing properties external to the site.

For this assessment, two scenarios were considered.

- *Pre-Developed Scenario*

Considers the Water Street catchment in its current existing situation with the Central Village Phase 1 site and flood mitigation works completed and the Central Village Phase 2 site in its current existing state; and

- *Post-Developed Scenario*


Modifies the pre-developed scenario to include the proposed Central Village Phase 2 development.

2 SITE AND DEVELOPMENT DESCRIPTION

2.1 Existing Topography and Drainage

The site is currently used for commercial purposes. An aerial photograph showing the current development of the site and external catchment is shown below, with the site location shown on Figure 1.

Ground levels surrounding the site range from 12.3 mAHD to 20.4 mAHD. The site typically falls from north to south with the highest point along Brunswick Street at the north-west corner of the site and the lowest point along Water Street at the south-east corner of the site.



Water Street Catchment and Site Boundary

The Water Street catchment is fully developed and is an older style of catchment, in that all stormwater discharge is piped, rainfall is rapidly converted to runoff which in turn is transported downstream quickly via the piped drainage system. From the start of heavy rainfall within the Water Street catchment, the peak stormwater discharge arriving at the Central Village Phase 2 site can peak in as little as 15 minutes and significant flooding can occur within the Water Street catchment with very little advance warning.

Overland flow that reaches the intersection of Water and Brunswick Streets (adjacent to the Central Village Phase 2 site) initially discharge down Water Street, however, as the discharge within the catchment increases water ponds and backs up within Brunswick Street and the section of Water Street upstream of this intersection. These flood waters back up due to the narrow opening of the Water Street overland flow path on the downstream boundary of the Brunswick Street intersection due to the location of the existing buildings situated on either side of Water Street.

The Central Village Phase 2 site is situated within the Water Street overland flow path which is currently choked immediately upstream of the site due to the existing buildings situated on either side of Water Street on the corners of Brunswick Street, as such, the development of the site must allow for the conveyance of existing flow without adverse flood impacts to neighbouring properties. The proposed Central Village Phase 2 development will effectively increase the overland flood path by approximately 3 metres along the Water Street frontage of the site.

Presently, the flooding within the catchment is exacerbated by the inadequate capacity of the existing pipe and overland drainage network. If designed today, the underground pipe system would be sized to convey the discharge from the 1 in 10 year storm event (i.e. the stormwater runoff that has a 10% probability of occurring in a one year period). The existing underground pipe system within the catchment can convey slightly less than the 1 in 2 year flood flow.

Overland flow will occur in the Water Street catchment any time rainfall within the catchment results in a flow greater than the capacity of the underground drainage system. In the case of the Water Street catchment, the overland flow discharges along Water Street, with subsequent flooding occurring on properties located on either side of Water Street. Since the Central Village Phase 2 site is situated in one of these areas and specifically situated at the upstream choke point of Water Street, it is imperative that all habitable floor levels, retail areas, basement carpark entries and building emergency exits are designed to the appropriate flood immunity level in accordance with Council's planning and development guidelines.

3 HYDROLOGIC ANALYSIS

3.1 Rational Method Calculations

The flows used for the TUFLOW model were derived using a RAFTS rainfall runoff model of the catchment. The model parameters were adjusted until a good agreement was obtained between predicted peak flow rates and those calculated using the Rational Method calculations as outlined in the Brisbane City Council (BCC) *Subdivision & Development Guidelines* and the *Queensland Urban Drainage Manual* (QUDM). This approach was considered to be acceptable due to the uniformity of the catchment and the relatively small subcatchment areas used for the comparison.

3.1.1 Rainfall Intensities

The rainfall intensities provided in Table BA2.7.1 of the BCC *Subdivision & Development Guidelines* were used to define catchment rainfall for design events.

3.1.2 Catchment Areas

The catchment area was divided into 9 smaller sub catchments in both the existing and developed cases to allow for a good representation of catchment runoff and to define appropriate inflows to the hydraulic model. The assumed catchment areas are detailed in Table 1 with the hydrologic catchment delineation shown on Figure 2.

Table 1 Catchment Areas

Name	Area (ha)	Name	Area (ha)	Name	Area (ha)
A0	34.83	A3	4.54	A6	1.86
A1	6.18	A4	7.94	A9	1.67
A2	5.55	A5	2.21	A10	1.79

3.1.3 Runoff Coefficient Values

The ultimate level of development for each sub catchment external to the site was determined from the BCC Planning Scheme. The runoff coefficients nominated in Table B2.2 of the BCC *Subdivision and Development Guidelines* were used to define appropriate runoff coefficients for each identified land use. The adopted land use and the corresponding runoff coefficients for the Water Street catchment are listed in Table 2.

Table 2 Runoff Coefficients

Developed Category	C ₁₀
High Density Residential	0.87
Low/Medium Density Residential	0.85
Commercial	0.88

3.1.4 Times of Concentration

The time of concentration of each catchment was determined using standard inlet times in accordance with QUDM Section 4 based on the catchment characteristics and assuming a pipe velocity of 2 m/s. A summary of the calculations is provided in Table 3.

Table 3 Time of Concentration Calculations

Catchment	Standard Inlet time (min)	Pipe Flow			Channel Flow			Total Tc (min)
		Length (m)	Velocity (m/s)	Time (min)	Length (m)	Velocity (m/s)	Time (min)	
A0	5	890	2.0	7.42	-	-	-	12.42
A1	5	240	2.0	2.00	-	-	-	7.00
A2	5	-	-	-	300	1.5	3.33	8.33
A3	5	-	-	-	200	1.5	2.22	7.22
A4	5	-	-	-	290	1.5	3.22	8.22
A5	5	135	2.0	1.13	-	-	-	6.13
A6	5	130	2.0	1.08	-	-	-	6.08
A9	5	65	2.0	0.54	-	-	-	5.54
A10	5	-	-	-	-	-	-	5.00

3.1.5 Peak Flows

The peak flow rate for each sub-catchment was calculated for the 50 and 100 year events. The results of the Rational Method analysis are detailed in Table 4.

Table 4 Rational Method Peak Flow – Existing Case

Catchment	Contributing Area (ha)	Coefficients of Runoff C ₁₀	Rainfall Intensity (mm/h)		Peak Flow (m³/s)	
			100 year ARI	50 year ARI	100 year ARI	50 year ARI
A0	34.83	0.86	234	209	22.60	20.00
A1	6.18	0.85	288	258	4.94	4.33
A2	5.55	0.85	271	242	4.17	3.65
A3	4.54	0.85	285	255	3.59	3.14
A4	7.94	0.85	272	243	5.99	5.25
A5	2.21	0.88	302	271	1.85	1.66
A6	1.86	0.88	302	271	1.56	1.40
A9	1.67	0.88	313	277	1.45	1.29

Catchment	Contributing Area (ha)	Coefficients of Runoff C_{10}	Rainfall Intensity (mm/h)		Peak Flow (m ³ /s)	
			100 year ARI	50 year ARI	100 year ARI	50 year ARI
A10	1.79	0.88	325	291	1.62	1.45

3.2 Hydrologic Modelling

A RAFTS hydrologic model of the catchment was setup to determine the discharge hydrographs from each of the sub catchments at their outlet points. RAFTS is an urban and rural rainfall runoff routing program that can be used to determine the peak stormwater flows for a catchment, based on parameters such as area, fraction impervious, slope and catchment storage. A Bx value of 1.0 was adopted for the RAFTS model.

A number of storm durations ranging from 15 minutes to 6 hours were considered to determine the critical storm duration. Rainfall losses of zero initial and continuing loss were adopted for impervious areas and a zero initial loss with a continuing loss of 2.5 mm/h adopted for pervious areas.

The peak flows calculated using the RAFTS model were compared to the results obtained from the Rational Method for the 100 year ARI event. RAFTS model parameters such as Manning's n, slope and Bx were varied within reasonable limits until an acceptable agreement was obtained between the RAFTS and Rational Method flow estimates for the 100 year ARI event. This approach was considered to be acceptable given the relatively small size of the catchments and their uniform nature. The results and comparisons to the Rational Method are presented below in Table 5.

Table 5 RAFTS Model Validation – 100 Year ARI Event

Catchment	Rational Method (m ³ /s)	RAFTS (m ³ /s)	Difference (%)	Catchment	Rational Method (m ³ /s)	RAFTS (m ³ /s)	Difference (%)
A0	22.61	22.62	0.0	A5	1.85	1.84	-0.5
A1	4.94	4.87	-1.4	A6	1.56	1.57	0.6
A2	4.17	4.21	1.0	A9	1.45	1.43	-1.4
A3	3.59	3.56	-0.8	A10	1.62	1.55	-4.5
A4	5.99	5.98	-0.2				

The results indicate that the RAFTS model is adequate to calculate the discharge hydrographs for the catchment. This validated model was used to derive runoff hydrographs for the 50 and 100 year ARI events. The hydrographs were input to the hydraulic model to enable peak flows and flood levels within the study area to be calculated.

4 HYDRAULIC ANALYSIS

4.1 Data Sources

The sources of the data used as part of the flood assessment of the subject site are listed below:

- Survey – external to the site, aerial laser survey data (collected in 2002) ; and within the site, detailed survey completed by Jensen Bowers
- Aerial Photography – Aerial photography of the site was obtained from Nearmap.

4.2 Stormwater Infrastructure

At present the current flooding situation within the Water Street catchment is exacerbated by the inadequate existing pipe and overland drainage network. If designed today, the underground system would be sized to convey the 10 year ARI event flow event (i.e. the stormwater runoff that has a 10% probability of occurring in a one year period). The current system can convey slightly less than the 2 year ARI event flow. Therefore flooding currently occurs more frequently and to a greater extent than would now be considered acceptable.

Any rainfall causing a flow greater than the capacity of the underground drainage system, the remaining flow is conveyed overland. In the case of the Water Street catchment, the overland flow occurs along Water Street, with consequent flooding of properties located on either side of the street.

Pipe details such as size, length and invert levels for the existing drainage network in the catchment were taken from the BCC's eBimap and stormwater drainage drawings obtained from the BCC Plan Custodian. This data was verified against information listed in a previous study completed for Council (Tod Group, circa 1997). As sections of the existing drainage network are quite old, some of the required information was not available. In these instances the best estimates were taken, i.e. by assuming slope of the pipes matched the surface slope. Appropriate manhole losses were adopted based on the recommendations of the QUDM.

A key consideration in modelling is the interaction of the surface and underground drainage networks. Allowing water to freely transfer between the two networks (a common modelling assumption) can lead to erroneous results as the quantum of water transferred (for instance in an area where the capacity of the piped drainage system is reduced) can be unrealistic.

To overcome this issue, particular care was taken to model the gully pits and small pipes that connect the pits to the trunk drainage system. All gully inlets for the entire catchment area were surveyed during the site visit.

The Central Village Phase 2 development is located immediately upstream of the Central Village Phase 1 development, which is currently nearing completion. Phase 1 of the Central Village development included the construction of an underground detention tank with a volume of 380 m³ and an outlet to the existing stormwater drainage system. The purpose of the tank was to provide storage to offset the filling associated with development of the Central Village Phase 1 site. A series of vertical inlets were provided along the frontage of the Central Village Phase 1 development to provide for the capture of flow during those events sufficient to exceed the capacity of the existing underground stormwater drainage system and cause overland flow along Water Street. For this reason, the Phase 1 works were included in the 'pre-developed' scenario for the Phase 2 flood assessment.

4.3 Existing Pre-Developed TUFLOW Scenario Model Setup

4.3.1 Model Data

To determine the impact of the proposed Central Village Phase 2 development, the site was modelled using TUFLOW and the resultant flood levels compared to those calculated for the pre-development scenario.

The pre-developed scenario also considers the adjacent Central Village Phase 1 site in its fully developed condition including the stormwater mitigation elements designed for the Central Village Phase 1 site. The Central Village Phase 1 works and associated flood assessment is detailed in Cardno's '*Central Village – Stage 2 Detailed Design – Flood Report*' dated 8th August 2013.

The stormwater drainage through the subject site was modelled using the linked one-dimensional / two-dimensional hydraulic model TUFLOW (Build 2012-05-AA). TUFLOW was considered to be suitable for use in this case due to its ability to model the underground drainage network one-dimensionally while allowing a detailed representation of the overland flow via a two-dimensional grid.

A digital terrain model (DTM) of the study site was setup based on ground level survey obtained from the BCC. The pre-developed TUFLOW model of the Central Village Phase 2 area is shown on Figure 3. Due to the urban nature of the study area, a 3 metre grid was adopted.

Stormwater pipes and gully inlets were modelled as one dimensional links, connected to the two dimensional domain.

4.3.2 Roughness Values

The Manning's n roughness values for the study area were derived from aerial photographs and site inspections. The typical values adopted for the model are listed below in Table 6. Based on site inspections certain man made features like brick buildings and wall within the modelled area site that were deemed to block the catchment overland flow paths were modelled as blockages to provide an accurate representation of the flow patterns.

Table 6 *Roughness Values*

Land Use	Manning's n
Residential / Commercial Areas	0.20
Roads and Carparks	0.02
Open Space and Parks	0.04
Fences and Gates	0.08

4.3.3 Inflows

The discharge hydrographs calculated for the catchments using the RAFTS hydrologic model were used in the TUFLOW hydraulic model as detailed in Section 3.

4.3.4 Tail water Conditions

A normal depth corresponding to a slope of one percent was assumed as the tail water condition occurring at the northern boundary of the model (corresponding to the slope of the tributary along Water Street downstream of Anderson Street). A water level of 8.04 mAHD, equal to obvert of the pipe at the downstream end of the model along the eastern boundary, was adopted for the one dimensional drainage network.

4.3.5 Time Step

The adopted time step used for the one dimensional / two dimensional model was one second. This relatively short time step was required to increase the model stability and reduce the continuity error within the nested grid model.

4.4 Post-Developed TUFLOW Scenario Model Setup

The post-developed model used the same data and setup as for the existing pre-developed model, with the existing structures on the Central Village Phase 2 site replaced by the proposed residential towers footprint.

4.5 Results

The pre- and post-development hydraulic models were run for the 1 in 50 and 1 in 100 year ARI storm events to determine the impact the Central Village Phase 2 development has on existing flood levels in the vicinity of the site.

Peak flood level, depth, speed and hydraulic afflux maps are provided in Appendix A and B for the pre- and post-development scenarios respectively.

The resultant peak water levels at a number of key points surrounding the Central Village Phase 2 site are detailed in Table 7 with a the locations of each point identified on Figures 3 and 4.

Table 7 Peak Water Surface Levels (mAHD)

Location	Pre-Development		Post-Development		Impact	
	Q100	Q50	Q100	Q50	Q100	Q50
His_01	15.989	15.989	15.985	15.857	-0.005	-0.133
His_02	15.887	15.887	15.878	15.824	-0.009	-0.063
His_03	15.853	15.853	15.820	15.751	-0.034	-0.103
His_04	15.871	15.871	15.837	15.763	-0.034	-0.108
His_05	15.872	15.872	15.837	15.763	-0.035	-0.109
His_06	15.831	15.831	15.764	15.679	-0.067	-0.151
His_07	15.757	15.757	15.632	15.530	-0.125	-0.228
His_08	15.845	15.845	15.742	15.620	-0.103	-0.225
His_09	14.528	14.528	14.164	14.112	-0.364	-0.416
His_10	13.313	13.313	13.249	13.251	-0.064	-0.062
His_11	13.135	13.135	12.830	12.778	-0.305	-0.358
His_12	12.673	12.673	12.687	12.614	0.014	-0.059

Location	Pre-Development		Post-Development		Impact	
	Q100	Q50	Q100	Q50	Q100	Q50
His_13	12.024	12.024	12.002	11.967	-0.022	-0.057
His_14	11.930	11.930	11.919	11.842	-0.011	-0.088
His_15	11.394	11.394	11.392	11.347	-0.002	-0.048
His_16	11.162	11.162	11.160	11.116	-0.002	-0.046
His_17	10.607	10.607	10.605	10.574	-0.002	-0.033
His_18	15.845	15.845	15.805	15.729	-0.040	-0.116
His_19	15.845	15.845	15.805	15.729	-0.040	-0.116
His_20	13.254	13.254	13.159	13.090	-0.095	-0.164
His_21	13.096	13.096	13.030	12.981	-0.067	-0.115
His_22	12.378	12.378	12.344	12.270	-0.033	-0.108
His_23	12.115	12.115	12.110	12.040	-0.005	-0.075

4.6 Discussion

The results presented in Table 7 and shown graphically in Appendix A and Appendix B indicate that the proposed development of the Central Village Phase 2 site typically yields a reduction in peak water levels in the area surrounding the site and does not adversely impact on properties within the vicinity of the subject site. Some localised increases in flood levels are predicted within the road reserve in Water Street. However, any increase in flood levels is limited to the road reserve only.

Following a detailed review of the cause of the impact, it was confirmed that the increase in level is due to the improved flow conveyance in Water Street that results from widening the road reserve associated with the Phase 2 development. In this context, the impact can be attributed to the widening of the road rather than the construction of the proposed Central Village Phase 2 building. Calculations indicate there would be no increase in flood levels within the catchment if the building were to be constructed to match the footprint of the existing building.

Furthermore, the impact is localised and limited to short spans of road reserve and not on any private properties. Flood depths upstream and downstream of the area (which no increase in level is obtained) are already well in excess of the depth necessary to cause road closure. Given this, it is considered that the increase in level will not materially affect the trafficability of the road or the flood risk in the Water Street area.

4.7 Minimum Development Levels

Subsequent to the January 2011 flood event, Brisbane City Council invoked a Temporary Local Planning Instrument (TLPI) in relation to flooding. The requirements of the planning instrument were subsequently incorporated into the version of City Plan current at the time of this report.

Although the area is administered through EDQ, EDQ typically sets minimum development levels with reference to the requirements of the relevant local authority. Consequently, the minimum development levels applicable to the site are:

Based on Council guidelines, the minimum design standards applicable to the site under the City Plan in force at the time of this report are listed below.

- Floors for Commercial (including retail) Purposes *50 Year Event (no additional freeboard);*
- Habitable Floors for Residential Purposes *50 Year Event plus 500mm freeboard;*
- Points of entry to basement car park (ramps, doors etc.) *100 Year Event plus 300mm freeboard; and*
- Substation (If not Community Infrastructure) *100 Year Event plus 500mm freeboard.*

The relevant minimum flood levels for the derivation of development levels are listed in Table 7. Due to the varying level along the frontage of the Central Village Phase 2 site 100mm contours of the water surface profile for the post-developed scenario of the 50 and 100 year events are included on Figures B.1.3 and B.1.4 in Appendix B.

4.8 Adopted Floor Levels

It is worth noting that the flood level changes significantly along the Water Street frontage of the Central Village Phase 2 site as stormwater ponds at the intersection of Water Street and Brunswick Street, and then funnels down Water Street, next to the Phase 2 site.

Lobby Entry

The lobby entry level has been set at 16.2. This level is adequate.

Basement Access

Since no essential services (i.e. electrical, communications or other services that would prevent building occupation) are proposed in the basement of the Central Village Phase 2 site, all points of access into basements used for residential purposes must be provided with 300 mm freeboard above the 100 year ARI flood level. This is achieved by providing a bunded ramp access to the carpark and adopting the highest water level across the driveway and adding 300 mm freeboard, the bund level for the basement is set at 13.65 mAHd.

Essential Services – Substation and Communications

The substation is the most critical piece of infrastructure and the new City Plan immunity requirements reflect this. Due to the frontage length of the substation, the design water level varies considerably. To provide an adequate freeboard, a level of 14.5 mAHd is acceptable, with access to the substation room towards the eastern most side of the room.

The communications room is situated at 13.65m AHD, this level provides an acceptable level of freeboard.

Retail Areas

The retail areas and residents gym on Level 1 are sufficiently high enough to be unaffected by flood levels along Brunswick Street.

The 52m² retail area situated at 12.72mAHd will be accessed from the laneway terrace on the north-eastern corner of the retail area, accordingly this level provides an acceptable level of freeboard.

The 161m² retail area identified in Plate 1 below indicates the 50 year ARI water surface levels surrounding the proposed retail area in the south-western corner of the Central Village Phase 2 site on the corner of Brunswick and Water Streets. Due to the topography in this area, the predicted flood levels vary considerably. The red lines in Plate 1 indicate the predicted 50 year water levels. Entry to this retail area will be along Water Street from the eastern most point of the retail area (next to the fire evacuation corridor where the water level is indicated at 14.2m AHD). A complete set of floor plans for the Central Village Phase 2 site are included in the reference drawings section of this report.




Plate 1 – Central Village Phase 2 161m² Retail Area Floor Level

5 CONCLUSION

A mixed use development is proposed at Central Village Phase 2 situated on Lot 1 RP10553, Lots 11 and 12 RP10552, Lots 5, 6 and 13 RP81335 and Lot 102 SP143465 in Fortitude Valley, Brisbane. A flood study of the catchment draining to the site was conducted to determine the existing flood levels within and surrounding the site and the subsequent impact of development on flood levels.

The results of the TUFLOW model are presented in Appendix B and indicate that the proposed development does not adversely impact on properties within the vicinity of the subject site. The development generally results in a reduction in flood levels, with a localised increase in flood level predicted in the road reserve in Water Street. However, any increase in flood levels is limited to the road reserve and does not affect private property.

Furthermore, it was determined that the reason for the increase in flood levels is the widening of Water Street rather than the construction of the Central Village Phase 2 building itself. If the building were to be constructed to match the footprint of the existing building; calculations indicate there would be no increase in flood levels within the catchment. As the increase occurs in an area where the water depths both upstream and downstream are higher, it was concluded that the trafficability of the road and the flood hazard in Water Street would not be materially affected by the change in level.

It is therefore considered that the Central Village Phase 2 development will not result in unacceptable adverse impacts on flooding in the catchment and can proceed.

Figures

- Figure 1 Site Location
- Figure 2 RAFTS Water Street Catchment Delineation
- Figure 3 Pre-Development Model Topography Map
- Figure 4 Post-Development Model Topography Map




LEGEND:
 Site Boundary

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014

October 2014

Metro Property Development Pty Ltd
CAD FILE: G:\J11078\Turfow\Truncated\results\Respro\DE020\Figures - J11078-R4 RAFTS.dwg
XREFs: Turfow_Results, xr-DCDB 3503-18 2013 MGA94 zone56



Scale 1:15,000 (A3)
FIGURE 1
SITE LOCATION

Project No.: J11078

PRINT DATE: 02 October, 2014 - 3:17pm



LEGEND:


 Site Boundary

 Catchment Boundary and Label

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014

October 2014

Metro Property Development Pty Ltd
CAD FILE: 0:\J11078\Turf\Truncated\Results\Respro\DE020\Figures - J11078-R4 RAFTS.dwg
XREFs: Turf\Results, xr-DCDB 3503-18 2013 MGA94 zone56



Scale 1:7,500 (A3)

FIGURE 2

RAFTS WATER STREET CATCHMENT DELINEATION

Project No.: J11078

PRINT DATE: 02 October, 2014 - 3:17pm



LEGEND:

-  Phase 1 Boundary
-  Phase 2 Boundary
-  Reporting Nodes

RESULTS LEGEND:
Topography (mAHD)

-  Above 27.00
-  25.00 to 27.00
-  23.00 to 25.00
-  21.00 to 23.00
-  19.00 to 21.00
-  17.00 to 19.00
-  15.00 to 17.00
-  14.00 to 15.00
-  13.50 to 14.00
-  13.00 to 13.50
-  12.50 to 13.00
-  12.00 to 12.50
-  11.50 to 12.00
-  11.00 to 11.50
-  10.50 to 11.00
-  10.00 to 10.50
-  9.00 to 10.00
-  Below 9.00

© Cardno All Rights Reserved 2014.


Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Aerial imagery courtesy of Nearmap, 2014

October 2014

Metro Property Development Pty Ltd

CAD FILE: 0\J11078\Tuflow\Truncated\results\Respro\BA02\Figures - J11078 - Tuflow Results.dwg
XREFs: Tuflow_Results, xr-DCDB 3503-18 2013 MGA94 zone56, xr - J11078 2014 DCDB MGA94 256



Scale 1:1,250 (A3)
FIGURE 3
PRE-DEVELOPED MODEL TOPOGRAPHY MAP (BA02)

Project No.: J11078


PRINT DATE: 02 October, 2014 - 4:55pm



- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Topography (mAHD)
- Above 27.00
 - 25.00 to 27.00
 - 23.00 to 25.00
 - 21.00 to 23.00
 - 19.00 to 21.00
 - 17.00 to 19.00
 - 15.00 to 17.00
 - 14.00 to 15.00
 - 13.50 to 14.00
 - 13.00 to 13.50
 - 12.50 to 13.00
 - 12.00 to 12.50
 - 11.50 to 12.00
 - 11.00 to 11.50
 - 10.50 to 11.00
 - 10.00 to 10.50
 - 9.00 to 10.00
 - Below 9.00

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014



Scale 1:1,250 (A3)

FIGURE 4

POST-DEVELOPED MODEL TOPOGRAPHY MAP (DE02d)


October 2014

Metro Property Development Pty Ltd
CAD FILE: C:\Users\laurence.alian\AppData\Local\Temp\AcPublish_9400\Figures - J11078 - Tuflow Results.dwg
XREFs: Tuflow_Results, xr-DCDB 3503-18 2013 MGA94 zone56, xr - J11078 2014 DCDB MGA94 z56

Project No.: J11078


PRINT DATE: 02 October, 2014 - 4:28pm


Reference Drawings



PRELIMINARY

STAGE 4 - BASEMENT 2






PRELIMINARY

STAGE 4 - PODIUM 1

bureau proberts


CLIENT: METRO PROPERTY DEVELOPMENT
PROJECT: PROJECT WATERS - PHASE 2
ADDRESS: CORNER WATER & BRUNSWICK ST

SCALE: 1:200 [A1]
DATE: 19.11.14
PROJECT NO: 14037
PHASE: SD
DRAWING NUMBER: 2.03
REVISION: 9
19/11/2014 5:57:53 PM




PRELIMINARY

STAGE 4 - PODIUM 2



PRELIMINARY

STAGE 4 - LEVEL 1



PRELIMINARY

STAGE 4 - LEVEL 2



2014 5:58:06 PM



PRELIMINARY

STAGE 4 - LEVEL 4



STAGE 4 - LEVEL 5 TO 6




PRELIMINARY

STAGE 4 - LEVEL 7 (LANDSCAPE DECK)





STAGE 4
STAGE 5



PRELIMINARY


STAGE 4 - LEVEL 14 TO 20



STAGE 4
STAGE 5

9m SETBACK

STAGE 4
LEVEL 21 TO 23




STAGE 5A
BY DR

LIFTS

PRELIMINARY

STAGE 4 - LEVEL 21 TO 23

bureau[^]proberts


15 1



STAGE 4
STAGE 5


9m SETBACK


STAGE 4
LEVEL 25 TO 28





STAGE 4
STAGE 5






1 NORTHERN ELEVATION
2.07 1 : 200

bureau proberts

ELEVATION

CLIENT:
METRO PROPERTY DEVELOPMENT
PROJECT:
PROJECT WATERS - PHASE 2
ADDRESS:
CORNER WATER & BRUNSWICK ST

SCALE:
1 : 200 [A1]
DATE:
19.11.14
NORTH:
12
PROJECT NO:
14037
PHASE:
SD
DRAWING NUMBER:
3.01
REVISION:
1
2011/2014 1:44:25 AM




1 EASTERN ELEVATION
2.07 1:200

bureau proberts

ELEVATION

CLIENT: METRO PROPERTY DEVELOPMENT
PROJECT: PROJECT WATERS - PHASE 2
ADDRESS: CORNER WATER & BRUNSWICK ST

SCALE: 1:200 [A1]
DATE: 19.11.14
PROJECT NO: 14037
PHASE: SD
DRAWING NUMBER: 3.02
REVISION: 1
2011/2014 1:35:23 AM




1 SOUTHERN ELEVATION
2.07 1 : 200

bureau proberts

CLIENT: METRO PROPERTY DEVELOPMENT
PROJECT: PROJECT WATERS - PHASE 2
ADDRESS: CORNER WATER & BRUNSWICK ST

SCALE: 1 : 200 [A1]
DATE: 19.11.14
PROJECT NO: 14037
PHASE: SD
DRAWING NUMBER: 3.03
REVISION: 1
2011/2014 1:35:34 AM

ELEVATION



1 WESTERN ELEVATION
2.07 1:200

Appendix A


Pre-Developed TUFLOW Results



- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Water Surface Level (mAHd)
- Above 16.40
 - 16.00 to 16.40
 - 15.60 to 16.00
 - 15.20 to 15.60
 - 14.80 to 15.20
 - 14.40 to 14.80
 - 14.00 to 14.40
 - 13.60 to 14.00
 - 13.20 to 13.60
 - 12.80 to 13.20
 - 12.40 to 12.80
 - 12.00 to 12.40
 - 11.60 to 12.00
 - 11.20 to 11.60
 - 10.80 to 11.20
 - 10.40 to 10.80
 - 10.00 to 10.40
 - 9.60 to 10.00
 - 9.20 to 9.60
 - Below 9.20

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014



Scale 1:1,250 (A3)

FIGURE A.1.1


PRE-DEVELOPED Q100 WATER SURFACE LEVELS (BA02)




- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Water Surface Level (mAHd)
- Above 16.40
 - 16.00 to 16.40
 - 15.60 to 16.00
 - 15.20 to 15.60
 - 14.80 to 15.20
 - 14.40 to 14.80
 - 14.00 to 14.40
 - 13.60 to 14.00
 - 13.20 to 13.60
 - 12.80 to 13.20
 - 12.40 to 12.80
 - 12.00 to 12.40
 - 11.60 to 12.00
 - 11.20 to 11.60
 - 10.80 to 11.20
 - 10.40 to 10.80
 - 10.00 to 10.40
 - 9.60 to 10.00
 - 9.20 to 9.60
 - Below 9.20

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014



Scale 1:1,250 (A3)
FIGURE A.1.2
PRE-DEVELOPED Q50 WATER SURFACE LEVELS (BA02)




- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes


RESULTS LEGEND:
Depth (m)

- Above 1.25
- 1.00 to 1.25
- 0.90 to 1.00
- 0.80 to 0.90
- 0.70 to 0.80
- 0.60 to 0.70
- 0.50 to 0.60
- 0.40 to 0.50
- 0.35 to 0.40
- 0.30 to 0.35
- 0.25 to 0.30
- 0.20 to 0.25
- 0.15 to 0.20
- 0.10 to 0.15
- 0.05 to 0.10
- 0.01 to 0.05

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014



Scale 1:1,250 (A3)
FIGURE A.2.1
PRE-DEVELOPED Q100 WATER DEPTH (BA02)




- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

RESULTS LEGEND:
Depth (m)


- Above 1.25
- 1.00 to 1.25
- 0.90 to 1.00
- 0.80 to 0.90
- 0.70 to 0.80
- 0.60 to 0.70
- 0.50 to 0.60
- 0.40 to 0.50
- 0.35 to 0.40
- 0.30 to 0.35
- 0.25 to 0.30
- 0.20 to 0.25
- 0.15 to 0.20
- 0.10 to 0.15
- 0.05 to 0.10
- 0.01 to 0.05

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014

October 2014
Metro Property Development Pty Ltd
CAD FILE: D:\J11078\Tufrow\Truncated\Results\Respro\BA02\Figures - J11078 - Tufrow Results.dwg
XREFs: Tufrow_Results, xr-DCDB 3503-18 2013 MGA94 zone56, xr - J11078 2014 DCDB MGA94 256



Scale 1:1,250 (A3)
FIGURE A.2.2
PRE-DEVELOPED Q50 WATER DEPTH (BA02)



- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Speed (m/s)
- Above 3.50
 - 3.25 to 3.50
 - 3.00 to 3.25
 - 2.75 to 3.00
 - 2.50 to 2.75
 - 2.25 to 2.50
 - 2.00 to 2.25
 - 1.75 to 2.00
 - 1.50 to 1.75
 - 1.25 to 1.50
 - 1.00 to 1.25
 - 0.75 to 1.00
 - 0.50 to 0.75
 - 0.20 to 0.50
 - 0.10 to 0.20
 - Below 0.10


© Cardno All Rights Reserved 2014.

Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Aerial imagery courtesy of Nearmap, 2014

October 2014


Metro Property Development Pty Ltd
CAD FILE: D:\J11078\Turf\Truncated\Results\Respro\BA02\Figures - J11078 - Turflow Results.dwg
XREFs: Turflow_Results, xr-DCDB 3503-18 2013 MGA94, zone56, xr - J11078 2014 DCDB MGA94 256



Scale 1:1,250 (A3)
FIGURE A.3.1
PRE-DEVELOPED Q100 WATER SPEED (BA02)

Project No.: J11078


PRINT DATE: 02 October, 2014 - 4:56pm



- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Speed (m/s)
- Above 3.50
 - 3.25 to 3.50
 - 3.00 to 3.25
 - 2.75 to 3.00
 - 2.50 to 2.75
 - 2.25 to 2.50
 - 2.00 to 2.25
 - 1.75 to 2.00
 - 1.50 to 1.75
 - 1.25 to 1.50
 - 1.00 to 1.25
 - 0.75 to 1.00
 - 0.50 to 0.75
 - 0.20 to 0.50
 - 0.10 to 0.20
 - Below 0.10

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014



Scale 1:1,250 (A3)
FIGURE A.3.2
PRE-DEVELOPED Q50 WATER SPEED (BA02)

Appendix B


Post-Developed TUFLOW Results



- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Water Surface Level (mAHd)
- Above 16.40
 - 16.00 to 16.40
 - 15.60 to 16.00
 - 15.20 to 15.60
 - 14.80 to 15.20
 - 14.40 to 14.80
 - 14.00 to 14.40
 - 13.60 to 14.00
 - 13.20 to 13.60
 - 12.80 to 13.20
 - 12.40 to 12.80
 - 12.00 to 12.40
 - 11.60 to 12.00
 - 11.20 to 11.60
 - 10.80 to 11.20
 - 10.40 to 10.80
 - 10.00 to 10.40
 - 9.60 to 10.00
 - 9.20 to 9.60
 - Below 9.20

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014




Scale 1:1,250 (A3)
FIGURE B.1.1
POST-DEVELOPED Q100 WATER SURFACE LEVELS (DE02d)





- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Water Surface Level (mAHD)
- Above 16.40
 - 16.00 to 16.40
 - 15.60 to 16.00
 - 15.20 to 15.60
 - 14.80 to 15.20
 - 14.40 to 14.80
 - 14.00 to 14.40
 - 13.60 to 14.00
 - 13.20 to 13.60
 - 12.80 to 13.20
 - 12.40 to 12.80
 - 12.00 to 12.40
 - 11.60 to 12.00
 - 11.20 to 11.60
 - 10.80 to 11.20
 - 10.40 to 10.80
 - 10.00 to 10.40
 - 9.60 to 10.00
 - 9.20 to 9.60
 - Below 9.20

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014



Scale 1:1,250 (A3)
FIGURE B.1.2
POST-DEVELOPED Q50 WATER SURFACE LEVELS (DE02d)



LEGEND:

- Phase 1 Boundary
- Phase 2 Boundary

RESULTS LEGEND:
Water Surface Level (mAHD)

- Above 16.40
- 16.00 to 16.40
- 15.60 to 16.00
- 15.20 to 15.60
- 14.80 to 15.20
- 14.40 to 14.80
- 14.00 to 14.40
- 13.60 to 14.00
- 13.20 to 13.60
- 12.80 to 13.20
- 12.40 to 12.80
- 12.00 to 12.40
- 11.60 to 12.00
- 11.20 to 11.60
- 10.80 to 11.20
- 10.40 to 10.80
- 10.00 to 10.40
- 9.60 to 10.00
- 9.20 to 9.60
- Below 9.20

© Cardno All Rights Reserved 2014.

Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.


Aerial imagery courtesy of Nearmap, 2014

October 2014

Metro Property Development Pty Ltd

CAD FILE: 0\J11078\Tuflow\Truncated\Results\Respro\DE02d\Figures - J11078 - Tuflow Results.dwg

XREFs: Tuflow_Results, xr-DCDB 3503-18 2013 MGA94 zone56; xr - J11078 2014 DCDB MGA94 156



POST-DEVELOPED Q100 WATER SURFACE LEVELS WITH 100mm CONTOURS (DE02d)

Scale 1:400 (A3)

FIGURE B.1.3

Project No.: J11078

PRINT DATE: 02 October, 2014 - 4:49pm



LEGEND:

- Phase 1 Boundary
- Phase 2 Boundary


RESULTS LEGEND:
Water Surface Level (mAHd)

- Above 16.40
- 16.00 to 16.40
- 15.60 to 16.00
- 15.20 to 15.60
- 14.80 to 15.20
- 14.40 to 14.80
- 14.00 to 14.40
- 13.60 to 14.00
- 13.20 to 13.60
- 12.80 to 13.20
- 12.40 to 12.80
- 12.00 to 12.40
- 11.60 to 12.00
- 11.20 to 11.60
- 10.80 to 11.20
- 10.40 to 10.80
- 10.00 to 10.40
- 9.60 to 10.00
- 9.20 to 9.60
- Below 9.20

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014


October 2014

Metro Property Development Pty Ltd
CAD FILE: 0\J11078\Tuflow\Truncated\Results\Respro\DE02d\Figures - J11078 - Tuflow Results.dwg
XREFs: Tuflow_Results, xr-DCDB 3503-18 2013 MGA94 zone56; xr - J11078 2014 DCDB MGA94 156



POST-DEVELOPED Q50 WATER SURFACE LEVELS WITH 100mm CONTOURS (DE02d)

Scale 1:400 (A3)
FIGURE B.1.4
Project No.: J11078
PRINT DATE: 02 October, 2014 - 4:49pm



LEGEND:

- Phase 1 Boundary
- Phase 2 Boundary
- His13 Reporting Nodes

RESULTS LEGEND:
Depth (m)

- Above 1.25
- 1.00 to 1.25
- 0.90 to 1.00
- 0.80 to 0.90
- 0.70 to 0.80
- 0.60 to 0.70
- 0.50 to 0.60
- 0.40 to 0.50
- 0.35 to 0.40
- 0.30 to 0.35
- 0.25 to 0.30
- 0.20 to 0.25
- 0.15 to 0.20
- 0.10 to 0.15
- 0.05 to 0.10
- 0.01 to 0.05

© Cardno All Rights Reserved 2014.

Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Aerial imagery courtesy of Nearmap, 2014

October 2014

Metro Property Development Pty Ltd



CAD FILE: G:\J11078\Turf\Truncated\results\Respro\DE02d\Figures - J11078 - Turf Results.dwg
XREFs: Turf_Results, xr-DCDB 3503-18 2013 MGA94, zone56; xr - J11078 2014 DCDB MGA94, zone56

12.5 0 12.5 25.0 37.5 50.0 62.5m 1:1250

Scale 1:1,250 (A3)
FIGURE B.2.1
POST-DEVELOPED Q100 WATER DEPTH (DE02d)

Project No.: J11078

PRINT DATE: 02 October, 2014 - 4:49pm



- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

RESULTS LEGEND:
Depth (m)

- Above 1.25
- 1.00 to 1.25
- 0.90 to 1.00
- 0.80 to 0.90
- 0.70 to 0.80
- 0.60 to 0.70
- 0.50 to 0.60
- 0.40 to 0.50
- 0.35 to 0.40
- 0.30 to 0.35
- 0.25 to 0.30
- 0.20 to 0.25
- 0.15 to 0.20
- 0.10 to 0.15
- 0.05 to 0.10
- 0.01 to 0.05

© Cardno All Rights Reserved 2014.

Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.


Aerial imagery courtesy of Nearmap, 2014

October 2014

Metro Property Development Pty Ltd

CAD FILE: 0\J11078\Truncated\results\Respro\DE02d\Figures - J11078 - Tuflow Results.dwg



XREFs: Tuflow_Results, xr-DCDB 3503-18 2013 MGA94, zone56; xr - J11078 2014 DCDB MGA94, zone56



Scale 1:1,250 (A3)
FIGURE B.2.2
POST-DEVELOPED Q50 WATER DEPTH (DE02d)

Project No.: J11078


PRINT DATE: 02 October, 2014 - 4:50pm




- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Speed (m/s)
- Above 3.50
 - 3.25 to 3.50
 - 3.00 to 3.25
 - 2.75 to 3.00
 - 2.50 to 2.75
 - 2.25 to 2.50
 - 2.00 to 2.25
 - 1.75 to 2.00
 - 1.50 to 1.75
 - 1.25 to 1.50
 - 1.00 to 1.25
 - 0.75 to 1.00
 - 0.50 to 0.75
 - 0.20 to 0.50
 - 0.10 to 0.20
 - Below 0.10

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014



Scale 1:1,250 (A3)
FIGURE B.3.1
POST-DEVELOPED Q100 WATER SPEED (DE02d)



LEGEND:

-  Phase 1 Boundary
-  Phase 2 Boundary
-  Reporting Nodes

RESULTS LEGEND:
Speed (m/s)

-  Above 3.50
-  3.25 to 3.50
-  3.00 to 3.25
-  2.75 to 3.00
-  2.50 to 2.75
-  2.25 to 2.50
-  2.00 to 2.25
-  1.75 to 2.00
-  1.50 to 1.75
-  1.25 to 1.50
-  1.00 to 1.25
-  0.75 to 1.00
-  0.50 to 0.75
-  0.20 to 0.50
-  0.10 to 0.20
-  Below 0.10

© Cardno All Rights Reserved 2014.


Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Aerial imagery courtesy of Nearmap, 2014

October 2014

Metro Property Development Pty Ltd

CAD FILE: D:\J11078\Turfow\Truncated\results\Respro\DE02d\Figures - J11078 - Turflow Results.dwg
XREFs: Turflow_Results, xr-DCDB 3503-18 2013 MGA94, zone56; xr - J11078 2014 DCDB MGA94, 156



Scale 1:1,250 (A3)

FIGURE B.3.2

POST-DEVELOPED Q50 WATER SPEED (DE02d)

Project No.: J11078

PRINT DATE: 02 October, 2014 - 4:50pm




- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Impact (mm)
- Above 150
 - 100 to 150
 - 50 to 100
 - 25 to 50
 - 10 to 25
 - 25 to -10
 - 50 to -25
 - 100 to -50
 - 150 to -100
 - Below -150

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014

October 2014
Metro Property Development Pty Ltd
CAD FILE: 0\J11078\Truncated\Results\Respro\DE02d\Figures - J11078 - Tuflow Results.dwg
XREFs: Tuflow_Results, xr-DCDB 3503-18 2013 MGA94, zone56; xr - J11078 2014 DCDB MGA94, z56




Scale 1:1,250 (A3)
FIGURE B.4.1
POST-DEVELOPED Q100 IMPACT (DE02d)



- LEGEND:
- Phase 1 Boundary
 - Phase 2 Boundary
 - His13 Reporting Nodes

- RESULTS LEGEND:
Impact (mm)
- Above 150
 - 100 to 150
 - 50 to 100
 - 25 to 50
 - 10 to 25
 - 25 to -10
 - 50 to -25
 - 100 to -50
 - 150 to -100
 - Below -150

© Cardno All Rights Reserved 2014.
Copyright in the whole and every part of this drawing belongs to Cardno and may not be used, sold, transferred, copied or reproduced in whole or in part in any manner or form or on any media, to any person other than by agreement with Cardno. This document is produced by Cardno solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.
Aerial imagery courtesy of Nearmap, 2014



Scale 1:1,250 (A3)
FIGURE B.4.2
POST-DEVELOPED Q50 IMPACT (DE02d)