


**BULK EARTHWORKS AND SHORING PLAN**

1:200

NOTE: - REFER TO ARCHITECT'S DRAWINGS FOR SETOUT OF GRIDS

SHORING WALL DESIGN SURCHARGE LOADS

1:125

NOTES

1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING 6005

DESIGN LOADS

AREA	SUPERIMPOSED DEAD LOAD	LIVE LOAD

CONCRETE

ALL WORKMANSHIP, MATERIALS & TESTING SHALL BE IN ACCORDANCE WITH AS 3600 EXCEPT AS VARIED BY THE CONTRACT DOCUMENTS AND SPECIFICATION. ALL CONCRETE COMPONENTS SHALL BE NORMAL CLASS WITH A 28 DAY COMPRESSIVE STRENGTH OF 32MPa (or N32) EXCEPT WHERE VARIED BY THE TABLE BELOW:-

COMPONENT	STRENGTH
BORED PIERS	S40
CAPPING BEAM	N40
SPRAYCRETE	S32

DD

N DENOTES NORMAL CLASS CONCRETE WITH THE FOLLOWING PROPERTIES U.N.O.

MAXIMUM AGGREGATE SIZE - 20mm

SLUMP - 80mm ±15

TESTING TYPE - PROJECT ASSESSMENT

S DENOTES SPECIAL CLASS CONCRETE WITH 650 MICROSTRAIN

MAXIMUM SHRINKAGE AS PER THE CONCRETE SPECIFICATION U.N.O.

S32(1) - DENOTES SPECIAL CLASS CONCRETE WITH 650 MICROSTRAIN

MAXIMUM SHRINKAGE CONTROL AND HIGH EARLY STRENGTH TO SUIT POST TENSIONING.

EXCAVATION AND SHORING NOTES

1. REFER TO THE EARTHWORKS AND SHORING SPECIFICATION FOR ALL REQUIREMENTS.

2. PRIOR TO COMMENCEMENT OF EXCAVATION LOCATE ALL EXISTING SERVICES WITHIN AND ADJACENT TO THE SITE.

3. ALL EXCAVATION AND SHORING DETAILS SHOWN IN THE DRAWINGS ARE PROVISIONAL AND TO BE CONFIRMED, VERIFIED AND CERTIFIED ON SITE BY AN APPROVED GEOTECHNICAL ENGINEER ENGAGED BY THE EARTHWORKS AND SHORING SUB-CONTRACTOR.

4. WHERE SITE CONDITIONS REQUIRE CHANGES TO THE SHORING DESIGN SHOWN IN THE DOCUMENTS THE CONTRACTOR SHALL SUBMIT TO THE MANAGING CONTRACTOR THE GEOTECHNICAL ENGINEERS FORM 15 COVERING THE DESIGN CHANGES AND FORM 16 CERTIFICATION FOR THE ENTIRE WORKS.

5. THE ROCK LEVELS SHOWN ON PLAN ARE APPROXIMATE AND INDICATIVE ONLY AND ARE TO BE VERIFIED ON SITE BY THE GEOTECHNICAL ENGINEER. REFER TO THE GEOTECHNICAL INVESTIGATION FOR A DETAILED DESCRIPTION OF THE ANTICIPATED SUBSURFACE PROFILE AS WELL AS POTENTIAL CONTAMINATED SOIL REQUIREMENTS.

6. ENSURE THAT ALL INSTALLED SHORING WALLS AND ANCHORS DO NOT DAMAGE ADJACENT ABOVE AND BELOW GROUND STRUCTURES AND SERVICES.

7. VIBRATION AND MOVEMENT MONITORING MUST BE UNDERTAKEN FROM THE COMMENCEMENT OF WORKS IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION AND RESULTS REGULARLY REPORTED TO THE MANAGING CONTRACTOR.

8. THE CONTRACTOR SHALL PROVIDE BOTH PRE AND POST CONSTRUCTION CCTV SURVEY OF ALL PILE LINES AND DRAINAGE STRUCTURES ADJACENT TO THE SITE.

9. STAGED EXCAVATION SHALL BE UNDERTAKEN IN ACCORDANCE WITH THE DOCUMENTATION UNLESS OTHERWISE APPROVED BY THE GEOTECHNICAL ENGINEER.

10. EARTH RAMPING INTO THE SITE FOR CONSTRUCTION ACCESS SHALL BE TO THE GEOTECHNICAL ENGINEERS APPROVAL ON SITE.

LEGEND

SW1 - DENOTES 900 DIAMETER ANCHORED PIERS AT 2400 MAXIMUM CENTRES.
 SW2 - DENOTES 900 DIAMETER ANCHORED PIERS AT 2400 MAXIMUM CENTRES.
 SW3 - DENOTES 900 DIAMETER CANTILEVER PIERS AT 1800 MAXIMUM CENTRES.
 SW4 - DENOTES 900 DIAMETER CANTILEVER PIERS AT 900 CENTRES.
 SW5 - DENOTES 900 DIAMETER CANTILEVER PIERS AT 1800 MAXIMUM CENTRES.
 SW6 - DENOTES 900 DIAMETER ANCHORED PIERS AT 2400 MAXIMUM CENTRES.
 SW7 - DENOTES 900 DIAMETER ANCHORED PIERS AT 2400 MAXIMUM CENTRES.

BP1# - DENOTES BORED PIER SETOUT IS GOVERNED BY THE FUTURE BUILDING STRUCTURE (COLUMNS AND WALLS) ABOVE GROUND FLOOR. REFER TO THE GROUND FLOOR PLAN ON DRAWING C-310-6070.

BEL - DENOTES BULK EXCAVATION LEVEL.




© Cardno Limited All Rights Reserved.
 This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn KBA	Date	Client RNA & LEND LEASE	Status PRELIMINARY
Checked KBA	Date	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK	NOT TO BE USED FOR CONSTRUCTION PURPOSES
Designed DRV	Date	Title BULK EARTHWORKS AND SHORING PLAN	Datum Date Scale Size A1
Verified MVH	Date		Drawing Number 161163-050-DD-C-301-6030
Approved	Date		Revision C



DATE PLOTTED: 31/07/2015 8:33:17 AM

MODEL PATH: C:\Temp\Roads\10597_ST_RVT_2015_kad.allen.rvt



NOTES

1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING 6005



PLANS AND DOCUMENTS
referred to in the PDA APPROVAL


14 OCT 2015

MEDQ






Rev	Date	Des.	Ver.	Appr.
B	31.07.2015	EDQ SUBMISSION		
A	13.07.2015	PRELIMINARY ISSUE		



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn KA	Date	Client RNA & LEND LEASE
Checked KA	Date	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Designed DRV	Date	Title SHORING ELEVATIONS - SHEET 1
Verified MVH	Date	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES
Approved	Date	Datum Date Scale Size A1
MVH	Date	Drawing Number 161163-050-DD-C-301-6035 Revision B

SECTION 4
1:100SECTION 6
1:100

NOTES

- FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING 6005
- REFER TO EARTHWORKS SPECIFICATION FOR ALL REQUIREMENTS IN RELATION TO EARTHWORKS AND SHORING.


PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015




MEDQ



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.





Drawn KA	Date	Client RNA & LEND LEASE
Checked KA	Date	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Designed DRV	Date	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES
Verified MVH	Date	Datum
Approved	Date	Date
	Date	Scale
	Date	Size A1
	Date	Drawing Number 161163-050-DD-C-301-6040
	Date	Revision B
	Date	SHORING SECTION - SHEET 1




ANCHORED PIERED WALL EXCAVATION & INSTALLATION METHOD

NOTE: THE NUMBER OF BENCHING LEVELS SHOWN IS INDICATIVE ONLY AND IS TO BE CONFIRMED ON SITE BY THE GEOTECHNICAL ENGINEER.



ALL ANCHORS ARE REQUIRED TO CLEAR THE CLEM 7 TUNNEL EXCLUSION ZONE




NOTES:

1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING C301-6045
2. REFER TO EARTHWORKS SPECIFICATION FOR ALL REQUIREMENTS IN RELATION TO EARTHWORKS AND SHORING.
1. FIXED LENGTH = BOND LENGTH REQUIRED TO PROVIDE WORKING LOAD
2. FOR TENDER PURPOSES, PROVISIONAL BOND LENGTHS ARE TO BE BASED ON THE FOLLOWING AND SUBJECT TO CONFIRMATION ON SITE BY THE GEOTECHNICAL ENGINEER.
 - ULTIMATE BOND STRENGTH OF 350kPa FOR XW ROCK.
 - TEMPORARY ROCK ANCHORS TO BE ANCHORED INTO ATLEAST XW ROCK.
3. FOR TENDER PURPOSES ALLOW FOR AN AVERAGE FREE LENGTH OF 10m TO BE CONFIRMED ON SITE TO THE GEOTECHNICAL ENGINEERS APPROVAL

TEMPORARY ANCHOR TESTING

1. REFER TO ANCHOR SPECIFICATION FOR ALL TESTING REQUIREMENTS.
2. A MINIMUM OF 10% ANCHORS ARE TO BE ACCEPTANCE TESTED.
3. ANCHORS TO BE TESTED ARE TO BE NOMINATED BY THE GEOTECHNICAL ENGINEER.
4. GROUT CUBE SAMPLES ARE TO BE TAKEN FOR TESTING ON EACH BATCH OF GROUT.
5. TEST RECORDS MUST BE SUPPLIED TO THE GEOTECHNICAL ENGINEER PROGRESSIVELY AND PRIOR TO COMMENCING EXCAVATION FOR THE NEXT PANEL STAGE.

TEMPORARY ROCK ANCHOR LENGTH DIAGRAM



NOTES

1. ALL ROCK ANCHORS TO BE 15.2mm SUPERGRADE STRESS RELIEVED LOW RELAXATION STRANDS WITH THE NUMBER OF STRANDS AS NOTED IN THE DETAIL SECTIONS.
2. THE SAFE WORKING LOAD OF EACH STRAND IS TO BE 150 kN.
3. PROVIDE CENTRALISERS TO STRANDS AT 2.5m MAXIMUM CENTRES AND WITHIN 300mm OF ENDS TO ENSURE A MINIMUM GROUT COVER OF 25mm IS PROVIDED.
4. ALL ANCHORS ARE TO BE SECONDARY GROUTED AFTER STRESSING AND WILL NOT REQUIRE DESTRESSING.

TYPICAL TEMPORARY ROCK ANCHOR DETAIL

1:10

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Cardno
Shaping the Future

Cardno (QLD) Pty Ltd ABN 57 051 074 992
LEVEL 11, 515 St Paul's Terrace
Fortitude Valley, QLD 4006
Tel: 07 3369 9822 Fax: 07 3369 9722
Email: brisbane@cardno.com.au Web: www.cardno.com.au

Drawn
KA
Checked
KA
Designed
DRV
Verified
MVH
Approved
MVH

Date Client **RNA & LEND LEASE**

Date Project **RNA SHOWGROUND REDEVELOPMENT
STORMWATER DETENTION TANK**

Date Title

Date

Date **SHORING DETAILS - SHEET 1**


Status **PRELIMINARY**
NOT TO BE USED FOR CONSTRUCTION PURPOSES

Datum Date Scale Size **A1**

Drawing Number **161163-050-DD-C-301-6045** Revision **C**

Rev	Date	Description	Des	Ver	Appr
C	31.07.2015	EDO SUBMISSION			
B	14.07.2015	PRELIMINARY ISSUE			
A	13.07.2015	PRELIMINARY ISSUE			

- NOTES:**
1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING C301-6005
 2. REFER TO EARTHWORKS SPECIFICATION FOR ALL REQUIREMENTS IN RELATION TO EARTHWORKS AND SHORING.



CANTILEVER PIERED WALL EXCAVATION & INSTALLATION METHOD

NOTE: THE NUMBER OF BENCHING LEVELS SHOWN IS INDICATIVE ONLY AND IS TO BE CONFIRMED ON SITE BY THE GEOTECHNICAL ENGINEER

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL


14 OCT 2015

MEDQ


Rev	Date	Des	Ver	Appr
B	31.07.2015	EDQ SUBMISSION		
A	13.07.2015	PRELIMINARY ISSUE		



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn KA	Date	Client RNA & LEND LEASE
Checked KA	Date	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Designed DRV	Date	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES
Verified MVH	Date	Datum
Approved	Date	Scale
M/H	Date	Size A1
		Drawing Number 161163-050-DD-C-301-6046
		Revision B
		SHORING DETAILS - SHEET 2




TYPICAL SHORING WALL DETAILS
1:20


SHORING WALL DESIGN PARAMETERS AND ASSUMPTIONS					
SHORING WALL DESIGNATION	WALL TYPE	PIER SIZE AND SPACING	ASSUMED LEVEL OF DW ROCK	PROVISIONAL PIER FOUNDING DEPTH	PIER MAXIMUM FOUNDING RL
SW1	ANCHORED PIERS	900 DIA @2400CRS	VARIES FROM RL 4.0 TO RL 5.0	RL 1.0	RL 1.0
SW2	ANCHORED PIERS	900 DIA @2400CRS	VARIES FROM RL 4.0 TO RL 5.0	RL 1.6	RL 1.6
SW3	CANTILEVER PIERS	900 DIA @1800CRS	RL 3.0	RL -2.0	-
SW4	CANTILEVER PIERS	900 DIA @900CRS	RL -3.6	RL -9.0	-
SW5	CANTILEVER PIERS	900 DIA @1800CRS	RL 1.0	RL -5.0	-
SW6	ANCHORED PIERS	900 DIA @2400CRS	RL 1.0	RL 0.0	RL 0.0
SW7	ANCHORED PIERS	900 DIA @2400CRS	RL 1.0	RL 0.0	RL 0.0

NOTES


1. ASSUMED BORED PIER GEOTECHNICAL DESIGN PARAMETERS FOR DISTINCTLY WEATHERED ROCK AS FOLLOWS:
ULTIMATE SHAFT FRICTION - 900kPa
ULTIMATE END BEARING - 9000kPa
2. ALL DESIGN PARAMETERS, ASSUMPTIONS AND BORED PIER FOUNDING RL'S TO BE CONFIRMED ON SITE BY THE GEOTECHNICAL ENGINEER.
3. REFER TO DRAWING C-301-6030 FOR DESIGN SURCHARGE LOAD PARAMETERS.
4. THE PIER MAXIMUM FOUNDING RL IS TO ENSURE THE PIERS DO NOT ENCR OACH WITHIN THE CLEM 7 TUNNEL EXCLUSION ZONE.




TYPICAL PIER/CAPPING BEAM DETAILS
1:20



TYPICAL SHORING WALL CAPPING BEAM CORNER DETAIL
1:20



TYPICAL SHORING WALL CAPPING BEAM STEP DETAIL
1:20



TYPICAL Ø900 CONTIGUOUS PIER DETAIL


PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ

NOTES:

1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING C301-6005
2. REFER TO EARTHWORKS SPECIFICATION FOR ALL REQUIREMENTS IN RELATION TO EARTHWORKS AND SHORING.




TYPICAL Ø900 PIER & SPRAYCRETE PANEL DETAILS


SECTION 1
1:20



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn K/A	Date	Client RNA & LEND LEASE
Checked K/A	Date	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Designed DRV	Date	Status PRELIMINARY
Verified M/H	Date	Datum
Approved	Date	Scale
M/H	Date	Size A1
		Revision B
		Drawing Number 161163-050-DD-C-301-6047
		SHORING DETAILS - SHEET 3



PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ

Rev	Date	Description	Des	Verif	Appd
B	31/07/2015	EDQ SUBMISSION	ZA	DS	MH
A	24/07/2015	PRELIMINARY ISSUE	ZA	DS	MH

© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Cardno
Shaping the Future


Cardno (Old) Pty Ltd | ABN 57 051 074 992
Level 11, 515 St Paul's Terrace
Fortitude Valley, QLD 4006
Tel: 07 3369 9822 Fax: 07 3369 9722
Web: www.cardno.com.au

Drawn	ZA	Date	JULY 2015
Checked	DS	Date	JULY 2015
Designed	ZA	Date	JULY 2015
Verified		Date	
Approved			

Client	RNA & LENDLEASE
Project	RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Title	SITE PLAN

Status	PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES		
DATUM	A.H.D.	Scale	AS SHOWN
Drawing Number	161163-050-CD-C-301-6008	Size	A1
Revision			B

DATE PLOTTED: 21 August 2015 3:37 PM BY: ZAID ALALI



STORMWATER DRAINAGE NOTES

1. ALL INTERNAL STORMWATER DRAINAGE SHALL COMPLY WITH AS3500 1998 NATIONAL PLUMBING AND DRAINAGE CODE.
2. ALL EXTERNAL STORMWATER DRAINAGE SHALL COMPLY WITH QUDM AND BRISBANE CITY COUNCIL STANDARDS AND SPECIFICATIONS.
3. MAINTAIN AND PROTECT EXISTING SERVICES TO BE RETAINED.
4. STORMWATER STRUCTURES AND CONNECTIONS ARE TO BE LOCATED AS INDICATED ON THE PLAN. ADJUSTMENTS TO THE DESIGN LAYOUT WHERE REQUIRED TO SUIT ACTUAL AS-CONSTRUCTED GEOMETRY SHALL REQUIRE THE ENGINEERS APPROVAL.
5. INTERMEDIATE CONNECTIONS OF DOWNPIPES ON DRAINLINES
A) LESS THAN 225Ø OBLIQUE JUNCTIONS;
B) IF GREATER THAN 225 CONNECTIONS SHALL BE SLOPED SADDLE CONNECTIONS.
6. TRENCH EXCAVATIONS FOR DRAINAGE SHALL COMPLY WITH WORKPLACE HEALTH AND SAFETY REQUIREMENTS.
7. PIPES SHALL BE BEDDED IN ACCORDANCE WITH AS3725-H1.
8. ALL PIPES SHALL BE RUBBER RING JOINTED.
9. PIPES EQUAL TO OR SMALLER THAN 225Ø SHALL BE uPVC, RCP OR FRC. PIPES GREATER THAN 225Ø SHALL BE RCP OR FRC.
10. uPVC PIPES SHALL BE CLASS SN8 UNLESS NOTED OTHERWISE. RCP AND FRC PIPES SHALL BE CLASS 3 UNLESS NOTED OTHERWISE.
11. SPOIL MATERIAL GENERATED FROM TRENCH EXCAVATION IS TO BE DISPOSED OF OFF SITE.
12. ALL STORMWATER TRENCHES SHALL BE BACKFILLED IN ACCORDANCE WITH BCC STANDARDS AND SPECIFICATION.
13. COMPACTION TESTING IS TO BE CARRIED OUT AT THE SPECIFIED FREQUENCY BY A N.A.T.A. REGISTERED GEOTECHNICAL TESTING AUTHORITY AT THE CONTRACTORS COST. THE CONTRACTOR SHALL PROVIDE DETAILS OF ALL TESTING TO THE ENGINEER PROGRESSIVELY THROUGH THE WORKS AND NOTIFY THE ENGINEER OF ANY NON-COMFORMANCES. ALL NON CONFORMING WORK IS TO BE RECTIFIED AS DIRECTED BY THE ENGINEER.
14. ALL OBLIQUE BRANCHES TO BE 150Ø U.N.O. AND CONSIST OF OBLIQUE APPROVED BRANCH FITTINGS OR SADDLES AS APPROPRIATE AND WITH APPROVED SCREW ON OR CLIP ON CAPS.
15. ALL DRAINAGE STRUCTURES ARE TO HAVE HALF HEIGHT BENCHING.
16. ALL PIPE STUBS ARE TO BE FITTED WITH HARDBOARD PLANKS TO SEAL OFF END OF PIPE AND BACKFILLED.

STORMWATER DRAINAGE STRUCTURE NOTES:

1. ALL DIMENSIONS PROVIDED ON STRUCTURE DETAILS ARE IN MILLIMETRES.
2. SETOUT POINTS GIVEN FOR ALL STORMWATER STRUCTURES ARE TO THE CENTER OF THE CHAMBER. FINISHED SURFACE LEVELS NOMINATED FOR:
2.1. ROADWAY GULLIES ARE AT THE ADJACENT LIP OF KERB;
2.2. FIELD INLETS ARE AT THE TOP OF THE GRATE;
2.3. ACCESS CHAMBERS ARE AT THE TOP OF THE ACCESS COVER.
3. THE USE OF PRECAST COMPONENTS SHALL BE IN ACCORDANCE WITH THE RELEVANT AUTHORITY'S APPROVED PRODUCT LIST AND SUBJECT TO THE ENGINEERS APPROVAL.
4. CONCRETE CLASS TO BE AS FOLLOWS:
- UNREINFORCED STRUCTURES N25
- REINFORCED STRUCTURES AS PER STRUCTURE DETAILS.
5. PROVIDE WEEPHOLES IN ACCORDANCE WITH DETAIL SHOWN. IN THE UPSTREAM FACE OF ALL DRAINAGE STRUCTURES TO DRAIN UPSTREAM BEDDING IN TRENCHES.
6. ALL PIPE ENDS ARE TO BE RENDERED FLUSH WITH THE INSIDE FACE OF DRAINAGE STRUCTURES WITH A MINIMUM 50mm COVER TO STEEL REINFORCEMENT.
7. JOINTS BETWEEN PRECAST UNITS ARE TO BE COMPLETELY SEALED USING A METHOD APPROVED BY THE ENGINEER.
8. BASES OF ALL DRAINAGE STRUCTURES ARE TO BE BENCHD SMOOTHLY UP TO HALF HEIGHT OF PIPES (SPRING LINE).
9. STEP IRONS/ACCESS LADDERS ARE TO BE PROVIDED TO ALL ACCESS CHAMBERS DEEPER THAN 850mm IN ACCORDANCE WITH BRISBANE CITY COUNCIL STANDARDS. STEP IRONS SHALL BE INSTALLED IN ACCORDANCE WITH AS1657.
10. COVERS AND GRATES TO BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.

CONTRACTOR TO CONFIRM LOCATION OF EXISTING SERVICES PRIOR TO COMMENCEMENT OF WORKS

WARNING!
BEWARE OF UNDERGROUND SERVICES
THE LOCATIONS OF UNDERGROUND SERVICES HAVE BEEN INTERPOLATED FROM GIS DATA OR KNOWN POSITIONS OF VALVES, MANHOLES ETC. OR INFORMATION SUPPLIED BY SERVICE AUTHORITIES. NO RESPONSIBILITY IS TAKEN FOR THE ACCURACY OF THE INTERPOLATED INFORMATION SUPPLIED. ENSURE ALL SERVICES ARE ACCURATELY LOCATED PRIOR TO COMMENCEMENT OF WORK.

COORDINATION OF ALL SERVICES IS TO BE CARRIED OUT BY CONTRACTOR PRIOR TO CONSTRUCTION.
CONTRACTOR TO UNDERTAKE ALL NECESSARY SERVICE RELOCATIONS / DIVERSIONS REQUIRED TO CONSTRUCT THE PROPOSED WORKS

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ

0 5 10 15 20 25m
SCALE: 1:250 @A1

XREF: XA10697-063, CIVIL DESIGN, XA10697-063, SURVEY, XA10697-063, STRUC
CAD File: XA10697-063, Civil & Structural, XA10697-063, 181163-050-CD-C-301-6020.dwg

Rev.	Date	Description	Des.	Verif.	Appd.
C	21/08/2015	EDQ SUBMISSION	ZA	DS	MH
B	31/07/2015	EDQ SUBMISSION	ZA	DS	MH
A	13/07/2015	PRELIMINARY ISSUE	ZA	DS	MH


© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Cardno
Shaping the Future
Cardno (Qld) Pty Ltd | ABN 57 051 074 992
Level 11, 515 St Paul's Terrace
Fortitude Valley, QLD 4006
Tel: 07 3369 9822 Fax: 07 3369 9722
Web: www.cardno.com.au

Drawn ZA	Date JULY 2015	Client RNA & LENDLEASE
Checked DS	Date JULY 2015	Project RNA SHOWGROUND REDEVELOPMENT
Designed ZA	Date JULY 2015	Stormwater Detention Tank
Verified	Date	
Approved	Date	

Title STORMWATER DRAINAGE LAYOUT PLAN		Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES
DATUM A.H.D.	Scale AS SHOWN	Size A1
Drawing Number 161163-050-CD-C-301-6020	Revision C	

LINE 37



1. ALL DIMENSIONS PROVIDED ON STRUCTURE DETAILS ARE IN MILLIMETRES.
2. SETOUT POINTS GIVEN FOR ALL STORMWATER STRUCTURES ARE TO THE CENTER OF THE CHAMBER. FINISHED SURFACE LEVELS NOMINATED FOR:
 - 2.1. ROADWAY GULLIES ARE AT THE ADJACENT LIP OF KERB;
 - 2.2. FIELD INLETS ARE AT THE TOP OF THE GRATE;
 - 2.3. ACCESS CHAMBERS ARE AT THE TOP OF THE ACCESS COVER.
3. THE USE OF PRECAST COMPONENTS SHALL BE IN ACCORDANCE WITH THE RELEVANT AUTHORITY'S APPROVED PRODUCT LIST AND SUBJECT TO THE ENGINEERS APPROVAL.
4. CONCRETE CLASS TO BE AS FOLLOWS:
 - UNREINFORCED STRUCTURES N25
 - REINFORCED STRUCTURES N32.
5. PROVIDE WEEPHOLES IN ACCORDANCE WITH DETAIL SHOWN, IN THE UPSTREAM FACE OF ALL DRAINAGE STRUCTURES TO DRAIN UPSTREAM BEDDING IN TRENCHES.
6. ALL PIPE ENDS ARE TO BE RENDERED FLUSH WITH THE INSIDE FACE OF DRAINAGE STRUCTURES WITH A MINIMUM 50mm COVER TO STEEL REINFORCEMENT.
7. JOINTS BETWEEN PRECAST UNITS ARE TO BE COMPLETELY SEALED USING A METHOD APPROVED BY THE ENGINEER.
8. BASES OF ALL DRAINAGE STRUCTURES ARE TO BE BENCHED SMOOTHLY UP TO HALF HEIGHT OF PIPES (SPRING LINE).
9. STEP IRONS ARE TO BE PROVIDED TO ALL ACCESS CHAMBERS DEEPER THAN 850mm. STEP IRONS SHALL BE INSTALLED IN ACCORDANCE WITH AS1657.
10. COVERS AND GRATES TO BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.

Drawn ZA		Date JULY 2015	Client RNA & LENDLEASE					
Checked DS		Date JULY 2015						
Designed ZA		Date JULY 2015						
Verified		Date						
Approved								
Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK			Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES					
Title STORMWATER DRAINAGE DETAILS AND SECTIONS			DATUM A.H.D.		Scale AS SHOWN	Size A1		
			Drawing Number 161163-050-CD-C-301-6021		Revision C			

STORMWATER DETENTION TANK

GENERAL NOTES:

- THESE DRAWINGS AND NOTES ARE TO BE READ IN CONJUNCTION WITH ARCHITECTURAL AND OTHER WORKING DRAWINGS, SPECIFICATIONS, AND WITH SUCH FURTHER DETAILS, AND INSTRUCTIONS WHICH MAY BE ISSUED. REFER ALL DISCREPANCIES TO THE ENGINEER BEFORE PROCEEDING WITH WORK.
- CONSTRUCTION OF ALL STRUCTURAL AND CIVIL WORK SHALL COMPLY WITH CURRENT EDITIONS OF RELEVANT SAA CODES.
- DIMENSIONS SHALL BE VERIFIED BEFORE COMMENCING CONSTRUCTION. DO NOT SCALE DRAWINGS TO OBTAIN DIMENSIONS.
- THROUGHOUT CONSTRUCTION THE STRUCTURE SHALL BE MAINTAINED IN A STABLE CONDITION AND NO PART SHALL BE OVER STRESSED.
- CONSTRUCTION SYSTEMS, PROCEDURES AND METHODOLOGY OF STRUCTURAL AND CIVIL WORK SHALL ENSURE COMPLIANCE WITH THE LOCAL AUTHORITY WORKPLACE HEALTH AND SAFETY LEGISLATION.

DESIGN CRITERIA:

- THE STRUCTURAL ELEMENTS SHOWN ON THESE DRAWINGS HAVE BEEN DESIGNED FOR SUPERIMPOSED DEAD AND LIVE LOADS AS NOMINATED ON THE RELEVANT DRAWINGS AND THE FOLLOWING:
WIND LOADS TO AS 1170.2
REGION 9
TERRAIN CATEGORY 3
BCA STRUCTURE IMPORTANCE LEVEL 3
Video p 547
EARTHQUAKE LOADS TO AS 1170.4, 2007
BCA STRUCTURE IMPORTANCE LEVEL 3
SITE SUBSOIL CLASS Bc
HAZARD FACTOR (Z) 0.05
DESIGN CATEGORY II
- CONCRETE ELEMENTS HAVE BEEN DESIGNED FOR THE FOLLOWING DURABILITY EXPOSURE TO AS 3600 (B1 EXPOSURE U.N.O.)
EXTERNAL -
INTERNAL -
FOOTINGS -

SAFETY IN DESIGN AND CONSTRUCTION:

- ALL CONSTRUCTION WORK SHALL COMPLY WITH THE REQUIREMENTS OF THE LOCAL AUTHORITY WORKPLACE HEALTH AND SAFETY LEGISLATION.
- CONSTRUCTION ACTIVITY CAN BE HAZARDOUS AND POTENTIAL SAFETY HAZARDS CONSIDERED BY THE DESIGNERS TO HAVE A HIGHER RISK THAN NORMAL CONSTRUCTION ACTIVITY ARE IDENTIFIED WITH APPROPRIATE NOTES IN THE DOCUMENTATION.
- DESIGNERS GENERALLY HAVE A LOWER LEVEL OF APPRECIATION OF THE SAFETY RISKS AND HAZARDS INVOLVED IN CONSTRUCTION COMPARED TO THAT OF A COMPETENT BUILDER / CONTRACTOR AND THEREFORE ALL THE SAFETY RISKS AND HAZARDS APPLICABLE TO THIS PROJECT MAY NOT BE IDENTIFIED.
- IT IS ESSENTIAL THAT PRIOR TO COMMENCEMENT OF CONSTRUCTION AN ADEQUATE SAFETY PLAN IS PREPARED BY THE BUILDER / CONTRACTOR FOR THE WORKS IN COMPLIANCE WITH STATUTORY REQUIREMENTS. THE SAFETY PLAN SHALL INCLUDE APPROPRIATE WORK METHOD STATEMENTS FOR ALL RISK ACTIVITIES. THE STRUCTURAL ENGINEER IS AVAILABLE TO BE CONSULTED IN REGARDS TO THE SAFETY PLANS.
- PRIOR TO ANY ERECTION OF STRUCTURAL ELEMENTS THE CONTRACTOR SHALL HAVE COMPLETED A RISK ASSESSMENT OF ALL CONSTRUCTION PROCEDURES AND ENSURED THAT WHERE POSSIBLE, ALL RISKS HAVE BEEN ELIMINATED AND WHERE NOT POSSIBLE THEIR SAFETY PLAN HAS ADDRESSED THOSE ISSUES AND IT HAS BEEN FORMULATED AND DOCUMENTED FOR STRICT ADHERENCE DURING THE CONSTRUCTION WORKS.
- PRIOR TO FABRICATION OF STEELWORK THE CONTRACTOR SHALL AGREE WITH THE ENGINEER ON AREAS OF RISK WHICH HAVE BEEN ADDRESSED BY THE DESIGN WHERE POSSIBLE AND AGREE ON SUITABLE CONSTRUCTION PROCEDURES WHERE AREAS OF RISK STILL EXIST.
- PRIOR TO THE USE OF THE PROJECT AS DESIGNED, THE OWNER SHALL HAVE COMPLETED A RISK ASSESSMENT OF ALL WORK PRACTICES AND ENSURED THAT WHERE POSSIBLE ALL RISKS HAVE BEEN ELIMINATED AND WHERE NOT POSSIBLE THEIR SAFETY PLAN HAS ADDRESSED THOSE ISSUES AND IT HAS BEEN FORMULATED AND DOCUMENTED FOR STRICT ADHERENCE AFTER COMMISSIONING.

DEMOLITION AND CLEARING NOTES:

- PRIOR TO CLEARING AND DEMOLITION OPERATIONS REMOVE WITHOUT DAMAGING ALL EXISTING INFRASTRUCTURE TO BE REUSED OR STORED AS NOTED AND DIRECTED BY THE SUPERINTENDENT.
- CLEARING AND DEMOLITION OPERATIONS SHALL BE CARRIED OUT ONLY WITHIN THOSE AREAS AFFECTED BY THE PROPOSED WORKS UNLESS NOTED OTHERWISE.
- DEMOLISH EXISTING REDUNDANT INFRASTRUCTURE SUCH AS KERBS, PAVEMENT SEALS, CONCRETE FOOTPATHS, ABANDONED SERVICE STRUCTURES ETC. TO A DEPTH OF 500mm BELOW PROPOSED PAVEMENT SUBGRADE LEVEL AND 300mm BELOW FINISHED LEVEL IN ALL OTHER AREAS AND REFILL AS NOTED BELOW. DISPOSE OF ALL SUCH MATERIAL OFF SITE.
- CLEAR RUBBISH, SCRUB, TREES, STUMPS ETC. AND GRUB OUT STUMPS AND ROOTS OVER 50mm DIAMETER TO A DEPTH OF 500mm BELOW PROPOSED PAVEMENT SUBGRADE LEVEL AND 300mm BELOW FINISHED LEVEL IN ALL OTHER AREAS AND REFILL AS NOTED BELOW.
- REFILL DEMOLITION EXCAVATIONS AND GRUB HOLES WITH ON SITE MATERIAL WON FROM CUT AREAS SUITABLE FOR USE AS FILL MATERIAL (REFER EARTHWORKS NOTES). PLACE AND COMPACT FILL MATERIAL IN ACCORDANCE WITH EARTHWORKS NOTES.

EARTHWORKS NOTES:

- THE EARTHWORKS DRAWINGS AND THESE NOTES ARE TO BE READ IN CONJUNCTION WITH THE EARTHWORKS SPECIFICATION.
- A SOILS INVESTIGATION OF THE SITE HAS BEEN CARRIED OUT BY CARDNO AND A COPY OF THIS REPORT IS INCLUDED IN THE EARTHWORKS SPECIFICATION, OR IS AVAILABLE FOR VIEWING AT THE ENGINEERS OFFICE.
- THE CONTRACTOR SHALL ALLOW TO ENGAGE AN APPROVED GEOTECHNICAL CONSULTANT TO CARRY OUT ALL INSPECTIONS, TESTING AND CERTIFICATIONS IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION.
- PRIOR TO COMMENCEMENT OF WORKS THE CONTRACTOR IS TO IDENTIFY AND BE SATISFIED OF THE CORRECT LOCATIONS OF ALL EXISTING SERVICES WHETHER INDICATED OR NOT ON THE PLANS. ANY DAMAGE TO EXISTING SERVICES IS TO BE RECTIFIED AS SOON AS POSSIBLE AT THE CONTRACTORS EXPENSE.
- CARRY OUT ALL EARTHWORKS IN ACCORDANCE WITH THE EARTHWORKS SPECIFICATION.
- ALL EXCAVATED BATTERS AND FILL EMBANKMENTS ARE TO BE INSPECTED AND APPROVED BY THE GEOTECHNICAL ENGINEER.
- REFER TO STRUCTURAL DRAWINGS FOR DETAILED EXCAVATION.
- REFER ALSO ARCHITECT, LANDSCAPE ARCHITECT AND HYDRAULICS ENGINEER FOR ADDITIONAL WORKS AND REQUIREMENTS.
- PRIOR TO COMMENCEMENT OF WORK CONFIRM ALL BULK EXCAVATION LEVELS WITH THE ARCHITECT.

FOOTING NOTES:

- THE BUILDER SHALL ALLOW TO ENGAGE AN APPROVED GEOTECHNICAL ENGINEER IN ACCORDANCE WITH THE EARTHWORKS AND OR THE BORED PIER SECTIONS OF THE SPECIFICATIONS TO CARRY OUT ALL INSPECTIONS AND TESTING TO CERTIFY THAT THE FOUNDING MATERIAL FOR HIGH LEVEL FOOTINGS AND OR THE CAPACITY OF BORED PIERS COMPLIES WITH THAT NOMINATED IN THE DOCUMENTATION. THE CERTIFICATION IS TO BE SIGNED BY A REGISTERED PROFESSIONAL ENGINEER OF QUEENSLAND.
- AN ALLOWABLE BEARING PRESSURE FOR HIGH LEVEL FOOTINGS OF 3500 kPa HAS BEEN ASSUMED IN THE DESIGN OF THE FOOTINGS.
FOR BORED PIERS AN ALLOWABLE END BEARING DESIGN PARAMETERS ARE SHOWN ON THE DRAWINGS.
- WHERE REQUIRED FOUNDING MATERIAL IS DEEPER THAN THE UNDERSIDE OF THE HIGH LEVEL FOOTINGS AS DETAILED ALLOW TO BACKFILL ADDITIONAL EXCAVATION WITH M20 CONCRETE.
- WHERE EXCAVATION WORK IS TO BE CARRIED OUT ADJACENT TO EXISTING FOOTINGS THE EXACT LEVEL OF THE UNDERSIDE OF THE FOOTINGS SHALL BE DETERMINED BY TEST PITS PRIOR TO EXCAVATION. UNDERPINNING SHALL BE CARRIED OUT AS DETAILED OR REQUIRED BY THE STRUCTURAL ENGINEER.
- ALL FOOTING EXCAVATIONS SHALL BE FORMED AS NECESSARY WHEN EXCAVATED FACE IS NOT STABLE. DEWATERED AND CLEANED OF LOOSE AND SOFT MATERIAL PRIOR TO PLACING CONCRETE.
- ALL WALLS AND COLUMNS SHALL BE CONCENTRIC WITH SUPPORTING FOOTINGS UNLESS NOTED OTHERWISE ON THE DRAWINGS.

BORED PIER NOTES:

- ALL BORED PIERS TO BE IN ACCORDANCE WITH THE BORED PIER SPECIFICATION.
- BORED PIERS SHALL BE DESIGNED FOR THE WORKING LOADS NOMINATED AT AN ECCENTRICITY OF 75mm IN ACCORDANCE WITH THE BORED PIER SPECIFICATION.
- PRIOR TO COMMENCEMENT OF ANY BORED PIER WORK THE BUILDER SHALL LOCATE ALL NEW AND EXISTING SERVICES RELATIVE TO PIER LOCATIONS. THE ENGINEER IS TO BE NOTIFIED OF ANY POTENTIAL CLASHES.
- BORED PIER CONTRACTOR IS TO MINIMISE ANY NOISE AND VIBRATION DUE TO PIER INSTALLATION ADJACENT TO EXISTING BUILDINGS AND SERVICES. REFER BORED PIER SPECIFICATION FOR REQUIREMENTS.
- THE BASE AND THE SHAFT OF THE BORED PIERS SHALL BE CLEANED OF ALL LOOSE MATERIAL BY THE USE OF A 'CLEAN-OUT' BUCKET.
- ALLOW FOR PIER LINERS WHERE EXISTING SITE CONDITIONS REQUIRE IT.
- AT COMPLETION OF BORED PIER INSTALLATION AND PRIOR TO COMMENCEMENT OF FURTHER WORK PROVIDE FOR APPROVAL FINAL SURVEY DETAILS OF THE AS CONSTRUCTED PIER LOCATIONS AND THE GEOTECHNICAL ENGINEERS CERTIFICATION OF THE BORED PIER LOAD CARRYING CAPACITIES IN ACCORDANCE WITH THE BORED PIER SPECIFICATION.

CONCRETE:

- ALL MATERIALS AND WORKMANSHIP SHALL CONFORM WITH CURRENT EDITIONS OF AS 1379, AS 3600 AND AS3610 EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS. REFER ALSO TO IN SITU CONCRETE, FORMWORK AND REINFORCEMENT SECTION OF THE SPECIFICATIONS.
- CONCRETE STRENGTH GRADE FOR PARTICULAR ELEMENTS SHALL BE AS NOTED ON THE DRAWINGS.
- PROJECT ASSESSMENT OF STRENGTH IN ACCORDANCE WITH AS 1379 SHALL BE ADOPTED FOR SAMPLING AND TESTING. REFER TO SPECIFICATION FOR FREQUENCY OF TESTS.
- SIZE OF ELEMENTS IS EXCLUSIVE OF APPLIED FINISHES. BEAMS DEPTHS INCLUDE SLAB THICKNESS AND ARE THE FIRST DIMENSION SPECIFIED, FOLLOWED BY WIDTH. UNLESS NOTED OTHERWISE ALL FORMED EDGES AND CORNERS OF CONCRETE MEMBERS SHALL HAVE 20mm CHAMFERS.
- CONSTRUCTION JOINTS SHALL BE MADE ONLY AT APPROVED LOCATIONS. AND, IN BEAMS AND SLABS SHALL BE CONSTRUCTED WITH A SHEAR KEY TO ENGINEERS DETAIL U.N.O. SURFACES OF CONCRETE AT ALL JOINTS SHALL BE THOROUGHLY MECHANICALLY SCABBLED, FULLY EXPOSING THE AGGREGATE MIX, UNLESS OTHERWISE NOTED.
- ALL REINFORCEMENT SHALL BE TO AS/NZS 4671 AND REINFORCEMENT GRADE IS DESIGNATED AS FOLLOWS:-
R: PLAIN ROUND BAR, GRADE 250
N: DEFORMED BAR, GRADE 500
SURL: WIRE REINFORCING FABRIC, GRADE 500
- REINFORCEMENT SHALL BE BENT COLD IN ACCORDANCE WITH AS3600 EXCEPT WHERE APPROVED BY THE STRUCTURAL ENGINEER. NO REBENDING SHALL BE PERMITTED.
- DO NOT CUT REINFORCEMENT ON SITE TO CLEAR PENETRATIONS. DISPLACE REINFORCEMENT SLIGHTLY AS NECESSARY TO CLEAR BLOCKOUTS.
- CONCRETE COVER AND LAPS TO REINFORCEMENT SHALL BE AS NOTED ON THE DRAWINGS.
- SLABS AND BEAMS SHALL BEAR ONLY ON LOAD BEARING ELEMENTS SHOWN ON THE PLANS. ALL OTHER NON LOAD BEARING ELEMENTS INCLUDING WINDOW MULLIONS, NON LOAD BEARING WALLS ETC. SHALL BE KEPT 20mm CLEAR FROM SOFFIT OF STRUCTURE.
- MASONRY WALLS SHALL NOT BE ERECTED ON SUSPENDED SLABS AND BEAMS UNTIL ALL PROPPING HAS BEEN REMOVED U.N.O.
- APPLY EVAPORATION RETARDER AND CURE ALL CONCRETE IN ACCORDANCE WITH THE CONCRETE SPECIFICATIONS.
- FORMWORK SHALL REMAIN UNDISTURBED FOR THE MINIMUM STRIPPING TIMES SPECIFIED IN AS3610, UNLESS OTHERWISE APPROVED.

REINFORCED CONCRETE MASONRY:

- ALL MATERIALS AND WORKMANSHIP SHALL CONFORM WITH THE CURRENT EDITION OF AS3700 EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS AND SPECIFICATIONS.
- CONCRETE MASONRY UNITS SHALL HAVE A MINIMUM CHARACTERISTIC UNCONFINED COMPRESSIVE STRENGTH OF 15 MPa IN ACCORDANCE WITH THE REQUIREMENTS OF AS/NZS 4455.1.
- PROVIDE ADEQUATE TEMPORARY PROPPING TO WALLS DURING CONSTRUCTION IN ACCORDANCE WITH AS 3700 AND THE WORK METHOD STATEMENT PREPARED BY THE BUILDER / CONTRACTOR.
- PROVIDE VERTICAL CONTROL JOINTS IN WALLS AT MAXIMUM 8 METRE CENTRES OR WHERE INDICATED ON DRAWINGS.
- ALL WALLS SHALL BE FULLY BONDED OR TIED AT THEIR INTERSECTIONS UNLESS DETAILED OTHERWISE.
- ALL NON-LOADBEARING MASONRY WALLS SHALL BE KEPT CLEAR OF SLAB/BEAM SOFFITS BY 20mm U.N.O. AND THE VOID FILLED WITH AN APPROVED COMPRESSIBLE FILLER AND FIRE RATED AS REQUIRED.
- NO MASONRY WALLS TO BE ERECTED ON SUSPENDED SLABS UNTIL ALL PROPPING HAS BEEN REMOVED.
- MORTAR SHALL BE MECHANICALLY MIXED AND TYPE M3 U.N.O. CONSISTING OF 1 PART CEMENT, 1 PART HYDRATED LIME AND 6 PARTS OF WELL GRADED SAND, AND SHALL COMPLY WITH THE REQUIREMENTS OF AS 3700.
- CORES OF ALL BLOCKS SHALL BE CLEAN AND FREE FROM PROJECTING MORTAR. PROVIDE CLEAN OUT OPENINGS AT BASE OF EACH LIFT. FORM THE FACE OF CLEAN OUT BLOCKS. INFILL BLOCK SHELLS SHALL NOT BE USED WITHOUT APPROVAL BY THE STRUCTURAL ENGINEER.
- CORE FILLING CONCRETE SHALL BE MIXED USING MAX 10mm AGGREGATE. SHALL HAVE F.C 20 MPa AND MAXIMUM SLUMP OF 230mm. CONCRETE SHALL BE PLACED TO COMPLETELY FILL CORES WITHOUT SEGREGATION OR VOIDS. COMPACT BY INTERNAL VIBRATION OR RODDING AND STRENGTH TEST IN ACCORDANCE WITH THE MASONRY SPECIFICATION.
- FILL CORES TO MAXIMUM 2.4 METRE HIGH FREE DROP IN ANY ONE POUR.
- BACKFILL RETAINING WALLS, ON ENGINEER'S APPROVAL, WITH CLEAN 20mm GRAVEL FILLING FREE FROM CLAY OR OTHER ORGANIC MATTER.
- RETAINING WALLS SHOULD NOT BE BACKFILLED UNTIL A MINIMUM OF 14 DAYS AFTER GROUT FILLING. PROPPED RETAINING WALLS SHALL NOT BE BACKFILLED UNTIL THE SLAB OVER HAS BEEN CAST A MINIMUM OF 7 DAYS AND THE WALL HAS BEEN GROUT FILLED A MINIMUM OF 14 DAYS.
- PROVIDE ALL AGRICULTURAL PIPES OR WEEPHOLES TO EARTH FACE OF ALL RETAINING WALLS AS NOTED IN THE DOCUMENTATION. ALL AGRICULTURAL PIPES OR WEEPHOLES TO BE PROTECTED FROM SILTATION BY THE USE OF GEOFABRIC. AGRICULTURAL DRAINS TO BE CONNECTED TO THE STORMWATER SYSTEM TO HYDRAULIC ENGINEERS DETAILS.
- PROVIDE WATERPROOF MEMBRANE & D.P.C. AS REQUIRED BY THE ARCHITECTURAL SPECIFICATION.

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL


14 OCT 2015

MEDQ


Rev	Date	Description	Des.	Ver.	Appr.
D	31.07.2015	EDQ SUBMISSION			
C	14.07.2015	PRELIMINARY ISSUE			
B	13.07.2015	PRELIMINARY ISSUE			
A	08.07.2015	PRELIMINARY ISSUE			



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn KA	Date	Client RNA & LEND LEASE
Checked KA	Date	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Designed DRV	Date	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES
Verified M/H	Date	Datum
Approved	Date	Date
M/H	Date	Scale
		Size
		A1
		Drawing Number
		161163-050-DD-C-301-6005
		Revision
		D
		NOTES SHEET



CONCRETE PAD FOOTING TYPE SCHEDULE			
MARK	SIZE		
	WIDTH (mm)	LENGTH (mm)	DEPTH (mm)
PF1	1200	1200	600
PF2	1500	1500	600
PF3	1800	1800	750
PF4	1800	3600	750
PF5	1800	4800	750
PF6	1800	7200	750
PF7	1800	3900	600

CONCRETE COLUMN TYPE SCHEDULE		
MARK	SIZE	
	WIDTH	LENGTH
C1	650	650
C2	650	900

CONCRETE BORED PIER TYPE SCHEDULE	
TYPE MARK	DIAMETER (mm)
BP1	900
BP2	1200

NOTES

1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING 6005

2. DESIGN LOADS

AREA	SUPERIMPOSED DEAD LOAD	LIVE LOAD

3. CONCRETE

ALL WORKMANSHIP, MATERIALS & TESTING SHALL BE IN ACCORDANCE WITH AS 3600 EXCEPT AS VARIED BY THE CONTRACT DOCUMENTS AND SPECIFICATION.
ALL CONCRETE COMPONENTS SHALL BE NORMAL CLASS WITH A 28 DAY COMPRESSIVE STRENGTH OF 32MPa (ie. N32) EXCEPT WHERE VARIED BY THE TABLE BELOW.

COMPONENT	STRENGTH
SLAB ON GROUND	S40
PAD FOOTINGS	N40
COLUMN	N50
BORED PIERS	S32

N DENOTES NORMAL CLASS CONCRETE WITH THE FOLLOWING PROPERTIES U.N.O.
MAXIMUM AGGREGATE SIZE: 20mm
SLUMP: 80mm ±15
TESTING TYPE - PROJECT ASSESSMENT
S DENOTES SPECIAL CLASS CONCRETE WITH 650 MICROSTRAIN
MAXIMUM SHRINKAGE AS PER THE CONCRETE SPECIFICATION U.N.O.
S32(1) - DENOTES SPECIAL CLASS CONCRETE WITH 650 MICROSTRAIN
MAXIMUM SHRINKAGE CONTROL AND HIGH EARLY STRENGTH TO SUIT POST TENSIONING.

LEGEND

- 150 SOG
DENOTES 150 MIN. THICK SLAB ON GROUND ON VAPOUR BARRIER ON 50mm DEPTH SAND BED REINFORCED WITH SL82 MESH 40 TOP COVER. WHERE ROCK IS NOT EXPOSED AT PLATFORM LEVEL ALLOW TO PREPARE SUBGRATE TO GEOTECHNICAL ENGINEERS APPROVAL ON SITE.
- CONCRETE COLUMN OVER
DENOTES CONCRETE COLUMN
- SL
DENOTES SLAB SURFACE LEVEL
- DJ1
DENOTES DOWEL JOINT.
- BJ
DENOTES BUTT JOINT.

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ


Rev	Date	Des	Ver	Appr
C	31.07.2015	EDO SUBMISSION		
B	13.07.2015	PRELIMINARY ISSUE		
A	08.07.2015	PRELIMINARY ISSUE		



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn KA	Date	Client RNA & LEND LEASE
Checked KA	Date	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Designed DRV	Date	Title DETENTION TANK BASE SLAB AND FOOTING PLAN
Verified M/H	Date	Revision 161163-050-DD-C-301-6050 C
Approved	Date	Scale A1



DETENTION TANK ROOF SLAB PLAN
1:200

NOTES

1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING 6005

2. DESIGN LOADS

AREA	SUPERIMPOSED DEAD LOAD	LIVE LOAD
INTERIM EKKA STAGE		
GENERAL		15 kPa
RETAIL/CARPARK STAGE		
GROUND FLOOR RETAIL	6.5 kPa	5 kPa
GROUND FLOOR CARPARK		2.5 kPa
GROUND FLOOR CARPARK DURING EKKA GRIDS E TO A		15 kPa
LOADING DOCK		
MAX. VEHICLE TOTAL LOAD		30 Tonnes
MAX. VEHICLE AXLE LOAD		8.4 Tonnes

3. CONCRETE

ALL WORKMANSHIP, MATERIALS & TESTING SHALL BE IN ACCORDANCE WITH AS 3600 EXCEPT AS VARIED BY THE CONTRACT DOCUMENTS AND SPECIFICATION. ALL CONCRETE COMPONENTS SHALL BE NORMAL CLASS WITH A 28 DAY COMPRESSIVE STRENGTH OF 32MPa (ie N32) EXCEPT WHERE VARIED BY THE TABLE BELOW.

COMPONENT	STRENGTH
SLABS AND BEAMS	S40
N DENOTES NORMAL CLASS CONCRETE WITH THE FOLLOWING PROPERTIES U.N.O. MAXIMUM AGGREGATE SIZE - 20mm SLUMP - 80mm ±15 TESTING TYPE - PROJECT ASSESSMENT	
S DENOTES SPECIAL CLASS CONCRETE WITH 650 MICROSTRAIN MAXIMUM SHRINKAGE AS PER THE CONCRETE SPECIFICATION U.N.O. S32(1) - DENOTES SPECIAL CLASS CONCRETE WITH 650 MICROSTRAIN MAXIMUM SHRINKAGE CONTROL AND HIGH EARLY STRENGTH TO SUIT POST TENSIONING.	

4. THE STRUCTURAL SLAB SURFACE HAS A CONSTANT FALL FROM RL 7.60 AT GRID 2 TO RL 7.35 AT GRID 9 EXCEPT IN AREA OF THE LOADING DOCK. ALL CONCRETE SLAB AND BEAM THICKNESSES ARE CONSTANT U.N.O. WITH SOFFIT FALL FROM GRID 2 TO 9 TO MATCH SURFACE LEVELS/FALLS
5. ALL FUTURE COLUMNS AND WALLS NOTED ON PLAN ARE TO HAVE STARTER BARS WITH PROPRIETARY MECHANICAL COUPLERS WITH PROTECTIVE CAPS CAST INTO THE FLOOR STRUCTURE. REFER FUTURE COLUMN/WALL DETAILS.

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ

Rev	Date	Des	Ver	Appr
D	31.07.2015	EDQ	SUBMISSION	
C	14.07.2015	PRELIMINARY	ISSUE	
B	13.07.2015	PRELIMINARY	ISSUE	
A	08.07.2015	PRELIMINARY	ISSUE	




© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.




Drawn	KA
Checked	KA
Designed	DRV
Verified	MVH
Approved	

Date	Client	RNA & LEND LEASE
Date	Project	RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Date	Title	DETENTION TANK ROOF SLAB PLAN


Status				PRELIMINARY	
NOT TO BE USED FOR CONSTRUCTION PURPOSES					
Datum		Date		Scale	
				Size	
				A1	
Drawing Number				Revision	
161163-050-DD-C-301-6070				D	




SECTION 1
1:20 6070




SECTION 2
1:20 6070



SECTION 3
1:20 6070



SECTION 4
1:20 6070



SECTION 4a
1:20 6070

NOTES

1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING 6005
2. REFER TO EARTHWORKS SPECIFICATION FOR ALL REQUIREMENTS IN RELATION TO EARTHWORKS AND SHORING.


PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn
KA
Checked
KA
Designed
DRV
Verified
M/VH
Approved
M/VH


Date Client RNA & LEND LEASE

Date Project RNA SHOWGROUND REDEVELOPMENT
STORMWATER DETENTION TANK

Date Title DETENTION TANK ROOF SLAB SECTIONS & DETAILS
SHEET 1

Status PRELIMINARY
NOT TO BE USED FOR CONSTRUCTION PURPOSES

Datum Date Scale Size A1
Drawing Number 161163-050-DD-C-301-6071
Revision B



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn KA	Date	Client RNA & LEND LEASE
Checked KA	Date	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Designed DRV	Date	Title DETENTION TANK ROOF SLAB SECTIONS & DETAILS SHEET 2
Verified MVH	Date	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES
Approved	Date	Datum
		Date
		Scale
		Size A1
		Drawing Number 161163-050-DD-C-301-6072
		Revision B



1. FOR ALL RELEVANT CONSTRUCTION NOTES REFER DRAWING 6005
2. REFER TO EARTHWORKS SPECIFICATION FOR ALL REQUIREMENTS IN RELATION TO EARTHWORKS AND SHORING

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ


[illegible]

© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



Drawn KA	Date	Client	RNA & LEND LEASE										
Checked KA	Date	Project	RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK				Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSE						
Designed DCU	Date						Datum		Date	Scale	Size	A1	
Verified MV/H	Date	Title					Drawing Number		161163-050-DD-C-301-6073			Revision	B
Approved	Date	DETENTION TANK ROOF SLAB SECTIONS & DETAILS SHEET 3											
M/H	Date												

DATE PLOTTED: 21 August 2015 3:38 PM BY: ZAID ALALI



SEDIMENT AND EROSION CONTROL NOTES

- CONSTRUCTION IS TO BE PROGRAMMED TO PROVIDE INSTALLATION OF PERIMETER LANDSCAPING/SURFACE TREATMENTS AS EARLY AS PRACTICAL.
- THE CONTRACTOR IS RESPONSIBLE FOR PROGRAMING WORKS SO THAT SATISFACTORY EROSION AND SEDIMENT CONTROL DEVICES ARE IN PLACE AND MAINTAINED AT ALL TIMES.
- A PHOTOGRAPHIC RECORD OF SEDIMENT AND EROSION CONTROL DEVICES AND THE IMMEDIATE DOWNSTREAM STORMWATER SYSTEM, IS TO BE CARRIED OUT ON A FORTNIGHTLY CYCLE AND AFTER EACH MAJOR STORM EVENT. CARRY OUT CORRECTIVE AND PREVENTATIVE ACTION AS REQUIRED.
- PUBLIC & WORKPLACE SAFETY ISSUES MUST BE CONSIDERED AND MONITORED FOR EACH DEVICE TO THE SATISFACTION OF THE SUPERINTENDENT.
- WOVEN FABRICS ARE TO BE USED FOR SEDIMENT FENCE FILTER FABRIC.
- SEDIMENTATION MANAGEMENT DEVICES SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES AND MAINTAINED AT A SUITABLE LEVEL/ CONDITION THROUGHOUT CONSTRUCTION. SEDIMENT FENCES ARE TO BE CLEANED OUT WHEN CAPACITY IS REDUCED BY 30%. DRAINAGE STRUCTURE PROTECTION IS TO BE CLEANED FOLLOWING EACH SIGNIFICANT RUNOFF PRODUCING STORM.
- THE SITE ACCESS POINT AND WASH DOWN AREA IS TO BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD. ACCESS TO AND FROM THE SITE IS TO BE VIA THE SHAKEDOWN FACILITY ONLY. ALL VEHICLES ARE TO BE WASHED DOWN PRIOR TO LEAVING THE SITE.
- THE CONTRACTOR SHALL PROVIDE TEMPORARY DRAINAGE CONTROL TO DIVERT FLOW FROM UNDISTURBED AREAS AROUND DISTURBED AREAS AND DIRECT FLOW FROM DISTURBED AREAS TOWARD CONTROL DEVICES.
- CLEAN PONDED RAINFALL SHALL BE PUMPED TO A DOWNSTREAM STORMWATER SYSTEM.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSPECTION AND MAINTENANCE OF SEDIMENT AND EROSION CONTROL DEVICES. ALL DEVICES ARE TO BE INSPECTED AT LEAST WEEKLY AND AFTER SIGNIFICANT RUNOFF PRODUCING STORMS.
- IF EROSION AND SEDIMENT CONTROL DEVICES HAVE BEEN FOUND TO BE DEFICIENT OR FAILED IN SERVICE DUE TO UNFORESEEN CIRCUMSTANCES, CORRECTIVE ACTION IS TO BE UNDERTAKEN BY THE CONTRACTOR IMMEDIATELY WHICH MAY INCLUDE AMENDMENTS/ADDITIONS TO THE ORIGINAL EROSION CONTROL PLANS. SUCH ADDITIONS OR AMENDMENTS ARE TO BE APPROVED BY THE SUPERINTENDENT.
- STRAW BALES USED IN SEDIMENT DEVICES ARE TO BE REPLACED AFTER A MAXIMUM SERVICE PERIOD OF 6 WEEKS.
- SEDIMENTATION MANAGEMENT DEVICES ARE TO BE MAINTAINED BY THE CONTRACTOR, AS NOTED AND DETAILED, UNTIL APPROVAL HAS BEEN GRANTED BY THE ENGINEER FOR THEIR REMOVAL. THE CONTRACTOR IS TO REMOVE AND DISPOSE OF THESE DEVICES OFF SITE.
- TREE PROTECTION IS INDICATIVE ONLY. TREE PROTECTION TO BE DIRECTED BY SUPERINTENDENT ON SITE.
- THE CONTRACTOR IS RESPONSIBLE FOR RELOCATING SEDIMENT AND EROSION DEVICES/ FENCES TO ACCOMMODATE EARTHWORKS AS AND WHEN REQUIRED. THE LOCATION OF THE SEDIMENT AND EROSION CONTROL DEVICES ARE INDICATIVE ONLY. IT IS THE CONTRACTORS RESPONSIBILITY TO SPECIFICALLY LOCATE, THEN ENSURE SEDIMENT IS NOT WASHED DOWNSTREAM.
- EROSION CONTROL MATTING IS TO BE INSTALLED, REMOVED AND REINSTATED AS REQUIRED TO ENSURE THAT BATTERS ARE PROTECTED AT ALL TIMES WHEN THEY ARE NOT BEING WORKED ON.
- ESC DRAWINGS TO BE READ IN CONJUNCTION WITH EROSION AND SEDIMENT CONTROL PLAN REPORT PREPARED BY CARDNO (QLD) PTY LTD. INTERIM ESC MEASURES ARE TO BE DESIGNED AND INSTALLED BY THE CONTRACTOR AS REQUIRED.

ALL WORKS ON THE SITE SHALL BE UNDERTAKEN IN ACCORDANCE WITH RECOMMENDATIONS MADE IN BOTH THE ENVIRONMENTAL MANAGEMENT PLAN AND THE ACID SULPHATE SOIL MANAGEMENT PLAN PREPARED BY GOLDER ASSOCIATES PTY LTD

CONTRACTOR TO CONFIRM LOCATION OF EXISTING SERVICES PRIOR TO COMMENCEMENT OF WORKS

LEGEND

- SEDIMENT CONTROL
- SF SEDIMENT FENCE
 - SFW SEDIMENT FENCE WEIR
 - DC DISCHARGE CHUTE
 - DSP DRAINAGE STRUCTURE PROTECTION
 - SEP STABILISED ENTRY/EXIT POINT
 - EXISTING TREE TO REMAIN
 - PROPOSED PUMP OUT PIT LOCATE PUMP OUT LINE TO SUIT SITE ACTIVITY REFER DRG 6011 FOR DETAIL

PLANS AND DOCUMENTS referred to in the PDA APPROVAL

14 OCT 2015

MEDQ



XREFS: X-A10697-063, CIVIL DESIGN, X-A10697-063, SURVEY, X-A10697-063, STRUC
CAD File: K:\A10697\Phase 063, Cad & Model\AutoCAD\Drawings\161163-050-CD-C-301-6010.dwg

Rev	Date	Description	Des	Verit	Appd
C	21/08/2015	EDQ SUBMISSION	ZA	DS	MH
B	31/07/2015	EDQ SUBMISSION	ZA	DS	MH
A	13/07/2015	PRELIMINARY ISSUE	ZA	DS	MH




© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Cardno
Shaping the Future
Cardno (Qld) Pty Ltd | ABN 57 051 074 992
Level 11, 515 St Paul's Terrace
Fortitude Valley, QLD 4006
Tel: 07 3369 9822 Fax: 07 3369 9722
Web: www.cardno.com.au

Drawn ZA	Date JULY 2015	Client RNA & LENDLEASE
Checked DS	Date JULY 2015	Project RNA SHOWGROUND REDEVELOPMENT
Designed ZA	Date JULY 2015	Stormwater DETENTION TANK
Verified	Date	
Approved	Date	
		Title EROSION AND SEDIMENT CONTROL LAYOUT PLAN

Status PRELIMINARY	Scale AS SHOWN	Size A1
DATUM A.H.D.	Revision 161163-050-CD-C-301-6010	Revision C

DATE PLOTTED 31 July 2015 10:06 AM BY: ZAID ALALI





FOR EROSION & SEDIMENT CONTROL NOTES & LEGEND, REFER TO DRG 161163-050-CD-C-301-C6010.

PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ



XREF's: CAD File: \\AUBMCFC02\asb\A10697\Phase 06\3_Cad & Models\AutoCAD\CivilDrawings\161163-050-CD-C-301-6011.dwg

Rev	Date	Description	Des	Verif	Appd
B	31/07/2015	EDQ SUBMISSION	ZA	DS	MH
A	13/07/2015	PRELIMINARY ISSUE	ZA	DS	MH



© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the benefit of and use by the client in accordance with the terms of the retainer. Cardno Limited does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

Cardno
Shaping the Future


Cardno (Qld) Pty Ltd | ABN 57 051 074 992
Level 11, 515 St Paul's Terrace
Fortitude Valley, QLD 4006
Tel: 07 3369 9822 Fax: 07 3369 9722
Web: www.cardno.com.au

Drawn ZA Date JULY 2015	Client RNA & LENDLEASE	Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES
Checked DS Date JULY 2015	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK	DATUM A.H.D.
Designed ZA Date JULY 2015	Title EROSION AND SEDIMENT CONTROL DETAILS SHEET 1	Scale N.T.S.
Verified Date		Size A1
Approved		Drawing Number 161163-050-CD-C-301-6011
		Revision B


FOR EROSION & SEDIMENT CONTROL NOTES &
LEGEND, REFER TO DRG 161163-050-CD-C-301-C6010.



ON GRADE GULLY PIT



SAG GULLY PIT



STAGE 2
STRUCTURE COMPLETE


ROADWAY GULLY PIT

DSP DENOTES DRAINAGE
STRUCTURE PROTECTION,
REFER LAYOUT PLAN FOR
LOCATION & EXTENTS.


PLANS AND DOCUMENTS
referred to in the PDA APPROVAL

14 OCT 2015

MEDQ




PLAN




STAGE 1

EXCAVATION AND PIPE INSTALLATION



ACCESS CHAMBER

ACCESS CHAMBER / INLET STRUCTURE




INLET STRUCTURE

STAGE 2

STRUCTURE COMPLETE UP TO TOP SLAB

DSP DENOTES DRAINAGE
STRUCTURE PROTECTION,
REFER LAYOUT PLAN FOR
LOCATION & EXTENTS.



INLET STRUCTURE

STAGE 3

STRUCTURE COMPLETE

Rev.	Date	Description	Des.	Verif.	Appd.
B	31/07/2015	EDQ SUBMISSION	ZA	DS	MH
A	13/07/2015	PRELIMINARY ISSUE	ZA	DS	MH

© Cardno Limited All Rights Reserved.
This document is produced by Cardno Limited solely for the
benefit of and use by the client in accordance with the
terms of the retainer. Cardno Limited does not and shall not
assume any responsibility or liability whatsoever to any third
party arising out of any use or reliance by third party on the
content of this document.

Cardno
Shaping the Future
Cardno (Qld) Pty Ltd | ABN 57 051 074 992
Level 11, 515 St Paul's Terrace
Fortitude Valley, QLD 4006
Tel: 07 3369 9822 Fax: 07 3369 9722
Web: www.cardno.com.au

Drawn ZA	Date JULY 2015	Client RNA & LENDLEASE
Checked DS	Date JULY 2015	Project RNA SHOWGROUND REDEVELOPMENT STORMWATER DETENTION TANK
Designed ZA	Date JULY 2015	Title EROSION AND SEDIMENT CONTROL DETAILS SHEET 2
Verified	Date	
Approved		
Status PRELIMINARY NOT TO BE USED FOR CONSTRUCTION PURPOSES		
DATUM A.H.D.	Scale N.T.S	Size A1
Drawing Number 161163-050-CD-C-301-6012	Revision B	