

BUTLER
PARTNERS

geotechnical • geo-environmental • groundwater

PLANS AND DOCUMENTS

referred to in the ULDA

APPROVAL 15/4/2011

**GEOTECHNICAL INVESTIGATION
HIGH RISE RESIDENTIAL DEVELOPMENT
29 - 35 CAMPBELL STREET
BOWEN HILLS**

Prepared for: Metro Property Development Pty Ltd
Project No. 010-203A, 18 February 2011

practical engineering



High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

Butler Partners Pty Ltd
ABN 14 816 574 868
79 Doggett Street
Newstead, Queensland 4006
P.O. Box 2267
Fortitude Valley BC
Queensland 4006

www.butlerpartners.com.au

Ph: 61 7 3852 3800
Fx: 61 7 3852 3808
enquiries@butlerpartners.com.au

TABLE OF CONTENTS

SECTION 1 - INTRODUCTION	3
1.1 Project	3
1.2 Proposed Scope of Work	3
1.3 Commission	4
SECTION 2 - THE SITE	5
2.1 Site Description	5
2.2 Geology	6
SECTION 3 - FIELDWORK	7
3.1 Drilling and Sampling Methods	7
3.2 Test Locations and Supervision	7
SECTION 4 - INVESTIGATION RESULTS	8
4.1 Results	8
4.2 Subsurface Conditions	8
4.2.1 Stratigraphy	8
4.2.2 Rock Defects	8
4.2.3 Rock Strength Inversions	8
4.3 Groundwater	9
4.4 Laboratory Testing	9
4.4.1 Erosion and Sediment Control	9
4.4.2 Particle Size Distribution	9
4.4.3 Plasticity	10
4.4.4 Acid Sulfate Soils	10
4.4.5 Rock Strength	10
SECTION 5 - COMMENTS	11
5.1 Ground Model	11
5.2 Earthworks	11
5.2.1 Existing Fill	11
5.2.2 Contamination	12
5.2.3 Excavatability	12
5.2.3.1 Bulk and Confined Excavation	12
5.2.3.2 Bored Piles	13
5.2.4 Traffickability	13
5.2.5 Acid Sulfate Soils	14
5.2.6 Erosion and Sediment Control	14
5.2.7 Reactivity	14
5.3 Anticipated Rock Structure	15
5.3.1 Continuity of Major Rock Discontinuities	15
5.4 Temporary Batter Slopes	15
5.5 Temporary Excavation Support Methods	16
5.5.1 Soldier Pile and Shotcrete Lagging	17
5.5.2 Hit and Miss Construction	17
5.5.3 Reinforced Panels	17
5.5.4 Rock Dowels	18
5.5.5 Prestressed Rock Anchors	18
5.5.6 Shotcrete	18
5.5.7 External Corners	18
5.5.8 Intermediate Face Support	18
5.5.8.1 Temporary	18
5.5.8.2 Permanent	18
5.6 Temporary Excavation Support Loads	19
5.6.1 Earth Pressures	19
5.6.2 Boundary Loadings	19

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

PLANS AND DOCUMENTS

referred to in the ULDA

APPROVAL dated / /

	5.6.2.1	Street Loadings	19
	5.6.2.2	Adjacent Building Loadings	19
	5.6.3	Rock Anchor Excavation Support	20
	5.6.3.1	Design Philosophy	20
	5.6.3.2	Analysis	20
	5.6.3.3	Stressed Anchor Loads	21
	5.6.3.4	Factor of Safety	22
	5.6.4	Rock Dowels	22
5.7		Temporary Anchors/Dowels	22
5.8		Shotcrete Design Pressures	23
5.9		Adjacent Building Underpinning	23
5.10		Boundary Movement	24
5.11		Approval and Services Checks	24
5.12		Groundwater Control	24
	5.12.1	Wall Drainage	24
	5.12.2	Under Slab Drainage	25
5.13		Construction Monitoring	25
	5.13.1	Rock Strength and Structure	25
	5.13.2	Vibration	26
	5.13.3	Boundary and Adjacent Building Movement	26
	5.13.4	Rock Anchor and Dowel Installation	26
	5.13.4.1	Rock Anchors	27
	5.13.4.2	Rock Dowels	27
5.14		Foundations	27
	5.14.1	Maximum Bearing Pressure	27
	5.14.2	Settlement	28
	5.14.2.1	Pad Footings	28
	5.14.2.2	Bored Piles	29
5.15		Floor Slab Subgrade Properties	29
5.16		Additional Investigation	29

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63 64 65 66 67 68 69 70 71 72 73 74 75 76 77 78 79 80 81 82 83 84 85 86 87 88 89 90 91 92 93 94 95 96 97 98 99 100 101 102 103 104 105 106 107 108 109 110 111 112 113 114 115 116 117 118 119 120 121 122 123 124 125 126 127 128 129 130 131 132 133 134 135 136 137 138 139 140 141 142 143 144 145 146 147 148 149 150 151 152 153 154 155 156 157 158 159 160 161 162 163 164 165 166 167 168 169 170 171 172 173 174 175 176 177 178 179 180 181 182 183 184 185 186 187 188 189 190 191 192 193 194 195 196 197 198 199 200 201 202 203 204 205 206 207 208 209 210 211 212 213 214 215 216 217 218 219 220 221 222 223 224 225 226 227 228 229 230 231 232 233 234 235 236 237 238 239 240 241 242 243 244 245 246 247 248 249 250 251 252 253 254 255 256 257 258 259 260 261 262 263 264 265 266 267 268 269 270 271 272 273 274 275 276 277 278 279 280 281 282 283 284 285 286 287 288 289 290 291 292 293 294 295 296 297 298 299 300 301 302 303 304 305 306 307 308 309 310 311 312 313 314 315 316 317 318 319 320 321 322 323 324 325 326 327 328 329 330 331 332 333 334 335 336 337 338 339 340 341 342 343 344 345 346 347 348 349 350 351 352 353 354 355 356 357 358 359 360 361 362 363 364 365 366 367 368 369 370 371 372 373 374 375 376 377 378 379 380 381 382 383 384 385 386 387 388 389 390 391 392 393 394 395 396 397 398 399 400 401 402 403 404 405 406 407 408 409 410 411 412 413 414 415 416 417 418 419 420 421 422 423 424 425 426 427 428 429 430 431 432 433 434 435 436 437 438 439 440 441 442 443 444 445 446 447 448 449 450 451 452 453 454 455 456 457 458 459 460 461 462 463 464 465 466 467 468 469 470 471 472 473 474 475 476 477 478 479 480 481 482 483 484 485 486 487 488 489 490 491 492 493 494 495 496 497 498 499 500 501 502 503 504 505 506 507 508 509 510 511 512 513 514 515 516 517 518 519 520 521 522 523 524 525 526 527 528 529 530 531 532 533 534 535 536 537 538 539 540 541 542 543 544 545 546 547 548 549 550 551 552 553 554 555 556 557 558 559 560 561 562 563 564 565 566 567 568 569 570 571 572 573 574 575 576 577 578 579 580 581 582 583 584 585 586 587 588 589 590 591 592 593 594 595 596 597 598 599 600 601 602 603 604 605 606 607 608 609 610 611 612 613 614 615 616 617 618 619 620 621 622 623 624 625 626 627 628 629 630 631 632 633 634 635 636 637 638 639 640 641 642 643 644 645 646 647 648 649 650 651 652 653 654 655 656 657 658 659 660 661 662 663 664 665 666 667 668 669 670 671 672 673 674 675 676 677 678 679 680 681 682 683 684 685 686 687 688 689 690 691 692 693 694 695 696 697 698 699 700 701 702 703 704 705 706 707 708 709 710 711 712 713 714 715 716 717 718 719 720 721 722 723 724 725 726 727 728 729 730 731 732 733 734 735 736 737 738 739 740 741 742 743 744 745 746 747 748 749 750 751 752 753 754 755 756 757 758 759 760 761 762 763 764 765 766 767 768 769 770 771 772 773 774 775 776 777 778 779 780 781 782 783 784 785 786 787 788 789 790 791 792 793 794 795 796 797 798 799 800 801 802 803 804 805 806 807 808 809 810 811 812 813 814 815 816 817 818 819 820 821 822 823 824 825 826 827 828 829 830 831 832 833 834 835 836 837 838 839 840 841 842 843 844 845 846 847 848 849 850 851 852 853 854 855 856 857 858 859 860 861 862 863 864 865 866 867 868 869 870 871 872 873 874 875 876 877 878 879 880 881 882 883 884 885 886 887 888 889 890 891 892 893 894 895 896 897 898 899 900 901 902 903 904 905 906 907 908 909 910 911 912 913 914 915 916 917 918 919 920 921 922 923 924 925 926 927 928 929 930 931 932 933 934 935 936 937 938 939 940 941 942 943 944 945 946 947 948 949 950 951 952 953 954 955 956 957 958 959 960 961 962 963 964 965 966 967 968 969 970 971 972 973 974 975 976 977 978 979 980 981 982 983 984 985 986 987 988 989 990 991 992 993 994 995 996 997 998 999 1000

TABLES

Table 1	Groundwater Measurements in Standpipe Piezometers	9
Table 2	Summary of Reported Emerson Class pH and Conductivity Test Results	9
Table 3	Summary of Reported Particle Size Distribution Test Results	10
Table 4	Summary of Reported Plasticity Results	10
Table 5	Summary of Reported Chromium Suite Test Results	10
Table 6	Preliminary Estimated Bulk Excavation Method Transition Depths	13
Table 7	Maximum Temporary Unsurcharged Cut Batter Slopes – 4m Maximum	16
Table 8	Estimated Minimum Continuous Support Depth	16
Table 9	Lateral Earth Pressure Coefficient – Bear Surface	19
Table 10	Adjacent Building Loads Assumed	19
Table 11	Rock Discontinuity Strength Parameters	20
Table 12	Temporary Rock Excavation Support Loads 10° Anchor Inclination Preliminary	21
Table 13	Summary of Preliminary Excavation Support Analysis Results – Rock Dowels	22
Table 14	Rock Anchor Working Bond Stress	23
Table 15	Working Shotcrete Pressure	23
Table 16	Preliminary Vibration Limits	26
Table 17	Maximum Working Bearing Pressures	28
Table 18	Estimated Isolated Pad Footing Settlement	28
Table 19	Floor Slab Subgrade Properties	29

ATTACHMENTS

Drawing o. 1	Locality Plan Test Locations
Appendix A	Bore Report Sheets with Explanatory Notes
Appendix B	Laboratory Test Results

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

SECTION 1 - INTRODUCTION

1.1 Project

It is understood the proposed development is to consist of basement car parking levels, a common podium and two residential towers approximately twenty-seven and thirty storeys in height. It is anticipated that column loads will be in the order of 20,000kN. Current planning envisages three basement car parking levels but site constraints and statutory requirements may necessitate four basement levels. The approximate location and extent of the development site are shown on Drawing No. 1 attached.

1.2 Proposed Scope of Work

Based on prior knowledge of the immediate area including other major adjacent sites located in Campbell Street it was anticipated that the site ground conditions may comprise fill and soil to approximately 1m depth overlying generally low to medium strength tuff that contains numerous clay seams. A shallow groundwater table was not envisaged.

Based on the scope of the proposed development, the anticipated ground conditions and the relatively limited current site access it was proposed to undertake geotechnical investigation by

- drilling and sampling six bores to 15m depth at accessible locations and
- installing two standpipe piezometers to enable groundwater level monitoring over time.

A preliminary contamination assessment and an acid sulfate soil (ASS) assessment of the site were undertaken at the same time as the geotechnical investigation. The results of the preliminary contamination assessment are reported separately and advice regarding the presence of ASS is contained herein.

Using the results of the fieldwork and laboratory testing outcomes it was proposed that a report would be produced that would provide geotechnical design information on each of the following topics

- Relevant subsurface information for nearby sites.
- Subsurface conditions and laboratory testing data.
- Earthworks and rock excavatability.
- Erosion and sediment control guidance.
- Shrink/swell characteristics and moisture reactivity classification of soils.
- Groundwater conditions, variability, initial estimates of the rates of inflow.
- Temporary and long term dewatering options.
- Suitable foundation options as appropriate and design parameters – footings, bored piers, precast piles, tension piles and recommendations on suitability of various options.
- Settlement characteristics of proposed foundation options and differential settlement estimates.
- Permanent and temporary retention options and design parameters.
- Soil/rock anchor design parameters.
- Impacts of excavation dewatering and shoring on adjoining structures.
- Stability criteria for open excavations and advice regarding excavation staging including bench heights and the like.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

- Advice on site traffickability after disturbance of the site at excavated levels.
- Advice on construction difficulties likely to be encountered.
- Pavement subgrade design parameters.
- Options for slab on ground components including the basement and external slabs – floating or suspended hydrostatic or non hydrostatic.
- Settlement characteristics for slabs on grade.
- Advice on effects of proposed development on settlements of existing structures both long term and short term due to construction activities such as piling and compaction.
- Construction related advice.
- Pavement and slab subgrade parameters.

1.3 Commission

Based on the proposed nature of the development the anticipated subsurface conditions and the scope of work a fee to undertake the investigation was presented in a proposal of 6 August 2010. Butler Partners Pty Ltd (Butler Partners) was subsequently commissioned by Metro Property Development Pty Ltd to conduct the geotechnical investigation as proposed which was undertaken in consultation with the Robert Bird Group Pty Ltd consulting engineers for the development. This report was first issued in draft for comment on 10 October 2011.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

SECTION 2 - THE SITE

2.1 Site Description

The site occupies an irregular shaped parcel of land covering an area of approximately 2,600m² bounded to the west by Mayne Road and to the south by Campbell Street. The east of the site is bounded partially by Hazlemount Street and partially by residential property. To the north of the site lie commercial premises. At the time of the investigation the site was occupied by a now vacant car sales yard predominately comprising car parking areas with a single storey sales office. The ground surface level generally falls from east to west between approximate RL19.9m and RL17.7m. A relatively recent aerial view of the site is shown in Photograph 1 and three general views of the site at the time of investigation are given in Photograph 2 to Photograph 4.



Photograph 1: Aerial view of site



Photograph 2: Panoramic view of the site looking north east to south west from the western side of Mayne Road

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011



Photograph 3: Panoramic view of the site looking east to south from the vicinity of Bore 2



Photograph 4: Panoramic view of the site looking north-west to north-east from the southern side of Campbell Street

2.2 Geology

Reference to the Geological Survey of Queensland's 1:31,680 Brisbane geological sheets indicates that the site is located in an area mapped close to the boundary between the Brisbane Tuff comprising rhyolitic tuff conglomerate and breccia with minor sandstone and shale and the Meranleigh-Fernvale Group comprising greywacke siltstone shale chert jasper and basic volcanics.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

SECTION 3 - FIELDWORK

3.1 Drilling and Sampling Methods

The investigation comprised the drilling and sampling of five bores (Bores 1 to 5) using either a truck mounted Mobile B40L or a Maco 350 drilling rig. The bores were initially drilled to between approximately 0.3m and 2.0m using solid flight augers. Casing was then installed and the bores were advanced until refusal or 'practical' refusal in rock using a 'TC' blade bit and wash boring techniques. The bores were then extended using MLC coring techniques to recover 50mm diameter core samples of rock, utilising 'mud' circulation for cuttings removal. Strata identification was based on inspection of cuttings recovered in the 'mud' circulation, supplemented with inspection of Standard penetration test (SPT) and rock core samples recovered. Pocket penetrometer tests were carried out within select cored sections of cohesive strata. On completion of drilling, Bores 2, 4 and 5 were backfilled with drill spoil and surface plugged with bituminous concrete. A standpipe piezometer was installed in Bore 1 and in Bore 3 to enable groundwater level monitoring over time. Of the original six bores proposed one bore was unable to be completed due to existing buildings in the south eastern corner of the site.

3.2 Test Locations and Supervision

Bore locations were set out by direct measurement from existing site features and are shown approximately on Drawing No. 1 attached. Ground surface levels at the bore locations were determined by interpolation from RPS Australia East Pty Ltd's *Detail Survey*, Drawing No. 1033561 dated 30 July 2010.

A senior geotechnician set out the test locations, logged the subsurface soil profiles, determined the in situ sampling and testing program and supervised the fieldwork.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

SECTION 4 - INVESTIGATION RESULTS

4.1 Results

The subsurface conditions encountered at the bore locations are given on Bore Report sheets included in Appendix A using classification and descriptive terms defined in accompanying notes. Laboratory test result sheets are included in Appendix B.

4.2 Subsurface Conditions

4.2.1 Stratigraphy

For a description of the stratigraphy encountered in the bores the Bore Report sheets should be referred to. The stratigraphy encountered in the bores was variable however in broad summary the subsurface conditions encountered in the bores comprised a surface layer of between 0.4m and 1.7m depth approximately of pavement construction predominately granular fill and/or isolated natural silty clay soil. Bore 2 underlain by extremely low to medium strength tuff that graded with depth to very high strength rock in all bores with the exception of Bores 3 and 5.

In Bore 2 a zone of silty clay was encountered between 2.95m and 3.95m and was underlying a medium to high strength tuff. Pocket penetrometer readings undertaken within core samples of clay recovered ranged between 150kPa and 450kPa uncorrected.

In Bore 5 a zone of brecciated rock (fault breccia) was encountered between 11.7m and 15.0m depth. The fault breccia contained several clayey zones and an uncorrected pocket penetrometer test undertaken in a core sample of clay recovered indicated a reading of 350kPa. It is considered possible that the presence of the fault breccia may indicate that the base of the tuff layer had been encountered in Bore 5 or that the base of the tuff layer may not be far below the termination depth of Bore 5.

4.2.2 Rock Defects

In general two sets of rock joints discontinuities were intersected in Bores 1 to 5 which dipped at approximately 10° to 25° and 40° to 90° with isolated joints at 30° to 35° and were generally clean tight and 'healed' at approximately 1mm thickness. However crushed sheared zones with zones of clay were encountered in Bore 5 between 12.4m and 15.0m depth.

4.2.3 Rock Strength Inversions

It should be carefully noted that 'strength inversions' (i.e. 'lower' strength rock and/or soils underlying 'higher' strength rock) were encountered in some bores. For example very high strength rock was underlain by high strength rock in Bore 1 at approximately 11.9m to 13.3m depth (i.e. approximately RL7.9m to RL6.5m) and high strength rock with medium strength zones was encountered underlying very high strength rock below 12.4m in Bore 4 (i.e. below approximate RL5.8m).

High Rise Residential Development
 29 - 35 Campbell Street, Bowen Hills
 Project No. 010-203A
 18 February 2011

4.3 Groundwater

Free groundwater was observed in the Bore 3 at 0.7m depth during initial auger drilling. No free groundwater was observed in Bores 1, 2, 4 or 5 during initial auger drilling. Beyond the depth of auger drilling, the use of water circulation for cuttings removal precluded further groundwater observations during drilling. The depth/RL of groundwater measured in the standpipe piezometers installed in Bores 1 and 3 are summarised in Table 1.

Table 1: Groundwater Measurements in Standpipe Piezometers

Bore	Groundwater Measurements			
	12 October 2011		18 February 2011	
	Depth (m)	Reading (m RL)	Depth (m)	Reading (m RL)
1	0.82	RL19.0m	Not Accessible	
3	1.17	RL17.0m	1.32	RL16.9m

□ Possibly not fully recovered following drilling

It is considered possible that groundwater levels may be influenced by existing or nearby development services. It is also considered that the groundwater level beneath the site could vary with season/prevaling weather and that local 'perched' water tables may occur over the site.

4.4 Laboratory Testing

Selected soil samples were tested in a geotechnical testing laboratory to determine erosion and sediment control parameters, particle size distribution, plasticity and acid sulfate soil (ASS) potential and selected rock core samples were tested for measurement of rock strength.

4.4.1 Erosion and Sediment Control

Three selected samples recovered from the bores were tested to determine Emerson Class, number, pH and electrical conductivity and a summary of the reported test results is presented in Table 2.

Table 2: Summary of Reported Emerson Class, pH and Conductivity Test Results

Bore	Depth (m)	Soil Description	Emerson Class	pH	Electrical Conductivity (S/m)
1	0.5 - 0.95	Fill	3	7.5	0.12
3	0.5 - 0.95	Fill	2	6.3	0.04
5	0.25 - 0.59	Fill	2	5.0	0.03

4.4.2 Particle Size Distribution

Three selected samples recovered from the bores were tested to determine particle size distribution using wash sieve grading techniques and the reported results are summarised in Table 3.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

Table 3: Summary of Reported Particle Size Distribution Test Results

B	D	D	S M C	G F ¹	S F ²	S C ³
2	0.5 – 0.95	Fill	17.8	21	27	42
3	0.5 – 0.95	Fill	24.6	53	23	14
5	0.25 – 0.59	Fill	18.7	16	54	38

¹ Particle size ≥ 60 mm ≤ 2 mm ² Particle size $\geq$ approximately ≥ 2 mm ≤ 0.75 mm ³ Particle size $\geq$ approximately ≥ 0.75 mm

4.4.3 Plasticity

One sample recovered from Bore 2 was tested for measurement of plasticity using Atterberg limit and linear shrinkage test methods. The reported test results are summarised in Table 4 and indicate that the sample tested is of medium plasticity.

Table 4: Summary of Reported Plasticity Results

L	D	S D	S M C	L L	L	I	S L	I D F ϕ' ¹	C
2	3.5 – 3.6	Silty Clay	27.5	47	29	18	8.5	28	CI

¹ Australian Standard AS1726:1993 Geotechnical site investigation

4.4.4 Acid Sulfate Soils

Two samples of the fill encountered in Bores 2 and 3 were tested for the presence of acid sulfate soils (ASS) using Chromium Suite analysis. The samples were kept on ice until transported to Australian Laboratory Services Pty Ltd (ALS) under standard chain of custody protocol and a summary of the test results is given in Table 5.

Table 5: Summary of Reported Chromium Suite Test Results

B	D	S D	H _{KCL}	T A A S	C R S – S _{CR} S	N A S
2	0.5 – 0.95	Fill	6.4	≤ 0.02	≤ 0.005	≤ 0.02
5	0.0 – 0.25	Fill	4.1	0.08	≤ 0.005	0.08

4.4.5 Rock Strength

Selected rock core samples recovered from the bores were tested for measurement of rock strength using Point Load Test (IS 50) methods and the test results are given on the relevant Bore Report sheets and a table of results is included in Appendix B.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

SECTION 5 - COMMENTS

5.1 Ground Model

The results of the investigation indicate that the site is covered at the bore locations by a surface layer up to approximately 1.7m depth comprising pavement construction materials predominantly granular fill and isolated natural silty clay soils underlain by extremely low to low to medium strength tuff that generally graded with depth to very high strength rock and contained 'strength inversions'. In these ground conditions geotechnical design will need to consider at least but not exclusively the following key issues

- conditions and compaction status of the existing fill
- shrink/swell characteristics of soils and rock
- earthworks and excavatability
- movement control to site boundaries and adjacent services etc.
- groundwater conditions and control construction and permanent within the proposed basement
- temporary and permanent excavation support
- effects on excavation stability of the presence of 'faults'/continuous clay coated joints etc. in the rock;
- potential settlement of adjacent services/roads due to excavation support movement
- retaining wall pressures
- suitable foundation types
- settlement characteristics of proposed foundation options
- appropriate founding depths and bearing pressures
- variations in footing founding depths and founding conditions across the site
- presence of strength 'inversions' and zones of 'clayey' material possible brecciated 'contact' zone with depth in the rock
- slab and pavement subgrade properties
- possible construction difficulties
- possible settlements of existing adjacent structures
- settlement characteristics for slab on ground and
- site traffickability

5.2 Earthworks

5.2.1 Existing Fill

It is not known whether the existing fill material at the site is 'controlled' (i.e. it is not known whether the fill has been placed and uniformly compacted to an appropriate engineering specification. If any of the existing fill is required to support settlement sensitive elements and compaction control documentation does not exist or the specification used for filling is not appropriate for the proposed development then it is suggested that the existing fill be assumed to be uncontrolled.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

If the fill cannot be shown to be controlled then consideration should be given to the potential for adverse variation to exist in both the composition and degree of compaction of the fill. The presence of voids within uncontrolled fill as well as potential soft/loose zones or inclusions of deleterious materials may lead to potentially significant future total and differential settlements occurring possibly over relatively short distances.

5.2.2 Contamination

At the time of preparing this report the site was listed on the Department of Environment and Resource Management's (DERM) Environmental Management Register (EMR). Earthworks design, planning and costing as well as groundwater control works must take into account the site's contamination status.

5.2.3 Excavatability

5.2.3.1 Bulk and Confined Excavation

Based on the results of the fieldwork excavation to the depths proposed would be expected to encounter some surface fill and soils overlying weathered tuff/rock. The rock encountered in the bores ranged from extremely low to very high strength, and it is considered possible that zones of 'stronger' and/or 'less jointed' rock may also exist within the proposed excavation depth.

Excavation of fill/soils and extremely low to low strength rock should be readily achieved in bulk excavation using a large hydraulic excavator. A large tractor D11 should be able to economically remove low strength and medium strength rock however supplementary rock breaking may be required to aid production in medium strength rock subject to existing rock fracturing. It should be noted that successful ripping would require the use of a large tractor and freedom to rip in all directions. If this is not possible it is likely that rock breakers will be required in lieu of ripping.

Bulk excavation of medium strength rock will require relatively major use of 'rock breaker' equipment unless joint spacing is moderately close (less than 0.3m). In high strength or stronger rock with relatively few discontinuities it is likely that the most economic method of excavation will involve blasting followed by either ripping with a heavy tractor or use of a large rock breaker. Without blasting/rock breaker excavation methods only would be expected to be very slow and potentially severely damaging to equipment.

In confined trench/footing/etc. excavations in medium strength rock heavy rock breaker equipment and slow excavation rates should be allowed for. In high strength or stronger rock blasting may be required in order to minimise equipment damage and to increase production.

Due to the inherent jointing and bedding planes contained in the rock over break should be allowed for in pricing.

High Rise Residential Development
 29 - 35 Campbell Street, Bowen Hills
 Project No. 010-203A
 18 February 2011

Based on past experience in similar conditions elsewhere in Brisbane the maximum economic depths of bulk excavation using various methods has been estimated at the location of Bores 1, 2, 3, 4 and 5 and the estimates are tabulated in Table 6. The depths given in the table must be read in conjunction with the Bore Report sheets. The excavatability of rock is critically dependent upon the depth of weathering, nature and distribution of rock defects (i.e. persistent joints, sheared, extremely to highly weathered or highly fractured zones) as well as strength, the 'size' of the excavation, the availability of plant and any site specific limitations.

Table 6: Preliminary Estimated Bulk Excavation Method Transition Depths

Excavation Method	Excavation Method and Another for 'Economic Bulk Excavation'				
	Bore				
	1	2	3	4	5
Hand Excavation ▼ D11 Rock Excavation ▼ Hand Rock Bore ▼ Bore	1	1 - 2	5 - 6	1	3 - 4
	1 - 2	1 - 2	5 - 6	1	4 - 5
	5 - 6	5 - 6	9 - 10	2 - 3	-

□ Possibly supplemented by heavy rock breaker work

5.2.3.2 Bored Piles

Heavy drilling equipment will be required to drill medium strength or stronger rock. In high strength and stronger rock low to very low production should be allowed for in pricing combined with high bit wear. Use of coring bucket/pilot hole drilling methods will be required in high strength or stronger rock.

5.2.4 Traffickability

Following excavation to basement level traffickability for plant may be very difficult in general and particularly in the 'wet' in any areas of soil or extremely to very low strength rock and consideration should be given to the placement of a coarse granular working surface (e.g. 'crushed concrete') over any such exposed subgrade. The required layer thickness will depend on the type of plant proposed to traffic the site and should be specifically assessed on a case by case basis. However a minimum layer thickness of approximately 0.1m may be required for 'light' equipment.

In addition and depending on final basement level the 'clayey' rock encountered in Bore 5 below approximately 12m depth may be exposed in the base of the excavation and traffickability is likely to be difficult to impossible for most construction plant particularly in the 'wet'.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

5.2.5 Acid Sulfate Soils

The very limited extent of clay soils encountered in the bores are considered to be residual soils derived from the in place weathering of underlying rocks of the Brisbane Tuff. It is considered that whilst site soils may be acidic because of the site geology they will not produce any additional acidity and are therefore not acid sulfate soils. An Acid Sulfate Soil Management Plan will therefore not be required for site development. However as a general precaution all collected stormwater should be checked for pH prior to off-site discharge if the pH is outside the range 6.5pH to 8.5pH units it should be treated to bring it within this range prior to discharge.

5.2.6 Erosion and Sediment Control

Earthworks at the site is to comprise excavation to depths below street level of up to approximately 10m to 12m across the site area. Based on the results of the bores the stratigraphy that will be encountered by basement excavation will consist of variable strength tuff rock overlain by some thin fill and soil.

Assessment of erodibility/dispersability of fill and soils on the site could initially be carried out using Brisbane City Council's Erosion Hazard Assessment Form (EHAF), which adopts 'scores' and 'trigger scores' to identify the erosion risk of sites due to the soils present site characteristics and disturbance proposed. Only sites with a high risk ranking would require a full Erosion and Sediment Control (ESC) Program.

The site will have fill and soil exposed during excavation until material with a very low erosion potential is intersected which varies greatly between approximately 1.0m (Bore 1) and 12.0m (Bore 5) below existing site levels. In addition the entire site is to be excavated below road level such that no direct runoff will occur to stormwater but rather water will accumulate in depressions within the excavation. Therefore it is considered that the published BCC Erosion Hazard Form is not applicable to the site and a detailed ESC Program is not warranted. However stormwater will collect in the excavation during rain events and it is therefore considered that a stormwater management program will be required. A stormwater management program will need to address the collection testing and discharge requirements for stormwater and groundwater entering the site.

Although it is considered that whilst an ESC Program is probably not required, 'good construction practices' will still need to be adopted to control potential sediment movement from the site particularly when site levels are at or near ground level during the initial stages of construction and where excavated fill soils and weathered rock are being removed from site.

5.2.7 Reactivity

It is anticipated that extremely low to very low strength rock if encountered is likely to have the potential to display reactive behaviour i.e. have a potential for shrink and swell movements associated with wetting up and drying back and would therefore be expected to readily change volume with change in moisture content especially if disturbed and recompacted.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

5.3 Anticipated Rock Structure

Positive excavation support will be required to maintain excavation stability and to control movement of any adjoining roads/services etc. In general, all excavations on site should be assessed by suitably qualified personnel as variations in geological structure and rock strength can occur over short distances and these variations must be assessed as excavation proceeds.

Joint dip angles obtained from the bores and previous projects undertaken in the tuff rocks of Brisbane are considered to indicate that the rock jointing at the site probably mainly comprises a set of 'low angle' (i.e. 0° to 20°) and a set of 'high angle' (i.e. 50° to 80°) joints that are probably tight. ***This geological structure (and resulting potential rock failure mode) should be considered as preliminary only and must be subject to confirmation and adjustment based on the results of additional investigation as well as by inspection and mapping as the excavation proceeds.***

5.3.1 Continuity of Major Rock Discontinuities

A sheared/brecciated zone was intersected in Bore 5 below approximately 12m depth. The continuity of such discontinuities and their dip/strike cannot be accurately determined from the current bores and mapping during excavation will be required for confirmation. Consideration should be given to the possibility that the sheared/brecciated zones may lie close to or directly underlie the maximum depth of excavation or at shallower depths elsewhere within the proposed excavation.

Butler Partner's experience with the geotechnical design and construction of ten basements/excavations to depths between 18m and 40m in Brisbane is that 40% of the excavations encountered significantly inclined low strength continuous discontinuities that generally were not intersected in the investigation bores some of which did not become evident until the excavations were almost completed.

Considering that large scale continuous discontinuities have been found in the Brisbane Tuff rock and that discontinuities in the form of sheared/brecciated zones have been intersected within Bore 5 at the site it is strongly recommended that until site mapping is undertaken during the actual excavation large scale continuous planar discontinuities should be assumed to exist at the site to neglect their potential presence would require the acceptance of a significant risk that calculated excavation support loads could be significantly underestimated.

5.4 Temporary Batter Slopes

If movement sensitive services/buildings etc. are not located 'close' to excavation crests and geometry permits temporary batter slopes may be adopted for temporary slopes to approximately 4m height. Provided slopes are protected from groundwater or surface water effects the maximum preliminary cut slope angles given in Table 7 may be used with a relatively low risk of instability for unsurcharged batters. However detailed inspection by an experienced geotechnical engineer will be required at the time of construction to confirm the stability of batter faces.

High Rise Residential Development
 29 - 35 Campbell Street, Bowen Hills
 Project No. 010-203A
 18 February 2011

Table 7: Maximum Temporary Unsurcharged Cut Batter Slopes – 4m Maximum

Material	Soil Condition	Maximum Slope
Fill (uncontrolled)	–	1:2.5H ¹
Silty Clay	stiff	1:2.0H ²
Tuff	extremely low	1:1.5H
	very low to low	1:1.0H ³
	medium to high or stronger	1:0.5H ³

¹ Subject to inspection, uncontrolled fill may include 'less stable' zones that may require flatter batter angles and/or positive support

² Not underlain by 'softer' soils

³ Subject to jointing and confirmation by inspection and analysis (possibly steeper)

At the batter angles nominated in Table 7 there may be some localised slumping of batter slopes and it will be necessary to ensure that any such slumping will not adversely affect any services (footpaths etc.) located behind the slopes.

If insufficient space exists for the construction of cut batters at the slopes given in Table 7 or risk of some slumping cannot be accepted, the excavation sides will need to be continuously supported in order to prevent instability.

5.5 Temporary Excavation Support Methods

It is considered that ground support for excavated faces could be provided by one or a combination of methods outlined below.

In areas of excavation not continuously supported, it may be necessary to use steel mesh or heavy gauge galvanised wire (as appropriate) strung between points of rock anchor support to provide protection to personnel from isolated pieces of rock falling from faces.

Surface filling (soils and extremely low to low strength rock) will require continuous support to prevent instability. As a preliminary guide for costing, the minimum depth of surface material potentially requiring continuous support (if cut vertical or near vertical) for each bore has been estimated and is given in Table 8 below. These depths may need to be adjusted for the location, depth and backfill quality of any adjacent service trenches etc.

Table 8: Estimated Minimum Continuous Support Depth

Bore	Estimated Minimum Continuous Support Depth
1	1
2	5
3	6
4	1
5	10 to 13

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

5.5.1 Soldier Pile and Shotcrete Lagging

Surface fill soils and extremely low to low strength rock will require continuous support to prevent instability and a system that has been used successfully in Brisbane comprises anchored cantilever soldier piles installed in predrilled holes which in turn retain shotcrete lagging. Due allowance should be made in pricing to remove remnant building structure along site boundaries prior to commencement of soldier pile installation.

As a preliminary guide for costing the depth of surface material requiring continuous support if cut vertical or near vertical has been estimated at the current bore locations and is given in Table 8. These depths are based on the stratigraphy revealed in the bores only and may need to be adjusted for the location depth and backfill quality of any service trenches located close behind excavation boundaries.

Where soldier piles do not extend the full depth of excavation the toes of the piles will require substantial restraint to prevent excessive vertical and/or horizontal deflection. A stiff, 'anchored toe beam' has previously been used to successfully restrain soldier pile toes on similar projects.

5.5.2 Hit and Miss Construction

Subject to ground conditions actually encountered it will probably be necessary to adopt a 'hit and miss' near surface excavation approach along most of the site boundaries. On site supervision during excavation may enable the hit and miss approach to be deleted however this cannot be determined in advance of excavation. Hit and miss excavation and shoring may also be required immediately below the founding level of soldier piles.

It is recommended that 'lift heights' for hit and miss panel construction be limited to 1.2m, with subsequent panels not excavated until hit panels are supported. Adoption of an increased panel height would involve H&S issues for personnel working in close proximity to the face during wall construction.

When undertaking a 'hit and miss' approach, the stable slopes of any temporarily unsupported face will primarily depend on the composition and strength of buttress materials the orientation of rock discontinuities and the presence of groundwater. Careful assessment and confirmation of individual faces must be made during construction to assess panel design.

5.5.3 Reinforced Panels

Lateral support to near surface materials located on the site boundary could be provided by a reinforced continuous concrete panels that are constructed on a 'hit and miss' basis and supported by prestressed rock anchors.

Subject to the design of the facing it may prove more cost effective to install additional rock anchors/dowels to reduce the span of the facing and hence its required thickness/reinforcement. An optimisation process is suggested between anchor spacing and required facing structural properties.

High Rise Residential Development
29 - 35 Campbell Street, Bowen Hills
Project No. 010-203A
18 February 2011

5.5.4 Rock Dowels

For excavation faces unsurcharged by building loads and/or where some movement tolerance exists, rock dowels and reinforced shotcrete facing could be adopted for face support. If rock dowel and shotcrete support is to be adopted for permanent works, dowels and shotcrete must be fully corrosion protected for at least the life of the structure, with dowels being P/C sheathed and galvanised. Galvanised dowels are considered necessary for temporary works.

5.5.5 Prestressed Rock Anchors

In 'good' quality rock (e.g. medium strength or stronger tuff) with limited discontinuities, excavation support could be provided by use of a regular grid of prestressed rock anchors. The exact location of anchors would need to be determined by inspection during excavation, however an anchor spacing of 3m to 4m is suggested for initial costing. In near surface zones, anchor depths and/or inclinations will be controlled by the location and depth of existing services and the requirement to minimise total anchor length.

5.5.6 Shotcrete

In order to stabilise any 'loose' and/or 'low strength' rock zones between rock anchors, reinforced shotcrete is suggested, primarily as a personal safety measure.

5.5.7 External Corners

It will be necessary to allow for continuous, anchored, reinforced concrete support facing over the full excavation depth for any external corners. It is suggested that the facing extend not less than 3m to 5m from each corner, along each face, with confirmation during construction.

5.5.8 Intermediate Face Support

5.5.8.1 Temporary

In order to stabilise any 'loose' and/or 'low strength' rock zones between rock anchors, shotcrete incorporating mesh welded to anchor plates is suggested, primarily as a personal safety measure. This support system could also be adopted to stabilise surface materials with the shotcrete being cantilevered off underlying rock using rock anchors for 'toe' support.

For the stabilisation of local zones of 'unstable rock' between anchors, 100mm thickness of reinforced shotcrete could be adopted for an anchor spacing of not more than 2.5m.

5.5.8.2 Permanent

Permanent support to medium strength or stronger rock located between floor slabs, permanent anchors etc. should be designed for a uniform working pressure of not less than given in Table 15 to be confirmed by inspection during construction, provided that the rock is not surcharged by adjacent foundation or building loads.

High Rise Residential Development
 29 - 35 Campbell Street, Bowen Hills
 Project No. 010-203A
 18 February 2011

5.6 Temporary Excavation Support Loads

Due allowance must be included in retention support load analysis for groundwater pressure, surcharge effects from construction loading, the effects of sloping retained materials, buildings, structures on adjacent sites etc, each of which may introduce loads into retaining walls.

5.6.1 Earth Pressures

Where soil, fill and/or extremely low strength rock is retained near surface, temporary wall pressures may be preliminarily calculated using the parameters given in Table 9 where the boundary is not surcharged by adjacent buildings and some movement tolerance exists. A triangular pressure distribution is suggested for a flexible cantilever wall section.

Table 9: Lateral Earth Pressure Coefficient – Near Surface

Material	Unit Weight (kN/m ³)	Lateral Earth Pressure Coefficient	
		C	K
Soil/Fill	1.8	0.4	0.6
Extremely low strength rock	2.4	0.3	0.5

5.6.2 Boundary Loadings

5.6.2.1 Street Loadings

An average street loading of 16 kPa has been adopted for footpath and road pavement. Detailed consideration must also be given to the location and loading from any proposed 'hard stand', material load out areas that may be located around the excavation perimeter. The analyses reported herein do not include any allowance for load out points as it is currently not known if they will be required and if so, where they are to be located.

5.6.2.2 Adjacent Building Loadings

Details of adjacent building loads, foundation levels along the site boundaries are not currently known and have been assumed for preliminary analysis purposes to be as indicated in Table 10, the loads/levels must be confirmed as part of design finalisation so that the relevant estimated support loads given in Table 12 can be revised as necessary.

Table 10: Adjacent Building Loads (Assumed)

Foundation	Foundation Spacing	Adjacent Building Foundation Depth	Adjacent Building Floor Level	Adjacent Building Floor Level
			DL	LL
Adjacent Residential	1m	1m		25
Adjacent Commercial	0m	1m	150	30

□ To be confirmed □ preliminary only